



OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide
this office letter No. PWD/JSD/TA/NIT/ 2025-26- 7750-59 dated 19/12/2025.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **29.12.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **27.12.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **26.12.2025 up to 11.30 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days:-**


Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain damages on link road Praga Da Gallu to Dehru Da Bar via village Dhar Km 0/00 to 3/00 (SH:- P/L CC pavement at RD 0/101 to 0/126.60)	99246.00	2000.00	Two Month	350/-
2	Restoration of rain damages on Karori Killi Duhak road Balh road Km 0/00 to 5/00 (SH:-C/O R/wall at RD 2/861 to 2/862)	64607.00	2000.00	Two Month	350/-
3	Restoration of rain damages on Ropri to Nahlna via Masand Basti road Km 0/00 to 3/105 (SH:-C/O Breast wall at RD 1/454 to 1/464)	99639.00	2000.00	Two Month	350/-
4	Restoration of rain damages on Link road to village Alung Km 0/00 to 0/750 (SH:- P/L 60 mm Thick interlocking paver blocks Km 0/030 to 0/060)	99235.00	2000.00	Two Month	350/-
5	Restoration of rain damages on Bandahu to Bhairghatta road Km 0/00 to 2/615 (SH:- C/O R/wall at Rd 0/375 to 0/379.15)	98753.00	2000.00	Two Month	350/-
6	A/R & M/O HSTM road Km 24/135 to 30/00 (SH:-Repair of Pot Hole / patch work between Km 27/00 to 30/00)	92800.00	2000.00	Two Month	350/-
7	Restoration of rain damages on Jangal to Oach Kallan road KM 0/00 to 11/00 (SH:- C/O R/Wall at RD 1/795 to 1/801.10)	99791.00	2000.00	Two Month	350/-
8	A/R & M/O various roads under Sub Division Panchrukhi HP.PWD Division Jaisinghpur (SH:-Supplying and stacking sign board)	99600.00	2000.00	Two Month	350/-
9	A/R & M/O link road from Rit to Zamara Badhala Kohala Banjar road KM 0/00 to 1/909, Tehsil Jaisinghpur, Distt. Kangra (HP) under Jaisinghpur Sub Division) (SH:- Preparation of Forest Diversion case under FCA, 1980)	27031.00	550.00	Two month	350/-
10	A/R & M/O various roads under Sub Division Jaisinghpur (SH:- Providing and fixing dual directional rumble strips)	99450.00	2000.00	Two month	350/-

Om

P.T.O.

Terms & conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST,EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 7750-59

Dated: 19/12/2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

①

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on link road Praga da gallu to Dehru da ward via village Dhar
Km 0/00 to 3/00 (SH:- P/L CC pavement at RD 0/101 to 0/126.60)

Estimated cost Rs.	99246.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.57	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	2325.00
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.05	1520.00	Rupees One Thousand Five Hundred Twenty Only	Per cubic metre	9196.00

3	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	6.05	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	12705.00
4	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.10	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	75020.00
	Total					99246.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Karori Killi Duhak road balh road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 2/861 to 2/862)

Estimated cost Rs.	64607.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.93	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	659.00

2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.48	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	63448.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	500.00
		Excess (+)			%	64607.00
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

(3)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Ropri to Nahlana via masand Basti road Km 0/00 to 3/105 (SH:-C/O Breast wall at RD 1/454 to 1/464)						
			Estimated cost Rs.		99639.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.95	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	3139.00

2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.60	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic Metre	92250.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4250.00
		Excess (+)			%	99639.00
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

(4)

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain damages on Link road to village Alung Km 0/00 to 0/750 (SH:- P/L 60 mm Thick interlocking paver blocks Km 0/030 to 0/060)				Estimated cost Rs.		99235.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) nominal size Grading-III to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.18 cum(zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the by the Government.	0.68	2000.00	Rupees Two Thousand Only	Per cubic Metre	1360.00

2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.26	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	7875.00
3	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	90.00	1000.00	Rupees One Thousand Only	Per square metre	90000.00
	Total					99235.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

5

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain damages on Bandahu to Bhairghatta road Km 0/00 to 2/615 (SH:- C/O R/wall at Rd 0/375 to 0/379.15)				Estimated cost Rs.		98753.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.42	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2292.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	23.82	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	89325.00

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.48	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4256.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	12.00	240.00	Rupees Two Hundred Forty Only	Per Running Metre	2880.00
	Total					98753.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O HSTM road Km 24/135 to 30/00 (SH:-Repair of Pot Hole / patch work between Km 24/135 to 30/00)					Estimated cost Rs.	92800.00
					Earnest Money Rs.	2000.00
					Time Limits	One Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion pressure distributor at the rate 0.225 kg (zero point two two five kilograme) per/ Square metre on the prepared Bituminous surface cleaned with hydraulic broom as per M.O.R.D. technical specifications section No. 503 or as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	275.00	20.00	Rupees Twenty Only	Per Square Metre	5500.00
2	Providing , laying and rolling of close-graded Mix-Seal Surfacing , surfacing material of 20 mm (twenty millimetre) compacted thickness composed of Type-A 11.2 mm (eleven decimal two millimetre) to 0.09 mm (Zero point zero nine millimetre) nominal size crushed stone aggregate at the rate of 0.338 cum (Zero point three three eight cubic meter) per ten Square meter mixed with penetration grade bitumen V-G-10(Viscosity Grade -Ten) at the rate of binder content at the rate of 27.50 Kg(Twenty seven point five zero kilogram) per ten Square meter or 5.11 % (five decimal one one percent) by weight and minimum density of mix seal surfacing should be 2.10 gm (two decimal one zero) gram/Cubic centimeter to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 (eight to ten) KN static roller , finishing to required level and grades excluding the cost of tack coat inclusive of all corrective measures such as laying of profile corrective coarse for all depth construction of super elevation and camber , where required as MORD Technical Specification Section 500 in all respect and as per the direction of Engineer in Charge including carriage of material within all leads , lifts and others incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government excluding GST.	275.00	310.00	Rupees Three Hundred Ten Only	Per Square Metre	85250.00

3	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	1.00	2050.00	Rupees Two Thousand Fifty Only	Per Cubic Metre	2050.00
	Total					92800.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Jangal to Oach Kallan road Km 0/00 to 11/00 (SH:- C/O R/wall at Rd 1/795 to 1/801.10)

Estimated cost Rs.	99791.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.33	250.00	Rupees Two Hundred Fifty Only	Per Cubic Metre	2333.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	21.84	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	82992.00

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.49	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	9966.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4500.00
	Total					99791.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

8

SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O various road Under sub Division Panchrukhi HP.PWD Division Jaisinghpur (SH:-Supplying and stacking sign board)				Estimated cost Rs.		99600.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Supplying and stacking 1200x900mm (One thousand two hundred into nine hundred) size direction and place identification retro-reflective sign board as per IRC made of 1.5mm (One decimal five millimetre) thick sheeting and supported on 40mm (Forty millimetre) dia pipe painted with red lead primer as per approved drawing and technical specification clause vide clause 1701.2.3 and entire satisfaction / directions of Engineer-in-charge including hauling of materials in all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government	12.00	4300.00	Rupees Four Thousand Three Hundred Only	Each	51600.00
2	Supplying and stacking 600x900mm (Six hundred into nine hundred) size, direction and place identification retro-reflective sign board as per IRC made of 1.5mm (One decimal five millimetre) thick sheeting and supported on 40mm (Forty millimetre) dia pipe painted with red lead primer as per approved drawing and technical specification clause vide clause 1701.2.3 and entire satisfaction / directions of Engineer-in-charge including hauling of materials in all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government	15.00	3200.00	Rupees Three Thousand Two Hundred Only	Each	48000.00
Total						99600.00
Quoted Rate (in Figures) Percentage			Excess (+)		%	
			Less (-)		%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O link road from Rit to Zamrara Badhala kohala banjar road Km 0/00 to 1/909 Tehsil Jaisinghpur Distt. Kangra (HP) under Jaisinghpur Sub Division) (SH:- Preparation of forest Diversion case under FCA,1980)				Estimated cost Rs.		27031.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
3	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.909	14160.00	Rupees Fourteen Thousand One Hundred Sixty Only	Per kilometre	27031.00
Total						27031.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O Various roads under Sub-Division Jaisinghpur (SH:- Providing and fixing dual directional rumble strips)				Estimated cost Rs.		99450.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
3	Providing and fixing dual directional rumble strips made of ABS (Acrylonitrile Butadiene styrene) material of size 250 mm x150 mm (Two hundred fifty to one hundred fifty millimetre) duly reflectorised with highly reflective glass panels on both sides and to be fixed with 2No. steel pins and suitable epoxy including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	78.000	1275.00	Rupees One Thousand Two Hundred Seventy Five Only	Each	99450.00
	Total					99450.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur