



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

E-Mail ID - ecpwd-ihb-bil@hp.gov.in

No-PW-JDT-CB/EA-I/Tender Notice/2025- 8379-82 Dated 22/12/2025

To


The Executive Engineer (IT Cell),
Nigam Bihar Shimla-2.
eeict-pwd-shi@hp.gov.in
cc-pwd-hp@nic.in

Subject: Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading on departmental website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh Notification No-PBW-(B) A(3) 1/2024 dated Shimla-2 the 3rd January 2024 & Adviser Planning HP Shimla-2 Notification No- PLG (F) RDP-5-4/2025 SDP-Misc. dated 05/07/2025 as the works mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.

Copy forwarded to the following for information and necessary action please.


1. The Engineer-in-Chief HPPWD Nirman Bhawan Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer 10th Circle HPPWD., Bilaspur.
4. All the Assistant Engineers working under this Division.
5. Notice Board.


Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.



CERTIFICATE

Certified that the tenders called vide this office letter No-
PW-JDT-CB/EA-I/Tender Notice/2025- 8379-82 Dated 22/2/2025 is
emergent nature in the public interest.


Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.





E-Mail ID - cepwd-jha-bil@hp.gov.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Scaled Item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form 29/12/2025 upto 12:00 PM
Date of issue/sale of Tender forms 29/12/2025 from 02:00 PM to 04:00 PM
Date of opening of tender 30/12/2025 at 11:00AM

The tender shall be received up to 10:30AM on 30/12/2025 and will be opened on the same day at 11:00AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on 29/12/2025 from 02:00 PM to 04:00 PM.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to accept or reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit	Class
1	R/o Repair of BJSM road from Km. 0/0 to 20/0 (SH: Maintenance of earthen shoulder and C/o unlined surface drain b/w Km. 0/0 to 1/500)	93858.00	2000.00	350.00	Two Month	Class-D & C
2	RRD on various roads at Marotan Section under Sub Division Kalol (SH: Hiring of Excavator cum Loader / JCB for removal of slips, C/o unlined drain, dressing of berms and other restoration work etc.)	94500.00	1900.00	350.00	One Month	Class-D & C
3	RRD on various roads at Kalol Section under Sub Division Kalol (SH: Hiring of Excavator cum Loader / JCB for removal of slips, C/o unlined drain, dressing of berms and other restoration work etc.)	94500.00	1900.00	350.00	One Month	Class-D & C
4	R/o Repair of BJSM road from Km. 0/0 to 20/0 (SH: Maintenance of earthen shoulder and C/o unlined surface drain b/w Km. 5/500 to 7/0)	96501.00	2000.00	350.00	Two Month	Class-D & C



5	Balance work of Sub Treasury Building at Jhandutta Tehsil Jhandutta Distt. Bilaspur (HP) (SH: Providing and Fixing in stair case) Deposit Work	97297.00	1900.00	350.00	Two Month	Class-D & C
6	R/o Repair of BJSM road from Km. 0/0 to 20/0 (SH: Maintenance of earthen shoulder and C/o unlined surface drain b/w Km. 2/0 to 3/500)	93374.00	2000.00	350.00	Two Month	Class-D & C
7	R/o Repair of link road Bharoli Khurd to Bagdu at Km. 0/0 to 3/0 (SH: Hiring of Excavator cum loader /JCB for C/o unlined drain, dressing of berms and other restoration works etc. at RD 0/0 to 1/500)	94500.00	1900.00	350.00	Two Month	Class-D & C
8	R/o link road to PHC Gah and Boatghat Km. 0/0 to 6/0 (SH: Hiring of Excavator cum loader /JCB for C/o unlined drain, dressing of berms and other restoration works etc.)	89250.00	1800.00	350.00	Two Month	Class-D & C

Terms and conditions:

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.
6. Payment for the works under N.I.T. shall be made as & when sufficient funds are available with the Department.
7. Tender form shall not be issued to those contractors who have two or more work in hand.

... HIM SUCHNA AVAM JAN SAMPARK...

Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.

DRAFT SCHEDULE OF QUANTITY

①

**Name of Work :- R/o Repair of BJSM road from km 0/000 to 20/000 (SH:-
Maintenance of Earthen shoulder and C/o unlined surface drain b/w km
0/000 to 1/500)**

Estimated cost:- ₹	93858.00
Earnest Money:- ₹	2000.00
Time allowed:- Two Months	
Only	

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1800.00	46.10	INR fourty six and Paise one zero Only	Per square Meter	82980.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines; grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including carriage of material with in all lead and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	370.00	29.40	INR twenty nine and Paise four zero Only	Per running meter	10878.00
Total:-						93858.00

Draft schedule of quantity No. 351 for the year 2025-26 approved for Rs- 93858/- only

Estimate No. 351
DNIT No. 35T
Head of Account .

Executive Engineer,
Jhandaufa Division
HPPWD, Jhandaufa

DRAFT SCHEDULE OF QUANTITY.

Name of work :- RRD on various roads at Marotan Section under Sub division Kalol (SH:- Hiring of Excavator cum loader/JCB for removal of slips, Construction of Unlined surface drain, dressing of berms and other restoration works etc.)		Estimated Cost:- Rs. 94500.00				
		Earrest Money:- Rs. 1900.00				
		Time allowed:- One Month				
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	2	3	4	5	6	7
1	Providing of Excavator 0.90 (zero point nine) cum bucket capacity @ 40 Cum per hour for removal of landslides /slip clearance, ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and left as per technical specification 302.3.5 and 1611 as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00	1050.00	Rs. One thousand fifty and paisa zero zero only.	Per Hours	94500.00
Total						94500.00

Terms and Condition:-

- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
- 2 The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair
- 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period.
- 4 The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work.

Draft schedule of quantity No 296 for the year 2025-26 approved for Rs- 94500/- only

Estimate No. :- 296
 DNIT No. :- 296
 Head of Account :-


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

3

DRAFT SCHEDULE OF QUANTITY.

Name of work :- RRD on various roads at Kalol Section under Sub division Kalol (SH:- Hiring of Excavator cum loader/SCB for removal of slips, Construction of Unlined surface drain, dressing of berms and other restoration works etc.)		Estimated Cost:- Rs. 94500.00				
		Earnest Money:- Rs. 1900.00				
		Time allowed:- One Month				
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	Providing of Excavator 0.90 (zero point nine) cum bucket capacity @ 40 Cum per hour for removal of landslides /slip clearance, ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of material with in all leads and left as per technical specification 302.3.5 and 1611 as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00	1050.00	Rs. One thousand fifty and paisa zero zero only.	Per Hours	94500.00
Total						94500.00

Terms and Condition:-

- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
- 2 The one number Excavator cum loader/SCB will be engaged on per hours bases working at site of work including cost of POL establishment and other
- 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period.
- 4 The contractor will be fully responsible for any local damages to any private Govt. Property during the execution of work.

Draft Schedule of quantity No. 294 for the year 2025-26 approved for Rs-94500/- only

Estimate No. :- 294
 DRAFT No. :- 294
 Head of Account :-

[Signature]
 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

④

Name of Work :- R/o Repair of BISM road from km 0/000 to 20/000 (SH-7/000)		Estimated cost:- ₹		96501.00	Only	
Maintenance of Earthen shoulder and C/o unlined surface drain b/w km 5/500 to 7/000)		Earnest Money:- ₹		2000.00	Only	
Time allowed:- Two Months						
Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1953.00	46.10	INR fourty six and Paise one zero Only	Per square Meter	90033.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including carriage of material with in all lead and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	220.00	29.40	INR twenty nine and Paise four zero Only	Per running meter	6468.00
Total:-						96501.00

Draft schedule of quantity by NBS for the year 2025-26 approved for Rs-96501/- only

Estimate No. **353**
DNIT No. **353**
Head of Account.

Executive Engineer,
Jhاندutta Division
HPPWD, Jhاندutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Balance work of Sub - Treasury Building at Jhandutta Tehsil Jhandutta Distt
 Jhalspur H.P. (SH:- Providing and Fixing in stair case). Deposit Work.


Estimated cost:- ₹ 97297.00	Only
Earnest Money:- ₹ 1900.00	Only

Time allowed:- Two Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1029.60	94.50	INR Ninety four and Paise five zero Only	per kilogram	97297.00
Total:-						97297.00

Draft schedule of quantity No. 298 for the year 2026 approved for Rs-97297/- only

Estimate No. 298
 DNIT No. 298
 Head of Account.
 Available Fund:-/-only


 Executive Engineer,
 Jhandutta Division,
 HPPWD, Jhandutta

5

DRAFT SCHEDULE OF QUANTITY

6

Name of Work :- R/o Repair of BJSM road from km 0/000 to 20/000 (SH-3/500)	Estimated cost:- ₹	93374.00	Only
	Earnest Money:- ₹	2000.00	Only
	Time allowed:- Two Months		

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 complete as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1764.00	46.10	INR fourty six and Paise one zero Only	Per square Meter	81320.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a fill upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including carriage of material with in all lead and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	410.00	29.40	INR twenty nine and Paise four zero Only	Per running meter	12054.00
Total:-						93374.00

Draft schedule of quantity No. 352 for the year 2025-26 approved for Rs - 93374/- only

Estimate No. 352
DNIT No. 352
Head of Account.

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

DRAFT SCHEDULE OF QUANTITY.


7

Name of work :- R/O Repair of link road Bharoli Khurad to Bagru at Km 0/0 to 3/00 (SH:- Hiring of Excavator cum loader/JCB for Construction of Unlined drain dressing of berms and other restoration works etc. at Rd 0/00 to 1/500.)		Estimated Cost:- Rs. 94500.00	/-Only			
		Earnest Money:- Rs. 1900.00	/-Only			
		Time allowed:-	Two Month			
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of silt. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00	1050.00	Rs. One thousand fifty only.	Per Hours	94500.00
2						
Total						94500.00

Terms and Condition:-

- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
- 2 The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL
- 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period.
- 4 The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work.

Estimate No. **159**
 DNIT No. **159**
 Head of Account .
 Available Fund:-/only


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

8


DRAFT SCHEDULE OF QUANTITY.

Name of work :- R/O link road to PHC Gah and boatghat km 0/0 to 6/00 (SH:- Hiring of Excavator cum loader/JCB for Removal of slips, Construction of Unlined surface drain ,dresssing of berms and other restoration works etc.)		Estimated Cost:- Rs. 89250.00 /-Only				
		Earnest Money:- Rs. 1800.00 /-Only				
		Time allowed::- Two Month				
Sr No.	Description of items.	Quantity	Rate In		Unit	Amount
			In Figure	In words.		
1	2	3	4	5	6	7
1	Providing one number Exacavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other constrction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.00	1050.00	Rs. One thousand fifty only.	Per Hours	89250.00
Total						89250.00

Terms and Condition:-

- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
- 2 The one number Exacavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.
- 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period.
- 4 The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work.

Estimate No. 475
 DNIT No. 475
 Head of Account .
 Available Fund:-/-only


 Executive Engineer,
 Jhandutta Division
 HPPWD. Jhandutta