

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

9245-47

Dated: - 20/12/2025


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,


Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.



Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2025-26-92

47 dated 20/12/25 are required to be carried out immediately being emergent nature of work in p

interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli Dist. (Una HP).

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so reach and open in his office as per time schedule given below. The offer of the tender will be open for days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - **26/12/25** up to 10.30 AM
2. Date of issue/sale of tender forms against cash payment(non-refundable): - **27/12/25** up to 3.00 PM
3. Date of receipt of tenders: - **29/12/25** up to 10.30 AM
4. Date of opening of tenders: - **29/12/25** at 11.00 AM

| Sr. No | Name of work | Estimated cost | EMD | Time Limit | Cost of tender | Eligible class of contractor |
|--------|--|----------------|--------|------------|----------------|------------------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 2/714 to 3/052) Deposit work | 99085 | 2000/- | One Month | 350/- | Class- C & D |
| 2 | Restoration of rain damages on Old Saloh Bhadouri road km. 0/00 to 9/615(SH:-Repair of existing Cause way at RD. 7/470 to 7/516) | 98670 | 2000/- | One Month | 350/- | Class- C & D |
| 3 | C/O road from Lower Panjwar covering Saini Mohalla, Dhakki, Dhakki Mohalla up to Daulatpur link road & Nagnoli Petrol Pump via ward No.5 up to Shiv Mandir Panjwar & Maadu ki Nihali se Madanka-Ghar Tak village Panjwar km. 0/00 to 8/00(SH:-Preparation of working estimate and DNIT including submission of Hard and soft copies) under NABARD-XXXI | 85000 | 1700/- | 15 day | 350/- | Class- C & D |
| 4 | Restoration of rain damages on Old Saloh Bhadouri road km. 0/00 to 9/615(SH:-P/L CC Over lay on existng Couse way at RD. 7/490 to 7/510.10) | 99495 | 2000/- | One Month | 350/- | Class- C & D |
| 5 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-IV | 99627 | 2000/- | One Month | 350/- | Class- C & D |

| | | | | | | |
|----|--|-------|--------|-----------|-------|--------------|
| 6 | C/O Rajiv Gandhi Day Boarding School at Haroli distt. Una (SH:-Preparation of Topographical & Contour site Plan) | 70320 | 1700/- | 15 day | 350/- | Class- C & D |
| 7 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-V | 99385 | 2000/- | One Month | 350/- | Class- C & D |
| 8 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-I | 99243 | 2000/- | One Month | 350/- | Class- C & D |
| 9 | C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 1/360 to 1/698) | 99085 | 2000/- | One Month | 350/- | Class- C & D |
| 10 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-II | 99268 | 2000/- | One Month | 350/- | Class- C & D |
| 11 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-VI | 99378 | 2000/- | One Month | 350/- | Class- C & D |
| 12 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-VI | 99774 | 2000/- | One Month | 350/- | Class- C & D |
| 13 | Restoration of rain damages on Laluwal Gondpur to Singha Jhungian upto Punjab Border road km. 0/00 to 13/575(SH:-Repair of Rain cuts at Various RDs from km. 12/275 to 13/575) | 99216 | 2000/- | One Month | 350/- | Class- C & D |
| 14 | Restoration of rain damages on Old Saloh Bhadouri road km. 0/00 to 9/615(SH:-Repair of existing Cause way at RD. 7/516 to 7/556) | 85800 | 2000/- | One Month | 350/- | Class- C & D |
| 15 | Restoration of rain damages on Link road Bathu to Bathri via Goushala km. 0/00 to 1/100 (SH:-Repair of Rain cuts at Various RDs from km. 0/00 to 1/100) | 98280 | 2000/- | One Month | 350/- | Class- C & D |


The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.

7. The contractor/firm shall have his resignation and GST No. and copy of same be attached with application.
8. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
9. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
10. The tender form will be issued to those contractors who have relevant machinery and equipment (the list of which may be attached with their application a/w proof of ownership of machinery/lease tie up arrangement).
11. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
12. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-harolli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

2

Schedule of quantity

Name of work: -Restoration of rain damages on Old Saloh Bhadouri road Km. 0/00 to 9/615

(SH: Repair of existing Couse way at Rd. 7/470 to 7/516)

Estimated Cost: Rs ₹ 98,670

Time:- One month

Earnest Money:- 2000

Rate in words

Amount

DESCRIPTION

1 Providing and laying cement concrete 1:4:8. (One cement: five sand : ten graded stone aggregate 40 mm nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.

Qty 29.90

Unit Cum

T.Rate 3300.00

Rupees Three Thousand Three Hundred Only

Amount 98670

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20

Total: 98670

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

566

Schedule of Quantity

Estimated cost : 85000
Earnest Money : 1700
Time Limit : 15 day

Name of Work : Construction of road from Lower Panjawar covering Saini Muhalla, Dhakki Muhalla up to Daulatpur link road & Nagdoli Petrol Pump via ward No.5 up to Shiv Mandir Panjawar & Maadu Ki Nihali se Madan-Ka-Ghar Tak village Panjawar Km 0/00 to 8/000 (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under NABARD.-XXXXI

| S. No. | Description of item | Qty. | Unit | Rate (Rs.) | Rate in words | Amount (Rs.) |
|--------|---|------|------|------------|----------------------------------|--------------|
| 1 | Preparation and approval of working estimate and Drafts Schedule of quantity from higher authority including submission of 5-set of estimate and soft copy of estimate .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 1 | Each | 85000 | Rupees Eighty five thousand only | 85000 |
| | 1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | Total = | 85000 |
| | Percentage quoted rate in Figures | | | | | |
| | Percentage quoted rate in words | | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected. | | | | | |

Executive Engineer
Haroli Division
HPPWD Haroli.

520

5

Draft Schedule of quantity

Name of work :- Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00

(S.H :- Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-IV

| Name of work :- Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 | | Estimated Cost: Rs | | ₹ 99,627 | |
|--|--|--------------------|------|---------------|--------------|
| | | Time:- | | One month | |
| | | Earnest Money:- | | 2000 | |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Amount |
| 1 | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Plain Cement concrete grade M15 nominal mix 1:2.5:5. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 13.00 | Cum | 4800.00 | 62400 |
| 2 | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Reinforced Cement concrete grade M20 nominal mix 1:2:4 in Bed block & dirt wall. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 5.84 | Cum | 4500.00 | 26302 |
| 3 | Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawings and technical specification Clauses 1002, 1010 and 1202. HPSR 2009 Item No. 13.3. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 115.00 | Kg | 95.00 | 10925 |
| | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(17)2/0212 dated 7.8.2018 | | | | |
| | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | |
| | Percentage quoted rate in Figures | | | | |
| | Percentage quoted rate in words | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected. | | | | |
| | | | | Total: | 99627 |

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

503

Schedule of Quantity



1400 70320

Estimated cost : 1700
Earnest Money : 1700
Time Limit : 15 day

Name of Work : Construction of Rajiv Gandhi Day Boarding School at Haroli Distt. Una (SH: Preparation of Topographical & Contour site plan)

| S. No. | Description of item | Qty. | Unit | Rate (Rs.) | Rate in words | Amount (Rs.) |
|--------|---|------|-------|------------|-----------------------------|--------------|
| 1 | Preparation of Topographical & Contour site plan of Day Boarding School Gram Panchayat Haroli which include showing all features like road, buildings, sheds, Electrical/ Telephone poles, drain, Manholes, Major trees, water bodies, open land, park, play ground, boundary etc. (Area = 5.86 Acres). The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 5.86 | Acres | 12000 | Rupees Twelve thousand only | 70320 |
| | 1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20 | | | | Total = | 70320 |
| | Percentage quoted rate in Figures | | | | | |
| | Percentage quoted rate in words | | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected. | | | | | |

Executive Engineer
Haroli Division
HPPWD Haroli

521

7

Draft Schedule of quantity

| Name of work :-Restoration of rain damages on Panjawar Bathri road km. 0/00 to 34/00 | | Estimated Cost: Rs | | ₹ 99,385 |
|---|------|--------------------|--------------------------------------|--------------|
| (S.H. : Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-V | | Time:- | | One month |
| S.NO | | DESCRIPTION | | 2000 |
| Qty | Unit | T.Rate | Rate in words | Amount |
| 6.40 | Cum | 6100.00 | Rupees Six Thousand One Hundred Only | 39060 |
| 635.00 | Kg | 95.00 | Rupees NinetyFive Only | 60325 |
| | | | Total: | 99385 |
| <p>Providing and laying reinforced cement concrete in superstructure complete as per drawings and Technical Specification Clauses 800, 1205.4 and 1205.5 Reinforced Cement Concrete Grade M25 (1:1.5:3) Nominal mix. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.</p> | | | | |
| <p>Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawings and technical specification Clauses 1002, 1010 and 1202. HPSR 2009 Item No. 13.3. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.</p> | | | | |
| <p>NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018</p> | | | | |
| <p>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20</p> | | | | |
| Percentage quoted rate in Figures | | | | |
| Percentage quoted rate in words | | | | |
| <p>Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.</p> | | | | |

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

504

91

Schedule of quantity

| Name of work: - C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work). | | Estimated Cost: Rs | ₹ 99,085 | | | | |
|--|--|--------------------|-----------|---------|--|--------|-------|
| (SH: Providing & laying 20mm thick premix carpet at Rd. 1/360 to 1/698) | | Time:- | One month | | | | |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Rate in words | Amount | |
| 1 | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including pre-mixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 13.94 | cum | 1300.00 | Rupees One Thousand Three Hundred Only | 18125 | |
| 2 | Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 241.67 | sqm | 55.00 | Rupees FiftyFive Only | 13292 | |
| 3 | Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 241.67 | sqm | 200.00 | Rupees Two Hundred Only | 48334 | |
| 4 | Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 241.67 | sqm | 80.00 | Rupees Eighty Only | 19334 | |
| Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018 | | | | | | Total | 99085 |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021 | | | | | | | |
| Percentage quoted rate in figures | | | | | | | |
| Percentage quoted rate in words | | | | | | | |
| Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected | | | | | | | |

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

192

Draft Schedule of quantity

| Name of work :- Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 | | | | | | | Estimated Cost: Rs | ₹ 99,360 |
|---|---|-------|------|---------|---|---------------|--------------------|-----------|
| (S.H. Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-III | | | | | | | Time:- | One month |
| | | | | | | | Earnest Money:- | 2000 |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Rate in words | Amount | | |
| 1 | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and Technical Specification Clauses 802, 803, 1202 and 1203. Plain Cement concrete grade M10 Nominal mix 1:3:6. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 5.76 | Cum | 4250 | Rupees Four Thousand Two Hundred Fifty Only | 24480 | | |
| 2 | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Plain Cement concrete grade M15 nominal mix 1:2.5:5. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 15.60 | Cum | 4800.00 | Rupees Four Thousand Eight Hundred Only | 74880 | | |
| | | | | | | Total: | 99360 | |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(17)2/0212 dated 7.8.2018 | | | | | | | | |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | | | | | |
| Percentage quoted rate in Figures | | | | | | | | |
| Percentage quoted rate in words | | | | | | | | |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected. | | | | | | | | |

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

485

13

Schedule of quantity

| Name of work: - Restoratin of rain damages on Laluwal Gondpur to Singha Jhungian upto Punjab Border road km. 0/0 to 13/575 | | | | | | | Estimated Cost: Rs | ₹ 99,216 |
|--|---|--------|------|--------|--------------------------------|--------------|--------------------|-----------|
| (SH: Repair of Rain cuts at Various RDs from km. 12/275 to 13/575) | | | | | | | Time:- | One month |
| | | | | | | | Earnest Money:- | 2000 |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Rate in words | Amount | | |
| 1 | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 413.40 | Cum | 240.00 | Rupees Two Hundred Fourty Only | 99216 | | |
| | | | | | Total: | 99216 | | |
| | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018 | | | | | | | |
| | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | | | | |
| | Percentage quoted rate in Figures | | | | | | | |
| | Percentage quoted rate in words | | | | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected. | | | | | | | |

M

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**


SSS

Schedule of quantity

Name of work: -Restoration of rain damages on Old Saloh Bhadouri road Km. 0/00 to 9/615

(SH: Repair of existing Couse way at Rd. 7/516 to 7/556)

| | | Estimated Cost: Rs | ₹ 85,800 | | | |
|------|---|--------------------|-----------|---------|--|--------------|
| | | Time:- | One month | | | |
| | | Earnest Money:- | 2000 | | | |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Rate in words | Amount |
| 1 | Providing and laying cement concrete 1:4:8. (One cement: five sand : ten graded stone aggregate 40 mm nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Maikana, toll tax , sale tax or other taxes imposed by the Government. | 26.00 | Cum | 3300.00 | Rupees Three Thousand Three Hundred Only | 85800 |
| | | | | | Total: | 85800 |
| | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018 | | | | | |
| | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | | |
| | Percentage quoted rate in Figures | | | | | |
| | Percentage quoted rate in words | | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected. | | | | | |


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

15

Schedule of quantity

| Name of work: - Restoratin of rain damages on Link road Bathu to Bathri via Goushala KM. 0/00 to 1/100 | | Estimated Cost: Rs | | ₹ 98,280 | | |
|--|---|--------------------|------|-----------|--------------------------------|--------------|
| (SH: Repair of Rain cuts at Various RDs from km. 0/00 to 1/100) | | Time:- | | One month | | |
| | | Earnest Money:- | | 2000 | | |
| S.NO | DESCRIPTION | Qty | Unit | T.Rate | Rate in words | Amount |
| 1 | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 409.50 | Cum | 240.00 | Rupees Two Hundred Fourty Only | 98280 |
| | | | | | Total: | 98280 |
| | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018 | | | | | |
| | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20 | | | | | |
| | Percentage quoted rate in Figures | | | | | |
| | Percentage quoted rate in words | | | | | |
| | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected. | | | | | |

Executive Engineer,
H.P.P.W.D. Division Harbhi
Distt. Una (H.P.)

556