

Himachal Pradesh  
Public Works Department

NO/PW/TLD/Tender/2025: - 9488-97  
To

Dated: - 24.11.2025


The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

Copy is forwarded to Superintending Engineer, 1<sup>st</sup> Circle,  
HPPWD Mandi for information please.

Copy to All the Assistant Engineers working under this  
Division.

Copy to AB/DB in this office.  
Copy to Notice board.

/   
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER"**

Sealed Percentage tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 08.12.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 05.12.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 06.12.2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, HPPWD Divisio (B&R), Thalout at Pandoh during office hour on any working day.

Sr. No.	Name of work	Estim ated cost	Earnest money	Cost of form	Time Period	For m No.	Eligib ility of Contr actors
1	R.R.D on road from Hanogi to Bandhi km. 0/00 to 15/00 (SH: Hiring of excavator cum loader for removal of slips/debries /mucks etc. at RD 0/00 to 5/00	99600	2,000	Rs. 350/-	One month	6&8	-do-
2	RRD on Thatta to Rangcha road Km. 0/0 to 3/0 (SH: Hiring of Excavator cum loader for removal of slips/boulders, muck debries etc. at various RD's)	99600	2,000	Rs. 350/-	One month	6&8	-do-
3	RRD Bhatwari to Rensh road Km. 0/00 to 8/640 (SH: C/o crated B/Wall from RD 4/855 to 4/865).	96202	2,000	Rs. 350/-	One month	6&8	-do-
4	Maintenance of Pandoh, Takoli Kullu by pass road old NH-21 Km. 222/700 to 227/600 (SH: Providing and Supplying WBM Grade-III between RDs 222/700 to 223/500) Job No. 2	98462	2,000	Rs. 350/-	One month	6&8	-do-
5	RRD on various roads under Balichowki Sub Division (SH: Hiring of Tipper for carriage of muck, debries etc. at various RDs in Balichowki Section).	98000	2,000	Rs. 350/-	One month	6&8	-do-
6	R.R.D on Batwari to Rensh road Km. 8/640 to 15/910 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 10/500 to 12/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on Chubhlu to Farsh road Km. 0/0 to 4/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on various roads under Balichowki Sub Division (SH: Hiring of Tipper for carriage of muck debries etc. from various RD's of various roads under Balichowki Section).	98000	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on various roads Pandoh Sub Division (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I) Job No. 4	99600	2,000	Rs. 350/-	One month	6&8	-do-



10	RRD on Panjain Bali Chowki Thata Tikki Shettadhar Ghat Tapnali Gadagushaini road (MDR-107) Km. 0/0 to 70/0 (SH: Hiring of Excavator cum loader for removal of slips/boulders, muck debries etc. at RD 8/0 to 16/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
11	R.R.D on road from Hatoun-Bhabas-Muthal km. 0/00 to 7/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 3/500 to 7/00)	99600	2,000	Rs. 350/-	One month	6&8	-do-
12	R.R.D on Karthach to Koon road Km. 0/00 to 3/500 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
13	Maintenance of Four laining of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Earthwork in filling at 223/300 to 223/400) Job No. 6	99980	2,000	Rs. 350/-	One month	6&8	-do-
14	RRD on Bhatludhar to Baggi road Km. 0/00 to 2/00 (SH: C/o R/Wall in PCC 1:4:8 at RD 0/092.50 to 0/095).	90079	2,000	Rs. 350/-	One month	6&8	-do-
15	R.R.D on Kuklah to Baggi road Km. 0/00 to 8/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/00 to 4/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
16	RRD on various roads on Pandoh Sub Division (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-1) Job No. 5	99600	2,000	Rs. 350/-	One month	6&8	-do-
17	R.R.D on Kholanal to Koon road Km. 0/00 to 3/500 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
18	Maintenance of Four laining of End Pandoh by pass to Takoli Kullu Section of NH-21 Km. 222/700 ot 227/600 (SH: Earthwork in filling at 223/300 to 223/400) Job No. 7	99980	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on road from Burah to Panjain Km. 0/00 to 11/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs between Km. 0/00 to 5/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
20	R.R.D on road from Deod to Hatoun km. 0/00 to 2/985 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
21	RRD on road from Sudhrani to Ghat Km. 0/00 to 5/500 (SH: Repair of Toe wall for existing slab culvert at RD 0/180).	98807	2,000	Rs. 350/-	One month	6&8	-do-
22	Maintenance of Four laining of End Pandoh bypass of Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH:	98000	2,000	Rs. 350/-	One month	6&8	-do-

	Hiring of Tipper for carriage of muck/debris etc. at various RDs in Pandoh Section-1)						
23	RRD on road from Burah to Panjain km. 0/00 to 11/000 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs between Km. 5/00 to 11/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
24	RRD on Bhatwari to Rensh road Km. 0/00 to 8/640 (SH: C/o Crated R/Wall at RD 4/480 to 4/485).	88294	2,000	Rs. 350/-	One month	6&8	-do-
25	RRD on Kuklah to Baggi road Km. 0/00 to 8/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 4/00 to 8/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
26	R.R.D on Dhingali to Gagan road Km. 0/0 to 6/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
27	RRD on various roads under Pandoh Sub Division (SH: Hiring of Tipper for carriage of muck, debries etc. at various RDs Pandoh Section-II) Job No. 2	98000	2,000	Rs. 350/-	One month	6&8	-do-
28	RRD on various roads of Panarsa Sub Division (SH: Hiring of Tipper for carriage of muck/debris etc. at various RDs in Nagwain Section) Job No. 2	98000	2,000	Rs. 350/-	One month	6&8	-do-
29	RRD on Bhatwari to Rensh road km. 0/00 to 8/640 (SH: C/o Created R/Wall at RD 4/475 to 4/480).	88314	2,000	Rs. 350/-	One month	6&8	-do-
30	RRD on Kashimblidhar to Badabunad road Km. 0/00 to 3/500 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
31	RRD on Chamarjani to Sansoi road Km. 0/0 to 2/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
32	R.R.D on Thatta to Samlwas road Km. 0/0 to 12/00 under Balichowki Sub Division (SH: Hiring of excavator cum loader for removal of slips and road side unlined surface drain) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
33	RRD on Takoli Bhamsoi to Bhalther road Km. 0/0 to 4/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs). Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
34	RRD on Bhatwari to Rensh road Km. 0/00 to 8/640 (SH: C/o Created R/Wall at RD 4/585 to 4/590)	88251	2,000	Rs. 350/-	One month	6&8	-do-
35	R.R.D. on Baggi to Kashimblidhar road Km. 0/00 to 3/000 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-



36	RRD on various roads of Panarsa Sub Division (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain Section) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
37	RRD on road from Khuhan to Diddar km. 0/0 to 6/00 (SH: C/o R/Wall at RD 2/787 to 2/789).	99934	2,000	Rs. 350/-	One month	6&8	-do-
38	RRD on various roads of Panarsa Sub Division (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs in Nagwain Section) Job No. 2	98000	2,000	Rs. 350/-	One month	6&8	-do-
39	RRD on Sudhrani to Thatta road Km. 0/0 to 5/0 (SH: Hiring of Excavator cum loader for removal of slips/boulders, muck debries etc. at various RD's)	99600	2,000	Rs. 350/-	One month	6&8	-do-
40	RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, derbies etc. at various RDs under Nagwain Section) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
41	RRD on road Khuhan to Diddar Km. 0/0 to 6/00 (SH: C/o R/wall at RD 2/791 to 2/793).	99397	2,000	Rs. 350/-	One month	6&8	-do-
42	RRD on Bhatwari to Rensh road Km. 0/0 to 8/640 (SH: C/o crated R/Wall at RD 4/590 to 4/595).	88268	2,000	Rs. 350/-	One month	6&8	-do-

**TERMS & CONDITIONS: -**

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

NO/PW/TLD/Tender/2025: -

9478-87

Dated: -

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1<sup>st</sup> Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.


Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

24-11-2025

Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

**Certificate**

Certified that the tender called vide this office letter No. PW/TLD/Tender/2025- 9478-87 dated 24.11.2025 is emergent nature and in Public interest.


  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

**BILL OF QUANTITY**

**Name of work:- R.R.D. on road from Hanogi to Bandhi km 0/000 to 15/000. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/00 to 5/00)**

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					<b>Total</b>	<b>99600.00</b>

*Bill of quantity approved for Rs 99600/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.




### SCHEDULE OF QUANTITY

**Name of work:-** RRD on Thatta to Rangcha road Km. 0/0 to 3/0  
(SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RD's)

**Estimated Cost:-** Rs. 99600.00  
**Earnest Money :-** Rs. 2000.00  
**Time :-** One Month

Sr. No.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator- cum- loader for removal of slips/ snow/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work at least 6 (Six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil/snow per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 (Twenty five) cubic metre per hour .	83	1200.00	Rupees one thousand two hundred and paise zero only.	Per Hour	99600.00
					Total:-	99600
	Quoted rate in figures					
	Quoted rate in words					

  
**Executive Engineer,**  
Thalout Division  
HP.PWD Thalout



**SCHEDULE OF QUANTITY**

**Name of work:- RRD Bhatwari to Rensh road Km. 0/000 to 8/640 SH:- C/O crated B/wall from RD. 4/855 to 4/865.**

**Estimated Cost: 96,202.00**  
**Earnest Money :- 2000.00**  
**Time :- One Month**

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	36.67	213.45	Rs. Two hundred thirteen and paise forty five only	Per Cubic Metre	7826.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3584.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	27.37	3098.00	Rs. Three thousand niny eight and paise zero only	Per Cubic Metre	84792.00
					<b>Total</b>	<b>96202.00</b>
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
 Talout Division  
 HP, PWD, Talout

### SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli Kullu by pass road old NH-21 km 222/700 to 227/600 (SH:- Providing and supplying WBM Grade-Ill between RDS 222/700 to 223/500) Job No-2

Estimated cost:-98462.00
--------------------------

Earnest Money:-2000.00
------------------------

Time:-	One Month
--------	-----------

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Providing, laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per technical specification clause 405 by Mechanical means . within all leads , lifts,carriage of materials and other incidental complete.	38.00	2591.10	Rs. Two Thousand five hundred ninety one and paise ten only	Per Cubic metre	98462.00
Total in figures						98462.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Total in figures

Rate quoted by contractor +/-

Quoted rate in figure

Quoted rate in words

Executive Engineer,  
Thalout Division  
HP PWD Thalout.

# SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Balichowki Sub Division (SH: - Hiring of tipper for carriage of muck, debries etc. at various RDs in Balichowki section )

Estimated Cost:-98000.00

Earnest Money:- 2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condition of minimum 5.50 (Five point five zero) cubic metre carriage capacity on daily basis from 9.000 AM to 5.00PM with hydraulic facility for carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-Charge.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per day	98000.00
	<b>Conditions:-</b>					
	1) The cost of P.O.L will be borne by the contractor/owner of the vehicle/machine at this own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
	3) The daily log book will be maintained at site which should be daily verified by the Engineer-in-Charge.					
					Total	98000.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division  
HP PWD Thalout



Name of work:- RRD on various roads under Balichowki Sub Division (SH:- Hiring of tipper for carriage of muck, debries etc. at various RDs in Balichowki section )

Estimated Cost:-98000.00
Earnest Money:- 2000.00
Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

SCHEDULE OF QUANTITY	
1.	loader for removal of slips/debries/mucks etc. at RD 10/500 to 12/500.)

Estimated Cost:-99,600.00
Earnest Money: 2000.00

**Earnest Money:-2000.00**

Time:- One Month

No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures					Total 99600.00
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Chubhlu to Farsh road km 0/0 to 4/00 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc.. at various RDs). Job No-2

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout



# SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Balichowki Sub Division  
(SH:- Hiring of Tipper for carriage of muck debris etc. from various RD's of various roads under Balichowki Section)

Estimated Cost:- Rs. 98000.00  
Earnest Money :- Rs. 2000.00  
Time :- One Month

Sr. No.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of tipper in good condition of minimum 5.50 (Five point five zero) cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility, jack facility for carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	28	3500.00	Rupees Three thousand five hundred and paise zero only.	Per day	98000.00
	<b>Conditions:-</b>					
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost					
	3) The daily log book will be maintained at site which should be daily verified by the Engineer-in-Charge.					
					Total:-	98000.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division  
HP.PWD Thalout

### SCHEDULE OF QUANTITY

**SCHEDULE OF QUANTITY**

Name of work:-	RRD on various roads of Pandoh Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I) Job No-4

Estimated Cost:-99600.00
--------------------------

Earnest Money:-2000.00
------------------------

Time:- One Month

[illegible]

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

# SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 99600.00  
Earnest Money :- Rs. 2000.00  
Time :- One Month

Name of work:- RRD on Panjain Bai Chowki Thatta Tikki Shettadhar Ghat Tapnali Gadagushaini road (MDR-107) Km. 0/0 to 70/0  
(SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debries etc. at RD 8/0 to 16/0 )

Sr. No.	Description	Qty.	Figure	Words	Unit	Amount
1	Hiring of Excavator- cum- loader for removal of slips/ snow/ debries / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work at least 6 (Six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil/snow per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 (Twenty five) cubic metre per hour .	83	1200.00	Rupees one thousand two hundred and paise zero only.	Per Hour	99600.00
					Total:-	99600.00
	Quoted rate in figures					
	Quoted rate in words					

  
Executive Engineer,  
Thalout Division  
HP.PWD Thalout



# SCHEDULE OF QUANTITY

Name of work:- R.R.D. on road from Hatoun-Bhabas-Muthal km 0/000 to 7/000. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 3/500 to 7/000)

Estimated Cost:-99,600.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout

SCHEDULE OF QUANTITY
Name of work:- R.R.D. on Karthach to Koon road km 0/000 to 3/500. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.)

Estimated Cost:-99,600.00

**Earnest Money:-2000.00**

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

## Name \_\_\_\_\_

Estimated Cost:-	99980.00
Earnest Money:-	2000.00

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



**SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhatnagar to Baggi road Km. 0/00 to 2/00 (SH:- C/O R/wall in PCC 1:4:8 at RD. 0/092.50 to 2/095.)

Estimated Cost :- 90,079.00  
Earnest Money :- 2000.00  
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.26	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	2493.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.78	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	82081.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	1.88	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	2375.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	8	391.20	Rupees Three hundred ninety one and paise twenty only	Each	3130.00
<b>Total in figures</b>						<b>90079.00</b>
			Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout

**SCHEDULE OF QUANTITY**

Name of work:- R.R.D. on Kuklah to Baggi road km 0/00 to 8/00. (SH:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/00 to 4/00.)

Estimated Cost:-99,600.00
Earnest Money:-2000.00

00.00

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



SCHEDULE OF QUANTITY	
Name of work:-	RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I) Job No-5

Estimated Cost:-99600.00
--------------------------

Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



**SCHEDULE OF QUANTITY**

Name of work:- R.R.D. on Kholanal to Koon road km 0/000 to 3/500. (SH:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.)	No.	Description	Unit	Quantity
	1	Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.	No.	1

**Estimated Cost:-99,600.00**

Earnest Money:-2000.00
------------------------

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation on a staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

NAME OF WORK	DATE OF COMPLETION	REMARKS
Maintenance of Four Laining of End Pandoh bypass to akoli Kullu Section of NH-21 Km 222/700 to 227/600 (SH: - Earthwork in filling at 223/300 to 223/400) Job No-7		

Estimated Cost:-99980.00
Earnest Money:- 2000.00

Time:- One Month

[illegible]

SCHEDULE OF QUANTITY	
Name of work:-	
KRD on road from Burah to Panjain km 0/00 to 11/000 (SH:- Hiring of loader for removal of slips/debries/mucks etc at road side)	

to 1,000 (SH: - Hiring of excavator cum  
spades/mucks etc. at various RDs between KM 0/000 to 5/000).

Estimated Cost:-99600.00

**Earnest Money:-2000.00**

Time:- One Month

26



Name of work:- R.R.D. on road from Deod to Hatoun km 0/000 to 2/985. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.)

Earnest Money:-2000.00

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		

27

# SCHEDULE OF QUANTITY

Name of work:- RRD on road from Sudhrani to Ghat km 0/0 to 5/500 (SH:- Repair of Toe wall for existing slab culvert at RD 0/180).

Estimated Cost:- 98807.00  
Earnest Money :- 2000.00  
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying flooring laid over cement concrete bedding in rubble stone laid in cement mortar 1:3 including carriage of material with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.29	2267.90	Rs. Two thousand two hundred sixty seven and paise ninety only	Per Cubic Metre	27872.00
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	12.29	5771.80	Rs. Five Thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	70935.00
Total						98807.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP.PWD,Thalout.

Name of work:-	Description of work:-	Quantity
Maintenance of Four Laining of End Pandoh bypass to akoli Kullu Section of NH-21 Km 222/700 to 227/600 (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDS in Pandoh Section-I)		

Estimated Cost:-98000.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



### SCHEDULE OF QUANTITY

Name of work:- RRD on road from Burah to Panjain km 0/00 to 11/000 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs between KM 5/000 to 11/000).

Estimated Cost:-99600.00

Earnest Money:-2000.00

Time:- One Month

[illegible]

Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH:- C/o created R/wall at RD 4/480 to 4/485).

SCHEDULE OF QUANTITY

Estimated Cost: 88294.00  
Earnest Money :- 2000.00  
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	19.20	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7645.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	76290.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.45	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	4359.00
Total						88294.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP, PWD, Thalout



Name of work:- R.R.D. on Kuklah to Baggi road km 0/000 to 8/000. (SH: - Hiring of excavator cum loader for removal of slips/debris/mucks etc. at RD 4/00 to 8/00.)

Estimated Cost:-99,600.00

**Earnest Money:-2000.00**

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



SCHEDULE OF QUANTITY	
Name of work:- R.R.D. on Dhingali to Gagan road km 0/0 to 6/000 (Sh:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	

33

SCHEDULE OF QUANTITY	
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

SCHEDULE OF QUANTITY	
Name of work:- RRD on various roads under Pandoh Sub Division (SH:- Hiring of tipper for carriage of muck, debries etc. at various RDs Pandoh Section-II ) Job No-2	

Estimated Cost:-98000.00

Earnest Money:-	2000.00
-----------------	---------

Time:- One Month

[illegible]

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

# SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs in Nagwain section) Job No.2

Estimated Cost:-98000.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Hiring of Tipper in good condition of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per dlection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	<b>Total</b>					<b>98000.00</b>
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH: - C/o created R/wall at RD 4/475 to 4/480).

SCHEDULE OF QUANTITY

S.No		Description of item		Quantity		Rate		Unit	Amount
				In figure	In word				
1		Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.		19.25	398.20	Rs. Three hundred ninety eight and paise twenty only		Per Cubic Metre	7665.00
2		Providing and laying of Boulder upon laid in wire crates with 4 mm (four millimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred millimetre) mesh (woven diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.		23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only		Per Cubic Metre	76290.00
3		Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.		3.45	1263.40	Rs. One thousand two hundred sixty three and paise forty only		Per Cubic Metre	4359.00
		Total							88314.00
		Quoted rate in figure							
		Quoted rate in words							

Executive Engineer,  
Thalout Division ,  
HP, PWD, Thalout

Executive Engineer,  
Thalout Division,  
HP,PWD,Thalout

# **SCHEDULE OF QUANTITY**

Name of work: P.R.D. on Keshimbhitar to Badaburned road km 8/800 to 3/500. (3pc. - widening of excavator cum loader for removal of slips/debris/muck etc. at various PDCs.)

Estimated Cost: Rs. 800.00  
 Estimated Money: 2000.00

Time: One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Months		
1	Hiring of Excavator-cum-loader for removal of snow/slip/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unremovable material materials from the road surface upto any leads and lifts in emergent cases and when required or as per direction of Engineer-in-charge The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/oil, charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand and paise zero only	Per hour	99600.00
	Quoted rate in figures				Total	99600.00
	Quoted rate in words					

Executive Engineer,  
 Road Division,  
 MP PWD Thakur.

Name of work:- RRD on Chamrajani to Sansoi road km 0/0 to 2/00 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS). Job No-2

Estimated Cost:-99600.00

Earnest Money:-2000.00

Time:- One Month

[illegible]

Executive Engineer  
Thalout Division,  
HP PWD Thalout.



SCHEDULE OF QUANTITY	
Name of work:- R.R.D. on Thatta to Samlwas road km 0/0 to 12/00 under Balichowki Sub division (SH:- Hiring of excavator cum loader for removal of slips and road side unlined surface drain) Job No 2	

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Takoli Bhamsoi to Bhalther road km 0/0 to 4/00 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs), Job No-2

loader for removal of slips/clearance of berms, debris etc. at various RDSs). Job No-2

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



# SCHEDULE OF QUANTITY

Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH: - C/o created R/wall at RD 4/585 to 4/590).

Estimated Cost: 88251.00  
Earnest Money :- 2000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	19.25	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7665.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four millimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred millimetre) mesh (woven) diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	76290.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.40	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	4296.00
Total						88251.00
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,  
Thalout Division ,  
HP, PWD, Thalout



SCHEDULE OF QUANTITY	
Name of work:- R.R.D. on Baggi to Kashimblidhar road km 0/000 to 3/000. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.)	

SCHEDULE OF QUANTITY	
Name of work:- R.R.D. on Baggi to Kashimblidhar road km 0/00 to 3/000. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs.)	

Estimated Cost:-99,600.00

**Earnest Money:-2000.00**

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures					Total 99600.00
	Quoted rate in words					

Executive Engineer,  
Thalout Division  
HP PWD Thalout.

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

# SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain Section) Job No.2

Estimated Cost:-99600.00  
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



# SCHEDULE OF QUANTITY

Name of work:- RRD on road from Kihuan to Diddar Km. 0/0 to 6/00 (SH :- C/O R/wall at RD 2/787 to 2/789)

Estimated Cost:- 99,934.00  
Earnest Money :- 2000.00

Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305-1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.62	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3432.00
2	Providing and laying in position cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate) bedding of specified grade including shuttering complete within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.44	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	6337.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:4:8 (one cement four sand : eight graded stone aggregate 40mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	0.87	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	4256.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	9.93	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	51608.00
5	Construction of dry rubble stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.29	3751.20	Rupees Three thousand seven hundred fifty one and	Per Cubic Metre	31097.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	2.14	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	2704.00
<b>Total in figures</b>					<b>Total</b>	<b>99434.00</b>
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout




## SCHEDULE OF QUANTITY

**Name of work:- RRD on various roads of Panarsa Sub Division (SH:- Hiring of Tipper for carriage of muck/debris etc. at various RRs in Nagwain Section) Job No-2**

**Estimated Cost:- 98000.00**  
**Earnest Money:- 2000.00**  
**Time:- One Months**

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
	Hiring of Tipper for carriage of debris/ muck / unservicable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of Engineer-in-Charge (9.00 am to 5.00 pm ) <b>Terms and conditions:-</b> 1. The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge. 2. During working hours any type of accident the owner is responsible. 3. Driver will be provided by the owner.	28	3500.00	Rupees Three thousand five hundred only	Per day	98000.00
					<b>Total</b>	<b>98000.00</b>
	Quoted rate in figures					
	Quoted rate in words					

  
**Executive Engineer,**  
**Thalout Division,**  
**HP PWD Thalout**

## SCHEDULE OF QUANTITY

Name of work:- RRD on Sudhrani to Thatta road Km. 0/0 to 5/0  
 (SH:- Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RD's)

Estimated Cost:- Rs. 99600.00  
 Earnest Money :- Rs. 2000.00  
 Time :- Two Months

Sr. No.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator- cum- loader for removal of slips/ snow/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials. from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work at least 6 (Six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil/snow per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83	1200.00	Rupees one thousand two hundred and paise zero only.	Per Hour	99600.00
					Total:-	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
 Thaltout Division  
 HP, PWD Thaltout

SCHEDULE OF QUANTITY	
Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain Section) Job No 1	

Estimated Cost:-99600.00
Earnest Money:-2000.00

S. No.	Description of item	Qty.	Time:- One Month		Amount
			Rate in	Unit	

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



# SCHEDULE OF QUANTITY

Name of work:- RRD on road Khuhhan to Diddar km 0/0 to 6/00 (SH :- C/O R/wall at RD 2/791 to 2/793.)

Estimated Cost :- 99,397.00

Earnest Money :- 2000.00

Time :- One Month

Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.21	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3269.00
2	Providing and laying in position cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate) bedding of specified grade including shuttering complete within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.44	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	6337.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:4:8 (one cement four sand eight graded stone aggregate 40mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	0.87	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	4256.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Coursed rubble masonry in cement mortar 1:6 (one cement six sand) complete within all leads, lifts carriage of material and other incidentals. 2nd sort	9.93	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	51608.00
5	Construction of Randum Rubble dry stone masonry as per MORC specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.29	3751.20	Rs. Three thousand seven hundred fifty one and paise twenty	Per Cubic Metre	31097.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	2.24	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	2830.00
<b>Total in figures</b>					<b>Total</b>	<b>99397.00</b>
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,  
Thalout Division,  
HPPWD, Thalout.


**SCHEDULE OF QUANTITY**

**Name of work:- RRD on Bhatwari to Rensh road Km 0/00 to 8/640 (SH: - C/o created R/wall at RD 4/590 to 4/595).**

**Estimated Cost: 88268.00**  
**Earnest Money :- 2000.00**

**Time :- One Month**

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	19.20	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic	7645.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) percent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	23.44	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic	76290.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.43	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic	4333.00
	<b>Total</b>					<b>88268.00</b>

  
 Executive Engineer,  
 Thalout Division,  
 HP, PWD, Thalout