



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

**"NOTICE INVITING TENDERS"**


Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **29-12-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 27-12-2025 up to **4.00 P.M** and the application for issue of tender form shall be received on 27-12-2025 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Tamloh to Bharanta road (Under PDNA) (C/O Wire crate R/Wall at RD. 0/040 to 0/047050 & P/L Cement Concrete work in km. 0/750 to 0/872)	4,55,550/-	9100/-	Three month	350/-
2	Restoration of rain damages on Link road from Bharth to Tillu Mata via Narah Basti km. 0/0 to 2/0 (SH:- C/O Wire crate R/Wall in km. 0/680 to 0/687)	99,919/-	2000/-	Three month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh


No. PWD/BWD/TA/NIT/2025-26/


12369-78

Dated:- 22/12/2025

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-12369-78 dated: 22/12/2025.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Schedule of Quantity

Name of Work :- Restoration of rain damages on Tamloh to Bharanta road. (Under PDNA)

(SH:- Construction of Wire crate R/wall at RD 0/040 to 0/047.50 & P/L Cement Concrete work in Km. 0/750 to 0/872).


Estimated Cost :-Rs. 4,55,550/-

Earnest Money :-Rs. 9100/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) , upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	16.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4050.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS.280 and IS-4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	32.40	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	90720.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.08	700.00	Rupees Seven Hundred Only	Per Cubic metre	4256.00
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm( two hundred millimetes) thickness in every layers and compacted with three Wheel Road Roller 80-100 ( eighty-hundred ) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.98	80.00	Rupees Eighty Only	Per Cubic metre	798.00

5	Providing, laying, Soling 90 to 45mm ( Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	2000.00	Rupees Two Thousand Only	Per Cubic metre	4000.00
6	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	56.73	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	351726.00
<b>Total :-</b>						<b>455550.00</b>
	<b>Quoted rates percentage in figures</b>					
	<b>Quoted rates percentage in words</b>					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna


### Schedule of Quantity

Name of Work :- Restoration of rain damages on Link road from Bharath to Tillu Mata via Narah Basti Km 0/00 to 2/00 (SH:-  
C/o Wire crate R/wall in Km 0/680 to 0/687)

Estimate Cost :- Rs. 99,919/-  
Earnest Money :- Rs. 2000/-  
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	9.75	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	2438.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	32.34	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	90552.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.11	700.00	Rupees Seven Hundred Only	Per Cubic metre	6377.00

4	Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred milimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevent clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty GST and other incidentals necessary to complete the work in all respects.	6.90	80.00	Rupees Eighty Only	Per Cubic metre	552.00
<b>Total :-</b>						<b>99919.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna