



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-
To

17988-93

Dated:-17.01.2026

**The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.**

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,


Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.


Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **29.01.2026** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **28.01.2026** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **27.01.2026** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	A/R & M/O to Residential building at Baijnath (SH: P/F factory made shutter and Painting work etc.)	99,192/-	2,000/-	Rs.350/-	Two Months
2	A/R & M/O to Rest house at Baijnath (SH: Repair of cement plaster, Painting work & P/F curtains, Rubbing work & Providing and supplying of bed box with mattress)	99,566/-	2,000/-	Rs.350/-	Two Months
3	Restoration of Rain Damage on Gawal Tikker Maheshgarh Road km 0/00 to 3/380 (SH: Hiring of Hydraulic Excavator/Breaker/JCB cum loader for breaking of boulders along the road)	99,000/-	2,000/-	Rs.350/-	One Month
4	C/O Record room/store for Division Office Building HPPWD Baijnath (SH: Steel work in Rack)	91,806/-	1,900/-	Rs.350/-	One Month
5	Construction of Baijnath Chobin Balandar Road km 0/00 to 14/2/00 (SH: C/O R/wall at RD 9/780 to 9/785.60) Under OFC	98,145/-	2,000/-	Rs.350/-	Two Months
6	Repair and Maintenance of HP BOSE Book Distribution Centre Paprola at Taragarh (SH: Painting, Plastering, Plaster of patches, Brick masonry etc.)	79,865/-	1,600/-	Rs.350/-	One Month

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer
Baijnath Division
HP.PWD, Baijnath
For & On behalf of the Governor of H.P.

1

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O to Residential building at Baijnath (SH:- P/F factory made shutter and Painting work etc)						Estimate Cost: 99,192.00 Earnest Money:2,000.00 Time Limit : Two Months		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Finishing wall with weather proof exterior grade emulsion of approved design (Apocalluma) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	119.60	Per Sqm	105.00	Rupees One Hundred & Five Only	12558.00		
2	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (two coats) and a subsequent coat to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	135.93	Per square metre	60.00	Rupees Sixty Only	8,156.00		
3	Distemporing (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth on walls. Priming coat with distemper primer. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	258.36	Per square metre	90.00	Rupees Ninety Only	23,252.00		
4	Painting one coat (excluding priming coat) and a subsequent coat of paint on previously painted wood and wood based surfaces with readymixed paint other than white brushing to give an even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	200.51	Per Square metre	95.00	Rupees Ninety Five Only	19,048.00		
5	Painting one or more coat G.I sheet with ready mixed paint of approved brand and manufacture and other metal surfaces. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	128.67	Per Square metre	70.00	Rupees Seventy Only	9,007.00		
6	Painting one coat (excluding priming coat) and a subsequent coat of paint on previously painted steel and other metal surfaces with Enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	116.34	Each	98.00	Rupees Ninety Eight Only	11,401.00		
7	Providing and fixing factory made PVC door frame single rebate of any clours of size 50x47mm with a wall thickness of 5mm made out of extruded 5mm rigid PVC foam sheet heat bond & mitred at corners and joined with 2 Nos. of 150mm long brackets of 15mmx15mm M.S. square tube, the vertical door profiles to be reinforced with 19mmx19mm M.S. square tube of 19 gauge EPDM rubber gasket weather seal to be provided throughout the frame i/c fixing of door frame to wall with M.S. screws 100mm long with wooden or rawl plugs embedded in masonry complete as per manufactures specification & direction of Engineer-in-Charge. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	7.63	Rmt	460.00	Rupees Four Hundred & Sixty Only	3,510.00		
8	Providing and fixing factory made shutters of solid PVC foam Profile 30 mm thick complete in all manner and fittings in all respect. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, oll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	1.92	Per square metre	3000	Rupees Three Thousand Only	5,760.00		
9	Providing and fixing Gyser 15 Liter (Fifteen) complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time.	1.00	Each	6500.00	Rupees Six Thousand Five Hundred Only	6,500.00		
Quoted rates Percentage in figures						99,192.00		
Quoted rates Percentage in words								

Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

7

Name of work :- A/R & M/O to Rest house at Bajinath
(SH:- Repair of cement plaster, Painting work & P/E curtains, Rubbing work & supplying of bed box with mattress)

Estimate Cost: 99,566.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joint sand and final finish after thoroughly cleaning the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	5.13	Per Square metre	264.35	Rupees Two Hundred & Sixty Four - Paise Thirty Five Only	1356.00
2	Finishing wall with weather proof exterior grade emulsion of approved design (Apexulima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	296.69	Per Square metre	105.00	Rupees One Hundred & Five Only	31152.00
3	Painting one coat (excluding priming coat) and a subsequent coat of paint on previously painted wood and wood based surfaces with readymixed paint other than white brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	283.92	Per Square metre	80.00	Rupees Eighty Only	22,714.00
4	Painting one coat (excluding priming coat) and a subsequent coat of paint on previously painted steel and other metal surfaces with white Enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	56.85	Per Square metre	98.00	Rupees Ninety Eight Only	5,571.00
5	Rubbing and Polishing of old marble flooring work complete in all respect & direction of Engineer-in-Charge "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.55	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	5,273.00
6	Providing and fixing cotton curtains for door & windows of premium quality. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	21.00	Each	500.00	Rupees Five Hundred Only	10,500.00
7	Providing and supplying Double bed Box size 6' x 6' foot (wooden ply of approved brand & best quality) as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	15000.00	Rupees Fifteen Thousand Only	15,000.00
8	Providing and supplying bed mattress size 6' x 6' foot for double bed box of best quality and approved manufacturer as per entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	8000.00	Rupees Eight Thousand Only	8,000.00
Quoted rates Percentage in figures						99,566.00
Quoted rates Percentage in words						

Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Dams on Gawal Tikker Maheshgarh Road km 9/00 to 3/380 .
(SH:- Hiring of Hydraulic Excavator/Breaker/JCB cum loader for breaking of boulders along the road .)

Estimated Cost:-	Rs 99,000.00
Earnest Money:-	Rs 2,000.00

③

SR. No.	Description of work	No. or Qty.	Unit	Time		Amount Rs. P
				One Month	Rate	
1	Hiring of Hydraulic Excavator cum Breaker to be deployed dressing of road side katcha drain and removal of slips Debris etc Including cost of fuel oil lubricants wages of operating staff The fuel and operational staff for Excavator/Breaker shall be borne by the contractor/ owner. Shifting of Machinery from one place to other place will be absolute responsibility of contractor. Earth Cutting in all kind of soil including loading into tipper/ truck The daily log book will be maintained at site which should be duly verified by the Engineer in charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	45.00	Per hour	2200.00	Rs. Twenty Two hundred only	99000.00
	Quoted rates Percentage in figures					99000.00
	Quoted rates Percentage in words					

Executive Engineer
Bainnath Division
HPPWD Bainnath

(4)

SCHEDULE OF QUANTITY

Name of Work : C/O Record room / Store for Division office bldg HPPWD Bajinath
(sh:- Steel work in Rack)

Estimate Cost: 91,806.00
Earnest Money: 1,900.00
Time Limit : One Month

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	243.60	Per kilogram	95.00	Rupees Ninety Five Only	23,142.00
2	Painting two or more coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	77.90	Per square metre	98.00	Rupees Ninety Eight Only	7,634.00
3	Providing and fixing aluminium wire mesh as per PWD specification. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	96.85	Per square metre	538.00	Rupees Five Hundred & Thirty Eight Only	52,105.00
4	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x10mm (two hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	21.00	Each	275.00	Rupees Two Hundred & Seventy Five Only	5,775.00
5	Providing and fixing anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete. 125mm (one hundred twenty five millimeter) size. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	21.00	Each	150.00	Rupees One Hundred & Fifty Only	3,150.00
	Quoted rates Percentage in figures					91,806.00
	Quoted rates Percentage in words					

Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of work : Construction of Bajinath Chobin Balandar Road km 0/00 to 14/2/00.
(SH: C/O R/wall at RD 9/780 to 9/785.60) under OFC .

Estimate Cost:98,145.00/- Earnest Money:2,000.00/- Time Limit : Two Months							
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including, setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.82	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,688.00	
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge . including carriage of material within all leads and lifts and other incidentals . "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	18.48	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	91,476.00	
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.86	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	3,821.00	
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	4.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,160.00	
Quoted rates Percentage in figures							
Quoted rates Percentage in words							
Total						98,145.00	


 Executive Engineer
 Bajinath Division
 HPPWID Bajinath

6(9)

SCHEDULE OF QUANTITY


Name of Work:- Repair and Maintenance of HP BOSE book distribution centre Paprola at Taragarh .
(SH:- Painting , Plastering , plaster of patches , Brick masonry etc

Estimate Cost: 79,865.00
Earnest Money: 1,600.00
Time Limit : One Month

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Painting one coat (excluding priming coat) and a subsequent coat of paint on previously painted steel and other metal surfaces with Enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	35.78	Per square metre	95.00	Rupees Ninety Five Only	3,399.00
2	Applying tera cota /cement paint specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	29.05	Per square metre	80.00	Rupees Eighty Only	2,324.00
3	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.81	Per cubic metre	7,500.00	Rupees Seven Thousand Five Hundred Only	13,575.00
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundations and plinth in cement mortar 1:4 (one cement : four coarse sand) "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.51	Per square metre	655.90	Rupees Six Hundred & Fifty Five - Paise Ninety Only	2,302.00
5	15 mm (Fifteen) cement plaster in single coat on rough side of brick/ stone masonry for interior plastering upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	7.02	Per square metre	240.00	Rupees Two Hundred & Forty Only	1,685.00
6	White washing with lime on undecorated wall surfaces two coats to give an even shade including thoroughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	21.06	Per square metre	4.75	Rupees Four - Paise Seventy Five Only	100.00
7	24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59x24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 20x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of "H" section, a uPVC hollow section of size 100x24 mm and 2 mm (± 0.2 mm) wall thickness, fixed to the shutter styles by means of plastic/galvanised M.S. "U" cleats. The shutter frame filled with a uPVC multi chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge. (For W.C. and bathroom door shutter). "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.90	Per square metre	1632.15	Rupees One Thousand Six Hundred & Thirty Two - Paise Fifteen Only	3,101.00
8	Providing and fixing 300x16mm (three hundred by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	275.00	Rupees Two Hundred & Seventy Five Only	275.00

(66)

9	Providing and fixing 200x16 mm (two hundred fifty by sixteen millimeter) Size steel sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.0	Each	150.95	Rupees One Hundred & Fifty - Paise Ninety Five Only	151.00
10	Providing and fixing 10 (ten) litres net capacity PTMT Coloured / white automatic flushing cistern with a pair of PVC / C.I. or M.S. bracket complete with fittings including PVC syphonic apparatus, mosquito proof lid, PVC union and coupling for connections with inlet, outlet and over flow pipes including cutting holes and making good the same (over flow pipe to be measured and paid for separately) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	1,185.25	Rupees One Thousand One Hundred & Eighty Five - Paise Twenty Five Only	1,185.00
11	Providing and fixing of jet pressure of ESS-ESS / Cera / Hindware for European seat with one meter tube of approved brand and manufacture, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	325.00	Rupees Three Hundred & Twenty Five Only	325.00
12	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.14	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	973.00
13	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. 60 mm "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	36.05	Per Square metre	1400.00	Rupees One Thousand Four Hundred Only	50470.00
Total:						79865.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath