



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**


Scaled percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **06-01-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 05-01-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 05-01-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Parour Chellian Dholt Gadiara Dharot road (Under PDNA) (C/O Wire crate R/Wall at RD. 0/125 to 0/150)	3,58,388/-	7200/-	Three month	350/-
2	Restoration of rain damages on Darang Khas to Bhrankhar road km. 0/00 to 2/400 (SH:- C/O Brest wall at RD. 1/400 to 1/410)	98,515/-	2000/-	Three month	350/-
3	A/R & M/O Bhilla Sarghooni road km. 0/0 to 4/185, Balakrupi Duhak Dhaniara road km. 1/400 to 6/800, Kona Pihri Nahllian road km. 0/0 to 5/0, Thural to Bachhwai road km. 0/0 to 6/195 and Santoshi Mata Malander to Gharthoon road km. 0/0 to 7/0 (SH:- Painting of Boards & Writing of letters etc)	99,970/-	2000/-	Three month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna  
On behalf of Governor of Himachal Pradesh

No. PWD/BWD/TA/NIT/2025-26/ **12539-48**

Dated:- **31/12/2025**

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-12539-48 dated 31-12-2025.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Schedule of Quantity


Name of Work :- Restoration of rain damages on Parour Chellian Dholt Gadiara Dharot road (Under PDNA). (SH:- C/o Wire crate Retaining wall at RD/1125 to 0/150).

Estimated Cost :-Rs. 3,58,388/-

Earnest Money :-Rs. 7200/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	30.75	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	7688.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (One Hundred millimetre into One Hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	117.00	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	327600.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33.00	700.00	Rupees Seven Hundred Only	Per Cubic metre	23100.00
<b>Total :-</b>						<b>358388.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity


Name of Work :- Restoration of rain damages on Darang Khas to Bhrankhar road Km 0/00 to 2/400. (SH:-C/o Breast wall at RD 1/400 to 1/410).

Estimated Cost :-Rs. 98,515/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.70	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4675.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer –in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.30	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	91590.00
3	Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9	250.00	Rupees Two Hundred Fifty Only	Each	2250.00
<b>Total :-</b>						<b>98515.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity


Name of Work :- A/R & M/O Bhillia Sarghooni road Km 0/0 to 4/185, Balakrupi Duhak Dhaniara road Km 1/400 to 6/800, Kona Pihri Nahllian road Km 0/0 to 5/0, Thural to Bachhwai road Km 0/0 to 6/195 and Santoshi Mata Malander to Gharthoon road Km 0/0 to 7/0.  
(SW:- Painting of Boards & Writing of Letters etc).

Estimated Cost :- Rs. 99,970/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches including carriage of materials within all leads, lifts, and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.96	6.00	Rupees Six Only	Per Square Metre	402.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	66.96	60.00	Rupees Sixty Only	Per Square Metre	4018.00
3	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	120.00	65.00	Rupees Sixty Five Only	Per Square Metre	7800.00
4	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.					
i)	Block letters/figures	19000.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	42750.00
ii)	Indian(letters/figures)	20000.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	45000.00
<b>Total :-</b>						<b>99970.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer,  
 Bhawarna Division,  
 HPPWD Bhawarna