



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"


Scaled percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **31-01-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 30-01-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 30-01-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O Various roads under HPPWD Sub Division Dheera (SH:- Supplying and stacking CC2001002000 Quick lime)	98,750/-	2000/-	Three month	350/-
2	A/R & M/O Parour Dheera Naura upto Purba road km. 10/0 to 17/00 (SH:- C/O Unlined drain & Maintenance of earthen shoulder at various RDs)	99,510/-	2000/-	Three month	350/-
3	A/R & M/O Dagchain Bangali Trutibat Jhareth Kanya Devi road km. 0/0 to 10/00 (SH:- C/O Unlined drain & Maintenance of earthen shoulder at various RDs)	98,612/-	2000/-	Three month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.



Executive Engineer
Bhawarna Division
HPPWD Bhawarna
On behalf of Governor of Himachal Pradesh

No. PWD/BWD/TA/NIT/2025-26/ **13750-59**

Dated:- **22/01/2026**

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-13750-59 dated 22/01-2026.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Work :- A/R & M/O various roads under HPPWD Sub-Division Dheera. (SH:- Supplying and stacking CC2001002000 Quick lime).

Estimated Cost :-Rs. 98,750/-
Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Supplying and stacking CC2001002000 Quick lime corresponding to class A as per specifications 712 as amended in polythene based gunny bags of 50 Kg (Fifty Kilogram) containing total calcium Magnesium oxide 70% (seventy percent) for construction works (25 Km (Twenty five kilogram) pack each bag complete as per the direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental. The rate is including octrai, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3950.00	25.00	Rupees Twenty Five Only	Per Kilogram	98750.00
Total :-						98750.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Bhawanya Division
HP PWD Bhawanya

Schedule of Quantity

Name of work:- A/R & M/O Parour Dheera Naura Upto Purba road Km 0/00 to 17/00. (SH:- C/o Unlined Drain & Maintenance of Earthen Shoulder at Various RD).

**Estimate Cost :-Rs. 99,510/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Months**

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	930.00	50.00	Rupees Fifty Only	Per Running Metre	46500.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1395.00	38.00	Rupees Thirty Eight Only	Per Square Metre	53010.00
Total :-						99510.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of work:- A/R & M/O Daghain Bangali Trutibat Khateen Jharath Kanya Devi road Km 0/0 to 10/00. (SH:- C/o Unlined Drain & Maintenance of Earthen Shoulder at Various RD).

Estimate Cost :-Rs. 98,612/-
Earnest Money :-Rs.2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	890.00	50.00	Rupees Fifty Only	Per Running Metre	44500.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1424.00	38.00	Rupees Thirty Eight Only	Per Square Metre	54112.00
Total :-						98612.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhatnagar