



Office of
Executive Engineer HP.PWD. Division Baijnath
Himachal Pradesh Public Works Department
Phone No. 01894-263035 E-Mail:- ee-baij-hp@nic.in

“ Corrigendum “

The tenders called vide this office NIT No. **PWD/BD/TA/NIT/2025-26/17988-93** dated **17.01.2026** published in web site of “Public works Department Government of Himachal Pradesh” for the work appearing at Sr. No. 5 “Construction of Baijnath Chobin Balander Road km 0/00 to 14/2/00 (SH: C/O R/wall at RD 9/780 to 9/785.60) Under OFC Estimated Cost. Rs.98,145/- Earnest Money Rs.2,000/- and Time limit Two Months may be read as “**Restoration/Reconstruction of Baijnath Chobin Balander Road km 0/00 to 14/2/00 (SH: C/O R/wall at RD 9/785.60 to 9/795.60)**” Estimated cost Rs.98,145/- Earnest Money Rs.2,000/- Time Limit Two Months.

Other terms and conditions of the N.I.T. will remain un-changed.

Executive Engineer
Baijnath Division,
HP.PWD., Baijnath.

NO:-PWD/BD/TA/Corrigendum/2025-26/-

18542-47

Dated:-

27/1/26

Copy forwarded for information to:-

1. The Executive Engineer, (IT Cell), Nirman Bhawan Nigam Vihar, Shimla-2 for uploading the corrigendum on the departmental website.
2. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
3. All the Assistant Engineers working under this Division.
4. The Drawing Branch of this office.
5. Notice Board.

Executive Engineer,
Baijnath Division.,
H.P.WD., Baijnath.

SCHEDULE OF QUANTITY

Name of work : Restoration / Reconstruction of Baijnath Chobin Balandar Road km 0/00 to 14/2/00 .
(SH: C/O R/wall at RD 9/785.60 to 9/795.60) .

Estimate Cost: 98,145.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer. In - Charge, including setting out, construction of shoring and bracing . removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.82	Per Cum	290 00	Rupees Two Hundred & Ninety Only	1,688 00
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge . including carriage of material within all leads and lifts and other incidentals... "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	18.48	Per Cum	4950 00	Rupees Four Thousand Nine Hundred & Fifty Only	91,476 00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.86	Per Cum	990 00	Rupees Nine Hundred & Ninety Only	3,821 00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	4.00	Each	290 00	Rupees Two Hundred & Ninety Only	1,160 00
Total						98,145.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						


 Executive Engineer
 Baijnath Division
 HPPWD Baijnath