

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-
To,

12006-14

Dated:- 21/01/2026


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 02.02.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 03.02.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 04.02.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 04.02.2026 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.


Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1.	Repair of Restoration of Rain damages on Barot Sanourth road Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 2/850 to 2/883.50)	Rs. 95,521/-	Rs.2000/-	One month	350/-	Class D&C
2.	Repair of Restoration of rain damages on Barot Sarela road at RD 1/720 to 1/778 Under SDF (D.C. Deposit) (SH:- Construction of P.C.C Retaining wall at RD 1/720 to 1/745) (RHS)	Rs. 94,771/-	Rs.1900/-	One month	350/-	Class D&C
3.	Repair of Restoration of rain damages on MTN Lohara to Manoh Sihal road RD 0/350 to 0/370 Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall at RD 0/350 to 0/360 LHS)	Rs. 94,501/-	Rs.1900/-	One month	350/-	Class D&C
4.	Repair of Restoration of rain damages on Shaheed Ashok Kumar road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 0/130 to 0/144.50)	Rs.94,248/-	Rs.1900/-	One month	350/-	Class D&C
5.	Repair of Restoration of rain damages on Hara Mandhot road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 3/925 to 3/935)	Rs.94,446/-	Rs.1900/-	One month	350/-	Class D&C
6.	Repair of Restoration of rain damages on Barot Hourri Devi via Kherian road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 4/170 to 4/173.50)	Rs.94,837/-	Rs.1900/-	One month	350/-	Class D&C
7.	Repair of Restoration of rain damages on Hatli Mohli road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 0/150 to 0/160)	Rs.94,347/-	Rs.1900/-	One month	350/-	Class D&C
8.	Repair of Restoration of rain damages on Bhatoli Malhanta Kafnali Nangal road Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain at RD 1/750 to 1/820 LHS)	Rs.93,994/-	Rs.1900/-	One month	350/-	Class D&C
9.	R/O Restoration of rain damages on Dehra Jawali Raja Ka Talab road Km. 79/00 to 81/00 Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain km. 80/866 to 80/876.50)	Rs.94,763/-	Rs.1900/-	One month	350/-	Class D&C
10.	Stock Storage under HPPWD Division Fatehpur (SH:- Providing and Fixing Road Sign Board)	Rs.92,250/-	Rs.1900/-	One month	350/-	Class D&C
11.	R/O Restoration of rain damages on Dehra Jawali Raja Ka Talab road Km. 79/00 to 81/00 Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain km. 80/878 to 80/888.50)	Rs.94,763/-	Rs.1900/-	One month	350/-	Class D&C
12.	A/R & M/O to various roads Under Rehan Sub Division HPPWD Rehan (SH:- Painting Lettering on road sign boards and Km. stones etc.) (Raja- Ka-Talab Section.)	Rs.99,891/-	Rs.2000/-	One month	350/-	Class D&C
13.	Stock Storage under Sub-Division Fatehpur HPPWD Fatehpur (SH:- Manufacturing and Supply of Informatory & village sign board). Job-II	Rs.94,509/-	Rs.1900/-	One month	350/-	Class D&C

14.	Balance work for Restoration of Rain Damages on road from Jagir Chowk to Sathana Shah Nehar Barrage road Under SDF (D.C. Deposit) (SH:- Providing and laying Interlocking paver block at R.D. 0/020 to 0/041).	Rs.94,986/-	Rs.1900/-	One month	350/-	Class D&C
15.	Stock Storage under HPPWD Division Fatehpur (SH:- Providing and Fixing Road Sign Board)	Rs.92,400/-	Rs.1900/-	One month	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of Rain damages on Barot Sanourth road Under SDF (D.C.Deposit)
(SH:- Providing and laying Cement Concrete Pavement at RD 2/850 to 2/883.50)

Estimated cost:- Rs.95521/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.59 Cubic meter.	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per cubic meter	95521.00
					Total:-	95521.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Mangra

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Barot Sarela road at RD 1/720 to 1/778 Under SDF (D.C. Deposit) (SH:- Construction of P.C.C Retaining wall at RD 1/720 to 1/745) (RHS)

Estimated cost:- Rs.94771/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	9.75 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3310.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.00 cubic meter	3390.80	Rupees Three Thousand Three Hundred Ninety And Paise Eighty Only	Per cubic meter	88161.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	3300.00
					Total:-	94771.00

Amount quoted by the contractor in % Above/Below

Executive Engineer

Fatehpur Division HPPWD
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on MTN Lohara to Manoh Sihla road RD 0/350 to 0/370 Under SDF (D.C.Deposit) (SH:- Construction of Retaining wall at RD 0/350 to 0/360 LHS)

Estimated cost:- Rs.94501/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In- Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.90 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3022.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.20 cubic meter	3390.80	Rupees Three Thousand Three Hundred Ninety And Paise Eighty Only	Per cubic meter	88839.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	2640.00
					Total:-	94501.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
Fatehpur Division, HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Shaheed Ashok Kumar road Under SDF (D.C. Deposit)
(SH):- Construction of P.C.C. Retaining wall at RD 0/130 to 0/144.50)

Estimated cost:- Rs.94248/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In- Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.75 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3989.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.23 cubic meter	3420.50	Rupees Three Thousand Four Hundred Twenty And Paise Fifty Only	Per cubic meter	86299.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	3960.00
					Total:-	94248.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
P.W.D. Division H.P.P.W.D.
Patalkot Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Hara Mandhot road Under SDF (D.C. Deposit)
(SH):- Construction of P.C.C. Retaining wall at RD 3/925 to 3/935)

Estimated cost:- Rs.94446/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.80 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2988.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.20 cubic meter	3390.00	Rupees Three Thousand Three Hundred Ninety Only	Per cubic meter	88818.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	2640.00
					Total:-	94446.00
	Amount quoted by the contractor in % Above/Below					



Executive Engineer
Patelpur Division HPPWD
Patelpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Barot Houra Devi via Kherian road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 4/170 to 4/173.50)

Estimated cost:- Rs.94837/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In- Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	12.25 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4159.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.97 cubic meter	3390.00	Rupees Three Thousand Three Hundred Ninety Only	Per cubic meter	88038.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	2640.00
					Total:-	94837.00
	Amount quoted by the contractor in % Above/Below					



Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Nongra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Hatli Mohli road Under SDF (D.C. Deposit) (SH:- Construction of P.C.C. Retaining wall at RD 0/150 to 0/160)

Estimated cost:- Rs.94347/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.51 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2889.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.20 cubic meter	3390.00	Rupees Three Thousand Three Hundred Ninety Only	Per cubic meter	88818.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	2640.00
					Total:-	94347.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPW
Panchajanya Distt. Kangra (A)

SCHEDULE OF QUANTITY

Name of work:- Repair of Restoration of rain damages on Bhatoli Malhanta Kafnali Nangal road Under SDF (D.C. Deposit) (SH):-
Construction of U-shape drain at RD 1/750 to 1/820 LHS)

Estimated cost:- Rs.93994/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	23.80 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	8080.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	19.57 cubic meter	4390.10	Rupees Four Thousand Three Hundred Ninety And Paise Ten Only	Per cubic meter	85914.00
					Total:-	93994.00
Amount quoted by the contractor in % Above/Below						


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- R/O Restoration of rain damages on Dehra Jawali Raja Ka Talab road Km. 79/00 to 81/00 Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain km. 80/866 to 80/876.50)				Estimated cost:- Rs.94763/- only		
				Earnest Money : Rs.1900/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	21.95 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	7452.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.29 Cubic meter.	4380.10	Rupees Four Thousand Three Hundred Eighty And Paise Ten Only	Per cubic meter	53831.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.40 cubic meter	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	13080.00
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto any floor level as per the direction of the Engineer-in-charge including carriage of materials. The rate are including of octrai, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	240.00 Kilogra mme	85.00	Rupees Eighty Five Only	Per kilogra mme	20400.00
					Total:-	94763.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HP
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Stock storage under HPPWD Division Fatehpur (SH:- Providing and fixing Road Sign Board).

					Estimated cost:- Rs.92250/- only	
					Earnest Money : Rs.1900/- only	
					Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Manufacturing and supplying of Retro reflective hazard sign Boards of size 300x900mm(Three hundred into nine hundred millimeter) of 3.5mm (Three point five millimeter) thick A.C.P./1.59mm M.S. sheet printed in Yellow and Black strips fitted on frame of M.S. angle 25x25mm with leg of 47mm (Forty Seven millimeters) M>S square pipe 1.20m (One Point Two meter) overall height painted black and white strips as per approved drawing & technical specification and directions of Engineer-in-Charge. The rates including Royalty, Malakna, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	15.00 Numbers	6150.00	Rupees six thousand one hundred fifty and paise zero	Each	92250.00
					Total:-	92250.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- R/O Restoration of rain damages on Dehra Jawali Raja Ka Talab road Km. 79/00 to 81/00 Under SDF (D.C.Deposit) (SH:- Construction of U-shape drain km. 80/878 to 80/888.50)							Estimated cost:- Rs.94763/- only	
							Earnest Money : Rs.1900/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In- Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	21.95 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	7452.00		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.29 Cubic meter.	4380.10	Rupees Four Thousand Three Hundred Eighty And Paise Ten Only	Per cubic meter	53831.00		
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.40 cubic meter	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	13080.00		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto any floor level as per the direction of the Engineer-in-charge including carriage of materials. The rate are including of octrai, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	240.00 Kilogra mme	85.00	Rupees Eighty Five Only	Per kilogra mme	20400.00		
					Total:-	94763.00		
Amount quoted by the contractor in % Above/Below								

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads Under Rehan Sub Division HPPWD Rehan (SH:- Painting Lettering on road sign boards and Km. stones etc.) (Raja- Ka- Talab Section.)									
Estimated Cost:- Rs.									
Earnest Money:- Rs.									
Time limit:- Tne Months									
Sr. No.	Description of items	Quantity	Rate		Unit	Amount.			
			In words	In figures					
1	Painting steel work with Deluxe Multi Surface paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sam (Zero point nine zero litre/ten square meter) over an under coat of primer @ 0.80 ltr./10 sqm (Zero point eight zero litre/ ten square meter) of approved bran and manufacture as required including carriage of material with in all leads and lifts. The rate Including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	45.00	99.20	Rupees Ninety Nine And Paise Twenty Only	Per square metre	4464.00			
2	Painting one coat (exculding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint of approved brands and manufacturing for use on floor to give and even shade including cleaning the surface of all dirt dust and other foreign matter and sand papering as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	40.00	95.30	Rupees Ninety Five And Paise Thirty Only	Per square metre	3812.00			
3	Writing letters of figures on any surface with black japan paint (Stop commas, hyphens and like not to be measured and paid separately)								
	(a) Indian Letter/Figure.	15900.00	3.30	Rupees Three And Paise Thirty Only	Per letter Per centi metre Height	52470.00			
	(b) Block letter/Figure.	11600.00	3.20	Rupees Three And Paise Twenty Only	Per letter Per centi metre Height	37120.00			
4	Painting index hand normal size or arrows (up to 40cm) long on any surfaces either black japan paint including carriage of material with in all leads & lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	30.00	67.50	Rupees Sixty Seven And Paise Fifty Only	Per Figure	2025.00			
					Total:-	99891.00			
	Amount quoted by the contractor in % Above/Below								

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of Work:- Stock Storage under Sub-Division Fatehpur HPPWD Fatehpur (SH:- Manufacturing and Supply of Informatory & village sign board). Job-II				Estimated Cost:- Rs.94509/- only	
				Earnest Money:- Rs.1900/- only	
				Time limit:- One Month	
Sr. No.	Description of items	Quantity	Rate		Amount.
			In words	In figures.	
1	Manufacturing and supplying informatory sign boards size 1200x900mm (One thousand two hundred into nine hundred millimetre) as per IRC-67 made of 1.59mm thick MS sheets vide clause 1701.2.3 with exceeding 0.9 sqm. supported on 40mm dia M.S. pipe height 2435mm, painted with red lead primer as per approved drawing an technical specification clause 1701 Including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15 Numbers	5230.40	Rupees Five Thousand Two Hundred Thirty and paise forty only.	78456.00
2	Manufacturing and supplying of village boards of size 600x450mm (six hundred into four hundred fifty millimeter) made of M.S. sheet of 16 (sixteen) guage with anble iron stand 45x45x6mm(forty five into forty five into six millimeter) height of 2.4 meters long with priming coat and as directed by the Engineer-in-charge including carriage of material with all leads and lifts. The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5 Numbers	3210.50	Rupees Three thousand Two hundred Ten and paise Fifty only.	16053.00
				Total:-	94509.00
Amount quoted by the contractor in % Above/Below					


 Engineer
 Fatehpur Division HPPWD
 Fatehpur Dist. Kangra (P.P.)

SCHEDULE OF QUANTITY


Name of work:- Balance work for Restoration of Rain Damages on road from Jagir Chowk to Sathana Shah Nehar Barrage road Under Estimated cost:- Rs.94986/- only
 SDRF Deposit work (SH):- Providing and laying Interlocking paver block at R.D. 0/020 to 0/041). Earnest Money : Rs.1900/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.06 Cubic meter.	3980.10	Rupees Three Thousand Nine Hundred Eighty And Paise Ten Only	Per cubic meter	12179.00
2	Providing and laying of interlocking concrete block pavement having thickness 80mm (eighty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	72.00 Square meter	1150.10	Rupees One Thousand One Hundred Fifty And Paise Ten Only	Per Square meter.	82807.00
					Total:-	94986.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt, Kangra (HP)

SCHEDULE OF QUANTITY

Name of work:- Stock storage under HPPWD Division Fatehpur (SH:- Providing and fixing Road Sign Board).					Estimated cost:- Rs.92400/- only		
					Earnest Money : Rs.1900/- only		
					Time limit:- one month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing and supplying of retro reflective cautionary board of size 600x600mm (six hundred into six hundred millimeter) of 3.5mm (Three point five millimeter) thick A.C.P. sheet fitted on a frame of M.S. angle 25x25mm (twenty five into twenty five millimeter) of 47mm (forty seven millimeter) M.S. square pipe height 3.00m (Three meter) overall height painted black and white strips as per approved drawing & technical specification and directions of Engineer-in-Charge. The rates including Royalty, Malakna, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	14.00 Numbers	6600.00	Rupees six thousand and six hundred and paise zero	Each	92400.00	
					Total:-	92400.00	
	Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Division HPPWD
 Fatehpur
 District Kangra (P.F.)