OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 9021-30 dated 27-01-2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **04.02.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **03.02.2026** up to **4:00 PM** and the application for issue of tender from shall be received on **01.02.2026** up to **4.00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75** days:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	C/O R/wall Near Bal Ashram saliana , Gadiara (SH:-C/O R/wall) **Deposit VKV/2024/1218)**	291185.00	5900.00	Two Month	350/-
2	C/O Concrete road from Simro Devi House road Batahan (SH:-C/O CC pavement leingth=23.00 Mtr.)) **Deposit SDF/2025/1193)**	74520.00	2000.00	Two Month	350/-
3	Balance work of R/O Jeepable road alongwith interlocking tile work from main road Guru Ravi Dass mandir ward No.4 Andretta (SH:-P/L soling and tile work in L =10.00 Mtrs) **Deposit SDF/2024/809)**	49216.00	1000.00	Two Month	350/-
4	C/O 1st floor Community Hall at Village Balu Ward No.1 G.P. Gadiara (SH:-C/O Structural steel for Truss work)) **Deposit MPLAD 2023/316**	98700.00	2000.00	Two Month	350/-
5	C/O road from Main road towards Urmila Devi House (Kangri) (SH:-F/C anf filling between Km 0/00 to 0/100) **Deposit SDF/2025/1190)**	74880.00	2000.00	Two Month	350/-
6	Restoration of rain Damages on Upper Lambagoan to Lahar road Km 0/00 to 3/300 (SH:-C/O Side Drain from RD 1/900 to 1/923)	96882.00	2000.00	Two Month	350/-
7	Restoration of rain damages on Link road From Mandh Khad Pul to Bari nadol (Bhoota Da Gaon) Km 0/00 to 3/500 (SH:-C/O 900 mm dia hume pipe culvert at RD 1/015)	99731.00	2000.00	Two month	350/-

-------Continued page- 2----

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works committments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur
On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 9021-30 **Dated:** 27/01/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
4-6. All the Assistant Engineer under this Division.
7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

(1)

SCHEDULE OF QUANTITY

Name of work :-C/O R/wall Near Ball Ashram saliana ,Gadiara (SH:-C/O R/wall) Deposit VKV/2024/1218)

Estimated cost Rs.	**291185.00**
Earnest Money Rs.	**5900.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	29.00	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	6525.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	71.60	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	275660.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	36.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	9000.00
	Total					**291185.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Concrete road from Simro Devi House road Batahan (SH:-C/O CC pavement leingth=23.00 Mtr.) **Deposit SDF/2025/1193)**

Estimated cost Rs.	**74520.00**
Earnest Money Rs.	**2000.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	6.90	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	8280.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.35	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	66240.00
	Total					**74520.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Balance work of R/O Jeepable road alongwith interlocking tile work from main road Guru Ravi Dass mandir ward No.4 Andretta (SH:-P/L soling and tile work in L =10.00 Mtrs) **Deposit SDF/2024/809)**	**Estimated cost Rs.**	**49216.00**
	Earnest Money Rs.	**1000.00**
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government.	3.10	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	3720.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.1	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	13020.00
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	0.24	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	1476.00

4	Providing and laying **80 mm thick** Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness **80mm (eighty millimetre)** as per drawings and Technical Specification Clause 1504 **(The execution of interlocking paver block shell be allowed after duly testing from the authorized labs)** and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	31.00	1000.00	Rupees One Thousand Only	Per square metre	31000.00
	Total					**49216.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O 1st floor Community Hall at Village Balu Ward No.1 G.P. Gadiara (SH:-C/O Structural steel for Truss work)) **Deposit MPLAD 2023/316**

Estimated cost Rs.	**98700.00**
Earnest Money Rs.	**2000.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat ofapproved steel primer all complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The Rate is inclusive of toll tax, GST and any other taxes imposed by the Government.	897.27	110.00	Rupees One Hundred Ten Only	Per Kilogram	98700.00
	Total					**98700.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O road from Main road towards Urmila Devi House (Kangri) (SH:-F/C and filling between Km 0/00 to 0/100) **Deposit SDF/2025/1190)**

Estimated cost Rs.	**74880.00**
Earnest Money Rs.	**2000.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	136.75	413.00	Rupees Four Hundred Thirteen Only	Per cubic metre	56478.00
2	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	92.01	200.00	Rupees Two Hundred Only	Per cubic Metre	18402.00
	Total					**74880.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Upper Lambagoan to Lahar road Km 0/00 to 3/300 (SH:- C/O Side Drain from RD 1/900 to 1/923)

Estimated cost Rs.	**96882.00**
Earnest Money Rs.	**2000.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	23.00	300.00	Rupees Three Hundred Only	Per cubic metre	6900.00

2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including	11.04	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	2760.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	16.56	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	81972.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	21.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5250.00
	Total					**96882.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Link road From Mandh Khad Pul to Bari nadol (Bhoota Da Gaon) Km 0/00 to 3/500 (SH:-C/O 900 mm dia hume pipe culvert at RD 1/015)

Estimated cost Rs.	**99731.00**
Earnest Money Rs.	**2000.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	30.36	240.00	Rupees Two Hundred Forty Only	Per cubic Metre	7286.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.00	3555.00	Rupees Three Thousand Five Hundred Fifty Five Only	Per cubic metre	3555.00

3	Providing and laying mechanically mixed and vibrated Plain/reinforced cement concrete in Sub structure as per drawing and MORTH technical specification section 1500, 1700, 2200 RCC Grade M-20 (M- twenty five) designed mix with cement contents not less than 344 kg. (Three hundred forty four) Kilogram per cubic meter with 40mm (forty millimeter) nominal size graded crushed stone aggregate and curing complete including cost of form work in abutment etcetra complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	10.44	6000.00	Rupees Six Thousand Only	Per cubic Metre	62640.00
4	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi,royality,Malkana, toll tax , or other taxes imposed by the Government.	7.50	3500.00	Rupees Three Thousand Five Hundred Only	Per Running metres	26250.00
	Total					**99731.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			**%**	
		Less (-)			**%**	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur