



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095 Phone No. 01894-228030

]

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 8593-8602 dated 17-01-2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

"NOTICE INVITING TENDERS"


Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **22.01.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **21.01.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **21.01.2026 up to 11.00 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	C/O Jeepable road Sapehad towards Bhoudi Sidh GP Suan (SH:- Improvement and formation cutting between km 0/00 to 0/100 and C/O R/wall, CC pavement at Km 0/00 to 0/100) Deposit MPLAD	4,99,645/-	10000/-	Two Month	350/-
2	Restoration of rain Damages on Ropri to Umber road Km 0/00 to 6/500 (SH:-C/O R/wall at Rd 6/050 to 6/070 (Under PDNA)	4,95,748/-	10000/-	Two Month	350/-
3	C/O Boundary wall to Protect the Shamshanghat Dodan Balli Bhuana (SH:- C/O crate work for the protection of road to Shamshanghat Dodan Balli) SDF/2024/972	99,999/-	2000/-	Two Month	350/-
4	C/o Keru Kelan to Kotlu road km. 0/000 to 1/550 including 40.00 mtr Span RCC Box Girder Bridge over Mandh Khad at RD 1/125(SH:-Painting & Weiting on Bridges, Bridges pedestal, crash Barrier, Rain shelters, Boards and Kilometers stones etc.)	99,848/-	2000/-	Two Month	350/-
5	Restoration of rain Damages on Khera Bhulla to Praga da Gallu road Km 0/00 to 16/330 (SH:-C/O B/wall in wire crate at Rd 9/831 to 8/836.50)	99,066/-	2000/-	Two Month	350/-
6	Restoration of rain damages on various roads under Balakrupi Sub Division(SH:-C/O unlined drain, maintenance of earthen Shoulders & cutting of brushes etc various roads under Gander Section)	99,515/-	2000/-	Two Month	350/-
7	Restoration of rain Damages on Khera Bhulla to Praga da Gallu road Km 0/00 to 16/330 (SH:-C/O B/wall in wire crate at Rd 9/825 to 9/830.50)	99,950/-	2000/-	Two Month	350/-
8	Construction of link road from Dhabhi to Kuthan KM 0/0 to 0/600 (SH:- C/O 4.00 meter span culvert at RD 0/550 alongwith approaches) SDP/ 2023/ 1424	4,98,788/-	10000/-	Two Month	350/-
9	Restoration of rain damages on Suan Bhodi Khajiar road KM 0/0 to 6/045 (SH:- C/O wing walls of 2.00meter span culvert at RD 0/270 towards Suan side under PDNA	3,16,847/-	6400/-	Two Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of (Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26-


8593-8602

Dated:

17/01/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-C/O Jeepable road sapehad towards Bhoudi Sidh GP Suan (SH:-Improvement and formation cutting between km 0/00 to 0/100 and C/O R/wall, CC pavement at Km 0/00 to 0/100) Deposit


Estimated cost Rs.	499645.00
Earnest Money Rs.	10000.00
Time Limits	Two Month

MPLAD

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 69.09 (sixty nine decimal zero nine) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	518.18	408.00	Rupees Four Hundred Eight Only	Per cubic metre	211417.00


2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.50	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	1013.00
3	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	11.16	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	42966.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1250.00

5	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	21.380	1200.00	Rupees One Thousand Two Hundred Only	Per cubic metre	25656.00
6	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	35.63	6100.00	Rupees Six Thousand One Hundred Only	Per Cubic Metre	217343.00
	Total					499645.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Ropri to Umber road Km 0/00 to 6/500 (SH:-C/O R/wall at Rd 6/050 to 6/070 (Under PDNA)				Estimated cost Rs.		495748.00
				Earnest Money Rs.		10000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25.88	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	5823.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	117.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic Metre	438750.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	40.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	10000.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	45.75	900.00	Rupees Nine Hundred Only	Per cubic metre	41175.00
	Total					495748.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-C/O Boundary wall to Protect the Shamshanghat Dodan Balli Bhuana (SH:-C/O crate work for the protection of road to Shamshanghat Dodan Balli) SDF/2024/972				Estimated cost Rs.		99999.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.20	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	2070.00
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	31.59	3100.00	Rupees Three Thousand One Hundred Only	Per cubic metre	97929.00
	Total					99999.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-C/O Keru Kelan to Kotlu road km. 0/000 to 1/550 including 40.00 mtr Span RCC Box Girder Bridge over Mandh Khad at RD 1/125(SH:-Painting & Weiting on Bridges, Bridges pedestal, crash Barrier, Rain shelters, Boards and Kilometers stones etc.)				Estimated cost Rs.		99848.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removing white or colour wash by scrapping , sand papering and preparing the surface smooth including necessary repairs to scratches ectera complete and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	59.40	12.80	Rupees Twelve And Paise Eighty Only	Per square metre	760.00
2	Painting steel work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr. (zero point nine zero liter /10 (ten) Per Square Metre. Over an under coat of primer applied @ 0.80 ltr (zero point eight)/ 10 (ten) Per Square Metre. of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	59.40	89.70	Rupees Eighty Nine And Paise Seventy Only	Per Square Metre	5328.00
3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With Water thinnable cement primer on wall surface having VOC content less than 50 grams/litre The rate is including octroi, royalty, Malkana, toll tax, GST or	264.56	48.62	Rupees Forty Eight And Paise Sixty Two Only	Per Square Metre	12863.00
4	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on concrete work.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	264.56	171.80	Rupees One Hundred Seventy One And Paise Eighty Only	Per Square Metre	45451.00
5	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface.and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	49.50	73.85	Rupees Seventy Three And Paise Eighty Five Only	Per Square Metre	3656.00


6	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, commas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer-in-Charge including hauling/hauling of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18700.00	1.70	Rupees One And Paise Seventy Only	Per letter per centimetre	31790.00
	Total					99848.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P. PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Shera Bhul'a to Praga da Gallu road Km 690 to 167350 (SE-C/O B'wall in wire area at RD 9831 to 8836.50)			Estimated cost Rs.		99066.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling & wedging out rocks (where blasting is prohibited) as per drawings and MCRB technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable & approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling of water (surface and sub soil water) upto any depth and any quantum of water including clearing of slush which may arise out during de-watering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.50	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2754.00
2	Providing and laying cement concrete 1:5:10 (One cement five sand ten graded crushed-broast stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.51	3850.00	Rupees Three Thousand Eight Hundred Only	Per cubic Metre	9538.00

3	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	25.51	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic metre	86734.00
	Total					99066.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain drainages on various roads under Jalainpur sub Division (SH-C/D utilised drain, maintenance of earthen Shoulders & cutting of brushes etc various roads under Canoe Section)			Estimated cost Rs.		99515.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Clearing and grubbing road land including grubbing with vegetation, grass, bushes, shrubs, saplings and trees of girth upto 500 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and raising of serviceable material to be used or stockpiled upto a bed of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 22.1 and as per direction by the Engineer-in-Charge. The rate is including cartage, royalty, GST, toll tax, or other taxes imposed by the Government.	0.45	42577.00	Rs. Forty Two Thousand Five Hundred Seventy Seven Only	Per Hectare	19150.00
2	Making up loss of material in irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at GMC upto a bed of 1000 m as per technical specification Clause 19.5 and as per directions of Engineer-in-Charge. Including cartage of material within all leads, lifts and other incidents and to the entire satisfaction of the Engineer-in-Charge. The rate is including cartage, royalty, GST, toll tax, or other taxes imposed by the Government.	480.00	56.00	Rs. Fifty Six Only	Per square metre	26880.00
3	Cost of utilised surface drains of average cross sectioned area 0.45 SQm in soil to specified lines grades level and dimensions, excavated material to be used in embankment within all leads and lifts as per technical specification clause 30.1 and as per direction by the Engineer-in-Charge. The rate is including cartage, royalty, GST, toll tax, or other taxes imposed by the Government.	575.00	53.00	Rs. Fifty Three Only	Per running metre	30475.00
Total						99515.00
Quoted Rate (in Figures) Percentage		Excess (-)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer
 Jalainpur Division
 HPPWD Jalainpur


SCHEDULE OF QUANTITY						
Name of work :- Restoration of rain Damages on Khara Bhuila to Praga Ga Ga road Km 650 to 16330 (SH-CGS Bhuila in wire cross at Rd 9425 to 9430.50)			Estimated cost Rs.		99950.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, broad walls, culverts, drains and parapet structure in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chipping & wedging out mass (where blasting is prohibited), as per drawings and MORD technical specification, class 3351 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of sludge and other objectionable materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated material & approved materials to the original surface in layers not exceeding 150mm one hundred (150 millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including clearing of silt which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including cartage, royalty, Malkata, toll tax, CST or other taxes imposed by the Government.	12.82	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2820.00
2	Providing and laying cement concrete 1:5:10 (One cement five sand ten graded crushed benben stone aggregate 40mm nominal size) and curing complete, excluding cost of kara work i.e. foundation and piling including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of cartage, royalty, Malkata, toll tax, CST and all type of other taxes imposed by the Government.	2.52	3800.00	Rupees Three Thousand Eight Hundred Only	Per cubic Metre	9614.00

3	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	25.74	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic metre	87516.00
	Total					99950.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Construction of Link road from Dhabhi to Kuthan Km 0/00 to 0/600 (SH:-C/O 4.00 Mtr. Span Culvert at RD 0/550 Alongwith approaches) SDP/2023/1424				Estimated cost Rs.		498788.00
				Earnest Money Rs.		10000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2.32	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	11484.00
2	Providing and laying mechanically mixed and vibrated Plain/reinforced cement concrete in Sub structure as per drawing and MORTH technical specification section 1500, 1700, 2200 RCC Grade M-20 (M- twenty five) designed mix with cement contents not less than 344 kg. (Three hundred forty four) Kilogram per cubic meter with 40mm (forty millimeter) nominal size graded crushed stone aggregate and curing complete including cost of form work in abutment etcetra complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	70.56	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic Metre	433944.00
3	Providing and laying flooring laid over cement concrete bedding complete using cement concrete block grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in flooring laid over bedding as per drawings and M.O.R.D. technical specification clause 1303 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidentals. The rate is including octroi, royalty, GST, or other taxes imposed by the Government.	3.04	6500.00	Rupees Six Thousand Five Hundred Only	Per cubic metre	19760.00


4	Supplying fitting and placing HYSD bar reinforcement in sub-structure complete as per drawing and MORTH technical specifications section 1600 and 2200 including cutting, bending, binding, straightening and placing in position complete in all respect including cost of binding wire upto all height and depth as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.28	95000.00	Rupees Ninety Five Thousand Only	Per Tonne	26600.00
5	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	28.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	7000.00
	Total					498788.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Suan Bhodi Khajar road Km 0/00 to 6/045 (SH:-C/O Wing walls of 2.00 Mtr. Span culvert at RD 0/270(towards Suan side) Under PDNA						
					Estimated cost Rs.	316847.00
					Earnest Money Rs.	6400.00
					Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	39.49	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	8885.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	75.35	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	290098.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	36.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	9000.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	9.33	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	8864.00
	Total					316847.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur