

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

11898-

Dated:- 19-1-2025

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229, E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **29.01.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 28.01.2026** for which the application should reach in this office **upto 1.00 PM 28.01.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	Preparation of Forest Diversion Case under FRA 2006 for the construction of Jait to Rashog road GP Teban Km. 0/00 to 1/600) DC Deposit	30,000/-	1,000/-	Two month	350/-
2	Preparation of Forest Diversion Case under FRA 2006 for the C/o road Kaith to Johad in GP Shout VKV/2024/124	30,000/-	600/-	Six month	350/-
3	A/R & M/O various road under Karsog Sub-Division (SH:- Painting and writing in KM stone and sign board etc)	99,836/-	2,000/-	One month	350/-
4	R/R damages on link road Kot to Chindi via Jaban (SH:- Maintenance of berms & C/o unlined drain in Km. 0/00 to 3/00)	99,537/-	2,000/-	One month	350/-
5	R/R damages on Tattapani to Shakra road Km. 0/00 to 10/00 (SH:- C/o of R/wall at RD 9/950 to 9/960) under PDNA	3,71,941/-	7,500/-	One month	350/-
6	R/R damages on link road to village Parlog road KM. 0/00 to 2/00 (SH:- C/o B/wall at RD 0/880 to 0/892 & R/wall at RD 1/715 to 1/730) under PDNA 2023	4,69,135/-	9,400/-	One month	350/-
7	R/R damages on Punni Naswar road KM. 0/00 to 3/00 (SH:- Widening of road at Km. 0/245 to 0/290, 0/335 to 0/445 & 0/485 to 0/570) under	4,99,980/-	10,000/-	Two months	350/-

8	R/R damages on Mahog Gawala road KM. 10/500 to 19/00 (SH:- C/o R/wall at RD 17/510 to 17/525 and removal of slips in various RDs Km. 16/00 to 19/00) under PDNA	4,87,532/-	9,800/-	Three months	350/-
9	VKV/2025/1030 C/o (Construction of) B/wall Danga Near Houe of Sh. Shet Ram Bhardwaj S/o Late Sh. Inder Singh Vill. Upper Nayara Ward No. 2 Karsog Sanarli road RD 3/105 to 3/114 and RD 3/115 to 3/124 (SH:- C/o PCC B/wall at RD 3/105 to 3/119)	99,760/-	2,000/-	Two months	350/-
10	R/R damages on link road to village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No. 1	99,520/-	2,000/-	One month	350/-
11	R/R damages on Kelodhar to Dogra road Km. 0/00 to 2/700 (SH:- removal of slips at various RDs between Km. 0/830 to 1/010) VKV/2024/1209	99,792/-	2,000/-	One month	350/-
12	R/R damages on Kelodhar to Dogra road Km. 0/00 to 2/700 (SH:- Removal of land slide slips at various RDs between Km. 1/060 to 1/240) VKV/2024/2509	99,936/-	2,000/-	One month	350/-
13	R/R damages on Shimla Mandi road Km. 90/00 to 115/00 (SH:- C/o U-shape drain in Km. 95/200 to 95/490) under PDNA 2023	4,94,539/-	10,000/-	Three months	350/-
14	R/R damages on Shimla Mandi road KM. 90/00 to 115/00 (SH:- C/o R/wall at RD 106/780 to 106/795) under PDNA 2023	3,73,787/-	7,500/-	Three months	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

No. PW-E-Tender-NIT/2025-26-

11890-95

Dated:-

19-1-2025

Executive Engineer
B&R Division
HPPWD Karsog

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

D.N.I.T / SCHEDULE OF QUANTITY

Estimated Cost Rs :- 30000/-
Earnest money:- 1000/-
Time :- Two Months

Name of work :- Preparation of Forest Diversion Case under FRA, 2006 for the Construction of Jai to Rashog Road GP Teban Km 0/0 to 1/600

Sr. No.	Description's	Qty.	Rate		Unit	Amount
			In figure	In Words		
1.	Preparation of Forest Diversion case under Forest Right Act, 2006 including preparation of revenue papers of land falling on the road alignment and collection of the other field data. All relevant documents/ formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and Forest conservation Govt. of India after getting the joint inspection/site including computer typing in six copies, binding complete and getting it through from HPPWD, Sub - Division Karsog, HPPWD Division Karsog , Office of concern Range Officer, Office of Divisional Forest Officer Karsog. Including attending all the observation, if raised, at any time by any above mentioned office and to prepare the same by neatly and accurately filling in all the formats/ Documents complete in all respect as per direction and complete satisfaction of HPPWD and Forest Department.	1 Case	30000	Rupees Thirty Thousand Only	Per Case	30000 .00
Total:-						30000 .00

Executive Engineer
Karsog Division
HPPWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 30000
Earnest Money 600
Time Six Months

Name of Work:- Preparation of Forest Diversion Case under Forest Right Act, 2006 for the C/O road from Kaith to Johad in G.P. Shout, (WKV/2024/124).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including	Total Amount with all taxes including GST in Rupees Thirty Thousand and Paise Zero Only
1	Preparation of Forest Diversion case under Forest Right Act, 2006 including preparation of revenue papers of land falling on the road alignment and collection of the other field data. All relevant documents/ formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and Forest conservation Govt. of India after getting the joint inspection/site including computer typing in six copies, binding complete and getting it through from HPPWD, Sub - Division Karsog, HPPWD Division Karsog, Office of concern Range Officer, Office of Divisional Forest Officer Karsog, including attending all the observation, if raised, at any time by any above mentioned office and to prepare the same by neatly and accurately filling in all the formats/ Documents complete in all respect as per direction and complete satisfaction of HPPWD and Forest Department. Preparation of Plan with GPS Coordinates 250 mtr. (two hundred fifty metre) Interval with collecting data from site including preparation of KML files and PDF files of Maps. (FRA Case).	1.00	Per Case	30000.00	30000.00	
Total in Figures					30000.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99836.00
Earnest Money 2000
Time One Month

Name of Work:-A/R & M/O various road under Karsog Sub Division (SH:- Painting and writing in Km stone and sign Board etc.)		Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Painting two coats with epoxy paint of approved bamed on concrete/steel surface after through cleaning of surface to give and even shade as per drawing and Technical Specification Clause 1701 or as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.			18.00	Per Square Meter	152.70	2749.00	Rupees Two Thousand Seven Hundred Forty Nine and Paise Zero Only
2	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered/Concrete surface as per drawing and technical specification as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.			33.00	Per Square Meter	140.65	4641.00	Rupees Four Thousand Six Hundred Forty One and Paise Zero Only
3	Printing new letters and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawing and technical specification clause 1701 or as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.			31878.00	Per Letter/Per centimeter height	2.90	92446.00	Rupees Ninety Two Thousand Four Hundred Forty Six and Paise Zero Only
Total in Figures							99836.00	
Quoted Rate in Figures								
Quoted Rate in Words								

Executive Engineer,
Karsog Division,
DHPWD, Karsog.

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Link road Kot to Chindi via Jaban (SH:- Maintenance of berms & C/O Unlined drain in Km 0/00 to 3/00).

Estimated Cost 99537
Earnest Money 2000
Time One Month

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST in Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	1050.00	Per Running Meter	23.80	24990.00	Rupees, Twenty Four Thousand Nine Hundred Ninety and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	3388.50	Per Square Meter	22.00	74547.00	Rupees Seventy Four Thousand Five Hundred Forty Seven and Paise Zero Only
Total in Figures					99537.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsoy Division,
CHPPWD, Karsoy.

Tender Inviting Authority:

Name of Work: R/R Damages on Tattapani to Shakra road Km. 0/00 to 10/00(Sub Head :- Construction of R/Wall at RD 9/950 to 9/960) under PDNA

Contract No:

Name of the
Bidder/ Bidding
Firm / Company**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 50 depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	34.25	Per Cubic Meter	390.20	13364.35	13364.35	INR Thirteen Thousand Three Hundred Sixty Four & Paise Thirty Five Only
2	Providing concrete for plain/reinforced concrete 1:4:8 (one cement : four course sand : eight graded stone aggregate) in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	59.65	Per Cubic Meter	5500.00	328075.00	328075.00	INR Three Lakh Twenty Eight Thousand Seventy Five & Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	40.00	Each	373.15	14926.00	14926.00	INR Fourteen Thousand Nine Hundred Twenty Six & Paise Zero Only

4	Back filling granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	12.98	Per Cubic Meter	1200.00	15576.00	15576.00	INR Fifteen Thousand Five Hundred Seventy Six & Paise Zero Only
Total in Figures					371941.35	371941.35	INR Three Lakh Seventy One Thousand Nine Hundred Forty One & Paise Thirty Five Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Bill of Quantity checked and approved for Rs. 371941.
Only for the year 2025-26 Sr. No. 281

Executive Engineer
Karsog Division
CHPPWD Karsog

Order Inviting Authority:

Name of Work: R/R Damages Link road to Village Parlog road Km 0/00 to 2/00(SH:- C/O BWall at RD 0/880 to 0/892 & R/Wall at RD 1/715 to 1/730) under PDNA 2023.

Contract No:

Name of the
Bidder/ Bidding
Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT With all Taxes Excluding GST in Rs. P	TOTAL AMOUNT With all Taxes Excluding GST in Rs. P	TOTAL AMOUNT In Words
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with lift upto any meter and lead upto any meter as per technical specification clause 1603.1.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	44.16	Per Cubic Meter	168.35	7434.34	7434.34	INR Seven Thousand Four Hundred Thirty Four & Paise Thirty Four Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 50 depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	36.81	Per Cubic Meter	331.15	12189.63	12189.63	INR Twelve Thousand One Hundred Eighty Nine & Paise Sixty Three Only
3	Providing concrete for plain/reinforced concrete 1:4:8 (one cement : four course sand : eight graded stone aggregate) in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	89.57	Per Cubic Meter	4722.80	423021.20	423021.20	INR Four Lakh Twenty Three Thousand Twenty One & Paise Twenty Only

4	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	53.00	Each	317.05	16803.65	16803.65	INR Sixteen Thousand Eight Hundred Three & Paise Sixty Five Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	8.63	Per Cubic Meter	1122.40	9686.31	9686.31	INR Nine Thousand Six Hundred Eighty Six & Paise Thirty One Only
Total in Figures					469135.13	469135.13	INR Four Lakh Sixty Nine Thousand One Hundred Thirty Five & Paise Thirteen Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					

Bill of Quantity checked and approved for Rs 4,69,135.13
For the year 2025-26 Sr. No 816

Executive Engineer
Karsog Division
CHPPWD Karsog

Percentage Schedule of Quantity

Estimated Cost 499980
Earnest Money 10000
Time Two Months

Name of Work:-R/R Damages on Punni Naswar Road Km 0/00 to 3/00 (Sh:- Widening of road at km 0/245 to 0/290, 0/335 to 0/445 & 0/485 to 0/570) Under PDNA).

St. No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 78.54 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 23563/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals	2015.64	Per Cubic Meter	248.05	499980.00	Rupees Four Lakhs Ninety Nine Thousand Nine Hundred Eighty and Paise Zero Only
Total in Figures					499980.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

487532
9800

Time

Three Months

Name of Work:- R/R Damages on Mahog Gawala Road Km. 10/500 to 19/00 (SH:- C/O R/Wall at-17/510 to 17/525 and Removal of slips in various RD's Km 16/00 to 19/00) Under PDNA

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mts dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mts depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.95	Per Cubic Metre	390.20	10126.00	Rupees Ten Thousand One Hundred Twenty Six and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802.803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	40.65	Per Cubic Metre	5500.00	223575.00	Rupees Two Lakhs Twenty Three Thousand Five Hundred Seventy Five and Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	373.15	11195.00	Rupees Eleven Thousand One Hundred Ninety Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.80	Per Cubic Metre	1200.00	12960.00	Rupees Twelve Thousand Nine Hundred Sixty and Paise Zero Only
5	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1913.97	Per Cubic Metre	120.00	229676.00	Rupees Two Lakhs Twenty Nine Thousand Six Hundred Seventy Six and Paise Zero Only
Total in Figures					487532.00	
Quoted Rate in Figures					0	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

7

Percentage Schedule Of Quantity

Estimated Cost 99760.00
Earnest Money 2000
Time Two Months

Name of Work:- VKV/2025/1030 C/O (Construction Of) BM/All Danga Near House of Sh. Shet Ram Bhardwaj S/O Lt. Sh. Inder Singh Vill Upper Nayara Ward No.2 Karsog Sanarail Road
RD 3/105 to 3/114 and RD 3/115 to 3/124 (SH:- C/O PCC BM/All at RD 3/105 to 3/119).

Sub-Head and Items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	9.24	Per Cubic Meter	390.20	3605.00	Rupees Three Thousand Six Hundred Five and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.94	Per Cubic Meter	5500.00	93170.00	Rupees Ninety Three Thousand One Hundred Seventy and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	Rupees Two Thousand Nine Hundred Eighty Five and Paise Zero Only
Total in Figures					99760.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
PHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money

99520
2000

Time

One Month

Name of Work:- R/R Damages on Link road to Village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No.1

Sub-Head and Items of works.

	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	33.60	Per Cubic Meter	390.20	13111.00	Rupees Thirteen Thousand One Hundred Eleven and Paise Zero Only
2	9.00	Per Cubic Meter	7036.00	63324.00	Rupees Sixty Three Thousand Three Hundred Twenty Four and Paise Zero Only
3	243.00	Per Kilo Gram	95.00	23085.00	Rupees Twenty Three Thousand Eighty Five and Paise Zero Only
Total in Figures					
Quoted Rate in Figures				99520.00	
Quoted Rate in Words					

Executive Engineer,
Karsog Division,
DHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99792
Earnest Money 2000

Time One Month

Name of Work:- R/R Damages on Kelodhar to Dogra road Km. 0/00 to 2/700(SH.- Removal of land slide slips at various RD's between Km. 0/830 to 1/010)/VKV/2024/1209.

Sub-Head and items of works.

	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST in Words
1	831.60	Per Cubic Meter	120.00	99792.00	Rupees Ninety Nine Thousand Seven Hundred Ninety Two and Paise Zero Only
Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in-all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.					
Total in Figures					
Quoted Rate in Figures				99792.00	
Quoted Rate in Words					

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99936
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar to Dogra road Km. 0/00 to 2/700(SH):- Removal of land slide slips at various RD's between Km. 1/060 to 1/240/VKV/2024/2509.

Sub-Head and Items of Works.

	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST In Words
1	832.80	Per Cubic Meter	120.00	99936.00	Rupees Ninety Nine Thousand Nine Hundred Thirty Six and Paise Zero Only
Total in Figures					
Quoted Rate in Figures				99936.00	
Quoted Rate in Words					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 494539.00
Earnest Money 9900
Time Three Months

Name of Work:- R/R Damages on Shimla Mandi road Km. 90/100 to 115/100 (SH:- C/O U-Shape Drain in Km 95/200 to 95/490) Under PDNA 2023.

Sub-Head and items of works.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in
Sr.No.						
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	135.58	Per Cubic Meter	360.00	48809.00	Rupees Forty Eight Thousand Eight Hundred Nine and Paise Zero Only
2	Providing and laying concrete for plain/reinforcement concrete 1:3:6 (one cement : three sand : six graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	76.85	Per Cubic Meter	5800.00	445730.00	Rupees Four Lakhs Forty Five Thousand Seven Hundred Thirty and Paise Zero Only
Total in Figures					494539.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 373787.00
Earnest Money 7500
Time Three Months

Name of Work:- R/R Damages on Shimla Mandi road Km. 90/00 to 115/00 (SH:- C/O R/Wall at RD 106/780 to 106/795) Under PDNA 2023.									
Sub-Head and items of works.									
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words			
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	44.40	Per Cubic Meter	360.00	15984.00	Rupees Fifteen Thousand Nine Hundred Eighty Four and Paise Zero Only			
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	60.39	Per Cubic Meter	5500.00	332145.00	Rupees Three Lakhs Thirty Two Thousand One Hundred Forty Five and Paise Zero Only			
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	360.00	7200.00	Rupees Seven Thousand Two Hundred and Paise Zero Only			
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.05	Per Cubic Meter	1150.00	18458.00	Rupees Eight Thousand Four Hundred Fifty Eight and Paise Zero Only			
Total in Figures									
Quoted Rate in Figures									
Quoted Rate in Words									


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.