

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWN-CB-Tender/2025-26- 7702-08
To


Dated:- 22/1/2026

The Executive Engineer (IT Cell),
Nigam Vihar, H.P.P.W.D., Shimla-2.
cc-pwd-hp@nic.in

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Notice Inviting Tender to be opened on 29.1.2026 for uploading on department website as per notification Secy.(PW) to the Govt. of H.P. No.PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and further No.PWD-B-A0(3)/8/2025-300858 dt.9.10.25 as the work mentioned in the notice is urgent nature and public interest.

Encl:- As above.


Executive Engineer,
B & R Division,
HPPWD., Nahan

Copy forwarded to the following for information & n/a to:-

1. The Engineer-in-Chief, HP.PWD., Shimla.
2. The Chief Engineer (SZ), HP.PWD., Shimla.
3. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
4. All the Assistant Engineers under this division.
5. All Head of Branches of this office.
6. The Notice Board.

Executive Engineer,
B & R Division,
HPPWD., Nahan

**Himachal Pradesh
Public Works Department
Notice inviting Tender**

Sealed percentage rate tender on form PWD 6 & 7 are invited by the Executive Engineer Nahan, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD, so as to reach in this office as per time schedule given below.

- | | |
|--|-------------------------|
| 1. Date of receipt of application of tenders forms:- | 28.1.2026 upto 11:00 AM |
| 2. Date of issue/ sale of tender Forms:- | 29.1.2026 upto 10.30 AM |
| 3. Date of receipt of tender | 29.1.2026 at 11:00 AM |
| 4. Date of opening of tender:- | 29.1.2026 at 12:00 Noon |

Sr. No.	Name of Work	Estimated Cost (in ₹)	Earnest Money (in ₹)	Time Limit	Cost of Tender Form (in ₹)
1	R/R Damages on Upper Surla Amta km 0/0 to 3/780 (SH:- C/O Retaining wall in wire crate at RD 0/305 to 0/310 & Balance work of R/wall at RD 0/310 to 0/315) PDNA	98918/-	2000/-	02 Month	350/-
2	R/R Damages to Khajurna Bikram Bag Suke4ti Kala Amb road km 0/00 to 15/00 (SH:- C/O R/wall at RD 4/758 to 4/765)	98239/-	2000/-	02 Month	350/-
3	R/R Damages to Pipalwala Salani Devni road km 0/00 to 4/750 (SH:- C/O R/wall at RD 4/684 to 4/691)	98038/-	2000/-	02 Month	350/-
4	R/R Damages on Nahan to Jabbal Ka Bag road km 0/00 to 5/00 (Sh:- C/O Retaining wall at RD 1/840 to 1/845)	99889/-	2000/-	02 Month	350/-
5	R/R damages of road from Shambhuwala to Kun Nehrla km0/00 to 7/040 (SH:- C/O of balance work of Slab in existing abutment at RD 0/100)	99730/-	2000/-	02 Month	350/-
6	C/O Play ground Jamli at Nahan. (SH:- C/O abutment for approach slab to Playgroud)	99844/-	2000/-	02 Month	350/-
7	C/O Play ground Jamli at Nahan (SH:- C/O approach slab to playground)	96955/-	2000/-	02 Month	350/-
8	C/O Play ground Jamli at Nahan (SH:- C/O side protection work for approach slab to playground)	92484/-	2000/-	02 Month	350/-

CERTIFICATE:-It is certified thatthe tenders of above works are of exigency/ emergent nature in public interest.

Terms & Conditions:-

1. The Contractors/ Bidders must submit copy of their Permanent Income Tax Account Number/ GST Number/ EPF No. along with the application for tender.
2. The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
3. The Contractors/Firms should attach copy of the Registration/ Renewal with the application.
4. The contractor/ bidder should quote his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 Crore each or above.
7. The offer shall remain valid up to 75 days.
8. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated.Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
9. The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reasons.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Upper Surla Amta km 0/0 to 3/780. (SH:- C/o Retaining wall in wire crate at RD 0/305 to 0/310 & Balance work of R/wal at RD 0/310 to 0/315) PDNA				Estimated Cost Rs.98,918/-	
				Earnest money: Rs. 2000/-	
				Time:- Two Months	
	Sub Head and item of work	Qty	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge	19.22	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only 5766.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 25 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.	32.65	Per cubic metre	2850.00	Rs. Two Thousand Eight Hundred Fifty & Paise Nil only 93053.00
Total					98819.00


Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Nahan Division,
HP PWD, Nahan

2

Name of work:- R/R Damages to Khajurna Bikram Bag Suketi Kala Amb road Km. 0/00 to 15/00. (SH:- C/o R/wall at RD 4/758 to 4/765)

SCHEDULE OF QUANTITY

Estimated Cost Rs.98,239/-

Earnest Money: Rs. 2000/-

Time:- Two Months


Sr. No.	Sub Head and item of work	Qty	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	11.81	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only 3543.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	20.47	Per Cubic metre	4,211.30	Rs. Four Thousand Two Hundred Eleven & Paise Thirty Only 86205.00
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614.709,1204.3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10	Per Each	270.00	Rs. Two Hundred Seventy & Paise Nil only 2700.00
4	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular materials as per HP PWD .. specification 1990 of Volume-1 (one) including carnage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	5.04	Per Cubic metre	1,149.00	Rs. One Thousand One Hundred Forty Nine & Paise Nil Only. 5791.00
Total					98239.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Nahan Division,
HP PWD, Nahan

9

SCHEDULE OF QUANTITY

Name of work:- R/R Damages to Pipalwala Salani Devni road Km. 0/00 to 4/750. (SH:- C/o R/wall at RD 4/684 to 4/691)

Estimated Cost Rs.98,038/-

Earnest Money: Rs. 2000/-

Time:- Two Months

Sr. No.	Sub Head and item of work	Qty	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	12.75	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only 3825.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand; eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	20.47	Per Cubic metre	4,211.30	Rs. Four Thousand Two Hundred Eleven & Paise Thirty Only 86205.00
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10	Per Each	270.00	Rs. Two Hundred Seventy & Paise Nil only 2700.00
4	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular materials as per HP PWD .. specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	4.62	Per Cubic metre	1,149.00	Rs. One Thousand One Hundred Forty Nine & Paise Nil Only 5308.00
Total					98038.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Nahan to Jabbal Ka Bag road km 0/00 to 5/00 (SH:- C/o Retaining wall at RD 1/840 to 845)				Estimated Cost Rs.99,889/-		
				Earnest Money: Rs. 2,000/-only		
				Time:- Two Months		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	9.40	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil only	2820.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement, four sand, eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	21.00	Per Cubic metre	4211.30	Rs. Four Thousand Two Hundred Eleven & Paise Thirty Only	88437.00
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614 709, 1204 3 7, including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10	Per Each	260.00	Rs. Two Hundred Sixty & Paise Nil only	2600.00
4	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204 3 8 Granular materials as per HP PWD, specification 1990 of Volume-1 (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	5.25	Per Cubic metre	1,149.00	Rs. One Thousand One Hundred Forty Nine & Paise Nil Only.	6032.00
Total						99889.00

Quoted Rate in Figure (+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost


Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

Work of work:- R/R damages of road from Shambhuwala to Kun Nehra km 0/00 to 7/040. (SH:-c/o of balance work of abutment in existing abutment at RD 0/100)

Estimated Cost Rs.99,730/-

Earnest money: Rs.2,000/-

Time:- Two Months

Sub Head and item of work		Qty	Unit	Rate	Amount
1	Providing mild steel/Tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level : Tor Steel including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	750.00	Per Koligram	75.40	Rs. Seventy Five & Paise Forty Only 56550.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 804, 805, 806, 807, 1202 and 1204 R.C.C. grade M-25 nominal size mix (1 1 5.3) (one cement: one point five sand: three crushed stone aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	6.35	Per cubic metre	6,800.00	Rs. Six Thousand Eight Hundred & Paise Nil Only. 43180.00
Total					99730.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

Line of work:- C/o Play ground Jamli at Nahan. (SH:- C/o abutment for approach slab to playground)

Estimated Cost Rs.99,844/-

Earnest Money: Rs. 2,000/-

Time:- Two Months


Sr.No	Sub Head and item of work	Qty	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m. dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	5.04	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only 1512.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802,803,1202 & 1203 nominal mix P.C.C. Grade M 20 Nominal mix (1:2:4) (i) upto 5 m height (ironito mix)	15.86	Per cubic metre	6200.00	Rs. Six thousand two hundred and Paise nil only 98332.00
Total					99844.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

Name of work:- C/o Play ground Jamli at Nahan. (SH:- C/o approach slab to playground)

Estimated Cost Rs.96,955/-

Earnest Money: Rs. 2,000/-

Time:- Two Months

Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 804, 805, 806, 807, 1202 and 1204 R.C.C. grade M-25 nominal size mix (1:1.5:3) (one cement, one point five sand, three crushed stone aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	1.84	Per cubic metre	6,800.00	Rs Six Thousand Eight Hundred & Paise Nil Only.	12512.00
2	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications	0.35	Per Tonne	75500.00	Rs Seventy Five Thousand Five Hundred & Paise Nil Only.	26425.00
3	Providing weep holes in brics/stone masonry plain/reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 m in horizontal towards drawing face complete as per specification clause 614, 709, 1204 3.7 as per HPPWD specification 1990 of Volume-1 (one) including carriage of all labour equipment & material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	15.00	Each	270.00	Rs. Two hundred Seventy & Paise nil only	4050.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8. (One cement : four sand : eight crushed stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.90	Per cubic metre	4250.00	Rs Four Thousand Two Hundred Fifty & Paise Nil Only.	42075.00
5	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204 3.8 Granular material as per HPPWD specification 1990 of Volume-1 (one) including carriage of all labour equipment & material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	10.35	Per cubic metre	1150.00	Rs. One Thousand One Hundred Fifty & Paise Nil only	11903.00
Total						96965.00

Quoted Rate in Figure (+/-) (..... %)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

Name of work:- C/o Play ground Jamli at Nahan. (SH:- C/o side protection work for approach slab to playground)				Estimated Cost Rs.92,484/-		
				Earnest Money: Rs. 9,000/-		
				Time:- Two Months		
Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	19.28	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only	5784.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802,803,1202 & 1203 nominal mix C.C. 1:4:8. (One cement : four sand : eight crushed stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	20.40	Per cubic metre	4250.00	Rs.Four Thousand Two Hundred Fifty & Paise Nil Only.	86700.00
Total						92484.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan