Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2025/ 16143-52 Dated/ 9/1/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pardesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer,5th Circle,HPPWD.,Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 16143-52 Dated 09-01-2026 are urgent in nature and in public interest.

Executive Engineer
Palampur Division
HPPWD Palampur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

'NOTICE INVITING TENDERS'

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **21.01.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 20.01.2026 up to 4.00 P.M and the application for issue of tender form shall be received 19.01.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	R/D on link road to village Gujrehra Km 0/00 to 0/500 (SW:- Providing and laying GSB from Km 0/00 to 0/140)	Rs. 99,278.00	Rs. 2,000.00	Two Month
2	R/D on Badsar to Ardi road Km 0/00 to 4/00 (SH:- Filling of Depressed Portion at RD 2/050 to 2/130 & U-Shape drain at various reaches between Km 2/00 to 3/00)	Rs. 99,600.00	Rs. 2,000.00	Two Month
3	Maintenance of link road Bindraban housing Society (Sood Colony) (M.C. Deposit) (SW:- P/L G-III & 20 MM thick Premix Carpet with seal coat from RD 0/00 to 0/027.80 (Stretch-I) and RD 0/00 to 0/022.50 (Stretch-II)	Rs. 99,695.00	Rs. 2,000.00	Three Month
4	Maintenance of link road Bindraban housing Society (Sood Colony) (M.C. Deposit) (SW:- P/L G-III & 20 MM thick Premix Carpet with seal coat from RD 0/025 to 0/083.15 (Stretch-II)	Rs. 99,689.00	Rs. 2,000.00	Three Month
5	Restoration of rain damages on link road Bindraban to Sidhpur Sarkari road at RD 0/000 to 6/000 (SW:- Dismantling Existing Slab & P/L 1:3:6 for Kuhal Edge wall)	Rs. 51,56[illegible].00	Rs. 1,100.00	Three Month
6	Restoration of rain damages on link road Bindraban to Sidhpur Sarkari road at RD 0/000 to 6/000 (SW:- Steel work for Grating work over Kuhal Crossing at RD 3/00)	Rs. 87,425.00	Rs. 1,800.00	Three Month
7	Restoration of main road Sarsawa to Vinod Kumar House (SW:- P/L G-II & CC Pavement at RD 0/000 to 0/036)	Rs. 98,154.00	Rs. 2,000.00	Three Months
8	Restoration of main road Sarsawa to Vinod Kumar House (SW:- P/L G-II & CC Pavement at RD 0/036 to 0/074)	Rs. 99,131.00	Rs. 2,000.00	Three Months
9	Restoration of Rain damages on various roads under Gopalpur Sub-Division Section Lahla (SW:- Painting and writing letters in Kilometer Stone and Bridge etc)	Rs. 99,680.00	Rs. 2,000.00	Two Months
10	Crossing water pipe line under Palampur Sub Division in Lugri Bhatti Kandi road Km 0/00 to 5/00 (SW:- C/o R/Wall at RD 1/800 to 1/808 (JSV Deposit)	Rs. 99,152.00	Rs. 2,000.00	Two Months
11	Crossing water pipe line under Palampur Sub Division in Lugri Bhatti Kandi road Km 0/00 to 5/00 (SW:- Balance work for C/o R/Wall at RD 1/800 to 1/808 (JSV Deposit)	Rs. 99,912.00	Rs. 2,000.00	Two Months
12	Preparation of Forest Diversion case under FCA, 1980 for the construction of link road from Sukeri to Sukeri Km 0/00 to 1/004 under Gopalpur Sub-Division in Tehsil Palampur Distt. Kangra (HP) (SW:- Preparation of Forest Diversion case under FCA, 1980)	Rs. 95,000.00	Rs. 1,900.00	Two Months

13	Preparation of Forest Diversion case under FCA, 1980 for the construction of link road from Sukeri to Sukeri Km 0/00 to 1/004, Link road from Rakh to Ghamrota Km 0/00 to 2/332 & Link road from PLC Kandi Bandla (Portion Sukeri to Kandi) Km 5/00 to 8/411 under Gopalpur Sub-Division in Tehsil Palampur Distt. Kangra (HP) (SW:- Preparation of Revenue Papers for Forest Diversion case under FCA, 1980)	Rs. 95,538.00	Rs. 2,000.00	Two Months
14	Maintenance of link road Bindraban housing Society (Sood Colony) (M.C. Deposit) (SW:- P/L G-III & 20 MM thick Premix Carpet with seal coat from RD 0/085 to 0/095.45 (Stretch-III)	Rs. 99,61[illegible].00	Rs. 2,000.00	Three Months
15	C/o Somkunj Circuit House at Palampur Distt. Kangra (HP) (SW:- Providing & Fixing Radges and Valleys)	Rs. 78,865.00	Rs. 1,600.00	Three Months
16	C/o Somkunj Circuit House at Palampur Distt. Kangra (HP) (SW:- Providing & Fixing Prepainted sheet and steel work)	Rs. 92,36[illegible].00	Rs. 1,600.00	Three Months
17	Restoration of Rain damages on Parour Lahla Gopalpur Rakh Sukeri Kandi Bandla Palampur road Km 0/00 to 33/00 (SW:- C/o R/Wall at RD 11/900 to 11/906)	Rs. 99,300.00	Rs. 2,000.00	Three Months
18	Restoration of Rain damages on Parour Lahla Gopalpur Rakh Sukeri Kandi Bandla Palampur road Km 0/00 to 33/00 (SW:- C/o R/Wall at RD 11/910 to 11/916)	Rs. 99,300.00	Rs. 2,000.00	Three Months
19	Minor repair work of Executive Engineer (Electrical) Residece at Holta Colony HP.PWD (SW:- P/F prepainted sheet & Cup board work etc)	Rs 97,28[illegible].00	Rs. 2,000.00	Three Months
20	Restoration of rain damages on link road from Dharaman to Gadiara Km 0/000 to 6/500 (SW:- C/o R/Wall at RD 0/900 to 0/906)	Rs 99,42[illegible].00	Rs. 2,000.00	Three Months
21	Restoration of rain damages on Dharaman to Gwal Tikker road Km 0/000 to 8/300 (SW:- C/o 1.00 mtrs Span RCC Slab culvert & approaches of 1.00 mtrs Span RCC Slab culvert at RD 0/485 (Approaches at RD 0/481.90 to 0/483.90 both side)	Rs 99,84[illegible].00	Rs. 2,000.00	Three Months
22	R/D on Chachian Khas to Rakh road KM 0/00 to 3/00 (SW:- C/o R/Wall at RD 2/190 to 2/195)	Rs. 97,82[illegible].00	Rs. 2,000.00	Two Months
23	R/D on Chachian Khas to Rakh road KM 0/00 to 3/00 (SW:- C/o R/Wall at RD 2/197 to 2/202)	Rs. 97,82[illegible].00	Rs. 2,000.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on link road to village Gujrehra Km 0/00 to 0/500. (SH:- P/L GSB from Km 0/00 to 0/140).	Estimated cost Rs.	99278.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of granular sub-base by providing well graded material as per table 400.1 spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with three wheel 80-100 (eighty to hundred) KN static roller to achieve the desired density, complete as per drawing and MORD technical specification section 400 for grading II material and as per the directions of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	64.05			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

(2)

SCHEDULE OF QUANTITY

Name of work:- R/D on Badsar to Ardi road Km 0/00 to 4/00. (SH:- Filling of depressed portion at Rd 2/050 to 2/130 & U-Shape drain at various reaches between 2/00 to 3/00).	Estimated cost Rs.	99600.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the government.	180.00			Per cubic metre	
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government .	750.00			Per Running metre	
	Total					

Executive Engineer,
Palampur Division
HP,PWD Palampur

Schedule of Quantity

Work No. 3

e of Work :-Maintenance of link road Binderaban housing society (Sood colony) (MC Deposit)
ab Work :- P/L G-III, & 20 mm. thick premix carpet with seal coat from RD 0/000 to 0/027.80 (Stretch-I) and RD 0/000 to 0/025.50(Stretch-II)

Estimate Cost :- Rs.:-99,695/-
Earnest Money :-Rs.:-2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	14.42	Cubic metre			Per Cubic metre	
2	Providing and applying Primer coat with Bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70-1.00 kg. per sqm(zero point seven zero to one kilogramme per square metre) using mechanical means as per M.O.R.D techanical specifications section 500 and as per the directions of Engineer-in -Charge including carriage of material within all leads ,lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.28	Square metres			Per Square metre	
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line,grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant ,laying and rolling with a three wheel 80-100 KN static rollercapacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.28	Square metres			Per Square metre	
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to specified levels, grade and cross fall using Type A, Type-B and Type C by Manual means Bitumen (S-90) as per technical specification Clause 510. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.28	Square metres			Per Square metre	
						TOTAl	

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work No. (4)

Name of Work :-Maintenance of link road Binderaban housing society (Sood colony) (MC Deposit)
Sub Work :- P/L G-III, & 20 mm. thick premix carpet with seal coat from RD 0/025 to 0/083.15 (Stretch-II)

Estimate Cost :- Rs.:-99,689/-
Earnest Money :-Rs.:-2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	14.42	Cubic metre			Per Cubic metre	
2	Providing and applying Primer coat with Bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70-1.00 kg. per sqm(zero point seven zero to one kilogramme per square metre) using mechanical means as per M.O.R.D techanical specifications section 500 and as per the directions of Engineer-in -Charge including carriage of material within all leads ,lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.26	Square metres			Per Square metre	
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line,grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant ,laying and rolling with a three wheel 80-100 KN static rollercapacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.26	Square metres			Per Square metre	
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to specified levels, grade and cross fall using Type A, Type-B and Type C by Manual means Bitumen (S-90) as per technical specification Clause 510. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.26	Square metres			Per Square metre	
						TOTAI	

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work:- Restoration of rain damages on link road Binderaban to Sidhpur Sarkari road At Rd 0/000 to 6/000
S.W.:-Dismantking existing slab & P/L 1:3:6 for Kuhal edge wall

Estimate Cost :- Rs 51,563/-
Earnest Money :- Rs. 1100/-
Time Limit :-Three months

5

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the government.	6.02	Cubic metre			Per cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government..	9.69	Cubic metre			Per Cubic metre	
					Total :-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Estimate Cost :- Rs 87,425/-
Earnest Money :- Rs.1800/-
Time Limit :-Three months

(6)

Name of Work:- Restoration of rain damages on link road Binderaban to Sidhpur Sarkari road At Rd 0/000 to 6/000
S.W.:-Steel work for Grating work over Kuhal Crossing at Rd 3/000

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge.The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	920.26	Kilogram me			Per Kilogram me	
					Total :-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Work No.

Schedule of Quantity

(S.W.:-P/L

Estimated Cost :- Rs. 98,154/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

e of Work:- Restoration on main road Sarsawa to Vinod Kumar house
.l & CC Pavement at RD 0/000 to 0/036.)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.70	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	12.83	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

(S.W.:-P/L

Work No. 8

Estimated Cost :- Rs. 99,131/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

of Work:- Restoration on main road Sarsawa to Vinod Kumar house & CC Pavement at RD 0/036 to 0/074 (Deposit)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.77	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	12.96	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under Gopalpur Division Section Lahla. (SH:- Painting and writing letters in Km Stone and bridges etc.).

Estimated cost Rs.	99680.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications . Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government	32.00			Per square metre.	
2	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) **Indian(letters/figures)**. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	34000.00			Per letter per cm. height	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	200.00			Per square metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- Crossing water pipe line under Palampur Sub Division in Lugri Bhatti Kandi road Km 0/00 to 5/00.(SH:- C/o R/wall at Rd 1/800 to 1/808). **JSV Deposit 426983/-**	Estimated cost Rs.	99152.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	14.40			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government	21.60			Per cubic metre	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	8.00			Each	
				Total		

Executive Engineer,
Palampur Division
HP,PWD Palampur

11

SCHEDULE OF QUANTITY

Name of work:- Crossing water pipe line under Palampur Sub Division in Lugri Bhatti Kandi road Km 0/00 to 5/00.(SH:- Balance work for C/o R/wall at Rd 1/800 to 1/808). **JSV. Deposit 426983/-**	Estimated cost Rs.	99912.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling (carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	23.04			Per cubic metre.	
2	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	3.00			Each	
				Total		

Executive Engineer
Palampur Division
HP.PWD Palampur

12

SCHEDULE OF QUANTITY

Name of work:- Preparation of forest diversion case under FCA, 1980 for the construction of link road from Sukeri to Sukeri Km 0/00 to 1/004 under Gopalpur Sub Division in Tehsil Palampur, Distt. Kangra H.P. (SH:- Preparation of Forest Diversion Case under FCA,1980).	Estimated cost Rs.	95000.00
	Earnest Money Rs.	1900.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	1.000			Job	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Preparation of forest diversion case under FCA, 1980 for the construction of link road from Sukeri to Sukeri Km 0/00 to 1/004 , Link road from Rakh to Ghamrota Km 0/00 to 2/332 & Link road from PLC Kandi Bundla (Portion Sukeri to Kandi) Km 5/00 to 8/411 under Gopalpur Sub Division in Tehsil Palampur, Distt. Kangra H.P. (SH:- Preparation of Revanue paper for Forest Diversion Case under FCA,1980).				Estimated cost Rs.		95538.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.747			Per Kilometre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

Schedule of Quantity

. of Work :-Maintenance of link road Binderaban housing society (Sood colony) (MC Deposit)
o Work :- P/L G-III, & 20 mm. thick premix carpet with seal coat from RD 0/085 to 0/095.45 (Stretch-III)

Work No. (14)
Estimate Cost :- Rs.:-99,613/-
Earnest Money :-Rs.:-2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	14.41	Cubic metre			Per Cubic metre	
2	Providing and applying Primer coat with Bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70-1.00 kg. per sqm(zero point seven zero to one kilogramme per square metre) using mechanical means as per M.O.R.D techanical specifications section 500 and as per the directions of Engineer-in -Charge including carriage of material within all leads ,lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge.The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.11	Square metres			Per Square metre	
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line,grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant ,laying and rolling with a three wheel 80-100 KN static rollercapacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.11	Square metres			Per Square metre	
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to specified levels, grade and cross fall using Type A, Type-B and Type C by Manual means Bitumen (S-90) as per technical specification Clause 510. The rate is including octroi, royality, GST, toll tax, and other taxes imposed by the Government.	192.11	Square metres			Per Square metre	
						TOTAl	

Executive Engineer,
Palampur Division,
HPPWD Palampur

Work No. 15

Estimated Cost :- Rupees 78,865/-
Earnest Money :- Rupees 1600/-
Time limit : Three Months.

Schedule of Quantity

Name of Work : - C/O Somkunj Circuit House at Palampur Distt. Kangra (H.P.)
S.W.:-Providing & Fixing Ridges and Valleys

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and fixing ridges or hips 60 cm(Sixty centimetre) over all with 0.60mm (zero point six Zero millimetre) thick prepainted steel sheets of Tata/ Reliance/ Jindal in roofing with hot dipped metalic zinc coated sheets with top coat of regular modified polyster organic coating of 20 (Twenty) microns over 5(Five) microns primer coating + back coat of polyster of 5(Five) microns over 5(Five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm (Six millimetres)dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts and other incidental as per the direction of Engineer in Charges.The rate including of octroi, royality, Malkana, tolltax , GST or any other taxes imposed by the Government.	63.30	Running Metre			Per Running metre	
2	Providing valleys of 90 cm (Ninety Centimetre) wide overall in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm (Eight Millimetre)dia G.I. limpet and bitumen washers complete :1.60 mm(One point sixty millimetre) thick with zinc coating not less than 350 gm/m (Three hundred fifty grammes per metre)within all leads,lifts and other incidental as per the direction of Engineer in Charges. The rate including of octroi, royality, Malkana , toll tax, GST or any other taxes imposed by the Government.	32.80	Running Metre			Per Running metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : - C/O Somkunj Circuit House at Palampur Distt. Kangra (H.P.)
S.W.:-Providing & Fixing prepainted Sheet and Steel Work

Work No. 16

Estimated Cost :- Rupees 92,362/-
Earnest Money :- Rupees 1600/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge.The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	658.18	Kilogram			Per Kilogram	
2	Providng and Fixing 0.60 mm (zero decimal six zero milimetre) thick prepainted steel sheet Tata/ Reliance/ Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating including fixing with preparinted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limp-et and rubber washers complete with all accesories with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government.	19.90	Square metre			Per Square metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

17

Schedule of Quantity

Work No.

Name of Work : - Restoration of Rain Damages on Parour, Lahla, Gopalpur, Rakh, Sukeri, Kandi, Bandla, Palampur road Km. 000 to 33/00
S.H.:- C/O R/Wall at RD 11/900 to 11/906

Estimated Cost :- Rs.99,300/-
Earnest Money :- Rs. 2000/-
Time limit :- Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	21.42	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	8.00	Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.32	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Work No. 18

Schedule of Quantity

Name of Work : - Restoration of Rain Damages on Parour, Lahla, Gopalpur, Rakh, Sukeri, Kandi, Bandla, Palampur road Km. 000 to 33/00

Estimated Cost :- Rs.99,300/-
Earnest Money :- Rs. 2000/-
Time limit :- Three Months.

S.H.:- C/O R/Wall at RD 11/910 to 11/916

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	21.42	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	8.00	Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.32	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Work No. (19)

Name of Work :- Minor repair work of Executive Engineer (Electrical) Residence at Holta Colony HPPWD (S.W.:- P/F prepainted sheet & Cup board work etc.

Estimate Cost :-Rs. 97,289/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint. In beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like. The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government.	65.00	Kilogram			Per Kilogram	
2	Providng and Fixing 0.60 mm (zero decimal six zero millimetre) thick prepainted polyster galvanised steel sheet of approved colour over steel trusses with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns of primer back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating fixed with prepainted J or L hooks, bolts and nuts 8mm (eight millimetre) dia bitumen and G.I. limpet washers filled with required colour and laid completed as per the Direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.The rate is including octroi, royality,GST, toll tax, or other taxes imposed by the Government.	46.80	Square metre			Per Square metre	
3	Providing and fixing ridges or hips 60 cm(Sixty centimetre) over all with 0.60mm (zero point six Zero millimetre) thick prepainted steel sheets of Tata/ Reliance/ Jindal in roofing with hot dipped metalic zinc coated sheets with top coat of regular modified polyster organic coating of 20 (Twenty) microns over 5(Five) microns primer coating + back coat of polyster of 5(Five) microns over 5(Five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm (Six millimetres)dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts and other incidental as per the direction of Engineer in Charges.The rate including of octroi, royality, Malkana, tolltax , GST or any other taxes imposed by the Government.	6.00	Running metre			Per Running metre	
4	Providing and fixing 19mm thick Commercial Board with hard wood edging cup boardsshutters i/c fixing with nickel platedbright finished piano hinges with screws etc. complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	3.87	Square metres			Per Square metre	
5	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	11.72	Square metres			Per Square metre	
6	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	3.87	Square metres			Per Square metre	
7	Providing and fixing 1st class deodar wood square edges cover fillets (beading) 19mmx6mm section in ceiling and lining i/c mitring at junctions with wood screws and nails complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	13.10	Running metre			Per Running metre	
8	Providing and fixing (100mmx10mm) aluminium tower bolts (berrel type) anodized trans parent or dyed to required shade and colour with screws etc. complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	8.00	Numbers			Each	

	Providing and fixing aluminium handles 100 mm anodized transparent or dyed to required colour & shade with necessary screws etc. complete with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	7.00	Numbers			Each	
10	Prokviding and fixing 65x35mm. special quality bright finished brass cup board locks or wardrobe locks with six levers including necessary screws etc. complete. (Indian make of approved quality) with in all leads, lifts and other incidental. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.00	Numbers			Each	
					Total :-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Work No. 20

Schedule of Quantity

Name of Work : - Restoration of rain damages on link road from Dharman to Gadiara km. 0/000 to 6/500
(S. W. :- C/O R/Wall at RD 0/900 to 0/906

Estimated Cost :- Rs. 99,423/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	21.33	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	12.00	Numbers			Each	
3	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.60	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : - Restoration of rain damages on Dharman to Gwal tikker road km. 0/000 to 8/300 (**S. W.** :- C/O 1.00 mtr. Span R.C.C. slab culvert & approaches of 1.00 mtr. Span R.C.C. slab culvert at RD 0/485 Approaches RD 0/481.90 to 0/483.90 both side)

Work No. 21

Estimated Cost :- Rs. 99,842/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	13.00	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	5.48	Cubic metre			Per Cubic metre	
3	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana, Tolltax, GST or other taxes imposed by the Government.	1.80	Cubic metre			Per Cubic metre	
4	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana, Tolltax, GST or other taxes imposed by the Government..	8.64	Cubic metre			Per cubic metre	
5	Providing concrete for plain/reinforced concrete in open foundations 1:1.5:3 (1cement:1.5 :3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete in super structure as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate including of octroi, royality, Malkana, Tolltax, GST or other taxes imposed by the Government..	0.96	Cubic metres			Per Cubic metre	
6	Supplying,fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202.as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	67.20	kilogram me			Per kilogram me	

67	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, Malkana,Toll tax, GST or any other taxes imposed by the Government.	10.00	Numbers			Each	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

22

SCHEDULE OF QUANTITY

Name of work:- R/D on Chachian Khas to Rakh road Km 0/00 to 3/00. (SH :- C/o R/wall at Rd 2/190 to 2/195).

Estimated cost Rs.	97827.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.92			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.83			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	6.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- R/D on Chachian Khas to Rakh road Km 0/00 to 3/00. (SH :- C/o R/wall at Rd 2/197 to 2/202).

Estimated cost Rs.	97827.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.92			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.83			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	6.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur