HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827
E-mail: ee-seraj-hp@gov.in

No. PW-SRJ-CB-TA/2025-26- 9223 Dated:- 19/01/2026

To

The Executive Engineer (I.T.) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject: - ***Regarding publication of the tender on departmental site.***

Enclosed please find herewith the copies of notice inviting tender for the up-loading on department web-site before 27.01.2026 as per notification issued by the Pr. Sec. (PW) to the Govt. of HP vide letter No. PBW(B) A(3)1/2024 dated 03.01.2024 and notification issued by the Pr. Sec. (PW) to the Govt. of HP vide letter No. PWD- B-A 0(3)/8/2025-300858 dated 13.11.2025 for Post Disaster Needs Assessments (PDNA).

Certified that the works mentioned in the tender notice are urgent in nature and in co-ordination with the disaster management Act. 2005.

DA: - As Above.

Executive Engineer,
HPPWD Division
Seraj at Janjehli.

Scanned with OKEN Scanner

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827
E-mail: ee-seraj-hp@gov.in

NOTICE INVITING TENDER

Sealed percentage rate short terms tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division, Seraj at Janjehli Distt. Mandi (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class, so as to reach in this office on 28.01.2026 upto 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of contractors or their authorised representative who wish to be present at that time. The application for obtaining the tender form will be received on 27.01.2026 between 10.00 A.M. to 01:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 27.01.2026 between 11.00 AM to 05.00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, HP.PWD Division, Serajat JanjehliDistt. Mandi H.P. must accompany with the tender form. Ambiguous/ Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. **The Executive Engineer, HP.PWD Division, Seraj at Janjehli reserve the right to reject/accept any offer of tender without assigning any reasons Under PDNA.**

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender	Time allowed
1	RRD on Lambathach Chiuni Chet Shetadhar road Km 0/000 to 25/000 (SH: C/o R/wall in wire crate at RD 3/820 to 3/835) Under PDNA.	4,94,338	10,000	350/-	Two Months
2	RRD on Chhatri Magarugala via Lassi road Km 0/000 to 8/825 (SH:- Removal of slips & Land slide in between 0/125 to 8/430). Under PDNA	4,58,145	10,000	350/-	Two Months
3	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rd 1/248 to 1/260 & 2/225 to 2/240). Under PDNA	4,96,431	10,000	350/-	Two Months
4	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rd 2/450 to 2/482). Under PDNA.	4,61,960	9,300	350/-	Two Months
5	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rd 2/570 to 2/579 & removal of slips at various Rds). Under PDNA	4,88,879	10,000	350/-	Two Months
6	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o PCC R/wall at Rds 0/015 to 0/025). Under PDNA 2023.	3,44,800	7,000	350/-	Two Months

Scanned with OKEN Scanner

7	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rds 0/120 to 0/153). Under PDNA	4,73,298	9,500	350/-	Two Months
8	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rds 0/090 to 0/120). Under PDNA	4,30,922	8,700	350/-	Two Months
9	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rds 0/025 to 0/047). Under PDNA	4,98,781	10,000	350/-	Two Months
10	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o R/wall at Rds 0/000 to 0/014). Under PDNA	4,79,932	9,600	350/-	Two Months
11	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o PCC R/wall at Rds 1/225 to 1/247). Under PDNA 2023	4,98,781	10,000	350/-	Two Months
12	RRD on Shivakhad Jhamach Spenidhar road Km 0/000 to 8/000 (SH:- C/o PCC R/wall at Rds 0/048 to 0/069). Under PDNA 2023	4,76,562	10,000	350/-	Two Months
13	RRD on Shilibagi Deol Jainshla road Km 0/000 to 10/000 (SH:- C/o PCC R/wall at Rds 1/470 to 1/483) Under PDNA 2023.	4,99,354	10,000	350/-	Two Months
14	RRD on Shilibagi Deol Jainshla road Km 0/000 to 10/000 (SH:- C/o R/wall in CC at Rds 4/645 to 4/657.50 & removal of slips at various Rds) Under PDNA.	4,87,820	9,800	350/-	Two Months
15	RRD on Shilibagi Deol Jainshla road Km 0/000 to 10/000 (SH:- C/o R/wall in CC at Rds 2/450 to 2/459 & 2/475 to 2/483) Under PDNA.	4,74,742	9,500	350/-	Two Months
16	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o embarkment/filling in km 2/500 to 2/900) Under PDNA	4,99,798	10,000	350/-	Two Months
17	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o R/wall in wire Crate at Rds 1/320 to 1/343) Under PDNA	4,88,419	10,000	350/-	Two Months
18	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o embarkment/filling in km 1/600 to 2/000) Under PDNA	4,94,535	10,000	350/-	Two Months
19	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o embarkment/filling in km 2/000 to 2/500) Under PDNA	4,95,360	10,000	350/-	Two Months
20	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- Removal of slips & land slides at various RDs in Km 3/500 to 11/000) Under PDNA	4,96,834	10,000	350/-	Two Months

Scanned with OKEN Scanner

21	RRD on Janjehli Bekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o embarkment/filling in km 2/900 to 3/200) Under PDNA	4,94,039	10,000	350/-	Two Months
22	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in PCC at Rds 2/675 to 2/688.20) Under PDNA 2023.	4,96,826	10,000	350/-	Two Months
23	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in wire Crate at Rds 1/710 to 1/723 & 2/010 to 2/020.50) Under PDNA 2023.	4,99,059	10,000	350/-	Two Months
24	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in CC at Rds 1/400 to 1/420) Under PDNA.	4,52,350	9,100	350/-	Two Months
25	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o B/wall in wire Crate at Rds 1/680 to 1/695 & 2/855 to 2/872) Under PDNA.	4,96,174	10,000	350/-	Two Months
26	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in wire Crate at Rds 3/760 to 3/780) Under PDNA.	4,24,713	10,000	350/-	Two Months
27	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in wire Crate at Rds 2/540 to 2/555) Under PDNA.	4,86,398	10,000	350/-	Two Months
28	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in CC at Rds 2/885 to 2/898) Under PDNA.	4,91,388	10,000	350/-	Two Months
29	RRD on Kadaun Helipad to Banadhar road Km 0/000 to 4/700 (SH:- C/o R/wall in PCC at Rds 2/575 to 2/588.20) Under PDNA 2023.	4,98,817	10,000	350/-	Two Months
30	RRD on Jognidhar Bahlidhar road Km 0/000 to 4/000 (SH:- C/o R/wall in wire crate at Rds 2/460 to 2/473) Under PDNA 2023.	3,82,283	8,000	350/-	Two Months
31	RRD on Khali Mod Doghari Sakaran road KM 0/000 to 7/100 (SH:- Removal of slips & Land slide in various RDs in KM 4/000 to 7/100).	4,24,983/-	10,000/-	350/-	Two Months
32	RRD on various roads under Bagachanogi Section under Janjehli Sub Division (SH:- Removal of slips & Land slide in various Roads).	4,90,186/-	10,000/-	350/-	Two Months
33	RRD on various road under Thunag Section Link road from dhajar to Sanrout-Reunal GP Pakhrair in Km 0/000 to 1/000, Link road from Rilla to Barkwali road in Km 0/000 to 7/000 & Thunag Banyad Madehlu road & Deji Banshil Shikari Mata road in Km 0/000 to 1/000 (SH:- Removal of slips & land slides in various road).	4,15,635/-	8,400/-	350/-	Two Months
34	RRD on Bagsaid Tikker road KM 0/000 to 7/500 (SH:- Removal of slips & Land slide in various RDs in KM 0/000 to 6/800).	3,36,668/-	8,000/-	350/-	Two Months

Scanned with OKEN Scanner

35	RRD on Mandi Gagal Chail Janjehli road Km 0/000 to 82/000 (SH:- Removal of slips & land slide at various Rds in Km 63/600 to 65/100).	4,09,600/-	8,200/-	350/-	Two Months

Terms and conditions:-

1. The contractors/firms are required to quote their rates clearly percentage rate, failing which the tender is liable to be rejected.
2. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.
3. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender.
4. Latest Income tax and GST tax clearance certificates as well as PAN Number and GST number must be attached with the application failing which tender documents will not be issued.
5. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
6. As per Govt. Notificaiton No. PW/CTR/32-20-General Isnt. CPWD/2020-37996-38095 dated 13.03.2023 the tender above 5% will be summarily rejcted and tenders amount below 30% of amont put to tender will also be accepted.

Executive Engineer,
HPPWD Division,
Seraj atJanjehli.

No. PW-SRJ/NIT/2025-26- 9213-22 **Dated:-** 19/01/2026.

1. Copy to the Director, Information and publication Department HP Shimla for favour of publication in one regional newspaper and one National newspaper.
2. Copy to the superintending Engineer 1st Circle HPPWD mandi for information please
3. Copy to Sub- Divisional office (Civil) Thunag Tehsil Thunag for information please.
4. Copy to Block Development office Janjehli Tehsil ThunagDistt. Mandi HP.
5. Copy to all the Assistant Engineer working under this Division.
6. Copy to Drawing Branch & Account Branch
7. Notice board of this office.

Executive Engineer,
HPPWD Division,
Seraj at Janjehli.

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: 4,94,338.00 Only
Earnest Money: 10,000.00 Only
Time :Two months

Name of Work :- RRD on Lambathach Chiuni Chet Shetadhar road KM 0/000 to 25/000 (SH:- Construction of Retaining wall in wire crate at RD 3/820 to 3/835) Under PDNA

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	54.38	Per Cubic metre	552.35	30,037.00	Rupees Thirty Thousand Thirty Seven Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G I wire conforming to 1.5.280 and 1.5. 4826 in 100mm x 100 (one hundred in to one hundred millimeters) in much (woven diagonally) including 10% extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. within all leads . lifts and carriage of materials and other incidentals .	140.60	Per Cubic Meter	3,140.50	4,41,554.00	Rupees Four Lakh(s) Forty One Thousand Five Hundred Fifty Four Only
3.00	Back filling with granular material behind abutment , wing wall and return wall complete as per drawings and technical specification clauses 1206.3 and 1604.7 complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	17.41	Per Cubic metre	1,306.55	22,747.00	Rupees Twenty Two Thousand Seven Hundred Forty Seven Only
			Total:-		4,94,338.00	

Bill of Qty approved for Rs. 4,94,338/ only

Executive Engineer
H.P.P.W.D. Division
Seraj at Janjehli

B17

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: 4,58,145.00 Only
Earnest Money: 10,000.00 Only
Time : Two months.

Name of Work:- RRD on Chhatri Magarugala via Lassi road KM 0/000 to 8/825 (SH:- Removal of slips & Land slide in Between KM 0/125 to 8/430). Under PDNA

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	3879.30	Cum	118.10	4,58,145.00	Rupees Four Lakh(s) Fifty Eight Thousand One Hundred Forty Five Only
			Total:-		**4,58,145.00**	

Bill of Quantity approved for Rs. 458,145/- only.

Executive Engineer,
HPPWD Division
Seraj at Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 1/248 to 1/260 & 2/225 to 2/240) Under PDNA

Estimated cost Rs. - 4,96,431.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	39.15	Per Cubic metre	552.35	21625.00	Rupees Twenty One Thousand Six Hundred & Twenty Five Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	83.97	Per Cubic metre	5236.10	439675.00	Rupees Four Lakh Thirty Nine Thousand Six Hundred & Seventy Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	45.00	Each	398.30	17924.00	Rupees Seventeen Thousand Nine Hundred & Twenty Four Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.17	Per Cubic metre	1306.55	17207.00	Rupees Seventeen Thousand Two Hundred & Seven Only
				Total	**496431.00**	

Bill of Qty approved for Rs. 4,96,431/ only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 2/450 to 2/482) Under PDNA

Estimated cost Rs. - 4,61,960.00
Earnest Money cost Rs. - 9,300.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	42.56	Per Cubic metre	552.35	23508.00	Rupees Twenty Three Thousand Five Hundred & Eight Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	79.04	Per Cubic metre	5236.10	413861.00	Rupees Four Lakh Thirteen Thousand Eight Hundred & Sixty One Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.00	Each	398.30	9958.00	Rupees Nine Thousand Nine Hundred & Fifty Eight Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.20	Per Cubic metre	1306.55	14633.00	Rupees Fourteen Thousand Six Hundred & Thirty Three Only
				Total	**461960.00**	

Bill of Qty approved
for Rs. 4,61,960/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 2/570 to 2/579 & removal of slips at various Rds) Under PDNA

Estimated cost Rs. - 4,88,879.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	14.40	Per Cubic metre	552.35	7954.00	Rupees Seven Thousand Nine Hundred & Fifty Four Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	35.19	Per Cubic metre	5236.10	184258.00	Rupees One Lakh Eighty Four Thousand Two Hundred & Fifty Eight Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	Each	398.30	7169.00	Rupees Seven Thousand One Hundred & Sixty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.94	Per Cubic metre	1306.55	7761.00	Rupees Seven Thousand Seven Hundred & Sixty One Only
5	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2385.58	Per Cubic metre	118.10	281737.00	Rupees Two Lakh Eighty One Thousand Seven Hundred & Thirty Seven Only
				Total	488879.00	

Bill of Qty Approved
Rs. 4,88,879 Only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of PCC Retaining wall at Rds 0/015 to 0/025) Under PDNA 2023

Estimated cost Rs	3,44,800.00
Earnest Money Rs	7,000.00
Time - Two Months	

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	23.90	Per Cubic metre	552.35	13,201.00	Rupees Thirteen Thousand Two Hundred & One Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	59.60	Per Cubic metre	5236.10	3,12,072.00	Rupees Three Lakh Twelve Thousand &Seventy Two Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	30.00	Each	398.30	11,949.00	Rupees Eleven Thousand Nine Hundred & Fourty Nine Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.80	Per Cubic metre	1306.55	7,578.00	Rupees Seven Thousand Five Hundred & Seventy Eight Only
				Total	3,44,800.00	

Bill of Qty approved for Rs 3,44,800/- only

Executive Engineer,
HPPWD Division
Seraj at Janjehli

359

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 0/120 to 0/153) Under PDNA

Estimated cost Rs. - 4,73,298.00
Earnest Money cost Rs. - 9,500.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	43.89	Per Cubic metre	552.35	24243.00	Rupees Twenty Four Thousand Two Hundred & Fourty Three Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	81.51	Per Cubic metre	5236.10	426795.00	Rupees Four Lakh Twenty Six Thousand Seven Hundred & Ninety Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	Each	398.30	7169.00	Rupees Seven Thousand One Hundred & Sixty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.55	Per Cubic metre	1306.55	15091.00	Rupees Fifteen Thousand &Ninety One Only
				Total	473298.00	

Bill of Qty approved for Rs. 4,73,298/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- **RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 0/090 to 0/120) Under PDNA**

Estimated cost Rs. - 4,30,922.00
Earnest Money cost Rs. - 8,700.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	39.90	Per Cubic metre	552.35	22039.00	Rupees Twenty Two Thousand &Thirty Nine Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	74.10	Per Cubic metre	5236.10	387995.00	Rupees Three Lakh Eighty Seven Thousand Nine Hundred & Ninety Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	Each	398.30	7169.00	Rupees Seven Thousand One Hundred & Sixty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.50	Per Cubic metre	1306.55	13719.00	Rupees Thirteen Thousand Seven Hundred & Nineteen Only
				Total	**430922.00**	

Bill of Qty approved for Rs. 430,922/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 0/025 to 0/047) Under PDNA

Estimated cost Rs. - 4,98,781.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	35.20	Per Cubic metre	552.35	19443.00	Rupees Nineteen Thousand Four Hundred & Fourty Three Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	86.02	Per Cubic metre	5236.10	450409.00	Rupees Four Lakh Fifty Thousand Four Hundred & Nine Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.00	Each	398.30	9958.00	Rupees Nine Thousand Nine Hundred & Fifty Eight Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	14.52	Per Cubic metre	1306.55	18971.00	Rupees Eighteen Thousand Nine Hundred & Seventy One Only
				Total	**498781.00**	

Bill of Qty approved for Rs. 4,98,781/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of Retaining wall at Rds 0/000 to 0/014) Under PDNA

Estimated cost Rs. - 4,79,932.00
Earnest Money cost Rs. - 9,600.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	33.46	Per Cubic metre	552.35	18482.00	Rupees Eighteen Thousand Four Hundred & Eighty Two Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads lifts as per direction of Engineer - in - charge .	83.44	Per Cubic metre	5236.10	436900.00	Rupees Four Lakh Thirty Six Thousand Nine Hundred Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	35.00	Each	398.30	13941.00	Rupees Thirteen Thousand Nine Hundred & Fourty One Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.12	Per Cubic metre	1306.55	10609.00	Rupees Ten Thousand Six Hundred & Nine Only
				Total	479932.00	

Bill of Qty approved
for Rs. 4,79,932 /only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of PCC Retaining wall at Rds 1/225 to 1/247) Under PDNA 2023

Estimated cost Rs	4,98,781.00
Earnest Money Rs	10,000.00
Time - Two Months	

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	35.20	Per Cubic metre	552.35	19,443.00	Rupees Nineteen Thousand Four Hundred & Fourty Three Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	86.02	Per Cubic metre	5236.10	4,50,409.00	Rupees Four Lakh Fifty Thousand Four Hundred & Nine Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.00	Each	398.30	9,958.00	Rupees Nine Thousand Nine Hundred & Fifty Eight Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	14.52	Per Cubic metre	1306.55	18,971.00	Rupees Eighteen Thousand Nine Hundred & Seventy One Only
				Total	4,98,781.00	

Bill of Qty approved for Rs. 4,98,781/- only

Executive Engineer,
HPWD (P) Division
Seraj at ...

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shivakhad Jhamach Spenidhar road km 0/000 to 8/000 (SH:- Construction of PCC Retaining wall at Rds 0/048 to 0/069) Under PDNA 2023

					Estimated cost Rs	4,76,562.00
					Earnest Money Rs	10,000.00
					Time - Two Months	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	33.60	Per Cubic metre	552.35	18,559.00	Rupees Eighteen Thousand Five Hundred & Fifty Nine Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	82.11	Per Cubic metre	5236.10	4,29,936.00	Rupees Four Lakh Twenty Nine Thousand Nine Hundred & Thirty Six Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	25.00	Each	398.30	9,958.00	Rupees Nine Thousand Nine Hundred & Fifty Eight Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.86	Per Cubic metre	1306.55	18,109.00	Rupees Eighteen Thousand One Hundred & Nine Only
				Total	4,76,562.00	

Bill of qty approved
for Rs. 9,76,562/only

Executive Engineer,
HPPWD Division
Serahan Jaiphli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shilibagi Deol Jalshala road KM 0/000 to 10/000 (SH:- Construction of PCC Retaining wall at Rds 1/470 to 1/483) Under PDNA 2023

Estimated cost Rs	4,99,354.00
Earnest Money Rs	10,000.00
Time - Two Months	

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	40.95	Per Cubic metre	552.35	22,619.00	Rupees Twenty Two Thousand Six Hundred & Nineteen Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	85.28	Per Cubic metre	5236.10	4,46,535.00	Rupees Four Lakh Fourty Six Thousand Five Hundred & Thirty Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	40.00	Each	398.30	15,932.00	Rupees Fifteen Thousand Nine Hundred & Thirty Two Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.92	Per Cubic metre	1306.55	14,268.00	Rupees Fourteen Thousand Two Hundred & Sixty Eight Only
				Total	4,99,354.00	

Bill of Qty approved for Rs. 4,99,354/ only

Executive Engineer,
HPPWD Division
Seraj at Janjehli

350

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shillibagi o Deol Jainshla road km 0/000 to 10/000 (SH:- Construction of Retaining wall in CC at Rds 4/645 to 4/657.50 & removal of slips at various Rds) Under PDNA

Estimated cost Rs. - 4,87,820.00
Earnest Money cost Rs. - 9,800.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	29.50	Per Cubic metre	552.35	16294.00	Rupees Sixteen Thousand Two Hundred & Ninety Four Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	70.13	Per Cubic metre	5236.10	367208.00	Rupees Three Lakh Sixty Seven Thousand Two Hundred & Eight Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	12.00	Each	398.30	4780.00	Rupees Four Thousand Seven Hundred & Eighty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	9.50	Per Cubic metre	1306.55	12412.00	Rupees Twelve Thousand Four Hundred & Twelve Only
5	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	737.73	Per Cubic metre	118.10	87126.00	Rupees Eighty Seven Thousand One Hundred & Twenty Six Only
				Total	487820.00	

Bill of Qty approved for Rs. 4,87,820= only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Shillibagi o Deol Jainshla road km 0/000 to 10/000 (SH:- Construction of Retaining wall in CC at Rds 2/450 to 2/459 & 2/475 to 2/483) Under PDNA

Estimated cost Rs. - 4,74,742.00
Earnest Money cost Rs. - 9,500.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	34.04	Per Cubic metre	552.35	18802.00	Rupees Eighteen Thousand Eight Hundred & Two Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	81.77	Per Cubic metre	5236.10	428156.00	Rupees Four Lakh Twenty Eight Thousand One Hundred & Fifty Six Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	30.00	Each	398.30	11949.00	Rupees Eleven Thousand Nine Hundred & Fourty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	12.12	Per Cubic metre	1306.55	15835.00	Rupees Fifteen Thousand Eight Hundred & Thirty Five Only
				Total	474742.00	

Bill of Only amount approved for Rs. 4,74,742/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- **RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:- Construction of embankment/filling in km 2/500 to 2/900) Under PDNA**

Estimated cost Rs. - 4,99,798.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2448.19	Per Cubic metre	204.15	499798.00	Rupees Four Lakh Ninety Nine Thousand Seven Hundred & Ninety Eight Only
				Total	**499798.00**	

Bill of Qty approved
for Rs. 4,99,798/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:- Construction of Retaining wall in wire crate at Rds 1/320 to 1/343) Under PDNA

Estimated cost Rs. - 4,88,419.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	32.66	Per Cubic metre	552.35	18040.00	Rupees Eighteen Thousand &Fourty Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	143.75	Per Cubic metre	3140.50	451447.00	Rupees Four Lakh Fifty One Thousand Four Hundred & Fourty Seven Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	14.49	Per Cubic metre	1306.55	18932.00	Rupees Eighteen Thousand Nine Hundred & Thirty Two Only
				Total	488419.00	

Bill of Qty approved
Rs. 1,88,419/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:- Construction of embankment/filling in km 1/600 to 2/000) Under PDNA

Estimated cost Rs. - 4,94,535.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2422.41	Per Cubic metre	204.15	494535.00	Rupees Four Lakh Ninety Four Thousand Five Hundred & Thirty Five Only
				Total	**494535.00**	

Bill of Qty approved
@ - Rs. 4,94,535/ only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:- Construction of embankment/filling in km 2/000 to 2/500) Under PDNA

Estimated cost Rs. - 4,95,360.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2426.45	Per Cubic metre	204.15	495360.00	Rupees Four Lakh Ninety Five Thousand Three Hundred & Sixty Only
				Total	**495360.00**	

Bill of qty approved
for Rs. 4,95,360/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:-Removal of slip & land slides at various RDs in km 3/500 to 11/000) Under PDNA

Estimated cost Rs. - 4,96,834.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	4206.89	Per Cubic metre	118.10	496834.00	Rupees Four Lakh Ninety Six Thousand Eight Hundred & Thirty Four Only
				Total	**496834.00**	

Bill of qty approved
Rs. 4,96,834/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Janjehli Bekhali Gadagusaini road km 0/00 to 11/00 (SH:- Construction of embankment/Earth filling in km 2/900 to 3/200) Under PDNA

Estimated cost Rs. - 4,94,039.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2419.98	Per Cubic metre	204.15	494039.00	Rupees Four Lakh Ninety Four Thousand &Thirty Nine Only
				Total	**494039.00**	

Bill of qty approved for Rs. 4,94,039/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in PCC at Rd 2/675 to 2/688.20) Under PDNA 2023

Estimated cost Rs	4,96,826.00
Earnest Money Rs	10,000.00
Time - Two Months	

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	41.58	Per Cubic metre	552.35	22,967.00	Rupees Twenty Two Thousand Nine Hundred & Sixty Seven Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	86.59	Per Cubic metre	5236.10	4,53,394.00	Rupees Four Lakh Fifty Three Thousand Three Hundred & Ninety Four Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	15.00	Each	398.30	5,975.00	Rupees Five Thousand Nine Hundred & Seventy Five Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.09	Per Cubic metre	1306.55	14,490.00	Rupees Fourteen Thousand Four Hundred & Ninety Only
				Total	4,96,826.00	

Bill of qty approved for
Rs. 4,96,826/- only

Executive Engineer,
HPPWD Division
Sarai at Jagjehi

(343)

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in wire crate at Rd 1/710 to 1/723 & 2/010 to 2/020.50) Under PDNA 2023

Estimated cost Rs. - 4,99,059.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	33.37	Per Cubic metre	552.35	18432.00	Rupees Eighteen Thousand Four Hundred & Thirty Two Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS : 280 and IS : 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	146.88	Per Cubic metre	3140.50	461277.00	Rupees Four Lakh Sixty One Thousand Two Hundred & Seventy Seven Only
3	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	14.81	Per Cubic metre	1306.55	19350.00	Rupees Nineteen Thousand Three Hundred & Fifty Only
				Total	499059.00	

Bill of Qty approved
for Rs. 499059/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in CC at Rd 1/400 to 1/420) Under PDNA

Estimated cost Rs. - 4,52,350.00
Earnest Money cost Rs. - 9,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	32.00	Per Cubic metre	552.35	17675.00	Rupees Seventeen Thousand Six Hundred & Seventy Five Only
4	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	78.20	Per Cubic metre	5236.10	409463.00	Rupees Four Lakh Nine Thousand Four Hundred & Sixty Three Only
6	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.00	Each	398.30	7966.00	Rupees Seven Thousand Nine Hundred & Sixty Six Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	13.20	Per Cubic metre	1306.55	17246.00	Rupees Seventeen Thousand Two Hundred & Fourty Six Only
				Total	452350.00	

Bill of qty approved for
Rs 4,52,350 /- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Brast wall in wire crate at Rd 1/680 to 1/695 & 2/855 to 2/872) Under PDNA

Estimated cost Rs. - 4,96,174.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	45.44	Per Cubic metre	552.35	25099.00	Rupees Twenty Five Thousand &Ninety Nine Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	150.00	Per Cubic metre	3140.50	471075.00	Rupees Four Lakh Seventy One Thousand &Seventy Five Only
				Total	**496174.00**	

Bill of qty approved for Rs 4,96,174/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in wire crate at Rd 3/760 to 3/780) Under PDNA

Estimated cost Rs. - 4,24,713.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	28.40	Per Cubic metre	552.35	15687.00	Rupees Fifteen Thousand Six Hundred & Eighty Seven Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	125.00	Per Cubic metre	3140.50	392563.00	Rupees Three Lakh Ninety Two Thousand Five Hundred & Sixty Three Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	12.60	Per Cubic metre	1306.55	16463.00	Rupees Sixteen Thousand Four Hundred & Sixty Three Only
				Total	**424713.00**	

Bill of Qty approved for Rs 4,24,713 /- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in wire crate at Rd 2/540 to 2/555) Under PDNA

Estimated cost Rs. - 4,86,398.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	54.15	Per Cubic metre	552.35	29910.00	Rupees Twenty Nine Thousand Nine Hundred & Ten Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	140.55	Per Cubic metre	3140.50	441397.00	Rupees Four Lakh Fourty One Thousand Three Hundred & Ninety Seven Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	11.55	Per Cubic metre	1306.55	15091.00	Rupees Fifteen Thousand &Ninety One Only
				Total	**486398.00**	

Bill of Qty approved for Rs 4,86,398 /- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in CC at Rd 2/885 to 2/898) Under PDNA

Estimated cost Rs. - 4,91,388.00
Earnest Money cost Rs. - 10,000.00
Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	40.95	Per Cubic metre	552.35	22619.00	Rupees Twenty Two Thousand Six Hundred & Nineteen Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	85.28	Per Cubic metre	5236.10	446535.00	Rupees Four Lakh Fourty Six Thousand Five Hundred & Thirty Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.00	Each	398.30	7966.00	Rupees Seven Thousand Nine Hundred & Sixty Six Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	10.92	Per Cubic metre	1306.55	14268.00	Rupees Fourteen Thousand Two Hundred & Sixty Eight Only
				Total	491388.00	

Bill of qty approved for Rs 4,91,388 /- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:- RR Damages on Kadaun Helipad to Banadhar road km 0/00 to 4/700 (SH:- Construction of Retaining wall in PCC at Rd 2/575 to 2/588.20) Under PDNA 2023

Estimated cost Rs 4,98,817.00
Earnest Money Rs 10,000.00
Time - Two Months

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	41.58	Per Cubic metre	552.35	22,967.00	Rupees Twenty Two Thousand Nine Hundred & Sixty Seven Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	86.59	Per Cubic metre	5236.10	4,53,394.00	Rupees Four Lakh Fifty Three Thousand Three Hundred & Ninety Four Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.00	Each	398.30	7,966.00	Rupees Seven Thousand Nine Hundred & Sixty Six Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.09	Per Cubic metre	1306.55	14,490.00	Rupees Fourteen Thousand Four Hundred & Ninety Only
				Total	4,98,817.00	

Bill of qty approved for Rs. 4,98,817 only

Executive Engineer,
HPWD Division
Seraj at Jangehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Name of Work:-RR Damages on Jognidhar Bahlidhar road km 0/00 to 4/000 (SH:- Construction of Retaining wall in wire crate at Rds 2/460 to 2/473) Under PDNA 2023

Estimated cost Rs. - 3,82,283.00
Earnest Money cost Rs. - 8000.00
Time - Two Months

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	73.32	Per Cubic metre	552.35	40498.00	Rupees Fourty Thousand Four Hundred & Ninety Eight Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS : 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	101.53	Per Cubic metre	3140.50	318855.00	Rupees Three Lakh Eighteen Thousand Eight Hundred & Fifty Five Only
3	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.55	Per Cubic metre	1306.55	22930.00	Rupees Twenty Two Thousand Nine Hundred & Thirty Only
				Total	**382283.00**	

Bill of Qty approved
for Rs. 3,82,283/ only

Executive Engineer
Serai Division B&R
HPPWD Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: 4,24,983.00 Only
Earnest Money: 10,000.00 Only
Time : Two months.

Name of Work:- RRD on Khali Mo|d Doghari Sakaran road KM 0/00 to 7/100 (SH:- Removal of slips & Land slide in various RDs in KM 4/000 to 7/100).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	3598.50	Cum	118.10	4,24,983.00	Rupees Four Lakh(s) Twenty Four Thousand Nine Hundred Eighty Three Only
			Total:-		**4,24,983.00**	

Bill of Qty approved for Rs. 4,24,983/only

Executive Engineer
H.P.P.W.D. Division
Seraj at Janjehli

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: 4,90,186.00 Only
Earnest Money: 10,000.00 Only
Time : Two months.

Name of Work:- RRD on Varios road under Bagachanogi Section Janjehli Sub Division (SH:- Removal of slips & Land slide in various Roads).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	4150.60	Cum	118.10	4,90,186.00	Rupees Four Lakh(s) Ninety Thousand One Hundred Eighty Six Only
			Total:-		**4,90,186.00**	

Bill of Qty approved for Rs. 4,90,186/only

Executive Engineer
H.P.P.W.D. Division
Seraj at Janjehli

312

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: Rs. 4,15,635.00
Earnest Money: Rs. 8400.00 Only
Time :- Two Months

Name of Work :-RR Damages on various road Thunag Section Link road from Jhajar to Sanrout- Reunal GP Pakhrair in km 0/00 to 1/00, Link road from Rilla to Barkwali road in km 0/00 to 7/00 & Thunag Banyad Mandehlu road & Deji Banshil Shikari Mata road in km 0/00 to 1/00 (SH:- Removal of slips & land slides in various roads)

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	3519.35	Per Cubic metre	118.10	415635.00	Rupees Four Lakh Fifteen Thousand Six Hundred & Thirty Five Only
				Total	**415635.00**	

Bill of Qty approved for Rs. 4,15,635/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

254

Scanned with OKEN Scanner

BILL OF QUANTITY

Estimate Cost: 3,36,668.00 Only
Earnest Money: 6,000.00 Only
Time : Two months.

Name of Work:- RRD on Bagsaid Tikkar road KM 0/00 to 7/500 (SH:- Removal of slips & Land slide in various RDs in KM 0/000 to 6/800).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	2850.70	Cum	118.10	3,36,668.00	Rupees Three Lakh(s) Thirty Six Thousand Six Hundred Sixty Eight Only
			Total:-		**3,36,668.00**	

Bill of Qty approved
for Rs. 3,36,668/only

Executive Engineer
H.P.P.W.D. Division
Seraj at Janjehli

Scanned with OKEN Scanner

Name of Work :- RR Damages on Mandi Gagal Chail Janjehli Chhatri road km 0/00 to 82/00 (SH:- Removal of Slips & land slides at Various Rds in km 63/600 to 65/100)

Estimate Cost: Rs 4,09,600.00 Only
Earnest Money: 8,200.00 Only
Time :- Two Months

S. No.	Sub Head and item of work	Qyt.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 including carriage of material and other incidentials in all leads and lifts and as per direction of Engineer in charge .	3468.25	per Cubic metre	118.10	4,09,600.00	Rupees Four Lakh(s) Nine Thousand Six Hundred Only
			Total		**4,09,600.00**	

Bill of qty approved for Rs 409,600/only

Executive Engineer
Seraj Division (B&R)
HPPWD Janjehli

Scanned with OKEN Scanner