

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

10674

Dated:- 24-1-2026

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _

Regarding NIT for uploading on HP PWD website .


Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 05 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2025-26-10675-89 Dated:- 24-01-2026 are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 08.02.2026 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 06.02.2026 up to 4:00 P.M. and the application for issue of tender form shall be received on 05.02.2026 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan, Preparation of Revenue Papers for forest diversion case under FCA,1980 for the construction of link road to village Patola km 0/00 to 4/487 under Baroh Sub division in Tehsil Nagrota Bagwan, District Kangra HP (SH: Preparation of Forest Diversion case under FCA, 1980).	52947.00	1100.00	Three Months
2	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan, Preparation of Revenue Papers for forest diversion case under FCA,1980 for the construction of link road from Dehra Gabla Andar km 0/00 to 4/487 under Baroh Sub division in Tehsil Nagrota Bagwan, District Kangra HP (SH: Preparation of Forest Diversion case under FCA,1980).	45017.00	900.00	Three Months
3	Restoration of rain damages on link road from Dantehar to Chhimag Mandir km 0/00 to 2/200 in Dist. Kangra HP (SH: Construction of cement concrete shoulder at RD 2/070 to 2/093 (R/Side) and V- shape drain with Edge wall at RD 2/070 to 2/100 (R/Side).	84362.00	1700.00	Three Months
4	Construction of Protection Near the house Smt. Beena Devi W/O Late Sh. Kishori Lal Village Rangehar G.P. Saddun Bargran in District Kangra HP Deposit work (SH: Construction of Retaining wall VKV/2025/1203)	39918.00	800.00	One Month
5	Balance work of O.B.C. Bhawan Tidu Ram Baidh Bhawan at Baroh in Tehsil Baroh, Dist. Kangra HP Deposit Work (SH: Balane work of Civil Work including water supply and sanitary installation etc SDP/2022/478)	198100.00	4000.00	Two Months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.


HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26-10675-89 Dated/ 24-1-2026

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.


Executive Engineer
H.P.W.D. Tanda Division
at Nagrota Bagwan


Executive Engineer
H.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

Estimated Cost : 52947/-
 Earnest Money : 1100/-
 Time Limit : THREE MONTH

Name of Work:-

A/R Baroh Various roads under HPPWD Division at Nagrota Bagwan
 Preparation of Revenue Papers for forest diversion case under FCA, 1980 for the construction of Link Road to Village Patola 0/00 to 4/487 under Baroh Sub Division in Tehsil Nagrota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	4.487			Per Km	

Executive Engineer
HPPWD Division
Nagrota Bagwan

SCHEDULE OF QUANTITY

Estimated Cost : 45017/-
 Earnest Money : 900/-
 Time Limit : THREE MONTH

Name of Work:-

A/R & M/O on various roads under HPPWD Division Tanda at Nagrota Bagwan for Preparation of Revenue Papers for forest diversion case under FCA, 1980 for the construction of 1. Link Road from Dehra Gabla Andrar 0/00 to 3/013, 2. Link Road from Samloti to Bhorani 0/00 to 0/802 under Baroh Sub Division in Tehsil Nagrota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.815			Per Km	

Signature of
 HPPWD Division
 Tanda at Nagrota Bagwan


SCHEDULE OF QUANTITY

ESTIMATED COST :-
EARNEST MONEY :-
TIME LIMIT :-

₹ 84362.00
₹ 1700.00
TWO MONTH

NAME OF WORK:- Restoration of rain damages on link road from Damtehar to Chhirnag Mandir Km 0/000 to 2/200 in Distt. Kangra (H.P.)
SUB HEAD:- Construction of cement concrete shoulder at RD 2/070 to 2/093 (R/Side) and V-Shape drain with Edge wall at RD 2/070 to 2/100 (R/Side).

Sl. No.	Description	Quantity	In fig.	Rate in words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and running of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead as per H.P.PWD specifications including entire carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.40 Cubic meters	4	5	Per cubic metre	7
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with upto any lead complete as per H.P.PWD specifications including entire carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	42.90 Square metres			Per Square metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete and as per H.P.PWD specifications including entire carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.94 Cubic metres			Per cubic metre	
TOTAL:-						


Executive Engineer,
H.P.P.W.D Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :-

Construction of Protection near the house Smt. Beena Devi W/O Late Sh. Kishori Lal village Ranghar G.P. Saddun Bargan in District Kangra, (H.P.).

Deposit work.

SUB-HEAD :-

Construction of Retaining wall. VKV/2025/1203

Sr No.

Description of items

1	2	3	RATES		Unit	Amount
			4 In fig	5 In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	3.00 Cubic metres			Per cubic metre	
2	Providing and laying in position concrete of specified grade including the cost of centering and shuttering - All work up to plinth level concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	8.40 Cubic meters			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	5.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	2.25 Cubic metres			Per cubic metre	
TOTAL:-						

ESTIMATED COST :-

Rs.

39918.00

EARNEST MONEY :-

Rs

800.00

TIME LIMIT

ONE MONTH

Executive Engineer,
H.P.W.D. Division,
Tanda at Nagrota Bagwan.