

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

10643

Dated:- 22-1-2026

To,


The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _

Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 13 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide
this office letter No. PW-DT-NIT-2025-26- Dated:- are
urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **04.02.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **03.02.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **02.02.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of Room for Shiv Gouri Mahila Mandal in District Kangra HP Deposit Work (SH:Construction of Civil Work VKV/2025/279).	99170.00	2000.00	Three Months
2	Special Repair to various Hostel at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP (SH: Cleaning of Chocked Chamber in Senior Boys Hostel, Senior Girls Hostel, Satluj Hostel, Ravi Hostel, Vivekanand Hostel, MBBS 1 st Year Boys & Girls Hostel etc).	99000.00	1900.00	One Months
3	Construction of Danga Near the House of Smt. Santosh Kumari W/O Late Capt.. Sunil Kumar Tika Panol G.P. Sunhi in District Kangra H.P. Deposit Work (SH: Construction of Retaining wall. VKV/2025/1201).	39887.00	800.00	One Months
4	A/R & M/O of various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road from Dehra Gabla Andrar km 0/00to 3/013 under Baroh Sub Division in Tehsil Nagrota Bagwan District Kangra HP (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
5	A/R & M/O of various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road to Village Patola km 0/00 to 4/487 under Baroh Sub Division in Tehsil Nagrota Bagwan District Kangra HP (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
6	Construction of Community Play ground at Sunehar Ward No. 5 in Tehsil Nagrota Bagwan Distt. Kangra HP (SH: Construction of wood work tiles work, plastering and painating etc (VKV/2022/2215)	192730.00	3900.00	Two Months
7	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road from Samloti to Bhorni km 0/00 to 0/802 under Baroh Sub Division in Tehsil Nagrota Bagwan , District Kangra HP(SH: Preparation of Forest Diversion case under FCA,1980).	95000.00	1900.00	Six Months
8	Construction of link road from Danoa Bhorla Kandi road at Kangu Chowk to Krishan Chand House in G.P. Danoa in District Kangra HP Deposit Work (SH construction of Breast Wall at RD 0/100 to 0/120, G-II & CC Pavement at RD 0/060 to 0/083 SDF/2025/140).	149960.00	3000.00	Three Months
9	Restoration of rain damanges on link road from Sakreh to Damtehar road km 0/00 to 6/00 in District Kangra HP Deposit work (SH: Construction of Retaining wall at Rd 0/825 to 0/827.34 SDF/2024/485).	99065.00	2000.00	Two Months
10	Mahila Mandal Bhawan in village Gadiara in G.P. Ustehar in District Kangra HP Deposit work (SH: Construction of civil work).	249985.00	5000.00	Three Months
11	Restoration of rain damages on link road from Yol to 53 Mile road (Yol Rajiana road) km 0/00to 10/550 in Distt. Kangra (SH: Repair of damaged Rain Shelter at RD 6/810 i.e. cement concrete work and MS B.P. Sheet work etc).	77326.00	1600.00	Two Months
12	Restoration of rain damages on link road from NH 88 paisa Chowk to Harizan Basti Balugaloa District Kangra HP (SH: Providing and laying G-III & cement concrete at RD 1/170 to 1/201.50).	98906.00	2000.00	One Months
13	Construction of Retaining wall to avoid Land Erosion near the house of Sh. Bahadur Singh S/O Rolu Ram Tika Kanol Rihiri Khawa in District Kangra HP Deposit Work (SH: Construction of Retaining wall. VKV/2025/1086).	49778.00	1000.00	One Month

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26-10644-58 Dated/ 22-1-2026

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **04.02.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **03.02.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **02.02.2026** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of Room for Shiv Gouri Mahila Mandal in District Kangra HP Deposit Work (SH:Construction of Civil Work VKV/2025/279).	99170.00	2000.00	Three Months
2	Special Repair to various Hostel at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP (SH: Cleaning of Chocked Chamber in Senior Boys Hostel, Senior Girls Hostel, Satluj Hostel, Ravi Hostel, Vivekanand Hostel, MBBS 1 st Year Boys & Girls Hostel etc).	99000.00	1900.00	One Months
3	Construction of Danga Near the House of Smt. Santosh Kumari W/O Late Capt.. Sunil Kumar Tika Panol G.P. Sunhi in District Kangra H.P. Deposit Work (SH: Construction of Retaining wall. VKV/2025/1201).	39887.00	800.00	One Months
4	A/R & M/O of various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road from Dehra Gabla Andrar km 0/00to 3/013 under Baroh Sub Division in Tehsil Nagrota Bagwan District Kangra HP (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
5	A/R & M/O of various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road to Village Patola km 0/00 to 4/487 under Baroh Sub Division in Tehsil Nagrota Bagwan District Kangra HP (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
6	Construction of Community Play ground at Sunehar Ward No. 5 in Tehsil Nagrota Bagwan Distt. Kangra HP (SH: Construction of wood work tiles work, plastering and painting etc (VKV/2022/2215)	192730.00	3900.00	Two Months
7	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA, 1980 for the construction of link road from Samloti to Bhomi km 0/00 to 0/802 under Baroh Sub Division in Tehsil Nagrota Bagwan, District Kangra HP(SH: Preparation of Forest Diversion case under FCA,1980).	95000.00	1900.00	Six Months
8	Construction of link road from Danoa Bhorla Kandi road at Kangu Chowk to Krishan Chand House in G.P. Danoa in District Kangra HP Deposit Work (SH construction of Breast Wall at RD 0/100 to 0/120, G-II & CC Pavement at RD 0/060 to 0/083 SDF/2025/140).	149960.00	3000.00	Three Months
9	Restoration of rain damanges on link road from Sakreh to Damtehar road km 0/00 to 6/00 in District Kangra HP Deposit work (SH: Construction of Retaining wall at Rd 0/825 to 0/827.34 SDF/2024/485).	99065.00	2000.00	Two Months
10	Mahila Mandal Bhawan in village Gadiara in G.P. Ustehar in District Kangra HP Deposit work (SH: Construction of civil work).	249985.00	5000.00	Three Months
11	Restoration of rain damages on link road from Yol to 53 Mile road (Yol Rajiana road) km 0/00to 10/550 in Distt. Kangra (SH: Repair of damaged Rain Shelter at RD 6/810 i.e. cement concrete work and MS B.P. Sheet work etc).	77326.00	1600.00	Two Months
12	Restoration of rain damages on link road from NH 88 paisa Chowk to Harizan Basti Balugaloa District Kangra HP (SH: Providing and laying G-III & cement concrete at RD 1/170 to 1/201.50).	98906.00	2000.00	One Months
13	Construction of Retaining wall to avoid Land Erosion near the house of Sh. Bahadur Singh S/O Rolu Ram Tika Kanol Rihiri Khawa in District Kangra HP Deposit Work (SH: Construction of Retainig wall. VKV/2025/1086).	49778.00	1000.00	One Month

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- **10644-58** Dated/ **22-1-2026**

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 99170.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Room for Shiv Gouri Mahila Mandal in District Kangra, (H.P.). Deposit work.

SUB-HEAD:- Construction of Civil work. VKV/2025/279

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	3 6.91 Cubic metres	4	5	6 Per cubic metre	7
2	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etcetera, with wooden battens and ballies for all heights/depth of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in Foundation footings, bases of columns and mass concrete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	7.12 Square metres			Per square metre	
3	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etcetera, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in columns, pillar, piers, abutments, post and struts including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	13.44 Square metres			Per square metre.	
4	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etcetera; with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in Lintals beams, plinth beams, cantilevers, girders, including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications, entire satisfaction and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	15.36 Square metres			Per square metre.	

5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	0.58 Cubic metres			Per cubic metre
6	Providing and laying cement concrete work of grade M-20 (M- twenty) design mix to obtain the minimum compressive strength of 20N/mm square (Twenty Newton per square millimetre) with cement contents not less than 320 kg (Three hundred twenty kilograms) per cubic meter, mechanically mixed and vibrated including curing complete, excluding cost of form work and reinforcement for reinforced concrete work in columns, pillars posts and struts for all floors heights complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.00 Cubic metres			Per cubic metre
7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level cement concrete 1:1.5:3 (One cement; one point five sand; three graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size, excluding cost of centering, shuttering, finishing and reinforcement complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.01 Cubic metres			Per cubic metre
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with cement concrete 1:1.5:3 (One cement; one point five sand; three graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	3.79 Cubic metres			Per cubic metre
9	Providing Tor steel reinforcement of Thermo Mechanically Treated bars of grade Fe-500D of Tata Tiscon/Sail for reinforced cement concrete work including bending, binding, cutting, straightening and placing in position complete including cost of binding wires complete upto all floor levels as per approved specifications, drawing, design, as per entire satisfaction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals.	430.85 Kilograms			Per kilo-gram
TOTAL :-					


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Special repair to Various Hostel at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.)
SUB HEAD :- Cleaning of Chocked Chamber in Senior Boys Hostel, Senior Girls Hostel, Satluj Hostel, Ravi Hostel, Vivekanand Hostel, MBBS 1st Year Boys & Girls Hostel etc.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Cleaning of Chocked Chambers complete as per direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals.	55 Numbers			Each	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagoya Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 39887.00
 EARNEST MONEY :- Rs. 800.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Danga near the House of Smt. Santosh Kumari W/O Late Capt. Sunil Kumar Tika Panol G.P. Sunhi in District Kangra, (H.P.). **Deposit work.**

SUB-HEAD :- Construction of Retaining wall. **VKV/2025/1201.**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	5.11 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	9.25 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	2.50 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	0.67 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

Estimated Cost : 95000/-
Earnest Money : 1900/-
Time Limit : SIX MONTH

Name of Work:-

A/R & M/O on various roads under HPPWD Division Tanda at Nagrota Bagwan for Preparation of forest diversion case under FCA, 1980 for the construction of Link Road from Dehra Gaba Andrar 0/00 to 3/013 under Baroh Sub Division in Tehsil NagrotaBagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1 Number			Each	

Executive Engineer
HPPWD Division
Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

Estimated Cost :95000/-
 Earnest Money :1900/-
 Time Limit : SIX MONTH

Name of Work:-

Preparation of forest diversion case under FCA, 1980 for the construction of Link Road to Village Patola0/00 to 4/487under BarohSub Division in Tehsil NagrotaBagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1 Number			Each	


 Executive Engineer
 HPPWD Division
 Tehsil Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 192730.00
 EARNEST MONEY :- ₹ 3900.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Community Play Ground at Sunehar Ward No-5 in Tehsil Nagoya Bagwan, Distt. Kangra (H.P.)

SUB-HEAD :- Construction of wood work, tiles work, plastering and painting etc; (VKV/2022/2215).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing Sal wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) complete including entire carriage of materials within all leads lifts and other incidentals and as directed by the Engineer-in-Charge.	0.08 Cubic metres			Per cubic metre	
2	Providing and fixing 35mm (Thirty five millimetre) thick panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, Kiln seasoned selected planks of sheesham wood complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	4.51 Square metres			Per square metre	
3	Providing and fixing 35mm (Thirty five millimetre) thick Second class teak wood wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (One point four millimetre) in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : with ISI marked M.S. pressed butt hinges bright finished of required size complete and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	7.28 Cubic meters			Per cubic metre	
4	Providing and fixing 35mm (Thirty five millimetre) thick glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	7.28 Cubic meters			Per cubic metre	
5	Providing and fixing 300x16mm (Three hundred into Sixteen millimetres) size aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	2 Number			each	

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
6	Providing and fixing 150x10mm (One hundred fifty into Ten millimetres) size aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	52 Numbers			Each	
7	Providing and fixing 100mm (One hundred millimetres) size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	26 Numbers			Each	
8	Providing and fixing 200mm (Two hundred millimetres) size bright finished brass hard drawn hooks and eyes complete with necessary screws etc; complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	12 Numbers			Each	
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm complete and as per direction of Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	36.21 Square metres			Per square metre	
10	6mm (Six millimetres) thick cement plaster to ceiling in cement mortar 1:3 (One cement: Three sand) upto all floor levels complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	69.62 Square metres			Per square metre	
11	15mm (Fifteen millimetres) thick cement plasters in single coat on fair/rough side of brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:4 (One cement : Four sand) complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	149.22 Square metres			Per Square metre	
12	Providing and applying white cement based putty of Birla / JK average thickness 1mm (One millimetres) thick, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	149.22 Square metres			Per square metre	

3

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
13	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre (Fifty grams per liter) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives complete. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (One point four three litre per ten square metre) Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point nine zero litre per ten square metre) complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	30.68 Square metres			Per square metre	
14	Wall painting (two coats) with premium acrylic emulsion paint of approved brand and manufacture on decorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	146.00 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P. WD., Division,
 Tanda at Nagrota Bagwan.


SCHEDULE OF QUANTITY

Estimated Cost : 95000/-
 Earnest Money : 1900/-
 Time Limit : SIX MONTH

Name of Work:- A/R & M/O on various roads under HPPWD Division Tanda at Nagrota Bagwan for Preparation of forest diversion case under FCA, 1980 for the construction of Link Road from Samloti to Bhorni 0/00 to 0/802 under Baroh Sub Division in Tehsil Nagrota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1 Number			Each	


 Executive Engineer
 HPPWD Division
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 149960.00
 EARNEST MONEY :- Rs. 3000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road from Danoa Bhorla Kandi road at Kangu Chowk to Krishan Chand House in G.P. Danoa in District Kangra, (H.P.). **Deposit work.**

SUB-HEAD :- Construction of Breast wall at RD 0/100 to 0/120, G-II & CC Pavement at RD 0/060 to 0/083. **SDP/2025/140**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	8.90 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	19.75 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	15.00 Running metre			Per running metre	
4	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	4.95 Cubic metres			Per cubic metre	

5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	8.95 Cubic metres		Per cubic metre
TOTAL:-				



Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99065.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road from Sakreh to Damtehar road Km 0/000 to 6/000 in Distt. Kangra (H.P.), DEPOSIT WORK.
 SUB HEAD:- Construction of Retaining wall at RD 0/825 to 0/827.34 (SDF/2024/485)

Sr. No.	Description	Quantity	In fig.	Rate in words	Unit	Amount
			4	5		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	3 9.08 Cubic metres			6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	23.12 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	4.00 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3.32 Cubic metres			Per cubic metre	
TOTAL:-						-


 Executive Engineer,
 H.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 249985.00
 EARNEST MONEY :- Rs. 5000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Mahila Mandal Bhawan in village Gadiara in G.P. Ustehar in District Kangra, (H.P.). **Deposit work.**

SUB-HEAD:- Construction of Civil work.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	14.08 Cubic metres			Per cubic metre	
2	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etcetera, with wooden battens and ballies for all heights/depth of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings balconies and access platform including carriage of material within all leads, lifts and other incidentals and as directed by the Engineer-in-charge.	24.85 Square metres			Per square metre	
3	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etcetera; with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in Lintals beams, plinth beams, cantilevers, girders, including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications, entire satisfaction and as directed by the Engineer-in-charge.	19.39 Square metres			Per square metre.	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.41 Cubic metres			Per cubic metre	
5	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement : Six sand : Twelve graded crushed stone aggregate 20mm (Twenty millimetre) nominal size at plinth level in cement mortar 1:6 (One cement: Six sand) complete, including carriage of material within all leads, lifts and other incidentals, as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	8.14 Cubic metre			Per cubic metre	

6	Providing and laying cement concrete work of grade M-20 (M- twenty) design mix to obtain the minimum compressive strength of 20N/mm square (Twenty Newton per square millimetre) with cement contents not less than 320 kg (Three hundred twenty kilograms) per cubic meter, mechanically mixed and vibrated including curing complete, excluding cost of form work and reinforcement for reinforced concrete work in columns, pillars posts and struts for all floors heights complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.16 Cubic metres			Per cubic metre
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with cement concrete 1:1.5:3 (One cement; one point five sand; three graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	5.02 Cubic metres			Per cubic metre
8	Providing Tor steel reinforcement of Thermo Mechanically Treated bars of grade Fe-500D of Tata Tiscon/Sail for reinforced cement concrete work including bending, binding, cutting, straightening and placing in position complete including cost of binding wires complete upto all floor levels as per approved specifications, drawing, design, as per entire satisfaction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals.	750.50 Kilograms			Per kilo-gram
9	Brick work using Second class common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:6 (One cement isto Six sand) and curing complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	11.56 Cubic metres			Per cubic metre
TOTAL :-					


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of rain damages on link road from Yol to 53 Mile road (Yol Rajiana road) Km 0/000 to 10/550 in Distt. Kangra (H.P.).
SUB-HEAD :- Repair of damaged Rain Shelter at RD 6/810 i.e. cement concrete work and MS B.P. sheet work etc;
ESTIMATED COST :- ₹ 77326.00
EARNEST MONEY :- ₹ 1600.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3 2.98 Cubic metres	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete and as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	5.46 Cubic metres			Per cubic metre	
3	Providing and fixing M.S. B.P. sheet 1.66 mm to 2mm thick in eaves board/facia/soffits/ ceiling including cutting, Fixing and welding to seal roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	37.10 Square metres			Per square metre	
Total :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 98906.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Restoration of rain damages on link road from NH-88 paisa Chowk to Harizan Basti Balugaloa District Kangra, (H.P.).
SUB-HEAD :- Providing and laying G-III & cement concrete at RD 1/170 to 1/201.50.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig 4	In words 5		
1	2 Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	3 7.09 Cubic metres		5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	14.18 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 49778.00
 EARNEST MONEY :- Rs. 1000.00
 TIME LIMIT : ONE MONTH
 Construction of Retaining wall to avoid Land Erosion near the house of Sh. Bahadur Singh S/O Rolu Ram Tika Kanol Rihri Khawa in District Kangra, (H.P.). **Deposit work.**

NAME OF WORK :-

SUB-HEAD :- Construction of Retaining wall. **VKV/2025/1086**

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	2.80 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	10.92 Cubic meters			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	5.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	1.20 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.