

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

10573

Dated:- 21-1-2026

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _

Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 16 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2025-26-10574-88 Dated:- 21-01-2026 are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **30.01.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **29.01.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **28.01.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road to village Khanog Km 0/00 to 1/500 in Distt. Kangra HP (SH: Providing and laying cement concrete pavement at Rd 0/150 to 0/178).	98910.00	2000.00	Two Months
2	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA. 1980 for the construction of link road from Rounkhar to Kaled Joining Poud km 0/00 to 2/969 under Nagrota Bagwan HP PWD Sub- Divisio in Tehsil Nagrota Bagwan, District Kangra HP. (SH: Preparation of Forest Diversion case under FCA, 1980).	42041.00	900.00	Three Months
3	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA. 1980 for the construction of link road Ramehar Tangroti Dhaloon road km0/00 to 4/990 under Nagrota Bagwan HP PWD Sub- Divisio in Tehsil Nagrota Bagwan, District Kangra HP. (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
4	Restoration of rain damages on link roadf Ustehar Nougzza Behra Banjar km 0/00 to 2/00 in Distt. Kangra HP (SH: Construction of Parapets at various Rd,s).	85560.00	1750.00	Two Months
5	Construction of road from Jalot Bhoma Jamula road km 0/00 to 2/00 in District Kangra HP (SH: Providing and laying soling & wearing at RD 0/590 to 0/680).	98906.00	1980.00	Two Months
6	A/R & M/O various roads under HP PWD Division Tanda at Nagrota Bagwan Preparation of forest diversion case under FCA. 1980 for the construction of link road from Malan to Garh Mata Mandir under Nagrota Bagwan HP PWD Sub- Divisio in Tehsil Nagrota Bagwan, District Kangra HP. (SH: Preparation of Forest Diversion case under FCA, 1980).	95000.00	1900.00	Six Months
7	Restoration of rain damages on link road from NH88 Paisa Chowk to Harizan Basti Balugaloa Distrikt Kangra HP (SH: Providing and laying G-III & cement concrete at RD 1/201.50 to 1/233).	98906.00	2000.00	One Months
8	Construction of Shed for Langar Near the statue of Shaheed Parveen Kumar at Aerla in Tehsil Baroh, Distt. Kangra HP Deposit work (SH: Construction of steel truss Shed etc: VKV/2025/550).	88037.00	1800.00	Two Months
9	Construction of link road to Dehru in G.P. Aerla in District Kangra HP Deposit work (SH: Construction of Breast wall at Rd 0/610 to 0/624. SDP/2025/135).	99885.00	2000.00	One Months
10	Restoration of rain damages on link road from Sakreh to damtehar road km0/00 to 6/00 in District Kangra HP Deposit work (SH: Construction of Retaining wall at RD 0/827.34 to 0/829.68 SDF/2025/544).	99017.00	2000.00	Two Months
11	Restoration of rain damages on link road from Sakreh to Damtehar road km 0/00 to 6/00 in District Kangra HP Deposit work (SH: Construction of Retaining wall at Rd 0/829.68 to 0/832.02 SDF/2024/1604).	99187.00	2000.00	Two Months
12	Repair work of Health Welfare centre (HWC) at Barana inTehsil Barh Distt. Kangra HP Deposit work (SH: Construction of Civil Work etc).	99999.00	2000.00	Two Months
13	Construction of link road from Dehri to Topu Nallah Ward No. 3 in District Kangra HP Deposit Work (SH: Providing and laying G-III & Cement concrete at RD 0/00 to 0/064. VKV/2025/276).	199578.00	4000.00	Three Months
14	Construction of Community Play Ground at Tikka Barai Ward No. 1 in Tehsil Nagrota Bagwan Distt. Kangra HP Formation cutting and cement concrete pavement road in km 0/00 to 0/026.50 Deposit Work VKV/2022/2213).	86240.00	1750.00	Two Months
15	Repair of Type-III Block N. Qtr. No. 6 in Dr. R.P. Govt. Medical College Tanda in District Kangra HP Deposit work (SH: Painting Curtain Rod, Glass Panes and Sanitary work etc).	75275.00	1550.00	Two Months
16	Construction of Protection wall behind the Residence of Sh. Amar Nath S/O Late Sh. Munshi Ram and Dalip Singh S/O Munish Ram Saddun Bargran in District Knagra HP Deposit work (SH: Construction of Retaining wall VKV/2025/1084).	49927.00	1000.00	One Months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

No.PW/NBD/TA/Tender/NIT/2025-26-10574-88 Dated/ 21-1-2026
Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST :- ₹ 98910.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road to village Khanog Km 0/000 to 1/500 in Distt. Kangra (H.P.).
 SUB HEAD :- Providing and laying cement concrete pavement at RD 0/150 to 0/178

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point Twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	6.30 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	14.70 Cubic metres			Per cubic metre	
					TOTAL :-	


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

Estimated Cost : 42041/-
 Earnest Money : 900/-
 Time Limit : THREE MONTHS

At R.P.W.D. Division Tanda at Nagrota Bagwan

Name of Work:-

Preparation of Revenue Papers for forest diversion case under FCA, 1980 for the construction of Link Road from Rounkhar to Kaled Joining Poud Km 0/00 to 2/969 under Nagrota Bagwan Sub Division in Tehsil Nagrota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.969			Per Kilometer	
Total:-						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

Estimated Cost : 95000/-
 Earnest Money : 19000/-
 Time Limit : SIX MONTHS

Name of Work:-

At 188 m/p various roads under HPPWD Division Tanda at Nagrota Bagwan

Preparation of forest diversion case under FCA, 1980 for the construction of Link Road Ramehar Tangroti Dhaloon Road Km 0/00 to 4/990 under Nagrota Bagwan HPPWD Sub Division in Tehsil Nagota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1 Number			Each	
Total:-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagoya Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 85560.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road Ustehar Nougazza Behra Banjar Km 0/000 to 2/000 in Distt. Kangra (H.P.)
 SUB HEAD:- Construction of Parapets at various RD's.

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete and as per HP.PWD specifications including entire carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3	4	5	6	7
		18.40			Per cubic metre	
						TOTAL:-


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 98906.00
EARNEST MONEY :- Rs. 1980.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of road from Jalot Bhorla Jamula road km 0/000 to 2/000 in District Kangra, (H.P.).

SUB-HEAD :- Providing and laying soling & wearing at RD 0/590 to 0/680.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing, laying, spreading and compacting stone aggregate size 90mm to 45mm (Ninety millimeter to forty five millimeter) Grading-I size [100mm (One hundred millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two milimetres) nominal size at the rate of 0.30cum (zero point thirty cubic metres) per ten square metres and binding material at the rate of 0.08 cum (zero point zero eight cubic metre) per 10 Sqm (ten square meter) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3 28.36 Cubic metres	4	5	6 Per cubic metre	7 7
2	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	21.27 Cubic metres			Per cubic metre	
TOTAL :-						


Executive Engineer,
H.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

Estimated Cost : 95000/-
 Earnest Money : 1900/-
 Time Limit : SIX MONTHS

Name of Work:-

A/R & M/O on various roads under HPPWD Division Tanda at Nagrota Bagwan for Preparation of Revenue Papers for forest diversion case under FCA, 1980 for the construction of link road from Malan to Garh Mata Mandir under Nagrota Bagwan Sub Division in Tehsil Nagrota Bagwan, District Kangra (H.P.).

(SH:- Preparation of Forest Diversion Case under FCA, 1980)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1 Number			Each	
Total :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :-	Rs.	98906.00
EARNEST MONEY :-	Rs.	2000.00
TIME LIMIT	:	ONE MONTH

NAME OF WORK :- Restoration of rain damages on link road from NH-88 paisa Chowk to Harizan Basti Balugaloa District Kangra, (H.P.).

SUB-HEAD :- Providing and laying G-III & cement concrete at RD 1/201.50 to 1/233.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	7.09 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	14.18 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-

Construction of Shed for Langar near the statue of Shaheed Parveen Kumar at Aerla in Tehsil Baroh, Distt. Kangra (H.P.). DEPOSIT WORK.

SUB-HEAD :-

Construction of steel truss Shed etc; (VKV/2025/550).

ESTIMATED COST:- ₹ 88037.00
EARNEST MONEY:- ₹ 1800.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	3	4	5	6	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	0.86				
3	Providing and laying cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size including centering, shuttering with mechanically mixed and curing complete excluding cost of forms work in foundation and plinth, as directed by the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	0.22				
4	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel in grating, frames, guard bar ladder, railings, bracket, gate and similar work complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	523.33				
5	Providing and fixing 0.60 mm (Zero point six zero millimetres) thick with zinc coating not less than 275 gm/ m ² corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	13.65				
6	Providing and fixing ridges or hips 60cm (Sixty centimeters) over all with 0.60mm (Zero point Sixty millimeters) thick pre-painted sheet roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with prepared iron J or L hooks, bolts and nuts 6mm (Six millimeters) diameters with prepared G.I. limpet and bitumen washers complete with all accessories as required complete and as directed by the Engineer-In-charge including carriage of material within all leads, lifts of materials and other incidentals	1.95				

3

plying, filling, spreading & leveling stone boulders under floors as per direction of Engineer-in-charge. as directed by the Engineer-In-charge, including carriage of materials within all leads, lifts and other incidentals.	1.71 Cubic metres
viding and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal complete and as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	1.71 Cubic metres
iting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm to point ninety liter / Ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eighty liter / square metre) of approved brand and manufacture including carriage of materials as directed by the Engineer-in-Charge, in all leads, lifts and other incidentals.	13.65 Square metres


 Executive Engineer
 HPPWD Division
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 99885.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of link road to Dehru in G.P. Aerla in District Kangra, (H.P.). Deposit work.

SUB-HEAD :- Construction of Breast wall at RD 0/610 to 0/624. SDP/2025/135

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	8.66 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	23.50 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	10.00 Running metre			Per running metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99017.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road from Sakreh to Dantehar road Km 0/000 to 6/000 in Distt. Kangra (H.P.), DEPOSIT WORK.
 SUB HEAD: - Construction of Retaining wall at RD 0/827.34 to 0/829.68 (SDF/2025/544).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	9.06 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	23.10 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	4.00 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3.37 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99187.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road from Sakreh to Damtehar road Km 0/000 to 6/000 in Distt. Kangra (H.P.). DEPOSIT WORK.
 SUB HEAD:- Construction of Retaining wall at RD 0/829.68 to 0/832.02 (SDF/2024/1604)

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	9.07 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	23.14 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	4.00 Running metres			Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3.38 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99999.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Repair work of Health Welfare Centre (HWC) at Barana in Tehsil Barh, Distt. Kanga (I.L.P.) DEPOSIT WORK.
 SUB-HEAD :- Construction of civil work etc;

S. No.	Description of Items	Quantity	In fig 4	Rate In words 5	Unit	Amount
1	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel in grating, frames, guard bar ladder, railings, bracket, gate and similar work complete including carriage of material within all leads, lifts and other incidentals and further as per HPPWD specifications, approved drawing, design and as directed by the Engineer-in-charge.	3 684.11 Kilogram			Per kilo gram	7
2	Providing and fixing 6 mm thick Cement fiber board as per IS: 14862 plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately) complete including carriage of material within all leads, lifts and other incidentals and further as per HPPWD specifications, approved drawing, design and as directed by the Engineer-in-charge.	46.02 Square metres			Per square metre	
3	Providing and fixing Kiln seasoned and chemically treated hollock wood specified wood frame work of doors, windows, clerestory windows and other frame, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs of dash fastener shall be paid for seperately) complete including carriage of material within all leads, lifts and other incidentals and further as per HPPWD specifications, approved drawing, design and as directed by the Engineer-in-charge.	0.04 Cubic metres			Per cubic metre	
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete including carriage of material within all leads, lifts and other incidentals and further as per HPPWD specifications, approved drawing, design and as directed by the Engineer-in-charge.	10.10 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 199578.00
 EARNEST MONEY :- Rs. 4000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of link road from Dehri to Topu Nallah Ward No. 3 in District Kangra, (H.P.). Deposit work
SUB-HEAD :- Providing and laying G-III & cement concrete at RD 0/000 to 0/064. VKV/2025/276

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental.	3 14.20 Cubic metres	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	28.65 Cubic metres			Per cubic metre	
TOTAL :-						



 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 86240.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Community Play Ground at Tikka Barai Ward No-1 in Tehsil Nagoya Bagwan, Distt. Kangra (H.P.)
SUB-HEAD :- Formation cutting and cement concrete pavement road in Km 0/000 to 0/026.50 (Deposit Work) (VKV/2022/2213).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases.	3 194.19 Cubic meters	4	5	6 Per cubic metre	7
2	Supplying, filling, spreading & leveling stone boulders of under floor wherever required thickness complete and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	7.55 Cubic meters			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand) : Four graded stone aggregate 20 mm (Twenty millimetres) nominal size as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	7.55 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Repair of Type-III Block N-Qtr No. 6 in Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) DEPOSIT WORK.
SUB-HEAD :- *Painting, Curtain Rod, Glass panes and Sanitary work etc;*
ESTIMATED COST:- ₹ 75275.00
EARNEST MONEY :- ₹ 1550.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats as per direction of Engineer - in - charge Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) complete as per direction of Engineer-in- Charge including carriage of materials within all leads, lifts and other incidentals.	3 206.90 Square metres	4	5	6 Per square metre	7
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete excluding cost of forms work in foundation and plinth, as directed by the Engineer-In-Charge, including carriage of materials within all leads, lifts and other incidentals.	124.14 Square metres			Per square metre	
3	Painting with synthetic enamel paint Two or more coats of approved brand and manufacture of required colour to give an even shade complete all as per direction of Engineer-in-Charge as directed by the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals.	132.55 Square metres			Per square metre	
4	Providing and fixing 15mm (Fifteen millimetres) diameters long nose brass bib cock (Superior or heavy type) Cera, Jaquar and Hindware complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
5	Providing and fixing 32mm (Thirty two millimetres) diameters P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings Flexible pipe complete and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
6	Providing and fixing 15mm (Fifteen millimetres) C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
7	Providing and fixing 100 mm sand cast Iron grating for gully trap. including cariae of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	2 Numbers			Each	
8	Providing and fixing 15mm (Fifteen millimetres) nominal size uplasticised PVC connection pipe with brass unions : 45 cm length and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	3 Numbers			Each	

5

9	Providing and fixing 25 mm (Twenty five millimetre) dia chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. including carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	7.60 Running metres			Per running metre.
10	Renewing glass panes with putty and nails wherever necessary including racking out the old putty Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm) and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals.	1.60 Square metres			Per Square metre
11	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	1 Number			Each
12	Providing and fixing 110mm (One hundred ten millimetre) dia PVC pipe including all fitting complete and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	69.00 Running metres			Per running metre.
TOTAL :-					


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 49927.00
EARNEST MONEY: - Rs. 1000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Protection wall behind the Residence of Sh. Amar Nath S/O Late Sh. Munshi Ram and Dalip Singh S/O Munshi Ram Saddun Bargran in District Kangra, (H.P.).

Deposit work.

SUB-HEAD :- Construction of Retaining wall. VKV/2025/1084

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	3.69 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	10.95 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	5.00 Running metre			Per running metre	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	0.86 Cubic metres			Per cubic metre	
TOTAL:-						


Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.