

Himachal Pradesh  
Public Works Department

NO/PW/TLD/Tender/2025: -12053-62  
To

Dated: - 31/12/25

The Executive Engineer IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

HPPWD Mandi for information please.


Copy is forwarded to Superintending Engineer, 1<sup>st</sup> Circle,

Division.

Copy to All the Assistant Engineers working under this

Copy to AB/DB in this office.

Copy to Notice board.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER"**

Sealed Percentage tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 07.01.2026 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 05.01.2026 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 06.01.2026 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, HPPWD Divisio (B&R), Thalout at Pandoh during office hour on any working day.


Sr. No.	Name of work	Estim ated cost	Earnest money	Cost of form	Time Period	For m No.	Eligib ility of Contr actors
1	RRD on Mani to Segali road Km. 0/0 to 4/500 (SH: - Removal of snow/slips, unlined drain, muck debries at various RDs)	99970	2,000	Rs. 350/-	One month	6&8	D
2	RRD on Hanogi to Bandhi rad Km. 0/0 to 15/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job-1	99600	2,000	Rs. 350/-	One month	6&8	-do-
3	RRD on Thalout Panjain Thachi Shetadhar road Km. 0/0 to 40/00 (SH: Removal of snow/slips/boulders, muck debries, etc. at RD 25/000 to 40/000).	99236	2,000	Rs. 350/-	One month	6&8	-do-
4	C/o Surad Mahudhar to Nalwagi road Km. 0/0 to 5/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/0 to 5/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
5	RRD on Bali to Thachi road Km. 0/00 to 25/00 (SH: F/C 5/7 mtr wide at RD 6/055 to 6/110).	96201	2,000	Rs. 350/-	One month	6&8	-do-
6	RRD on Dhamu to Deori road Km. 0/0 to 2/650 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in Km. 0/0 to 2/650).	99600	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on Burah to Panjain road Km. 0/00 to 11/000 (SH: Removal of snow/slips, unlined drain, muck debries at various RDs between 0/00 to 3/00).	99970	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on Hatoun Bhavash Muthal road KM. 0/0 to 6/500 (SH: Hiring of excavator cum loader for slips/clearance of berms, debris etc. at various RDs in Km. 3/0 to 6/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on Thalout Panjain Thachi Shetadhar road Km. 0/0 to 40/00 (SH: -Removal of snow/slips/boulders, muck debries etc. RD 15/00 to 25/00).	99236	2,000	Rs. 350/-	One month	6&8	-do-
10	RRD on Masar to Binoul road km. 0/0 to 4/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in Km. 0/0 to 4/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
11	RRD on Burah to Panjain road Km. 0/00 to 11/00 (SH: - Removal of snow/slips, unlined drain, muck debries at various RDs between 3/00 to 6/00).	99970	2,000	Rs. 350/-	One month	6&8	-do-
12	RRD on Hatoun Bhavash Muthal road KM. 0/0 to 6/500 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in Km. 0/0 to 3/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-

13	RRD on Bali to Thachi road Km. 0/00 to 25/00 (SH: F/C 5/7 mtr wide at RD 6/010 to 6/055).	96204	2,000	Rs. 350/-	One month	6&8	-do-
14	C/o Govt. Senior Secondary School Deori (SH: Earthwork in filling for construction of playground) Job No. 1	99185	2,000	Rs. 350/-	One month	6&8	-do-
15	Repair and Maintenance of Govt. Sen. Sec. School at Balichowki in Tehsil Balichowki Mandi (HP) (SH: - P/L PCC 1:4:8 Repairs Plaster and Kota Stone). Deposit	97321	2,000	Rs. 350/-	One month	6&8	-do-
16	RRD on Dhamu to Masar road Km. 0/0 to 4/500 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in Km. 0/0 to 4/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
17	RRD on Sudharani to Teeldhar road Km. 0/00 to 4/500 (SH: - Removal of snow/slips, unlined drain, muck debries at various RDs).	99970	2,000	Rs. 350/-	One month	6&8	-do-
18	C/o Lambathach Kalhani Pandoh MDR-91 road km. 36/00 to 62/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 36/00 to 55/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on Dhingali to Gagan road km. 0/00 to 6/00 (SH: - Removal of snow/slips, unlined drain, muck debries at various RDs).	99970	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on Hanogi to Bandhi road KM. 0/0 to 15/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. II	99600	2,000	Rs. 350/-	One month	6&8	-do-
21	RRD on Thatta to Katwanu road Km. 0/00 to 0/00 to 5/000 (SH: - Removal of snow/slips, unlined drain, muck debries at various RDs )	99970	2,000	Rs. 350/-	One month	6&8	-do-
22	C/o Govt. Senior Secondary School Deori (SH: - Earthwork in filling for construction of playground) JOB-II	99185	2,000	Rs. 350/-	One month	6&8	-do-
23	RRD on various roads under Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs in Balichowki Section) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
24	RRD on various roads of Pandoh Sub Division (SH: - Hiring of Tipper for carriage of muck/debries etc. at various RDs in Pandoh Section-I) Job No. II	98000	2,000	Rs. 350/-	One month	6&8	-do-
25	RRD on Mani to Segali road Km. 0/0 to 4/0 (SH: - Removal of land slides, slips/boulders, muck debries etc. at RD 3/00 to 4/00).	99970	2,000	Rs. 350/-	One month	6&8	-do-
26	RRD on various roads of Pandoh Sub Division (SH: - Hiring of Tipper for carriage of muck/debries etc. at various RDs in Pandoh Section-I) Job No. V	98000	2,000	Rs. 350/-	One month	6&8	-do-
27	R.R.D on various Roads under Balichowki Sub-Division Section Balichowki (SH: Removal of slips at various RD in reaches).	99970	2,000	Rs. 350/-	One month	6&8	-do-
28	RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-

29	RRD on Tikki to Stattadhar road Km. 0/0 to 3/0 (SH: - Removal of land slides, slips/boulders, muck debries etc. at various RDs).	99970	2,000	Rs. 350/-	One month	6&8	-do-
30	R.R.D on road from Deod to Hatoun Km. 0/00 to 2/750 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/000 to 2/750)	99600	2,000	Rs. 350/-	One month	6&8	-do-

**TERMS & CONDITIONS: -**


1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

NO/PW/TLD/Tender/2025: -12043-52


Dated: -  
31/12/25

- Copy forwarded to the following for information and necessary action: -
1. The Engineer-in-Chief HPPWD Shimla.
  2. The Deputy Commissioner Mandi Distt. Mandi HP.
  3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
  4. The Chief Engineer, (MZ) HPPWD Mandi.
  5. The Superintending Engineer, 1<sup>st</sup> Circle, HPPWD Mandi HP.
  6. The Distt. Panchayat Officer Mandi HP.
  7. All AEs under this Division.
  8. The President of Contractor's Association.
  9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

Certificate

Certified that the tender called vide this office letter No. PW/TLD/Tender/2025- 12043-52 dated 31-12-2025 is emergent nature and in Public interest.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

**BILL OF QUANTITY**

Name of work:- RRD on Mani to Segali road Km 0/00 to 4/500 (SH: - Removal of snow/slips, unlined drain , muck debries at various RDs)


Estimated Cost:-99970.00

Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
			Words	Words	Amount	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the servicable material and disposal of unservicable materail as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only	Per cubic metre	99970.00
					<b>Total</b>	<b>99970.00</b>

*Bill of quantity approved for Rs 99970/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.



**BILL OF QUANTITY**

Name of work:- RRD on Thalout Panjain Thachi Shetadhar road km 0/0 to 40/00 (SH:- Removal of snow/slips/boulders, muck debries etc. at RD 25/00 to 40/00).


Estimated Cost:- 99236.00

Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Removal of snow/slips land slide in all kinds of soil in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechanical means including cutting and trimming of slips and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in Charge.	793.25	125.10	Rs. One hundred twenty five and paise Ten only	Per cubic metre	99236.00
					<b>Total</b>	<b>99236.00</b>

*Bill of quantity approved for Rs 99,236/- only.*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

**BILL OF QUANTITY**

Name of work:- C/O Surad Mahudhar to Nalwagi road km 0/0 to 5/00 (SH:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/0 to 5/0).

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
<b>Total</b>							<b>99600.00</b>

*Bill of quantity approved for Rs. 99600/-*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

5

297.

BILL OF QUANTITY


Name work:- RRD on Bali to Thachi road km 0/00 to 25/000 (SH:-F/C 5/7 mtr wide at RD 6/055 to 6/110)

Estimated Cost:- Rs. 96201.00

Earnest Money:- Rs. 2000.00

Time:- One Month

Sr. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
1	Earth work in excavation in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required and sorting out useful/un useful materials and stacking the same in all leads and lifts and then disposing of surplus excavated earth in on approved dumping sites through all modes of transportation along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if any required). Recovery for useful stone of 203.96 cubic metre @ Rs.300/- (Rupees three hundred ) per cubic metre amounting to Rs. 61188 /- (Rupees three lacs twenty thousand five hundred eight) only , which shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including carriage of material with in all leads, lifts and other incidentals and as per the direction of the Engineer-in-Charge.	690.11	139.40	Rupees One hundred ninety three and paise seventy eight only.	Per Cubic Metre	96201.00	
<b>Total in Figures</b>						<b>Total:-</b>	<b>96201.00</b>
		<i>Bill of Quantity approved previously - only</i>					

  
 Executive Engineer,  
 Thalout Division (B&R),  
 HPPWD,Thalout.

**BILL OF QUANTITY**

Name of work:- RRD on Dhammu to Deori road km 0/0 to 2/650 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS in km 0/0 to 2/650).

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
			Words	Words	Amount	
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationa staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					<b>Total</b>	<b>99600.00</b>

*Bill of quantity approved @ Rs. 99600/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on Burah to Panjain road Km 0/00 to 11/000 (SH: - Removal of snow/slips, unlined drain , muck debries at various RDS between 0/00 to 3/00)

Estimated Cost:-99970.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the servicable material and diposal of unservicable materail as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only	Per cubic metre	99970.00	
	<b>Total</b>					<b>99970.00</b>	

*Bill of quantity approved for Rs 99970/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

**BILL OF QUANTITY**

Name of work:- RRD on Hatoun Bhavash Muthal road km 0/0 to 6/500 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 3/0 to 6/500).

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material and materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
						<b>Total</b>	<b>99600.00</b>

*Bill of quantity approved for Rs. 99600.00*

  
**Executive Engineer,**  
 Thalout Division,  
 HP PWD Thalout.

**BILL OF QUANTITY**

Name of work:- RRD on Thalout Panjain Thachi Shetadhar road km 0/0 to 40/00 (SH:- Removal of snow/slips/boulders, muck debris etc. at RD 15/00 to 25/00).

Estimated Cost:- 99236.00  
 Earnest Money:- 2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
1	Removal of snow/slips land slide in all kinds of soil in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechanical means including cutting and trimming of slips and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in Charge.	793.25	125.10	Rs. One hundred twenty five and paise Ten only		Per cubic metre	99236.00
						<b>Total</b>	<b>99236.00</b>

*Bill of quantity approved for Rs 99,236 only.*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on Masar to Binoul road km 0/0 to 4/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 0/0 to 4/00).

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					<b>Total</b>	<b>99600.00</b>

*Bill of quantity approved for Rs. 99,600/- only.*

  
**Executive Engineer,**  
 Thalout Division,  
 HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on Burah to Panjain road Km 0/00 to 11/000 (SH: - Removal of snow/slips, unlined drain , muck debries at various RDS between 3/00 to 6/00)

Estimated Cost:-99970.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the servicable material and diposal of unservicable materail as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only		Per cubic metre	99970.00
						<b>Total</b>	<b>99970.00</b>

*Bill of quantity approved for Rs 99970/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.



**BILL OF QUANTITY**


Name work:- RRD on Bali to Thachi road km 0/00 to 25/000 (SH:-F/C 5/7 mtr wide at RD 6/010 to 6/055)

Estimated Cost:- Rs. 96204.00

Earnest Money:- Rs. 2000.00

Time:- One Month

Sr. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Percent		
1	Earth work in excavation in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required and sorting out useful/un useful materials and stacking the same in all leads and lifts and then disposing of surplus excavated earth in on approved dumping sites through all modes of transportation along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if any required). Recovery for useful stone of 203.96 cubic metre @ Rs.300/- (Rupees three hundred ) per cubic metre amounting to Rs. 61188 /- (Rupees three lacs twenty thousand five hundred eight) only , which shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including carriage of material with in all leads, lifts and other incidentals and as per the direction of the Engineer-in-Charge.	690.13	139.40	Rupees One hundred ninety three and paise seventy eight only.		Per Cubic Metre	96204.00
<b>Total in Figures</b>							<b>96204.00</b>
		<i>Bill of Quantity approved for Rs 96204/- only.</i>					

  
 Executive Engineer,  
 Thalout Division (B&R),  
 HPPWD, Thalout.


**BILL OF QUANTITY**

Name of work:- C/O Govt. Senior Secondary School Deori (SH: - Earthwork in filling for construction of playground) JOB-1

Estimated Cost:- 99185.00  
 Earnest Money:- 2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits upto any lift , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto any lead as per Technical Specification Clause 301.5 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in Charge.	332.00	298.75	Rs. Two hundred ninety eighth and paise seventy Five only	Per day	99185.00
					<b>Total</b>	<b>99185.00</b>

*Bill of quantity approved for Rs. 99185/- only.*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

15  
BILL OF QUANTITY

Name of Work:- Repair and Maintenance of Govt. Sen. Sec. School at Balichowki in Tehsil Balichowki Mandi (HPP) (SH:- P/L PCC 1:4:8, Repairs Plaster and Kota Stone.) **Deposit**

Estimated Cost:- 97,321.00  
Earnest Money :- 2,000.00  
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge as per specifications, drawings and direction of Engineer-in-charge complete.	2.34	5707.95	Rs. Five Thousand seven hundred seven and paise ninty five only	Per Cubic Metre	13357.00
2	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge as per specifications, drawings and direction of Engineer-in-charge complete.	4.20	1642.75	Rs. One Thousand six hundred forty two and paise seventy five only	Per Square Metre	6900.00
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge as per specifications, drawings and direction of Engineer-in-charge complete.	190.00	405.60	Rs. Four hundred five and paise sixty only	Per Square Metre	77064.00
<b>Total</b>						<b>97321.00</b>

*Bill of quantity approved for Rs 97321/-*

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout



**BILL OF QUANTITY**

Name of work:- RRD on Sudharani to Teeldhar road Km 0/00 to 4/500 (SH: - Removal of snow/slips, unlined drain , muck debries at various RDS)


Estimated Cost:-99970.00

Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the servicable material and diposal of unservicable materail as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only		Per cubic metre	99970.00
						<b>Total</b>	<b>99970.00</b>

*Bill of quantity approved for Rs 99970 only*

  
 Executive Engineer,  
 Thalout Division ,  
 HP PWD Thalout.






**BILL OF QUANTITY**

Name of work:- RRD on Hanogi to Bandhi road Km 0/0 to 15/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS ). JOB-II

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
	<b>Total</b>						<b>99600.00</b>

*Bill of quantity approved of Rs. 99600/- only*

  
**Executive Engineer,**  
 Thalout Division,  
 HP PWD Thalout.

**BILL OF QUANTITY**

Name of work:- RRD on Thatta to Katwannu road Km 0/00 to 5/000 (SH: - Removal of snow/slips, unlined drain , muck debries at various RDS)


Estimated Cost:-99970.00

Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the servicable material and disposal of unservicable materail as per technical specification 302.3.5 and 1611 including carriage of material and other incidentials in all leads and lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only	Per cubic metre	99970.00
	<b>Total</b>					<b>99970</b>

*Bill of quantity approved for Rs 99970 only*

  
 Executive Engineer  
 Thalout Division  
 HP PWD Thalout


**BILL OF QUANTITY**

Name of work:- C/O Govt. Senior Secondary School Deori (SH: - Earthwork in filling for construction of playground) JOB-II

Estimated Cost:-99185.00  
 Earnest Money:- 2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits upto any lift , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto any lead as per Technical Specification Clause 301.5 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in Charge.	332.00	298.75	Rs. Two hundred ninety eight and paise seventy Five only	Per day	99185.00
					<b>Total</b>	<b>99185.00</b>

*Bill of quantity prepared for Rs 99185/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on various roads under Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs in balichowki section ) Job No-2

Estimated Cost:- 99600.00  
 Earnest Money:- 2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					<b>Total</b>	<b>99600.00</b>

*Bill of quantity approved for Rs. 99,600/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.





Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDS in Pandoh Section-I) Job No-V

Estimated Cost:-98000.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Hiring of Tipper in good condition of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material from the road surface upto any leads and lifts in emergent cases as and when required or as per dlection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	<b>Total</b>					<b>98000.00</b>

*Bill of quantity approved for Rs. 98000.00*

*[Signature]*  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

(27)


**BILL OF QUANTITY**

Name of work:- R.R.D. on various Roads under Balichowki Sub- Division Section Balichowki  
(SH: - Removal of slips at various RD in reaches)

Estimated Cost:- 99970.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in	Unit	Amount
				Words		
1	Removal of land slide in all kinds of soli in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechanical means including cutting and trimming of slops and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in-Charge	790.90	126.40	Rs. One hundred Twenty six and paise fourty only	Per cubic metre	99970.00
<b>Total</b>						<b>99970.00</b>

*Bill of Quantity approved for Rs 99970/- only*

  
Executive Engineer,  
Thalout Division,  
HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS under Pandoh Section-I) Job No-1

Estimated Cost:-99600.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	<b>Total</b>					<b>99600.00</b>

*Bill of quantity approved for Rs. 99600 only*

  
 Executive Engineer,  
 Thalout Division  
 HP PWD Thalout.


**BILL OF QUANTITY**

Name of work:- RRD on Tikki to Shattadhar road km 0/0 to 3/0 (SH:- Removal of land slides, slips/boulders, muck debries etc. at various RDs.)

Estimated Cost:- 99970.00  
 Earnest Money:-2000.00  
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in Words	Unit	Amount
1	Removal of land slide in all kinds of soil in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechanical means including cutting and trimming of slops and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer-in Charge.	790.90	126.40	Rs. One hundred Twenty six and paise fourty only	Per cubic metre	99970.00
<b>Total</b>						<b>99970.00</b>

*Bill of Quantity approved for Rs 99970/- only*

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.

Name of work:- R.R.D. on road from Deod to Hatoun km 0/000 to 2/750. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/000 to 2/750)

Estimated Cost:-99,600.00  
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
<b>Total</b>						<b>99600.00</b>

Bill of quantity approved for Rs. 99600.00

Executive Engineer  
Thalout Division,  
HP PWD Thalout.