

Himachal Pradesh
Public Works Department

NO.PW.THG/CB-tender/2025-26-12427-38

Dated:- 24-1-2026

To

✓ The Executive Engineer, (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., NirmnBhawan, Shimla-2

Subject:- Publication of Tender notice.

Sir,

I am enclosing herewith Notice Inviting Tender for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3) 1/2020 dated 16th July 2021.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- The Deputy Commissioner, Shimla Distt. Shimla H.P
- The Superintending Engineer, 4th circle H.P.P.W.,D , Shimla-3.
- The Sub-divisional officer© Theog.
- The municipal Council Theog.
- Block development officer, Theog block.
- All the Assistant Engineer working under this division
- Superintendent Gr-II (Estt.) in this division.
- Drawing branch in this office.
- Notice Board


Executive Engineer,
TheogDivision, B&R,
H.P.P.W.D., Theog

**Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER**

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **11.02.2026** up to 11.00 A.M. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **10.02.2026** up to 4.00 P.M. and the application for issue of tender form shall be received on **09.02.2026** up to 4.00 P.M.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	EMD (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	7
1	C/O Govt. Sr. Sec. School Building at Chanair Tehsil Theog Distt Shimla (H.P) (SH:- C/O Steel work for Gate & fencing etc)	Theog	186450/-	3,730/-	350/-	One Month
2	R/R Damages on Nangal devi to Naleha road km 0/0 to 5/00 (SH:- C/O B/wall at Km/Rd 1/550 to 1/563)	Theog	1,42,597/-	3,000/-	350/-	One Month
3	R/R Damages on Various Roads under Sainj Sub-Division (Deha Section) (SH:- Hiring of JCB for removal of slips & surface dressing)	Theog	99,750/-	2,000/-	350/-	One Month
4	R/R Rain Damages on Runkali Chikhar Road Km 0/0 to 6/500 (SH:- C/O RCC R/wall at RD 5/420 to 5/428)	Theog	3,37,004/-	6,750/-	350/-	One Month
5	R/R Rain Damages on Meha Dandi Road Km 0/0 to 4/930 (SH:- C/O RCC B/wall at Rds 4/300 to 4/315 & 4/355 to 4/370)	Theog	4,05,678/-	8,200/-	350/-	One Month
6	R/R Damages on Nangel Devi Naleha Road Km 0/0 to 5/0 (SH:- C/O R/wall at RD 2/165 to 2/178)	Theog,	3,34,971/-	7,000/-	350/-	One Month
7	R/R Damages on Chhailla Sainj Neripul Yashyant Nager Solan Road Km 0/00 to 18/435 (SH:- C/O PCC R/wall at RD 5/533 to 5/550)	Theog,	4,99,716/	10,000/-	350/-	One Month
8	R/R of Snow Damages on Chhailla Sainj Neripul Yashwant Nager Solan Road Km 0/0 to 18/435 (SH:- Providing & Fixing G.I pipe 32mm dia at Maipul)	Theog	37,065/-	800/-	350/-	One Month

9	C/O Dhatti to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at Rd 0/980 to 1/006 and R/wall 1/010 to 1/023)	Theog,	4,99,309/-	10,000/-	350/-	One Month
10	R/R Damages on Sandhu Talash Bago Road Km 0/0 to 3/200 (SH:- C/O B/wall at RD 0/710 to 0/725 and 0/820 to 0/840)	Theog	4,53,828/-	9,070/-	350/-	One Month
11	R/R Damages on Kuthar Kanowari Road Km 0/00 to 11/075 (SH:- C/O PCC R/wall at RD 6/475 to 6/495)	Theog	3,35,616/-	6,700/-	350/-	One Month
12	R/R Damages on Chhaila Shalowa Tikker Road KM 0/00 11/100 (SH:- C/O PCC B/wall at Rd 10/880 to 10/900)	Theog,	2,75,872/-	5,517/-	350/-	One Month
13	R/R Damages on Meha Dandi Road Km 0/0 to 4/900 (SH:- C/O PCC B/wall at Rd 3/395 to 3/415)	Theog	3,65,384/-	7,308/-	350/-	One Month
14	R/R Damages on Various Roads under Theog Sub-Division (SH:- Hiring of JCB for removal of slips in Various Rds)	Theog	1,99,500/-	4,000/-	350/-	One Month
15	R/R Rain Damages on Kargoli Nallah to Deha Road Km 0/0 to 8/00 (SH:- C/O PCC B/wall at Rd 0/390 to 0/425)	Theog	4,88,454/-	10,000/-	350/-	One Month
16	R/R Rain Damages on Ghorna Deothi Road Km 0/0 to 5/435 (SH:- Removal of land slide slips in Km RD 0/0 to 5/435)	Theog	2,86,622/-	5,800/-	350/-	One Month
17	A/R & M/O Circuit House at Theog (SH:- C/O Wall around the park , C/o chamber , Railling and minor repair etc. in the vicinity of circuit house)	Theog	4,97,628/-	9,953/-	350/-	One Month
18	A/R & M/O Chhaila Sainj Neripul Yashwant Nager Solan Road Km 0/0 to 18/435 (SH:- Providing and Laying Patch work by providing 25 mm thick Bituminous concrete in Km 3/00 to 6/00)	Theog	4,37,017/-	8,800/-	350/-	One Month
19	C/O Sarion to Gowai via Bhalech Jadeog Road Km 0/0 to 8/00 (SH:- Formation cutting in earth work at RD 4/00 to 4/870)	Theog	4,99,490/-	10,000/-	350/-	One Month
20	A/R & M/O Circuit House at Theog (SH:- P/F glass panes, Stair to chowkidar Resideancae and minor repair etc. in the vicinity of circuit house)	Theog	1,36,570/-	2,733/-	350/-	One Month
21	R/R Damages on Sandhu Talash Bago Road Km 0/0 to 3/120 (SH:- C/O B/wall at RD 2/320 to 2/348)	Theog	4,97,344/-	9,947/-	350/-	One Month
22	R/R Damages on Dhamandri Jais Road Km 0/0 to 7/00 (SH :- C/O B/wall at RD 1/272 to 1/273.20 and 1/282 to 1/295)	Theog	2,24,534/-	4,490/-	350/-	One Month
23	R/R Damages on Tihana to Pargeya Road Km 0/0 to 4/285 (SH:- C/O PCC B/wall at RD 4/270 to 4/282)	Theog	1,64,443/-	3,289/-	350/-	One Month
24	R/R Rain Damages on Bala Kishore via Deothi Road Km 0/0 to 1/600 (SH:- C/O RCC B/wall at RD 0/405 to 0/430)	Theog	3,22,480/-	6,500/-	350/-	One Month
25	C/O Dhatti to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at Rd 0/820 to 0/843)	Theog	2,15,329/-	4,300/-	350/-	One Month
26	R/R Rain Damages on Balaghar Tihanadhar Kalna	Theog	2,13,912/-	4,300/-	350/-	One


	Road km 0/0 to 24/500 (SH:- C/O RCC B/wall at RD at RD 13/180 to 13/195)					Month
27	R/R of Rain Damages on Various Road Under Theog Sub-Division (SH:- Hiring of Excavator - cum-Loader /Tipper for removal of snow/ slips and surface dressing in various Roads under fagu section)	Theog	4,98,000/-	10,000/-	350/-	One Month
28	Extention of Ground by Providing R/wall anf fencing over wall in Govt Degree Colleage at Theog (SH:- C/O R/wall & Fencing over it)	Theog	4,97,676/-	10,000/-	350/-	One Month

- The contractors are required to be produce a copy of their PAN No. GST and should also produce a copy of enlistment /renewal letter.
- Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act,1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.


 Executive Engineer.
 Theog Division B&R,
 H.P.P.W.D. Theog.

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2025-26 12427-38 dt. 24-01-2026 are of emergent nature in exigency of public interest.


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Cost 186450/-
Earnest Money 3730.00
Time: One Months

Name of work:-C/O Govt Snr. Sec School Building at Chanair Theog Distt Shimla (H.P) (SH:- C/O Steel work for Gate & fencing etc)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	1.20	235.05	Rupees Two Hundred Thirty Five and Paise Five Only	P/Cum	282.06	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . (1.4:8:40mm nominal size)	1.20	4655.20	Rupees Four Thousand Six Hundred Fifty Five and Paise Twenty Only	P/Cum	5586.24	
3	Steel work welded in built up sections trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat red lead paint up to all floor level including all leads and lifts of materials or as per the direction of Engineer -in -Charges.	1374.81	107.45	Rupees One Hundred Seven and Paise Forty Five Only	Per Kg	147723.33	
4	providing and fixing welded mesh 25mm X 25mm X 3mm thick as per approved design by welding with electrical plant complete including priming coat of red lead paint as per HP.PWD specification 1990 volume-I including carriage of materials upto all leads and lifts	50.12	655.60	Rupees Six Hundred Fifty Five and Paise Sixty Only	Per Kg	32858.67	
Total							186450.31
Quoted rate in figer+ / - (%-----)							
Quoted rate in words							


Executive Engineer,
Theog Division,
HP.PWD. Theog

2

SCHEDULE OF QUANTITY

Estimated Cost 142597/-
Earnest Money: 3000.00
Time: One Months

Name of work:- R/R Damages on Nangal Devi to Naleha Road Km 0/0 to 5/00 (SH:- C/O B/wall at RD 1/550 to 1/563)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge. specification clause 1603.1	28.00	150.00	Rupees One Hundred Fifty Only	P/Cum	4200.00	
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	11.20	220.00	Rupees Two Hundred Twenty Only	P/Cum	2464.00	
3	Providing and laying concrete 1:48 (1 cement : 4 sand : 6 graded stone aggregate 25mm nominal size) in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203. including all leads and lifts or as per the direction of Engineer - in Charge .	30.60	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	P/Cum	133979.04	
4	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall, R/wall with 110 mm dia (4kg per Cm2 pressure) PVC pipe approved brand /c all leads and lifts as per directions of the Engineer - in Charge .	8.00	244.30	Rupees Two Hundred Forty Four and Paise Thirty Only	Each	1954.40	
Total							
			Quoted rate in figer+ /-(%.....)			142597.44	
			Quoted rate in words				

Executive Engineer,
Theog Division,
HP.PWD. Theog

1st copy

(3)

DNIT/SCHEDULE OF QUANTITY

Estimated Cost: 99750 /-
Earnest Money: 2000 /-
Time: 1 month

Name of Work:- R.R Damages on various road under Sainj Sub Division (SH:- Hiring of JCB for removal of slips) ← Dehra Section

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in figure	Rate in words		
1	Hiring of JCB excavator to be deployed for removal of slips i.e cost of fuel oil, lubricants, wages of operational staff's any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to another at required location, actual working hour will be accounted for payment and proper disposal slip snow by the contractor will be insured and i c all leads and lifts as per the direction of the Engineer-in-Charge	95.00	1050.00	Rupees one thousands fifty zero paise only	P/Hour	99750
					Total	99750

Assistant Engineer
Sainj Sub-Division
H.P.W.D. Sainj

DAE

DNIT approved for Rs 99750/- only

S.N. (181)

Executive Engineer
H.P.W.D. (B & R)
Division Theog

for 2025-26

Schedule Of Quantity

Estimated Cost: 337004/-
Earnest Money: 6750 /-

Time: One month

Name of Work:- R/R Rain Damages on Runkali Chikhar Road Km 0/0 to 6/500(SH:- C/O RCC R/Wall at RDs 5/420 to 5/428)

Sr. No.	Description of Items	QTY.	Rate	in words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	37.76	in feg 214.1	Rupees Two Hundred Fourteen and Paise Ten Only	P/cum	8084.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	67.07	4600.00	Rupees Four Thousand Six Hundred Only	P/cum	308522.00
3	Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment. B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	27.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen	Each	6538.05
4	Back stone Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	13.20	1050.00	Rupees One Thousand Fifty Only	P/cum	13860.00
Total:-						337004.00
		Quoted Rates (In Fig)		(% above/below / at Par)		
		Quoted Rates (In Words)				


Executive Engineer
Theog Division
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 334971/-
 Earnest Money: 7000.00
 Time: One Months

Name of work:- R/R Damages on Nangel Devi Naleha Road Km 0/0 to 5/0 (SH:- C/O R/wall at RD 2/165 to 2/178)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount	
				Rate in words				
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	41.47	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		P/Cum	8878.73	
2	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 including all leads and lifts as per direction of the Engineer-in Charge	61.42	4597.00	Rupees Four Thousand Five Hundred Ninety Seven Only		P/Cum	282347.74	
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge. (1:4:8:) 40mm nominal size)	4.29	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		Each	18783.34	
4	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall, R/wall with 100 mm dia (4kg per Cm2 pressure) PVC pipe approved brand i/c all leads and lifts as per directions of the Engineer - in Charge .	22.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only		Each	5327.30	
5	Stone Filling Behind the retaining wall B/wall and wing wall complete as per Drawing technical specification clause 1204.2.8 i/c all leads and lift as per directions of the Engineer - in Charge.	15.60	1258.65	Rupees One Thousand Two Hundred Fifty Eight and Paise Sixty Five Only		P/Cum	19634.94	
Total								334971.00
			Quoted rate in figer+/- (%-----)					
			Quoted rate in words					


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 499716/-
Earnest Money: 10000.00
Time: One Months

Name of work:- R/R Damages on Chhailla Sainj Neripul Yashyant Nagar Solan Road Km 0/00 to 18/435 (SH:- C/O PCC R/wall at RD 5/533 to 5/550

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	55.76	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	11938.22	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . (1:4:8:) 40 mm nominal size)	100.64	4540.00	Rupees Four Thousand Five Hundred Forty Only	P/Cum	456951.00	
3	Providing and fixing weapholes in brick masonry/ stone masonry ,plain RCC abutment , B/wall & R/wall with 100 mm dia PVC pipe extending through the full width of the slopes of 1.20 towards drawing free complete as per drawing and T/S classes 614,709,1204.3.7 i/c all leads and lifts as per directions of the Engineer - in Charge.	30.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	7264.50	
4	Back Filling stine filling Behind Abutment, Wing Wall And Return Wall Complete as per Drawing technical specification clause 1204.3.8 (i) Granular material i/c all leads and lift as per directions of the Engineer - in Charge.	22.44	1050.00	Rupees One Thousand Fifty Only	P/Cum	23562.00	
Total							
			Quoted rate in figer+ /-(%-----)				
			Quoted rate in words				


Executive Engineer,
Theog Division,
HP.PWD. Theog

8

Schedule of Quantity

Estimated Cost: 37065/-
Earnest Money: 800/-
Time: 15 Days

Name of Work:- R/R of snow damages on Chhailla Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435(SH:-
Providing & Fixing GI Pipe 32mm dia at Maipul)

Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Providing and fixing G.I. Pipes Complete with G.I fitting including trenching refilling etc(1) 32 mm dia nominal bore i/c all leads and lifts and as per direction of the Engineer-in- Charge.	100.00	370.65	P/cum	37065.00
				Total:	37065.00
	Quoted Rate (In Fig)				(% above/below & at par DNIT amount)
	Quoted Rate (In words)				


Executive Engineer,
Theog Division,
HP.PWD. Theog

9

SCHEDULE OF QUANTITY

Estimated Cost 499309/-
Earnest Money: 10000.00
Time: One Months

Name of work:- C/O Dhatti to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at RD 0/980 to 1/006 and R/wall 1/010 to 1/023)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	114.27	220.00	Rupees Two Hundred Twenty Only	P/Cum	25139.40
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203,including all leads and lifts or as per the direction of Engineer - in Charge . (1:4:8)	95.42	4700.00	Rupees Four Thousand Seven Hundred Only	P/Cum	448474.00 *
3	Providing weepholes in brck masonry/ stone masonry . plain reinforcement concrete abutment , wing wall , R/wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing with in all leads and lifts as per directions of the Engineer-in-Charge)	52.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	12591.80
4	Back Filling Behind Abutment, Wing Wall And Return Wall Complete as per Drawing technical specification clause 1204.3.8 (j) Granular material i/c all leads and lift as per directions of the Engineer - in Charge.	12.48	1050.00	Rupees One Thousand Fifty Only	P/Cum	13104.00
Total						499309.20
			Quoted rate in figer+/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 453828/-
 Earnest Money: 9077.00
 Time: One Months

Name of work:- R/R Damages on Sandhu Talash Bago Road Km 0/0 to 3/200 (SH:- C/O B/wall at RD 0/710 to 0/725 and 0/820 to 0/840)

Sr.No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
			Rate in words	Rate In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge. specification clause 1603.1	55.05	180.00	Rupees One Hundred Eighty Only	P/Cum	9909.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	31.50	220.00	Rupees Two Hundred Twenty Only	P/Cum	6930.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203. including all leads and lifts or as per the direction of Engineer - in Charge . (1:48)	89.67	4700.00	Rupees Four Thousand Seven Hundred Only	P/Cum	421449.00
4	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall, R/wall with 100 mm dia PVC pipe 1/c all leads and lifts as per directions of the Engineer - in Charge .	62.00	250.65	Rupees Two Hundred Fifty and Paise Sixty Five Only	Each	15540.30
Total						
			Quoted rate in figer+/- (%-----)			453828.30
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 335616/-
Earnest Money: 6700.00
Time: One Months

Name of work:- R/R Damages on Kuthar to Kanowari Road Km 0/00 to 11/075 (SH:- C/O PCC R/wall at RD 6/475 to 6/495)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	39.80	220.00	Rupees Two Hundred Twenty Only	P/Cum	8756.00
2	Providing and laying concrete in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . 1:48 (1 cement : 4 sand : 6 graded stone aggregate 40 mm nominal size)	63.40	4900.00	Rupees Four Thousand Nine Hundred Only	P/Cum	310660.00
3	Providing and fixing weapholes in brick masonry/ stone masonry .plain RCC abutment . B/wall & R/wall with 100 mm dia PVC pipe extending through the full width of the slopes of 1:20 towards drawing free complete as per drawing and T/S classes 614,709,1204.3.7 i/c all leads and lifts as per directions of the Engineer - in Charge.	60 00	270.00	Rupees Two Hundred Seventy Only	Each	16200.00
Total						335616.00
			Quoted rate in figer+/- (%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Divisy6h,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 275872/-
Earnest Money: 5517.00
Time: One Months

Name of work:- R/R Damages on Chhaila Shalowa tikker Road Km 0/00 to 11/100 (SH:- C/O PCC B/wall at RD 10/880 to 10/900)						
Sr.No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	61.60	220.00	Rupees Two Hundred Twenty Only	P/Cum	13552.00
2	Providing and laying concretein open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203,including all leads and lifts or as per the direction of Engineer - in Charge . 1:48 (1 cement : 4 sand : 6 graded stone aggregate 40 mm nominal size)	52.40	4800.00	Rupees Four Thousand Eight Hundred Only	P/Cum	251520.00
3	Providing and fixing weapholes in brick masonry/ stone masonry ,plain RCC abutment , B/wall & R/wall with 100 mm dia PVC pipe extending through the full width of the slopes of 1:20 towards drawing free complete as per drawing and T/S classes 614,709,1204.3.7 i/c all leads and lifts as per directions of the Engineer - in Charge.	40.00	270.00	Rupees Two Hundred Seventy Only	Each	10800.00
Total						
			Quoted rate in figer+ /-(%-----)			275872.00
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 365384/-
 Earnest Money: 7308.00
 Time: One Months

Name of work:- R/R Damages on Meha to Dhandi Road Km 0/0 to 4/900 (SH:- C/O PCC B/wall at RD 3/395 to 3/415)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	94.10	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	20146.81
2	Providing and laying concrete 1:48 (1 cement : 4 sand : 6 graded stone aggregate 20 mm nominal size) in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge .	71.60	4700.00	Rupees Four Thousand Seven Hundred Only	P/Cum	336520.00
3	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall, R/wall with 100 mm dia (4kg per Cm2 pressure) PVC pipe approved brand i/c all leads and lifts as per directions of the Engineer - in Charge .	36.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	8717.40
Total						
			Quoted rate in figer+ /-(%.....)			
			Quoted rate in words			365384.21


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

14

SCHEDULE OF QUANTITY

Estimated Cost 199500
Earnest Money: 4000.00

Time: One month

Name of work:- R/R Damages on Various Roads in Theog Sub-Division (SH:- Hiring of J.C.B for removal of slips)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
			Rate in words	Rate in words		
1	Hiring of JCB (Excavator -Cum-Loader) including P.O.L charges. Shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoide damage to the properties of the people or in case any damage took place, the contractor is liable for it All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of snow shall have to be neatly stacked along road side on road burms Minimum 30 cubic meter of snow work shall be done by machine in one hour , other wise number of hours shall be reduced accordingly . The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads	190.00	1050.00	Rupees One Thousand & Fifty only	Per /Hour	199500.00
Total						
			Quoted rate in fig+/- (%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

17

497628/-
497628/-
9953.00

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money:
Time: One Months

Name of work:- A/R & M/O Circuit house at Theog. (SH:-C/O Wall around the Park, c/o chamber, Railling and minor repair etc. in the vicinity of circuit house.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Dismantling dressed stone work ashlar face stone work, marble work or precast concrete work manually/ by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	47.19	1183.45	Rupees One Thousand One Hundred Eighty Three and Paise Forty Five Only	P/cum	55847
2	Providing and laying cement concrete 1:4:8(One cement Four sand Eight graded cursed/broken stone aggregate 40mm) (forty millimeters nominal size) mechanically mixed and curing complete, excluding cost of form work in foundation and plinth, including carriage of material all leads and lifts and as per direction of the Engineer-in-Charge.	5.22	4500	Rupees Four Thousand Five Hundred Only	P/cum	23490
3	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level Masonry work (first sort), in cement mortar 1:4 (1 cement 4 coarse sand)	10.33	6550.9	Rupees Six Thousand Five Hundred Fifty and Paise Ninety Only	P/cum	67671
4	Providing concrete for plain/reinforced concrete in oper foundations complete as per drawings & Technical Specification Clause 802, 803, 1202 & 1203. M-10(1:3:6 nominal mix) (20mm)	36.86	5420.4	Rupees Five Thousand Four Hundred Twenty and Paise Forty Only	Each	199796
5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge (1:2:4)	2.52	7000	Rupees Seven Thousand Only	Each	17640
6	Providing and laying damp-proof course 50mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand) 4 graded stone aggregate 20mm nominal size)	17.4	346.85	Rupees Three Hundred Forty Six and Paise Eighty Five Only	P/sqm	6035
7	Providing & applying a coat of residual petroleum bitumen of grade of VG-10 of approved quality using 1.7kg per square metre on damp proof course after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil.	17.4	95.85	Rupees Ninety Five and Paise Eighty Five Only	P/sqm	1668
8	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:4 (1cement: 4 coarse sand)	97	390	Rupees Three Hundred Ninety Only	P/sqm	37830
9	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	97	95	Rupees Ninety Five Only	P/sqm	9215
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	97	105	Rupees One Hundred Five Only	P/sqm	10185

11	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint					
12	In gratings framed guard bars, ladders, railing brackets and similar works including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	580	105	Rupees One Hundred Five Only	Kg	60900
13	Ruled / Flush pointing on Red sand stone masonry surface with lime, surkhi and marble dust mortar in the ratio of 1 1/2 (One lime 1.5 surkhi (50% red and 50% light yellow surkhi) 1/2 marble dust) (The rate is inclusive of all materials & labours involved except scaffolding)	44.95	163.55	Rupees One Hundred Sixty Three and Paise Fifty Five Only	P/Rmt.	7352
Total						497628
				Quoted rate in figer+ / (%-----)		
				Quoted rate in words		



Executive Engineer,
Theog Division,

SCHDEULE OF QUANTITY

Estimated Cost 437017

Earnest Money:-8800

Time One Month

Name of work:- A/R &M/O Chhailla Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435 (SH:-Providing and laying Patch Work by providing 25mm thick Bituminous concrete in Km. 3/00 to 6/00).

Sr. Description of items

Sr. No	Description of items	Quantity	Unit	Rate	Amount
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	1150.85	Per Sqm	17.25	19852.00
2	Providing and laying 25mm thick Bituminous Concrete with 100-120 (One Hundred to One hundred Twenty) TPH batch type hot mix plant producing an average output of 75 (Seventy Five) tonnes per Hour using crushed aggregates of specified aggregates of specified grading, premixed with bituminous binder (VG-10) @ 5.5 (Five point five) per cent of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORT&H specification clause No. 509 complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	28.77	Per Cum	14500.00	417165.00
Total:-					437017.00
Quoted Rate in Fig					% above/below /at par
Quoted Rate in Words					


 Executive Engineer
 B&R Division, HP. PWD.
 Theog


19

SCHEDULE OF QUANTITY

Estimated Cost: 499490/-
Earnest Money: 10000 /-
Time: one month

Name of work: C/O Sarion to Gowai via Bhalech Jadeog Road km 0/0 to 8/00(SH:-Formation cutting in earth work at RD4/00 to 4/870

Sr. No.	Sub Head and Item of work	Qty.	Rate	Unit	Amount
1	<p>2</p> <p>Cutting in earth work in all depths and heights in all kinds of soils including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock, with chiseling and wedging out of rock. (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required setting out true to the required lines grades side slopes, trimming of bottoms and levels as shown on the drawing and as directed by the Engineer-in charge at site, according to the HP.PWD. specification of 1990 volume-1 and sorting of useful and un useful materials and stacking the same in all lead and left and transportation of the un useful material for filling in road way embankments for grade improvement and leveling to required grades and then disposing of surplus excavated materials in acquired width of the road or on approved dumping site/sites through all modes of transportation including head loads, animals loads or mechanical means along with its leveling and fine dressing and carriage of all labour, machinery, materials tools, equipments and safety measures and other incidental necessary to completes the work by mechanical means and /or labour (if any required complete as per directions of Engineer-in Charge) All useful materials, such as stones, shingles, aggregate and slates etc. shall be sorted out. The recovery of 34.92cum useful stone during the course of execution shall be made @300/cum on prorata basis. Any loss to the public and private property during the courses of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect. including all leads and lifts as per direction of the Engineer-in-Charge.</p>	3492.45	143.02	P/cum	499490.00
				TOTAL:-	499490.00
	Quoted Rates in Fig			% above/Below/at par DNIT amount	
	Quoted Rates in Words				


Executive Engineer,
Theog Division,
HP.PWD. Theog.

20

SCHEDULE OF QUANTITY

Estimated Cost 136570/-
 Earnest Money: 2733.00
 Time: One Months

Name of work:- A/R & M/O Circuit house at Theog. (SH:-P/F glass panes, Stair to chowkidar Residence and minor repair etc. in the vicinity of circuit house)

Sr. No.	Description of Item	Qty.	Rate in fig.	Rate		Unit	Amount
				Rate in words	Rate in words		
1	Supplying & fixing glass panes, with putty and nails wherever necessary including removal of old broken glass.	3.72	950	Rupees Nine Hundred Fifty Only	Rupees Nine Hundred Fifty Only	P /sqm	3534
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Stairs, (excluding landings) except spiralstaircases	13.8	444.4	Rupees Four Hundred Forty Four and Paise Forty Only	Rupees Four Hundred Forty Four and Paise Forty Only	P /sqm	6133
3	Providing and laying cement concrete 1:1.5:3 (1cement :1.5 sand :3 graded stone aggregate 20mm. nominal size) and curing complete excluding cost of form work and reinforcement for feirforced concrete work in:Stairs, (excluding landings) except spiralstaircases	1.2	8500	Rupees Eight Thousand Five Hundred Only	Rupees Eight Thousand Five Hundred Only	P /cum	10200
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level	144	98	Rupees Ninety Eight Only	Rupees Ninety Eight Only	Kg	14112
5	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required .W.C. pan with ISI marked white solid plastic seat and lid	1	20000	Rupees Twenty Thousand Only	Rupees Twenty Thousand Only	Each	20000
6	Providing and fixing automatic flushing cistern with a pair of C.I. Or M.S. brackets complete with fittings including C.I. Syphonic apparatus, mosquito proof lid, C.P. Brass unions and coupling for connections with inlet, outlet and overflow pipes including cutting holes and making good the same (overflow pipe to be measured and paid for separately) 5 litres capacity including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	2	2700	Rupees Two Thousand Seven Hundred Only	Rupees Two Thousand Seven Hundred Only	Each	5400
7	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings Flat back 550mmx400mm including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	1	6700	Rupees Six Thousand Seven Hundred Only	Rupees Six Thousand Seven Hundred Only	Each	6700

8	Providing and fixing brass bib tap (Superior or heavy type) including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	2	779.8	Rupees Seven Hundred Seventy Nine and Paise Eighty Only	Each	1560
9	Construction chamber 300millimeters x 300millimeters x 500mm inside size for stop cock with C.I.surface box 100millimeters x 100millimeters x 75millimeters (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1cement :2 sand :4 graded stone aggregate 20millimeters nominal size) 75millimeters thick foundation concrete 1:5:10 (1cement :5 sand :10 grades stone aggregate 40millimeters nominal size) and inside plastering with cement mortar 1:3 (1cement :3 sand) finished with a floating coat of neat cement with 100millimeters thick walls of brick masonry in cement mortar 1:5 (1cement :5 sand). including curing complete. including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	1	11500	Rupees Eleven Thousand Five Hundred Only	Each	11500
10	Providing and fixing aluminum handels anodized transparent to dyed to required colour of shade with necessary screws etc complete 150 mm. including all leads and lifts as per the direction of Engineer-in-Charge.	4	125	Rupees One Hundred Twenty Five Only	Each	500
11	Providing and fixing tower bolt anodized transparent to dyed to required colour of shade with necessary screws etc complete 200mm. including all leads and lifts as per the direction of Engineer-in-Charge.	4	95	Rupees Ninety Five Only	Each	380
12	Providing and fixing high pressure PVC spigot and socket , waste and ventilating pipes including fixing with rubber gasket/ approved adhesive etc. complete 150 mm	60	731.15	Rupees Seven Hundred Thirty One and Paise Fifteen Only	Rmt	43869
13	Providing and fixing PVC door bend with oval access door , insertion rubber washer 3 mm thick bolts and nuts complete including fixing with rubber gasket/ approved adhesive etc. complete 150 mm	5	618.85	Rupees Six Hundred Eighteen and Paise Eighty Five Only	Each	3094
14	Providing and fixing PVC collers including fixing with rubber gasket/ approved adhesive etc complete 150 mm	20	479.4	Rupees Four Hundred Seventy Nine and Paise Forty Only	Each	9588
Total						136570
			Quoted rate in words			
			Quoted rate in figures - (%-----)			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 497344/-
 Earnest Money: 9947.00
 Time: One Months

Name of work:- R/R Damages on Sandhu talash Bago Road Km 0/0 to 3/120 (SH:- C/O B/wall at RD 2/320 to 2/348)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge-specification clause 1603.1	83.16	148.00	Rupees One Hundred Forty Eight Only	P/Cum	12307.68
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	43.96	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	9411.84
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . (1:6:12)	8.82	4370.50	Rupees Four Thousand Three Hundred Seventy and Paise Fifty Only	P/Cum	38547.81
4	Stoe masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1:6 (1 cement : 6 Sand) as per drawing HPPWD Technical specification including all leads and lifts as per direction of the Engineer-in Charge	92.23	4597.00	Rupees Four Thousand Five Hundred Ninety Seven Only	P/Cum	423981.31
5	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts as per directions of the Engineer - in Charge.	54.00	242.50	Rupees Two Hundred Forty Two and Paise Fifty Only	Each	13095.00
Total						497344.00
Quoted rate in fig+/- (%-----)						
Quoted rate in words						


 Executive Engineer,
Theog Division,
HP.PWD. Theog

22

SCHEDULE OF QUANTITY

Estimated Cost 224534/-
Earnest Money: 4490.00
Time: One Months

Name of work:- R/R Damages on Dhamandri Jais Road Km 0/0 to 7/00 (SH:- C/O B/wall at Rd 1/272 to 1/273.20 and 1/282 to 1/295)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount	
				Rate in words	Rate in fig.			
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical including all leads, lifts and carriage of material by all mode of transportation and as per the direction of engineer in charge. specification clause 1603.1	30.01	148.00	Rupees One Hundred Forty Eight Only		P/Cum	4441.48	
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	18.10	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		P/Cum	3875.21	
3	Providing and laying concrete for plain /reinforced in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge 1:4:8.	46.60	4500.00	Rupees Four Thousand Five Hundred Only		P/Cum	209700.00	
4	Providing weepholes in brick masonry/ stone masonry , plain RCC abutment , B/wall, R/wall with 100mm dia PVC pipe i/c all leads and lifts as per directions of the Engineer - in Charge .	26.00	250.65	Rupees Two Hundred Fifty and Paise Sixty Five Only		Each	6516.90	
Total								224534.00
							Quoted rate in figer+ / - (%-----)	
							Quoted rate in words	


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost: 164443/-
 Earnest Money: 3289.00
 Time: One Months

23

Name of work:- R/R Damages on Tihana to Pargeya Road Km 0/0 to 4/285 (SH:- C/O PCC B/wall at RD 4/270 to 4/282)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in Fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305 1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	36.96	220.00	Rupees Two Hundred Twenty Only	P / Cum	8131.20
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . (1:4:8) (40 mm Nominal size)	31.44	4800.00	Rupees Four Thousand Eight Hundred Only	P / Cum	150912.00
3	Providing weepholes in brick masonry/ stone masonry , plain RCC abutment , B/wall, R/wall with 100 mm dia PVC pipe extending through the full width of the slopes of 1:20 towards drawing free complete as per drawing and T/S classes 614,709,1204.3.7 i/c all leads and lifts.	20.00	270.00	Rupees Two Hundred Seventy Only	P / Rmt	5400.00
Total						164443.20
Quoted rate in figer+ / (% -----)						
Quoted rate in words						


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

Schedule Of Quantity

Estimated Cost 322480/-
Earnest Money: 6500 /-
Time: One month

Name of Work:- R/R Rain Damages on Bala Kiashor via Deothi Road km 0/0 to 1/600 (SH:-C/O RCC B/Wall at RD0/405 to 0/430)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	18.50	in fig 280.00	in words Rupees Two Hundred Eighty Only	P/cum 5180.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	62.00	4900.00	Rupees Four Thousand Nine Hundred Only	P/cum 303800.00
3	Providing and fixing weapholes in brick masonry/stone masnory, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	50.00	270.00	Rupees Two Hundred Seventy Only	Each 13500.00
Total:-					322480.00
		Quoted Rates (In Fig)		Quoted Rates (In Words)	
				(% above/below / at Par)	


Executive Engineer
Theog Division
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 215329/-
Earnest Money: 4300.00
Time: One Months

Name of work:- C/O Dhatti to Manlog via Teer Road Km 0/0 to 3/0 (SH:- C/O PCC B/wall at RD 0/820 to 0/843 Km)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (ordinary soil)	69.00	220.00	Rupees Two Hundred Twenty Only	P/Cum	15180.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge . (1:4:8)	41.40	4700.00	Rupees Four Thousand Seven Hundred Only	P/Cum	194580.00
3	Providing weepholes in brick masonry/ stone masonry , plain reinforcement concrete abutment , wing wall , R/wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 (V) 20 (H) towards drawing face complete as per drawing with in all leads and lifts as per directions of the Engineer-in-Charge)	23.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	5569.45
Total						215329.45
			Quoted rate in figer+/- (%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

26

Schedule Of Quantity

Estimated Cost: 213912/-
Earnest Money: 4300/-
Time: One month

Name of Work:- R/R Rain Damages on Balghar Tihanadhar Kalna Road km 0/0 to 24/500 C/O RCC BWall at RD13/180 to 13/195)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	51.15	in feg 280.00	in words Rupees Two Hundred Eighty Only	P/cum 14322.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size)	39.30	4900.00	Rupees Four Thousand Nine Hundred Only	P/cum 192570.00
3	Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	26.00	270.00	Rupees Two Hundred Seventy Only	Each 7020.00
Total:-					213912.00
		Quoted Rates (In Fig)		(% above/below /at Par)	
		Quoted Rates (In Words)			



Executive Engineer
Theog Division
HP.PWD. Theog

27

SCHEDULE OF QUANTITY

Estimated Cost: 498000/-
Earnest Money: 10000/-
Time Three month

Name of Work:- Restoration of rain damages on Various Road under Theog sub division (SH:-Hiring of Excavator-Cum Loader/Tipper for removal of snow/slips and surface dressing in Various Roads under Fagu Section)

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	260.00	1050.00	Hrs	273000.00
2	Hiring of full size Tipper 5.50 cum/10 tons loading capacity, self-unloading system on daily basis (for eight hour daly in good condition including the charges of POL Repair ad maintenance and wages of Driver/Operator for lifting of excavated earth/sone slips, drain and disposal of the same in all leads and lifts including disposal of the same in all leads and lifts including carriage of material and as per HPPWD specification of 1990 Vol.I and as per the direcion of Engineer in Charge at site.)	50.00	4500.00	P/day	225000.00
				Total	498000.00
					% above/Below/as per DNIT amount
					Quoted Rate In Fig
					Quoted Rate In Words


Executive Engineer,
Theog Division,
HP.PWD. Theog

98

Schedule Of Quantity

Estimated Cost:497676/-
Earnest Money10000 /-
Time: one month

Name of Work:-Extension of Ground by Providingf R/Wall and fencing over Wall in Govt Degree College at Theog (SH:-C/O R/Wall & Fencing over it)

Sr. No.	Description of items	QTY.	Rate	Unit	Amount
			in fig		
				in words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	64.80	220.00	P/cum	14256.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203. including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8)25 mm nominal size	92.00	5000.00	P/cum	460000.00
4	Providing and fixing weapholes in brick masonry/stone masonry, plain RCC abutment, B/wall, R/wall with 100 mm dia PVC pipe i/c all leads and lifts. as per direction of the Engineer-in-Charge	50.00	250.00	Each	12500.00
5	Back Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	10.40	1050.00	P/cum	10920.00
				Total:-	497676.00
					(% above/below / at Par)
					Quoted Rates (In Fig)
					Quoted Rates (In Words)


Executive Engineer
Theog Division
HP.PWD Theog