

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **09/03/2026** up to 10.30 A.M. and will be opened on the same day at **11.00 A.M.** in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **05/03/2026** up to 5.00 PM and the tender form can be had from this office on **07/03/2026** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I, HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Restoration of rain damages on link road Govt. Primary School to Harizan Basti Baldi in Gram Panchayat Malyawar. (SH: Providing and laying precast paver block in road pavement 80 mm thick with under layer CC 1:3:6 and side lock in CC 1:2:4 at KM 0/062 to 0/080)	94,777/-	2000/-	350	One month
2	Restoration of damages due to laying Sewerage line on Chandigharh Mandi Manali road KM 127/0 to 140/0. (SH: C/O catch pit at RD 133/670.	97,331/-	2000/-	350	One month
3	A/R & M/O non residential building at Changer Sector Bilaspur (SH: Re-filling of fire extinguisher in Session Court Bilaspur HP.)	52,650/-	1100/-	350	One month
4.	Repair of Quarter No. 22 Type-II at Police line Bilaspur (SH: Dismantling and P/F door window, repair of slab and repair of plaster patches etc.)	99,833/-	2000/-	350	One month
5	Special repair on Punch Karma Unit at R/wall in Distt. Ayurvedic Hospital Bilaspur. (SH:- P/L interlocking, plaste work, shutter & painting etc.)	96,695/-	2000/-	350	One month
6	C/O Moksh Dham at Benla Brahmna (SH: C/O shed etc.).	3,99,571/-	8,000/-	350	One month
7	C/O link road to Village Chakli Plare road KM 0/0 to 0/460. (SH: C/O B/Wall at RD 0/140 to 0/165.)	3,23,825/-	7,000/-	350	One month
8	C/O link road to Village Chakli Plare road KM 0/0 to 0/460. (SH: C/O R/Wall at RD 0/135 to 0/160.)	4,39,399/-	9,000/-	350	One month
9	Special repair to Govt. Degree College Bilaspur, Distt. Bilaspur (SH: Repair of plaster in Girls Hostel Building outside LH side and front side)	99,401/-	2000/-	350	One month
10	Special repair to Govt. Degree College Bilaspur, Distt. Bilaspur (SH: Repair of plaster in Girls Hostel Building RH side, back side and brick work)	98,843/-	2000/-	350	One month

	A/R and M/O residential building Changer Sector Bilaspur. (SH: C/O brick masonary, steel work, painting and geyser etc in Various Quarters D-2 T/S.)	97,147/-	2000/-	350	One month
12	Special repair to Govt. Degree College Bilaspur, Distt. Bilaspur (SH: Repair of plaster in Girls Hostel Building parapet wall etc.)	99,827/-	2000/-	350	One month
13	Special repair to Regional Hospital Distt. Bilaspur. (SH: P/F BP sheet, pre-painted sheet in MCH Building.)	80,482/-	1700/-	350	One month
14	A/R and M/O Residential accommodation at Nihal Sector Distt. Bilaspur HP. (SH: P/F wooden shutter for Quarter No. 125 to 128.)	97,928/-	2000/-	350	One month
15	Restoratio of damages due to laying of sewerage line on various roads under Sub Division No. II, HPPWD Bilaspur (SH: P/F duel direction speed breaker.)	99,450/-	2000/-	350	One month
16	Special repair to CHC Building Kuthera Distt. Bilaspur, (SH: Repair of Hospital Building)	98,895/-	2000/-	350	One month
17	Special repair to CHC Building Kuthera Distt. Bilaspur, (SH: Repair of Hospital Building)	99,220/-	2000/-	350	One month
18	A/R and M/O Residential accommodation at Nihal Sector Distt. Bilaspur HP. (SH: P/F panelled glazed shutter, painting, distempering at Quarter No. 125 to 128.)	91,543/-	2000/-	350	One month
19	A/R & M/O link road from Kandrouer Bamta road to Village Behal Kandela KM 0/0 to 0/400. (SH: C/O B/Wall at RD 0/090 to 0/120.20)	99,887/-	2000/-	350	One month
20	A/R & M/O residential building Changer Sector Bilaspur. (SH:- White washing, painting and tile work in D2-8 D/S).	93,666/-	2000/-	350	One month
21	A/R & M/O residential building Changer Sector Bilaspur. (SH:- P/L floor tiles in D-2-7 D/S in room except drawing halls).)	86,323/-	2000/-	350	One month
22	A/R & M/O residential building Changer Sector Bilaspur. (SH:- P/L geyser toilet seat, sink and etc. work in Qtrs D-2-7 D/S).	98,720/-	2000/-	350	One month
23	Repair and restoration of rain damages on Panoh Harlog Samella road KM 0/0 to 10/0. (SH: C/O B/Wall at RD 6/035 to 6/042.70 under PDNA-2023	92,232/-	2000/-	350	One month
24	Repair and restoration of rain damages on Panoh Harlog Samella road KM 0/0 to 10/0. (SHP/L WBM and tarring between KM 2/450 to 2/497.50) under PDNA-2023	99,839/-	2000/-	350	One month
25	Repair and restoration of rain damages on Harlog Kuh Trifalghat road KM 0/0 to 20/0. (SH: Formation cutting at RD 2/300 to 2/345.) under PDNA-2023.	99,141/-	2000/-	350	One month
26	Restoration of rain damages on NH-124 Chandigarh Mandi Manali road KM 140/0 to 146/0. (SH: Re-construction of U-shape drain at RD 144/355 to 144/520) under PDNA-2023.	4,98,840/-	2000/-	350	One month
27	Repair and restoration of rain damages on Panoh Harlog Samella road KM 0/0 to 10/0. (SH: C/O B/Wall at RD 6/055 to 6/061) under PDNA-2023	99,684/-	2000/-	350	One month
28	Repair and restoration of rain damages on link road Palela to Badar KM 0/0 to 1/500. (SH: Re-construction of R/Wall cum edge Wall at RD 1/105 to 1/120.) under PDNA-2023.	3,02,490/-	6,100/-	350	One month

	Repair and restoration of rain damages on Harlog Kuh Trifalghat road KM 0/0 to 20/0. (SH: C/O R/Wall at RD 3/150 to 3/154.15, 3/155 to 3/159.85 and 3/160 to 3/164.15) under PDNA-2023	3,12,412/-	6,300/-	350	One month
30	A/R & M/O residential building Changer Sector Bilaspur. (SH:- Dismantling PVC floor matt, tile work, door frame etc. qtr No. D2-7 D/S).	84,369/-	2000/-	350	One month

1. **Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.**

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/GST/EPF/Registration should be attached with the application otherwise tender form will not be issued.

Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 20140-60

Dated :- 27/02/2026

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.


DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 94,777/-only
 Earnest Money Rs. = 1,900/- only.
 Time Limit. = One Month

Name of Work:- R/R damages on link road Govt. Primary School to Harizan Basti Bafdi in Gram Panchyat Malyawar (SH:- Providing and laying precast paver block in road pavement 80mm thick with under layer C.C 1:3:6 & side lock in C.C 1:2:4 at km. 0/062 to 0/080).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	16.20	Square Metre	5	6	8
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne (Eight to twelve toone) capacity after excavating earth to an average of 22.5 cm (Twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 m (Fifty metres). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations, complete as per drawings and technical specifications clause 802,803,1202 & 1203. plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.40	Cubic Meter			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocksNTC in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern. finishing and weeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-50 grade with approved color design and pattern. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.20	Square metre			

Sr No		Description of items.	Qty.		Rates		Amount
			3	4	In Figure	In words	
SCHEDULE OF QUANTITY.							
Estimated cost Rs. = 97,331/-only							
Earnest Money Rs. = 2000/- only.							
Time Limit, = One Month							
name of work:-Restoration of road damages due to laying of sewerage lin on Chandigarh Mandi Manali road Km. 127/00 to 140/00. (SH:- C/O							
atch pit at RD. 134/670).							
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.00	Per Cubic metre	5	6	7
2	2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802.803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.81	Per Cubic metre			
3	3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Each			
TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.		Estimated cost Rs. = 52,650/-only	
		Earnest Money Rs. = 1100/- only.	
		Time Limit. = One Month.	
Name of work :- A/R & M/O non residential building at Changer Sector Bilaspur. (SH:- Re-filing of fire extinguisher in session court Bilaspur (H.P).)			
Sr. No.	Description of items.	Qty.	Unit
		In Figure	In words
1	2	5	6
1	Re-filing and recharging of fire protection device Mono Ammonium Phosphate Base fire extinguisher cylinders ABC stored pressure type-9 (Nine) Kilogramme capacity as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	7
		26.00	Each
TOTAL			
			8




Executive Engineer,
Bilaspur Division No.1
HP.PWD, Bilaspur

		Estimated cost Rs. 99,833/-only		Earnest Money Rs. 2000/- only.		Time Limit = One month	
		In Figure	In Word	In Figure	In Word	Unit	Amount
Schedule of quantity							
Name of work:- Repair of qtrs No. 22 type-II at Police line Bilaspur. (SH:- Dismantling & P/F door and window , repair of slab & repair of plaster patches etc.)							
Sr No	Description of items.	Qty.	Rates		Unit	Amount	
1	2	3	4	5	6	7	
1	Dismantling doors, window, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each		
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.140			Per Cubic Metre		
3	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty millimetre) thick 2nd (Second) class teak wood, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.73			Per Square Meter		
4	Surface dressing of the ground including dressing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.73			Per Square Meter		

5	<p>Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm (Zero point seventy - onePer Square Metre) using mechanical means as per Technical Specification Clause 502. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	171.46	Per Square Meter
6	<p>Providing and laying LDPE Black point liner Taapauling sheet 500 micron. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	85.73	Per Square Metre
7	<p>Cement concrete flooring 1:2:4 (One cement : Two coarse and : Four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of Eaching of steps etc. complete. 40 mm (Forty millimetre) thick with 20 mm (Twenty millimetre) nominal size stone aggregate. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	85.73	Per Square Metre
8	<p>Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ Per Square Meter including pointing the joints with white cement and matching pigments etc., complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	7.03	Per Square Metre

9	Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.10	Per Square Meter	
10	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.			
10.1	300x16 mm. (Three hundred fifty into sixteen millimetre).	2.00	Each	
10.2	150x10 mm. (One hundred fifty into ten millimetre).	8.00	Each	
11	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 125 mm (One hundred twenty five millimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	
	Total			3



 Executive Engineer,
 Bilaspur Division No.1
 HP PWD, Bilaspur

Schedule of Quantity

		Estimated cost Rs. = 99,695/- only		Earnest Money Rs. = 2,000/- only		Time Limit = One month	
Name of Work:- Special repair on Punch Karma Unit at R/Wall in Distt. Ayurvedic Hospital Bilaspur. (SH;- P/L interlocking, plaste work, shutter & painting etc.).							
Sr No	Description	Qty.	In Figure	In words	Unit	Amount	
1	2	3	5	6	7	8	
1	Providing and laying granite stone 20mm thick over self steel already laid thin granite laid single without cement. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.98			Per Square Metre		
2	Providing and fixing Door spring of approved brand and manufacture (Confirming to IS 6315) floor aluminium doors complete, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each		
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and weeping extra sand, complete all as per direction of Engineer-in Charge 6 0 mm (sixty millimetre) thick ISI marked C.C. paver block of M-50 grade with approved color design and pattern, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.42			Per Square Metre		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm(Twenty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.51			Per Cubic Metre		

5	<p>Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty millimetre) thick 2nd (Second) class decidar wood. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.44		Per Square Meter	
6	<p>Repairs to plaster in patches of 2.50 Sq.M (Two point fifty Per Square Metre), and under and 10 to 15mm (Ten to fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 (Twenty) metres with Cement Mortar 1:5 (One Cement : five) Sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	20.3		Per Square Metre	
7	<p>Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including snad smooth complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	32.90		Per Square Metre	
8	<p>Providing and fixing 10 liter hot water tank in best quality cromton as WH-3D/0 including all type fitting, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	1.00		Each	
9	<p>Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen millimetre) C.P. brass pillar taps, 32 mm (Thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 450x360 mm (four hundred fifty into three hundred millimetre) with a pair of 15 mm (Fifteen millimetre) C.P. brass pillar taps including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	


10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.73			Kilograms		
11	Providing and fixing 0.47mm (Zero point forty seven millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP.PWD Specification . including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax . Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.55			Per Square Meter		
TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of Quantity

Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
		3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 Per Square Metre (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms. lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.45			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802.803.1202 & 1203 : plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.45			Per Cubic Metre	
3	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floor including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. Lintle beam plinth	11.02			Per Square Metre	
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm (Twenty millimetre) nominal size), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.76			Per Cubic Meter	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhanna, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.80			Kilogramme	

6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1878.80			Kilogramme
7	Providing and fixing 0.63mm (Zero point sixty three millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with top dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts, 6mm diameter with pre-painted limpet and rubber washers complete with all accessories, as per HP.PWD Specification, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.67			Per Square Meter
8	Boulder filling dry hand packed tightly in wire crates vertical bunds with sloping face (wire crates to be measured separately), including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50			Per Cubic Metre
9	Providing ridges or hips of width 60 cm (Sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumien washers complete. 0.63 mm (Zero point sixty millimeter) thick with zinc coating not less than 275 gm/m ² . (Two hundred seventy five gramme / Per Square Metre), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.80			Per Running Metre
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 course sand). Bricks already available at site and only rate applying cement mortar and labour, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.83			Per Cubic Metre
TOTAL					



 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 3,23,825/-only
 Earnest Money Rs. = 6500/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Construction of link road to village Chakli Plare road Km. 0/00 to 0/460. (SH:- C/O B/wall at Rd's 0/140 to 0/165).

Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m. (One point five metre) as directed by Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	73.25	Per Cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	19.75	Per Cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:10 (One cement - Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	59.00	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Each			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 4,39,398/- only
 Earnest Money Rs. = 8800/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.


Name of work:- Construction of link road to village Chakli Plare road Km. 0/00 to 0/460. (SH:- C/O R/wall at Rd's 0/135 to 0/160).

Sr No	Description of items.	Qty.	Rates		Amount
			In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.25	Per Cubic metre	8	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.75	Per Cubic metre		
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Each		
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.25	Per Cubic metre		
TOTAL					



 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 7

Sr. No.		Description of items.	Qty.	Rates		Unit	Amount
				In Figure	In words		
<p style="text-align: center;">SCHEDULE OF QUANTITY.</p> <p>Estimated cost Rs. = 99,401/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month.</p>							
<p>Name of work :- Special repair to Govt. Degree College Bilaspur Dist. Bilaspur. (SH:- Repair of plaster in Girl Hostel Building outer side LH side & front side).</p>							
1	1	<p>2</p> <p>Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	3	5	6	7	8
				TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Sr. No.		Description of items.	Qty.	Rates		Unit	Amount
				In Figure	In words		
1		2	3	5	6	7	8
1		Brick work with common burnt clay F.P.S. (Each modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (One cement : Six coarse sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.58			Per Cubic Metre	
2		Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	154.31			Per Square Meter	
			TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur


Schedule of quantity

Name of work:- A/R & M/O residential building Changer Sector Bilaspur. (SH:- C/O Brick masonry, steel work, painting and geyser etc. in various Qtrs D-27/S).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1.	Stone soling under floor tightly hand packed as per HP.PWD Specification clause 11.1.4.1.8. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.47			Per Cubic Meter	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm (Twenty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.38			Per Cubic Metre	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (One cement : Six coarse sand), including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.18			Per Cubic Metre	
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	126.16			Per Kilogramme	

5	<p>Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories, as per HP.PWD Specification . including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	13.75	Per Square Meter
6	<p>15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto all floor level in any height including arrises, internal rounded ngles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1:5 (One cement : five Sand), as per HP.PWD Specification clause 17 & 4.4.1. including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	12.64	Square Meter
7	<p>Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	42.64	Per Square Metre
8	<p>Finishing wall with weather proof exterior grade emulsion of approved design (Apex ultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete, including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	63.64	Per Square Meter
9	<p>Repair of 3 Nos steel gate level rise including hinges and fixing with welding & steels, including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	3.00	Each

10	Deputr one number skilled carpenter of opening door and windows and re-fixing after size curtaling good finished as per direction of Engineer. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00		Per day	
11	Providing and fixing UPVC pipes 15mm complete with fitting and clamps i/c fitting and making good the walls etc. internal work (Finoles) as per direction by Engineer-in-Charge including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00		Per Running Metre	
TOTAL					



 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Sr. No.		Description of items.	Qty.	Rates		Unit	Amount
				In Figure	In words		
1	2	Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	5	6	7	8
			307.16			Per Square Meter	
			TOTAL				

SCHEDULE OF QUANTITY.

Estimated cost Rs. = 99,827/-only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One Month.

Name of work :- Special repair to Govt. Degree College Bilaspur Distt. Bilaspur. (SH:- Repair of plaster in Girl Hostel Building parapet wall etc).



 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. 80,482/-only
 Earnest Money Rs. 1700/- only.
 Time Limit. = One month

Schedule of quantity

Name of work:- Special repair to Regional Hospital Distt. Bilaspur. (SH: - P/F B.P sheet, preprinted sheet etc. in MCH building).

Sr No	Description of items.	Qty.	Rates		Unit	Amount	
			In Figure	In Word			
1	2 Providing and fixing M.S. BP Sheet 1.66mm to 2mm (one point sixty six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 23.49	5	6	7 Per Square Metre	8	
2	Providing and fixing 0.47mm (Zero point sixty millimetre) thick pre-painted steel sheet of TATA / DURO SHINE or its equivalent in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts, 6mm (Six millimetre) diameter with pre-painted limpet and rubber washers complete with all accessories as required, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.11			Per Square Metre		
TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur


Job No. 164

Estimated cost Rs. 97,928/- only
 Earnest Money Rs. 2000/- only.
 Time Limit. = One month

Schedule of quantity

Name of work:- A/R & M/O residential accommodation at Nihal Sector Distt. Bilaspur. (SH:- P/F wooden shutter for Qtr No. 125 to 128).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.216			Per Cubic Metre	
3	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty millimetre) thick 2nd (Second) class teak wood. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.00			Per Square Meter	
6	Providing and fixing SS sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :250x16 mm. including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
		Total				



 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 99,450/-only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Restoration of rain damages due to sewerage line on various road under Sub Division No. II HPPWD Bilaspur.
 (SH:- P/F dual direction speed breaker).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2 Providing and fixing dual directional reflective speed breaker/rumble-strip /yellow plastic high impact resistant plastic body size 275 X 150 X 32mm having 6 glass large 12mm (Twelve millimeter) dia white reflector lenses to one side (12 Nos on both side) provided with two steel zink plated nails of 12 (Twelve millimeter) and of length 120mm (One hundred twenty millimeter) and epoxy for fixing to road by hammering. CAT PART No. GPL-07-02 Make Greenlite. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	130.00	Each	5	6	8
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of quantity

Name of work:- Special repair to CHC building Kuthera Distt. Bilaspur. (SH:- Repair of hospital building).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty millimetre) thick 2nd (Second) class teak wood. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.60			Per Square Meter	
2	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
3	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00			Each	
4	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00			Each	

5	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (1) Single socketed pipes 110 mm diameter, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.60			Per Running Metre
6	Providing and fixing PVC accessories PVC rain water pipes including joining with seating.				
6.1	Couplers 75mm dia	6.00			Each
6.2	Single tee with door 75x75x75 mm dia (Seventy five into Seventy five into Seventy five millimetre)	12.00			Each
6.3	Single tee without door 75x75x75 mm dia (Seventy five into Seventy five into Seventy five millimetre)	4.00			Each
6.4	Bend 75mm	4.00			Each
7	Providing and fixing PVC door bend 110 mm (one hundred ten millimetre) diameter, with oval access door, insertion rubber washer 3mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00			Per Running Metre
8	Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen millimetre) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required.- White Vitreous China Wash basin size 550x400 mm (Five hundred fifty into four hundred millimetre) with a 15 mm (Fifteen millimetre) CP Brass single hole basin mixer including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	52.00			Each
9	Providing and fixing 32mm (Thirty two millimetre) dia PVC D-plast FINOLEX waste pipe for wash basin or sink of superior quality approved by bureau of Indian Standard, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each

10	<p>Providing and fixing 10.00 liters (Ten liters) PVC low level flushing cistern COMMANDER / CORAL / CERA/ HINDWARE (SLIMLINE) /HINDUSTAN with a pair of C.I or mild steel brackets complete with fitting such as lead valve less Jing syphon, 15 mm (Fifteen millimeter) nominal size brass ball valve with polygonal float C.P brass handles union and coupling for connection with inlet, outlet and over flow pipe 40 mm (forty millimeter) C.P flus band and including cutting holes in walls and making good the same and connecting the flush bend with cistern including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each.	
11	<p>Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	
12	<p>Providing and fixing Hindware/Cera/Jaquar 600X120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	
13	<p>Providing and fixing PTMTs towel Rail Complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass 600*20mm. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	4.00		Each	
14	<p>Providing and fixing PTMT liquid soap container and brackets fixed to wooden plugs with C.P. Brass screws Glass container. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	4.00		Each	

15	<p>Providing and fixing ball valve (horizontal plunger type) High pressure with polythene plastic floats 25mm (Twenty five millimetre) nominal bore. including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	
16	<p>Providing and fixing uplasticeised PVC connection pipe with brass unions . 45 cm length 15 mm nominal bore. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	8.00		Each	
17	<p>Providing and fixing PVC pipe 15mm dia including all type fitting. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	9.00		Per Running Metre	
18	<p>Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS:8931 : 15 mm (Fifteen millimetre) nominal bore and weight not less than 690 grms. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	6.00		Each	
19	<p>Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931. 15mm (Fifteen millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	9.00		Each	
20	<p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap heading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) : Aluminium strip 40mm (Forty millimetre) wide and 2 mm (Two millimetre) thick for ceiling. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	34.80		Per KG	

20.1	For shutters of doors windows & ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately)	37.45		Per Kilogramme
21	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item). With float glass panes of 4.0 mm (Four millimetre) thickness (weight not less than 10 kg/ Per Square Meter (Ten kilogramme / Squaremetre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.92		Per Square Metre
22	Renewing glass panes with wooden fills wherever float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm), including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.32		Per Square Metre
	TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of quantity

Name of work:- Special repair to CHC building Kuthera Distt. Bilaspur. (SH:- Repair of hospital building).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 Per Square Meter (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m. (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhama, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.55			Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhama, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.70			Per Cubic Metre	
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm (Twenty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhama, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.25			Per Cubic Metre	
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in Charge 80 mm (Eighty millimetre) thick C.C. paver block of M-50 grade with approved color design and pattern, including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhama, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.00			Per Square Metre	
Total						


 Executive Engineer,
 Bilaspur Division No.1
 HP.P.W.D., Bilaspur

Schedule of quantity

Name of work:- A/R & M/O residential accommodation at Nihal Sector Distt. Bilaspur. (SH:- P/F panelled glazed shutters, painting, distemping at Qtrs No. 125 to 128).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty millimetre) thick 2nd (Second) class teak wood, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.72			Per Square Meter	
2	Providing and fixing SS sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16 mm. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
3	Providing and fixing 150mm (one hundred fifty millimeters) aluminum handles anodized transparent or dyed to required colour and shade with necessary screws etcetera upto all floor level/height complete, including entire carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, Goods service tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
4	Providing and fixing 150X10 mm(One hundred fifty into ten millimetres) M.S. tower bolts (barrel type) with necessary screws etcetra complete including carriage of materials as per HP.PWD Specification clause 12. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00			Each	

5	<p>Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	324.16		Per Square Metre	
6	<p>Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	324.16		Per Square Metre	
7	<p>Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	162.08		Per Square Metre	
8	<p>Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood), including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	42.71		Per Square Metre	
9	<p>Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping with white enamel paint, as per HP.PWD Specification clause 16, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	121.52		Per Square Metre	

10	<p>Providing & fixing White vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba, all complete as per the direction of Engineer-in charge, Orissa pattern W.C Pan of size 580x440 mm. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	
11	<p>Providing and fixing 75 mm (Seventy five millimetre) diameter high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	6.00		Per Running Metre	
Total					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 19

Estimated cost Rs. = 99,887/- only

Earnest Money Rs. = 2,000/- only.

Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of Work:- A/R & M/O on link road from Kandrour Bamta road to village Behal Kandela Km. 0/00 to 0/400. (SH:- C/O B/Wall at RD. 0/090 to 0/102.20).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lit upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of this same.	16.40	Per Cubic metre	5	6	8
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1.5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.84	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of this same.	7.00	Each			
TOTAL						



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Estimated cost Rs. 93,666/- only
 Earnest Money Rs. 2000/- only.
 Time Limit. = One month

Schedule of quantity

Name of work: A/R & M/O residential building Changer Sector Bilaspur. (SH:- white washing, painting and tile work in D2-8 D/S)

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/Per Square Meter, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight millimetre) thick, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.09			Per Square Metre	
2	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	387.71			Per Square Meter	
3	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matt finish to the surface complete. As per HP.PWD specification. Including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.93			Per Square Meter	
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	387.71			Per Square Metre	
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give uneven shade One or more coats on old work, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	202.86			Per Square Metre	


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD, Bilaspur

Job No. 24

Estimated cost Rs. 86,323/-only
 Earnest Money Rs. 2000/- only.
 Time Limit. = One month

Schedule of quantity

Name of work:- A/R & M/O residential building Changer Sector Bilaspur. (SH:- P/L floor tiles in D-2 -7 D/S in room except drawing halls).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS:15622. of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:3 (One cement : three coarse sand), jointing with grey cement slurry @ 3.3 kg/ Per Square Meter (Three point three kilogramme / Per Square Metre) including grouting the joints with white cement and matching pigments etc., complete size tiles 600x600 mm. (Six hundred into six hundred millimetre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.51			Per Square Metre	


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD, Bilaspur

Estimated cost Rs. 98,720/-only

Earnest Money Rs. 2000/- only.

Time Limit. = One month

Schedule of quantity

Name of work:- A/R & M/O residential building Changer Sector Bilaspur. (SH:- P/F geyser toilet seat, sink and etc. work in Qtrs D-2- 7 D/S).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Providing and fixing geyser (Orient make) in bath room and kitchen including fitting all accessories. Paints of electing including socket complete fitting at site as per direction in-Engineer. 25 Litre capacity. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
2	Providing and fixing geyser (Orient make) in bath room and kitchen including fitting all accessories. Paints of electing including socket complete fitting at site as per direction in-Engineer. 5 Litre capacity. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
3	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm (Forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required : 470x420 mm (Four hundred seventy into four hundred twenty millimetre) bowl depth 178 mm (One hundred seventy eight millimetre), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
4	Providing and fixing white vitreous china pedestal type (European type) wash down type) water closet pan Hindware 92631 S-22 Sharpshire with flush seat cover, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	

5	<p>Providing and fixing uplasticsed PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	12.00		Each	
6	<p>Providing and fixing C.P. brass stop / angle cock (concealed) of approved quality conforming to IS-8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	10.00		Each	
7	<p>Providing and fixing C.P. brass bib tap 15mm (Fifteen millimetre) dia with capstern, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	7.00		Each.	
8	<p>Providing and Fixing ISI marked C.P Brass Jaquar pillar tap swan neck with Capstian head 15 mm (Fifteen millimeter) dia,including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	2.00		Each	
9	<p>Providing and fixing 32mm (Thirty two millimetre) dia PVC D-plast FINOLEX waste pipe for wash basin or sink of superior quality approved by bureau of Indian Standard. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	3.00		Each	
10	<p>Providing and fixing Chromium plated brass soap dish of Jaquar with C.P. brass brackets fixed to wooden cleats with C.P. brass screws. including entire carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	4.00		Each	

11	<p>Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/Per Square Meter, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight millimetre) thick, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	8.28		Per Square Metre
12	<p>Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:3 (One cement : three coarse sand), jointing with grey cement slurry @ 3.3 kg/ Per Square Meter (Three point three kilogramme / Per Square Metre) including grouting the joints with white cement and matching pigments etc., complete size tiles 600x600 mm. (Six hundred into six hundred millimetre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	9.00		Per Square Metre


 Executive Engineer,
 Bilaspur Division No.1
 HP.P.W.D., Bilaspur

Job No. 23

Estimated cost Rs. = 92,232/-only

Earnest Money Rs. = 2000/- only.

Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 10/00. (SH:- Construction of B/wall at RD. 6/035 to 6/042.70). (Under PDNA 2023)

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m. (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads, and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.18	Per Cubic metre	5	6	8
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.170	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Each			
TOTAL.						



Executive Engineer,
Bilaspur Division No.1
HP.PWD, Bilaspur


Estimated cost Rs. = 99,839/-only
Earnest Money Rs. = 2000/- only.
Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair and restoration of rain damages on Panoh Harlog Samaila road Km 0/00 to 10/00. (SH:- P/L WBM & Tarring between Km. 2/450 to 2/500.) (Under PDNA 2023).

1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.45	Per Cubic metre			
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.73	Per Cubic metre			
3	Providing and laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / bedding material to fill up interstices of coarse aggregate, watering and compacting to the required density. 90 mm to 45 mm size stone aggregate. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.04	Per Cubic Metre			

4	<p>Providing and applying tack coat using bitumen emulsion conforming to IS 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom With rapid setting bitumen emulsion. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	147.25	Per Square Metre	
5	<p>2 cm premix carpet surfacing with 1.8 cum (One point eight) and 0.90 cum (Zero point ninety Per Cubic Metre) of stone chippings of 13.2 mm (Thirteen point two millimetre) size and 11.2 mm (Eleven point two millimetre) size respectively per 100 sqm (One hundred square) and 52 kg (Fifty two kilogramme) and 56 kg (Fifty six kilogramme) of hot bitumen per cum of stone chippings of 13.2 mm (Thirteen point two millimetre) size and 11.2 mm (Eleven point two millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne (Six to nine millimetre) capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 (VG-thirty) with no solvent. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.</p>	147.25	Per Square Metre	
TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 25

Estimated cost Rs. = 99,141/-only


Earnest Money Rs. = 2,000/- only.

Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of Work: Repair & Restoration of damages on Harlog Kub Trifalghat road Km. 0/00 to 20/00. (SH:- Formation cutting at RD. 2/300 to 2/345). Under PDNA 2023.

Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) ordinary rock including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy oncess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	330.47	Per Cubic metre			
		TOTAL				



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost Rs. = 4,98,840/- only
 Earnest Money Rs. = 10000/- only.
 Time Limit. = One Month

Name of Work:- Restoration of rain damages on NH-154 Chandigarh Mandi Manali roads Km. 140/00 to 146/00. (SH:- Re-construction of U-shape drain at RD. 144/355 to 144/520) (under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m. (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	148.50	Per Cubic metre	5	6	8
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802.803, 1202 & 1203, plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8085	Per Cubic metre			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 99,684/-only


Earnest Money Rs. = 2000/- only.

Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Smaila road Km. 0/00 to 22/615. (SH:- C/O B&W at Rd's 6/055 to 6/061).
Under PDNA 2023.

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan). including dressing of sides and retaining of bottoms. lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.46	Per Cubic metre	5	6	8
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.00	Each			
TOTAL						


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 28

Estimated cost Rs. = 3,02,490/-only
 Earnest Money Rs. = 6100/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on link road Palela to Badar KM. 0/00 to 1/500. (SH:- Re-Construction of R/wall cum edge wall at RD. 1/105 to 1/120). (Under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	33.75	Per Cubic metre	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan). including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	54.000	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	13.50	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Each			
TOTAL						

Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 3,12,412/-only
 Earnest Money Rs. = 6300/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Restoration of rain damages on Harlog Kuh Trifalghat road Km. 0/00 to 20/00. (SH:- C/O R/waal at Rd's 3/150 to 3/154.15 , 3/155 to 3/159.85 & 3/160 to 3/164.15).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.98	Per Cubic metre	5	6	8
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.57	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V) 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.00	Each			
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1209 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.95	Per Cubic metre			
		TOTAL				

Executive Engineer,
 Bilaspur Division No.1
 HP.P.W.D., Bilaspur


Schedule of quantity

Estimated cost Rs. 84,369/-only
Earnest Money Rs. 2000/- only.
Time Limit. = One month

Name of work:- A/R & M/O residential building Changer Sector Bilaspur. (SH:- Dismantling PVC floor matt, tile work, door frame etc Qtr No. D2-7 D/S).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	4	5	6	7
1	Dismantling PVC floor matt with skilled carpenter / belder including tools and proper disposing including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00			Per day	
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS: 15022, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:3 (One cement : three coarse sand), jointing with grey cement slurry @ 3.3 kg/ Per Square Meter (Three point three kilogram / Per Square Metre) including grouting the joints with white cement and matching pigments etc., complete size tiles 600x600 mm. (Six hundred into six hundred millimetre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.60			Per Square Metre	
3	Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:3 (One Cement : five approved Sand) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.68			Per Square Metre	
4	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.170			Per Cubic Metre	
5	Providing and fixing 110 mm (one hundred ten millimetre) dia, high pressure PVC spigot and socket, waste and ventilating pipes Finolux (S) marked including fixing with approved adhesive etcetera complete in all height as per the including entire carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, Goods service tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.50			Per Running Metre	

6	Providing and fixing PVC plain bend ISI marked i/c fixing with approved adhesive etc. complete 110 mm (One hundred ten millimetre), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each
7	Providing and fixing liquid soap container with C.P. Brass lid and brackets fixed to wooden plugs with C.P. Brass screws :- Plastic container, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each
8	Providing and fixing Tooth brush tumbler including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each
9	Providing & fixing fly proof wire gauze to windows, clerestory windows & door with MS Flat 15x3 mm and nuts and bolts complete. Galvanised M.S. Wire gauze with 0.63 mm dia wire and 1.4 mm aperture on both sides, including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.92			Per Square Metre
10	Applying Birla white putty wall care putty over plaster surfaces after thoroughly brushing the surface free mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.68			Per Square Meter
11	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.68			Per Square Meter


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur