



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 10069-78 dated 21-02-2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

“NOTICE INVITING TENDERS”

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **27.02.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **26.02.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **26.02.2026 up to 11:00 AM.** The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Molag to Maila road Km 0/00 to 7/500 (SH:-C/O R/wall and drain Km 1/145 to 1/160) PDNA	499781.00	10000.00	Two Month	350/-
2	Restoration of rain Damages on Bhawarna Jhunga Devi Road Km 15/500 to 26/250 (SH:-Providing R/wall to damaged road portion at RD 23/700 to 23/709) PDNA	491378.00	9900.00	Two Month	350/-
3	Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 9/630 (SH:- C/O Edge wall and Maintenance of Earthen Shouldera between Km 6/00 to 9/630) PDNA	167863.00	3400.00	Two Month	350/-
4	Restoration of rain Damages on Chadhiar Mungal Haler road (Portion Km 2/600 to 10/100 (SH:- C/O Breast wall and Drain Km 7/135 to 7/360) PDNA	498620.00	10000.00	Two Month	350/-
5	Restoration of rain Damages on Panchrukhi Lambagaon road Km 10/00 to 22/00 (SH:-C/O R/wall at Rd 19/240 to 19/250) PDNA	142538.00	2900.00	Two Month	350/-
6	Restoration of rain Damages on Alampur to Harsipattan road Km 8/00 to 19/00 (SH:-Providing R/wall at Scoured road stretch from RD 16/255 to 16/265) PDNA	495593.00	10000.00	Two Month	350/-
7	Restoration of rain Damages on Gander Siyara Kudana road km 0/00 to 9/780 (SH:-C/O R/wall from RD 6/100 to 6/120) PDNA	499325.00	10000.00	Two Month	350/-
8	Restoration of rain Damages on Haler to Ropa via Guhan road Km 0/00 to 4/00 (SH:-C/O wire crate R/wall 2nd step over existing wire crte at Rd 0/550 to 0/575)	70050.00	2000.00	Two Month	350/-
9	C/O Link road from Village Dabhi to Kuthan Km 0/00 to 0/700 (SH:- Balance work C/O 6.00 Mtr. Span RCC slab Culvert at RD 0/640) (Abutment upto Floor level) Deposit SDP/2023/1332	499352.00	10000.00	Two Month	350/-
10	Restoration of rain Damages on Alampur Harsipattan road between Km 8/00 to 19/00 (SH:-C/O concrete Jacketing to Haroti Khad Bridge at RD 15/900 to Pier No. 2,3 Abutment i/c river training wall on U/S) PDNA	459920.00	9200.00	Two Month	350/-
11	Restoration of rain damages on Alampur Harsipattan road KM 0/00 to 25/00 (SH:- Providing and fixing dual directional rumble strips different vulnerable location between KM 0/00 to 25/00) PDNA	497250.00	10000.00	Two Month	350/-

-----Continued page- 2-----

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.




Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
On behalf of Governor of (Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 10069-78

Dated: 21-02-2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineers under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.




Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

①

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Molag to Maila road Km 0/00 to 7/500 (SH:-C/O R/wall and drain Km 1/145 to 1/160) PDNA						Estimated cost Rs.	499781.00
						Earnest Money Rs.	10000.00
						Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	52.05	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	11711.00	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	118.20	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	455070.00	

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	22.50	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	21375.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	30.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	7500.00
5	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.50	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	4125.00
Total						499781.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						




Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

(2)

SCHEDULE OF QUANTITY							
Name of work :-Restoration of rain Damages on Bhawarna Jhunga Devi Road Km 15/500 to 26/250 (SH:- Providing R/wall to damaged road portion at RD 23/700 to 23/709) PDNA						Estimated cost Rs.	491378.00
						Earnest Money Rs.	9900.00
						Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	46.58	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	11645.00	
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	103.49	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	439833.00	

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	36.00	900.00	Rupees Nine Hundred Only	Per cubic Metre	32400.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	30.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	7500.00
Total						491378.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

4

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Chadhiar Mungal Haler road (Portion Km 2/600 to 10/100)
(SH:- C/O Breast wall and Drain Km 7/135 to 7/360) PDNA

Estimated cost Rs. 498620.00
Earnest Money Rs. 10000.00
Time Limits Two Month


S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	79.20	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	19800.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	104.8	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	403480.00

4

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Chadhiar Mungal Haler road (Portion Km 2/600 to 10/100 (SH:- C/O Breast wall and Drain Km 7/135 to 7/360) PDNA						
					Estimated cost Rs.	498620.00
					Earnest Money Rs.	10000.00
					Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	79.20	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	19800.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	104.8	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	403480.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	40.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	10000.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.20	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Metre	65340.00
Total						498620.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

5


SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Panchrukhi Lambagaon road Km 10/00 to 22/00 (SH:-C/O R/wall at Rd 19/240 to 19/250) PDNA			Estimated cost Rs.		142538.00	
			Earnest Money Rs.		2900.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.90	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	2903.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	35.1	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	135135.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4500.00
Total						142538.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
G.Total in Figures		Less (-)			%	
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	48.00	900.00	Rupees Nine Hundred Only	Per cubic Metre	43200.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	27.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	6750.00
Total						495593.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	48.00	900.00	Rupees Nine Hundred Only	Per cubic Metre	43200.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	27.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	6750.00
Total						495593.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

9

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gander Siyara Kudana road km 0/00 to 9/780 (SH:-C/O R/wall from RD 6/100 to 6/120) PDNA						
					Estimated cost Rs.	499325.00
					Earnest Money Rs.	10000.00
					Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.60	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	11385.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	106.00	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	450500.00

3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	25.20	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	23940.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	54.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	13500.00
Total						499325.00
Quoted Rate (in Figures) Percentage						Excess (+) %
G.Total in Figures						Less (-) %
G.Total in Words						




Executive Engineer,
Jaisinghpur Division,
H.P.PWD Jaisinghpur

8

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Haler to Ropa via Guhan road Km 0/00 to 4/00 (SH:-C/O wire crate R/wall 2nd step over existing wire crte at Rd 0/550 to 0/575) PDNA						Estimated cost Rs.	70050.00
						Earnest Money Rs.	2000.00
						Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	15.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per cubic metre	47250.00	
2	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	24.00	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	22800.00	
Total							70050.00
Quoted Rate (in Figures) Percentage		Excess (+)			%		
		Less (-)			%		
G.Total in Figures							
G.Total in Words							



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(9)

SCHEDULE OF QUANTITY

Name of work :-C/O Link road from Village Dabhi to Kuthan Km 0/00 to 0/700 (SH:-Balance work C/O 6.00 Mtr. Span RCC slab Culvert at RD 0/640) (Abutment upto Floor level) Deposit SDP/2023/1332


Estimated cost Rs. 499352.00

Earnest Money Rs. 10000.00

Time Limits Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of bridge structure in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and MORT&H technical specification section 300 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	85.32	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	29862.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	7.80	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	38610.00

3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in Sub Structure using grade M-20 (M -twenty) design mix with cement contents not less than 330 kg (three hundred thirty kilogram) per cubic metre with 40mm (forty millimetre) nominal size graded crushed stone aggregate as per drawing and M.O.R.D. technical specification section 800,900,1200 including the cost of form work and curing complete in aboutment etcetera and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.20	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	407130.00
4	Supplying fitting and placing HYSD bar for reinforcement in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding wire as per the direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.25	95000.00	Rupees Ninety Five Thousand Only	Per Metric Tonne	23750.00
Total						499352.00
Quoted Rate (in Figures) Percentage				Excess (+)	%	
				Less (-)	%	
G.Total in Figures						
G.Total in Words						



 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

(10)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur Harsipattan road between Km 8/00 to 19/00 (SH: C/O concrete Jacketing to Haroti Khad Bridge at RD 15/900 to Pier No. 2,3 Abutment i/c river training wall on U/S) PDNA						
Estimated cost Rs.					459920.00	
Earnest Money Rs.					9200.00	
Time Limits					Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of bridge structure in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and MORT&H technical specification section 300 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government	34.50	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	12075.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in Sub structure complete as per drawing and MORTH technical specification section 1500, 1700, 2200 RCC Grade M-25 (M- twenty five) designed mix with cement contents not less than 450 kg. (Four hundred fifty) Kilogram per cubic meter including curing complete using crushed stone aggregate 20mm (Twenty millimeter) nominal size including formwork but excluding the cost of reinforcement in retaining walls, breast wall etcetra as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.60	8600.00	Rupees Eight Thousand Six Hundred Only	Per cubic Metre	134160.00

3	Steel reinforcement TATA TISCO/SAIL for reinforced cement concrete work including strengthening, cutting, bending, binding and placing in position complete and binding all complete above plinth level TMT bar grade Fe-500 (FE- Five Hundred) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	485.00	117.00	Rupees One Hundred Seventeen Only	Per Kilogram	56745.00
4	Providing and laying mechanically mixed and vibrated Plain/reinforced cement concrete in Sub structure as per drawing and MORTH technical specification section 1500, 1700, 2200 RCC Grade M-20 (M- twenty five) designed mix with cement contents not less than 344 kg. (Three hundred forty four) Kilogram per cubic meter with 40mm (forty millimeter) nominal size graded crushed stone aggregate and curing complete including cost of form work in abutment etcetra complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.44	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic Metre	256940.00
Total						459920.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

11

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Alampur Harsipattan road Km 0/00 to 25/00 (SH:- Providing and fixing dual directional rumble strips different vernable location between Km 0/00 to 25/00) PDNA				Estimated cost Rs.	497250.00	
				Earnest Money Rs.	10000.00	
				Time Limits	Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing dual directional rumble strips made of ABS (Acrylonitrile Butadiene styrene) material of size 250 mm x150 mm (Two hundred fifty ito one hundred fifty millimetre) duly reflectorised with highly reflective glass panels on both sides and to be fixed with 2No. steel pins and suitable epoxy ncluding carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	390.000	1275.00	Rupees One Thousand Two Hundred Seventy Five Only	Each	497250.00
Total						497250.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
J.P.PWD Jaisinghpur