

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26

11929 -37

Dated:- 07/02/2026


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **17.02.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **16.02.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **16.02.2026 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

| Sr. No | Name of Work | Estimated Cost | Earnest Money | Time | Cost of Form |
|--------|---|----------------|---------------|---------|--------------|
| 1 | C/o Khalighati Kaldwar Falodan road km. 0/0 to 6/900(SH:-C/o Hume pipe culvert 900mm dia at Rd 3/300)DMFT Deposit. | 3,94,589/- | 8000/- | 1 Month | 350/- |
| 2. | C/o Khalighati Kaldwar Falodan road km. 0/0 to 6/900(SH:-C/o R/wall at Rd 1/190 to 1/200)DMFT Deposit. | 2,60,795/- | 5300/- | 1 Month | 350/- |
| 3 | Restoration of formation deficiency on K.B.S.B road portion Km. 39/0 to 56/200)Under Jainagar section(SH:-Hill cutting fromm Km. 40/050 to 40/080) | 99,974/- | 2000/- | 2 Month | 350/- |
| 4 | C/o link road from Syarli to Skore km. 0/0 to 3/810(SH:-Formation cutting in Kandi to Skor in km. 0/0 to 0/405)Under DFMT | 4,18,931/- | 8500/- | 1 Month | 350/- |
| 5 | Construction of Play Ground for Senior Secondary School at Basantpur Tehsil Arki Distt. Solan(SH:-Cutting work for play ground at 0/020 to 0/050)DMFT | 3,63,222/- | 8000/- | 1 Month | 350/- |
| 6 | Construction of Play Ground for Senior Secondary School at Basantpur Tehsil Arki Distt. Solan(SH:-Cutting work for play ground | 1,83,392/- | 4000/- | 1 Month | 350/- |

| | | | | | |
|---|---|------------|--------|--------|-------|
| | at 0/050 to 0/060)DMFT | | | | |
| | Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road portion km. 17/500 to 26/0(SH:-Construction of R/wall at Rds 17/645 to 17/652)Under PDNA 2023 | 3,13,861/- | 7000/- | 1Month | 350/- |
| 8 | Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road portion km. 17/500 to 26/0(SH:-Construction of R/wall at Rds 17/670 to 17/679)Under PDNA 2023 | 4,06,024/- | 8500/- | 1Month | 350/- |

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.


No: PW-AD-EA-I-Tender-2025-26-

11929-37

Dated:- 07/02/2026


Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 8(Eight) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

| Name of Work:- C/o of Khalighati Kaldwar Falodan Road Km 0/00 to 6/900 {SH:- C/o Hume Pipe Culvert 900 mm. Dia at Rd 3/300} DMFT Deposit. | | | | | | Estimated Cost: -Rs394589/- only | |
|--|---|----------|-----|---------|---|----------------------------------|---------------|
| | | | | | | Earnest Money :-8000/-Only | |
| | | | | | | Time :-One Month | |
| S. No | Sub head and items of work | Quantity | | Rate In | | Unit | Amount |
| | | | | Figure | Words | | |
| 1 | 2 | 3 | | 4 | | 5 | 6 |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge | 40.20 | Cum | 171.40 | Rupees One hundred seventy one and paise forty only | P.Cum. | 6890 |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:4:8 (1 cement: 4 sand :8 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 35.97 | Cum | 4955.20 | Rupees. four thousand nine hundred fifty five and paise twenty only | P.Cum. | 178239 |
| 3 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:3:6 (1 cement: 3 sand :6 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 31.00 | Cum | 5291.95 | Rupees five thousand two hundred ninety one and paise ninety five only | P.Cum. | 164050 |
| 4 | Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge. | 9.72 | Cum | 1203.30 | Rupees one thousand Two hundred three and paise thirty only | P.Cum. | 11696 |
| 5 | Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe.including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 7.50 | Rmt | 3851.55 | Rupees three thousand eight hundred fifty one and paise fifty five only | P.Rmt. | 28887 |
| 6 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 17.60 | Rmt | 274.25 | Rupees two hundred seventy four and paise twenty five only | P.Rmt. | 4827 |
| Total | | | | | | | 394589 |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
Arki-Division HPPWD
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs2,60,795/- only

Name of Work:-C/o Khalighati Kaldwar Falodan Road Km 0/00 to 6/900.(SH:- C/o R/wall at Rd 1/190 to 1/200.) DMFT Deposit

Earnest Money :-Rs5300/-Only

Time :-One Month

| S. No. | Sub head and items of work | Qty. | Rate In | | Unit | Amount |
|--------|---|-------|---------|--|--------|--------|
| | | | Figure | Words | | |
| 1 | 2 | 3 | 4 | 5 | 6 | |
| 1 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge | 26.40 | 171.40 | Rupees One hundred seventy one and paise forty only | P.Cum. | 4525 |
| 2 | Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge | 52.20 | 4390.60 | Rupees four thousand three hundred ninety and paise sixty only | P.Cum. | 229189 |
| 3 | Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge | 17.40 | 1203.30 | Rupees one thousand two hundred three and paise thirty only | P.Cum. | 20937 |
| 4 | Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge | 22.40 | 274.25 | Rupees two hundred seventy four and paise twenty five only | P.Rmt | 6143 |
| | | | | | Total | 260795 |

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of work :-Restoration of formation deficiency on K.B.S.B road Portion km 39/00 to 56/200. Under Jainagar Section. (SH:-Hill cutting from km 40/050 to 40/080)

Estimated Cost :- Rs 99,974.00

Earnest money :- Rs 2000.00

Time: Two months

| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
|--------|--|--------|-----|-----------|---|-----------------|-----------------|
| | | | | In figure | In words | | |
| 1 | 2 | 3 | | 4 | 5 | 6 | 7 |
| 1.00 | Excavation in earth work in hilly area all height and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specification for rural Road, August, 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-IN-Charge for smooth riding. The recovery of useful stone that is 44.29 cum . In all cases, @ Rupees 300/-cum. shall be effected on pro rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 379.68 | cum | 263.31 | Rupees two Hundred sixty three and paise thirty on only | Per cubic metre | 99974.00 |
| | | | | | | Total | 99974.00 |

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Arki Division (B&R)

HP: PWD: Arki.

Division Arki

SCHEDULE OF QUANTITY

| Name of Work:- C/o Link Road from Syarli to Skore Km 0/00 to 3/810 (SH:-Formation Cutting in Kandi to Sakor in Km 0/00 to 0/405) (Under DMFT) | | Estimated Cost: -Rs 4,18,931/- only | | | | |
|---|--|-------------------------------------|--------------|--------|---|--------|
| | | Earnest Money :-Rs8,500/-Only | | | | |
| | | Time :- One Month | | | | |
| S.No | Sub head and items of work | Qty. | Unit | Rate | | Amount |
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stablity of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materiel inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 238.57 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. | 2197.50 | Per. Cum. | 190.64 | Rupees one hundred Ninety and paise sixty four only . | 418931 |
| | | | | | Total | 418931 |

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
B&R Division HPPWD
Arki

SCHEDULE OF QUANTITY

**NAME OF WORK:- Construction of Play Ground for Senior Secondary School at Basantpur
Tesil Arki Distt Solan HP.(Sh:-Cuuting work for play ground at 0/020 to 0/050) UNDER DMFT**

Estimated Cost :- Rs 3,63,222.00

Earnest money :- Rs 8,000.00

Time: One month

| Sr.No | Sub Head and Items of Work | Qty. | Rate | | Unit | Amount | |
|-------|---|---------|-----------------|----------|--|--------------|----------------|
| | | | In figure | In words | | | |
| 1 | Excavation in earth work by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of mixed soil, ordinary rock and hard rock and all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side, the track shall be excavated with chiseling and wedging out rock (where blasting is prohibited) all earth work in cutting/excavation, including rock excavation shall be carried out true lines, grades dices, slopes, width, camber, super elevation and level as shown on the drawings or as directed by Engineer in Charge, in conformity with the requirement of technical specification for rural road, clause 1603.1 and 1603.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal and dumping to be arranged by the contractor of unsuitable materials in specified manner, trimming filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer in Charge for smooth riding. the recovery for stones, whether useful or not, for 0.00 cum () shall be made in all cases, otherwise recovery at the rate of Rupies 170/- only (Rupies one hundred seventy only) per cubic metre shall be effected on pro-rata basis. any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractors, which shall compensated by him in all cases. | 2040.00 | Per cubic metre | 178.05 | Rupees One hundred seventy eight and paise five only | Cum | 363222 |
| | | | | | | Total | 363222. |

Quoted Rate in Word
Quoted Rate in Figure.

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

**NAME OF WORK:- Construction of Play Ground for Senior Secondary School at Basantpur
Tesil Arki Distt Solan HP.(Sh:-Cuuting work for play ground at 0/050 to 0/060) UNDER DMFT**

Estimated Cost :- Rs 1,83,392.00

Earnest money :- Rs 4,000.00

Time: One month

| Sr.No | Sub Head and Items of Work | Qty. | Rate | | Unit | Amount | |
|-------|--|---------|-----------------|----------|--|------------------|--------|
| | | | In figure | In words | | | |
| 1 | | | | | | | |
| 1 | Excavation in earth work by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of mixed soil, ordinary rock and hard rock and all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side, the track shall be excavated with chiseling and wedging out rock (where blasting is prohibited) all earth work in cutting/excavation, including rock excavation shall be carried out true lines, grades dices, slopes, width, camber, super elevation and level as shown on the drawings or as directed by Engineer in Charge, in conformity with the requirement of technical specification for rural road, clause 1603.1 and 1603.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal and dumping to be arranged by the contractor of unsuitable materials in specified manner, trimming filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer in Charge for smooth riding. the recovery for stones, whether useful or not, for 0.00 cum () shall be made in all cases, otherwise recovery at the rate of Rupies 170/- only (Rupies one hundred seventy only) per cubic metre shall be effected on pro-rata basis. any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractors, which shall compensated by him in all cases. | 1030.00 | Per cubic metre | 178.05 | Rupees One hundred seventy eight and paise five only | Cum | 183392 |
| | | | | | Total | 183392.00 | |

Quoted Rate in word

Quoted Rate in figure

Executive Engineer
Arki Division,
HPFWD, Arki

SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain damages on Shalaghat Arki Kunihar Barotiwala Road portion km 17/500 to 26/00. (Sh:-Construction Retaining wall at Rds 17/645 to 17/652) Under PDNA-2023

Estimated Cost :- Rs 3,13,861.00

Earnest money :- Rs 7,000.00


Time: One month

| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
|--------|---|-------|-----|-----------|--|-------------------|------------------|
| | | 3 | | In figure | In words | | |
| 1.00 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge | 18.48 | Cum | 171.40 | Rupees One Hundred Seventy One and Forty paise Only | Per cubic metre | 3167.00 |
| 2.00 | Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge. | 65.95 | Cum | 4390.60 | Rupees Four Thousand Three Hundred Ninety and Sixty paise Only | Per cubic metre | 289560.00 |
| 3.00 | Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge. | 9.45 | Cum | 1203.30 | Rupees One Thousand Two Hundred Three and Thirty paise Only | Per cubic metre | 11371.00 |
| 4.00 | Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge. | 35.60 | Rmt | 274.25 | Rupees Two Hundred Seventy Four and Twenty Five paise Only | Per running metre | 9763.00 |
| | | | | | | Total | 313861.00 |

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain damages on Shalaghat Arki Kunihar Barotiwala Road portion km 17/500 to 26/00. (Sh:-Construction Retaining wall at Rds 17/670 to 17/679) Under PDNA-2023

Estimated Cost :- Rs 4,06,024.00

Earnest money :- Rs 8,500.00


Time: One month

| Sr.No. | Sub Head and Items of Work | Qty. | | Rate | | Unit | Amount |
|--------|---|-------|-----|-----------|--|-------------------|------------------|
| | | 3 | | In figure | In words | | |
| 1.00 | Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge | 23.76 | Cum | 171.40 | Rupees One Hundred Seventy One and Forty paise Only | Per cubic metre | 4072.00 |
| 2.00 | Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge. | 84.52 | Cum | 4390.60 | Rupees Four Thousand Three Hundred Ninety and Sixty paise Only | Per cubic metre | 371094.00 |
| 3.00 | Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge. | 12.15 | Cum | 1203.30 | Rupees One Thousand Two Hundred Three and Thirty paise Only | Per cubic metre | 14620.00 |
| 4.00 | Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge. | 59.21 | Rmt | 274.25 | Rupees Two Hundred Seventy Four and Twenty Five paise Only | Per running metre | 16238.00 |
| | | | | | | Total | 406024.00 |

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.