



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

“NOTICE INVITING TENDERS”

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **05-03-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 03-03-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 03-03-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.


Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O EE office building at HPPWD Bhawarna (SH:- Repair of Bathrooms etc)	99,659/-	2000/-	Three month	350/-
2	A/R & M/O Various roads under Section Khairai-II under Sub Division Bhawarna (SH:- Writing on Boards and kilometres stones, 200mtrs stone etc)	99,488/-	2000/-	Two month	350/-
3	A/R & M/O Various roads under Garh Section under Sub Division Bhawarna (SH:- Painting and Writing on Boards etc)	98,111/-	2000/-	Three month	350/-
4	Restoration of rain damages on various roads under HPPWD Sub Division Bhawarna (Section Darph Garh) (SH:- C/O Unlined drain and maintenance of earthen shouder on various roads)	99,520/-	2000/-	Three month	350/-
5	A/R & M/O Naura Kiarwan road km. 0/0 to 3/345 (SH:- Painting & Writting on Bridges, Bridges Pedestal, Rain shelter, Boards and kilometres stones etc)	97,573/-	2000/-	Two month	350/-
6	A/R & M/O Parour Kharouth Ocha Kuhana Thaliyal Purba road km. 0/0 to 17/0 (SH:- Providing and fixing dual Directional retro reflective cat eyes studs in between km. 13/200 to 13/600)	99,200/-	2000/-	Three month	350/-
7	A/R & M/O Parour Kharouth Ocha Kuhana Thaliyal Purba road km. 0/0 to 17/0 (SH:- Painting & Writting, Rain Shelter, Boards and kilometres stones etc)	99,782/-	2000/-	Three month	350/-
8	A/R & M/O Various roads HPPWD Sub Division Thural (SH:- C/O Unlined drain and maintenance of earthen shouder on various roads)	99,720/-	2000/-	Three month	350/-
9	A/R & M/O Nagni Gharana road km. 0/0 to 10/0 (SH:- Painting on 87.50mtr span Steel trush bridge over Neugal khad at RD. 1/150 & Writing of Bridge Pedestal, Boards and kilometre stones etc)	99,860/-	2000/-	Two month	350/-
10	A/R & M/O Naura to Balota road km. 0/0 to 3/00 (SH:- P/LCC pavement work in km. 2/610 to 2/645)	99,330/-	2000/-	Three month	350/-
11	A/R & M/O Naura to Balota road km. 0/0 to 3/00 (SH:- P/LCC pavement work in km. 2/550 to 2/585)	99,540/-	2000/-	Three month	350/-



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna


On behalf of Governor of Himachal Pradesh

Dated:- 24/02/2026

No. PWD/BWD/TA/NIT/2025-26/ 14943-54

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-14943-54 dated 24/02-2026.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of Work :- A/R & M/O EE Office Building at HPPWD Bhawarna . (SH:- Repair of Bathrooms etc.).

Estimated Cost :-Rs. 99,659/-


Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and laying 10mm (Ten millimeters) thick antiskid water proof stain and impact resistant heavy duty vitrified tiles Nitco/Kajaria/cera or its equivalent double charged 600x600x10mm (Six hundred into six hundred into ten millimeters) manufactured of approved shade and colour in flooring, tread of steps and landings laid over 12mm (Twelve millimeters) thick cement mortar 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete upto all floor level in all heights including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	3 00	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square metre	4350.00
2	Providing and laying 300x450 (three hundred into four hundred fifty millimeter) acid resistance vetrified tiles of Restile/ Nitco/ Rak/ Simpolo/ Kajaria/ Johnson as per approved shade and design as per drawing and specification in dado laid over 12 mm (twelve millimeters) thick cement mortar 1.3 (one cement: three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as reured complete. The rates are inclusive cost and carriage of materials with in all leads. lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	12 60	1500.00	Rupees One Thousand Five Hundred Only	Per Square metre	18900.00
3	Providing and fixing 15mm (Fifteen millimetre) PVC pipes for water supply including clamps at one meter spacing, cutting fixing and making good the wall etc. complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2 00	100.00	Rupees One Hundred Only	Per Running metre	200 00
4	Providing and fixing Viterous china urinal large flat back no 60002 size (39x37.50x59 cm) (thirty nine into thirty seven point five into fifty nine centimetre) of Hindware/ Cera/ Jaguar of Star white/ snow white shade including connecting the urinal with waste pipe by means of white lead mixed with chopped hemp (waste pipe to be measured and Paid for separately) including carriage of material within all leads, lifts of material and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	2000.00	Rupees Two Thousand Only	Each	2000.00
5	Providing and fixing 100mm (One hundred milimetre) nominal size diameters CP grating of ESS or nahani trap of approved brand complete, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	2 00	100.00	Rupees One Hundred Only	Each	200 00
6	Providing and fixing PVC Waste pipe for wash basin or sink including brass check net with in all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government	3 00	350 00	Rupees Three Hundred Fifty Only	Each	1050 00

7	Providing and fixing high pressure 75 mm (Seventy five millimeters) dia PVC spigot and socket soil, waste and ventilating pipes ISI Marked including fixing with approved adhesive etc. Complete of Finolex/Vectus/red pipe within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.00	400.00	Rupees Four Hundred Only	Per Running metre	4000.00
8	15mm (fifteen millimetre) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth, in rough side with cement mortar 1:5 (one cement isto five sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.20	220.00	Rupees Two Hundred Twenty Only	Per Square metre	924.00
9	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches including carriage of materials within all leads, lifts, and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.12	6.00	Rupees Six Only	Per Square metre	289.00
10	Applying Birla / J.K. white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	48.12	60.00	Rupees Sixty Only	Per Square metre	2887.00
11	Wall painting (two coats) with interior emulsion paint of Asian paint / Nerolac Suraksha Paint/ Berger paint / Dulux paint of approved shade for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty required for matting the surface including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	178.12	75.00	Rupees Seventy Five Only	Per Square metre	13359.00
12	Providing and fixing exhaust fan complete with all accessories with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	1500.00	Rupees One Thousand Five Hundred Only	Each	1500.00
13	Providing and fixing water cooler having capacity 80.00 litre and 40.00 litre per hour cooling capacity fully automatic of Stainless steel of Blue Star or its equivalent brand complete with all accessories with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	45000.00	Rupees Forty Five Thousand Only	Each	45000.00
14	Providing and fixing heavy quality stainless steel kitchen sink of approved standard ISI marked with drain board and C.P. waste pipe C.I. or M.S. brackets painted white i/c cutting holes and making good the same including fitting 600x450x250 mm (six hundred into four hundred fifty into two hundred fifty millimetre) with bowl depth 20 mm (twenty millimetre) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	2000.00	Rupees Two Thousand Only	Each	2000.00

15	Providing and fixing C.P. brass pillar tap Continental/Classic series /lorol series of Jagware/Hindware/Cera 15mm (fifteen millimetre) dia (Heavy duty makes ISI marked No. 8931 & 8934) Including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	1500.00	Rupees One Thousand Five Hundred Only	Each	1500.00
16	Providing and fixing to wall ceiling and floor galvanised mild steel tubes 15 mm (Fifteen millimetre) nominal bore (Medium grade) tube fittings and clamps including making good the wall, ceiling and floor. The rates are including cost and carriage within all leads and lifts and other incidentals as per PWD specification and entire satisfaction/direction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.00	150.00	Rupees One Hundred Fifty Only	Per Running metre	1500.00
Total :-						99659.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity.


Name of Work :-A/R & M/O Various roads under Section Khara-II under HPPWD Sub Division Bhawarna (SH:- Writing on Boards and Kilometers stones, 200 mtrs stones etc.)

Estimated Cost :- Rs.99,488/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	42.12	5.00	Rupees Five Only	Per Square metre	211.00
2	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamelpaint of approved bran other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42.12	60.00	Rupees Sixty Only	Per Square Metre	2527.00
3	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.					
3.1	Block (letters/figures)	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	48375.00
3.2	Indian(letters/figures)	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	48375.00
Total :-						99488.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division,
 HP PWD Bhawarna

Schedule of quantity


Name of Work :-A/R & M/O various roads under Daroh Garh Section under Bhawarna Sub-Division (SH:- Painting & Writing, on Boards)

Estimated Cost :- Rs. 98,111/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.68	60.00	Rupees Sixty Only	Per Square Metre	1361.00
i)	Indian(letters/figures)	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	48375.00
i)	Block (letters/figures)	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	48375.00
Total :-						98111.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Bhawarna (Section Daroh Garh). (SH:- Removal of slips, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimated Cost :-Rs.99,520/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1 50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	637.33	90.00	Rupees Ninety Only	Per Cubic metre	57360.00
2	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	410.00	40.00	Rupees Forty Only	Per Running metre	16400.00
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	736.00	35.00	Rupees Thirty Five Only	Per Square metre	25760.00
Total :-						99520.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity.

Name of Work :-A/R & M/O Naura Kiarwan road Km 0/00 to 3/345 (SH:- Painting & Writing on Bridges, Bridges Pedestal, Rain Shelter, Boards and Kilometers stones etc.)

Estimated Cost :- Rs. 97,573/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	15.12	6.00	Rupees Six Only	Per Square metre	91.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.12	60.00	Rupees Sixty Only	Per Square Metre	907 00
3	Applying Birla white cement based putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	236.00	70.00	Rupees Seventy Only	Per Square metre	16520.00
4	Applying priming coat on new concrete/ masonry/ asbestos cement plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand appearing as required with ready mixed primer complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	504.00	50.00	Rupees Fifty Only	Per Square metre	25200 00

5	Finishing walls with water proofing cement paint of new work (Two or more coats applied @ 3.84 kg/10 sqm) required shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	504.00	95.00	Rupees Ninety Five Only	Per Square metre	47880.00
6	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.					
i)	Indian(letters/figures)	3100.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	6975.00
Total :-						97573.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- A/R & M/O Parour Kharouth Ballah Panaper Ocha Kuhana Naura Thaliyal Purba road Km 0/0 to 17/0.


Estimate Cost :- Rs. 99200/-

Earnest Money :- Rs. 2000/-

(SH:- Providing and Fixing Dual Directional retro reflective cat eyes studs in between Km 13/200 to 13/600.

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	248.00	400.00	Rupees Four Hundred Only	Each	99200.00
Total:-						99200.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer,
Bhawarna Division,
HPPWD Bhawarna.

Schedule of quantity.


Name of Work :-A/R & M/O Parour Kharouth Ballah Panaper Ocha Kuhana Naura Thaliyali Purba road (SH:- Painting & Writing, Rain Shelter, Boards and Kilometers stones etc.)

Estimated Cost :- Rs. 99,782/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	23.76	6.00	Rupees Six Only	Per Square metre	143.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.76	60.00	Rupees Sixty Only	Per Square Metre	1426.00
i)	Indian(letters/figures)	43650.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	98213.00
Total :-						99782.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Thural. (SH:- C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimated Cost :-Rs.99,720/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1450.00	40.00	Rupees Forty Only	Per Running metre	58000.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1192.00	35.00	Rupees Thirty Five Only	Per Square metre	41720.00
Total :-						99720.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity.

Name of Work :-A/R & M/O Nagni Gharana road Km 0/00 to 10/00 (SH:- Painting on 87.00 mtr. Span Steel Truss Bridge over Neugal khad at Rd 1/150 & Writing on Bridges Pedestal, Boards and Kilometers stones etc.)


Estimated Cost :- Rs. 99,860/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1364.19	6.00	Rupees Six Only	Per Square metre	8185.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1364.19	60.00	Rupees Sixty Only	Per Square Metre	81851.00
3	Finishing walls with water proofing cement paint of new work (Two or more coats applied @ 3.84 kg/10 sqm) required shade The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.	18.15	95.00	Rupees Ninety Five Only	Per Square metre	1724.00
4	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.					

i)	Indian(letters/figures)	3600.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	8100.00
Total :-						99860.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Draft Schedule of Quantity


me of Work :- A/R & M/O Naura to Balota road Km 0/000 to 3/000. (SH:- P/L CC Pavement work in Km 2/610 to 2/645).

Estimated Cost :- Rs. 99,330/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10	2100.00	Rupees Nineteen point five zero only	Per Cubic metre	4410.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.56	7000.00	Rupees Seven Thousand Only	Per Cubic metre	94920.00
Total :-						99330.00
Quoted rates percentage in figures						
Quoted rates percentage in words						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- A/R & M/O Naura to Balota road Km 0/000 to 3/000. (SH:- P/L CC Pavement work in Km 2/550 to 2/585).

Estimated Cost :- Rs. 99,540/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.20	2100.00	Rupees Nineteen point five zero only	Per Cubic metre	4620.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.56	7000.00	Rupees Seven Thousand Only	Per Cubic metre	94920.00
Total :-						99540.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna