



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **20-02-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 19-02-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 19-02-2026 up to **1.00 PM.**

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.


| Sr. No. | Name of Work   | Estimated Cost | Earnest Money | Time Limit  | Cost of Tender form |
|---------|--|----------------|---------------|-------------|---------------------|
| 1       | Restoration of rain damages on Bhattu Sullah Nanaon upto Kural (SH:- Painting & writing on Bridge, Bridge pedestal, Rain Shelter, Boards and kilometres stones etc)                              | 99,770/-       | 2000/-        | Two month   | 350/-               |
| 2       | A/R & M/O Various roads under Bhawarna Section under Bhawarna Sub Division (SH:- Painting & writing on Boards etc)   | 98,014/-       | 2000/-        | Two month   | 350/-               |
| 3       | Restoration of rain damages on various roads under HPPWD Sub Division Bhawarna (Section Darang) (SH:- Removal of slips, C/O Un-lined drain and Maintenance of earthen shoulder on various roads) | 99,210/-       | 2000/-        | Three month | 350/-               |
| 4       | Restoration of rain damages on Darang Ghanetta Jharet road (SH:- Construction of U-shape drain with edge wall in km. 2/400 to 2/427)   | 99,232/-       | 2000/-        | Three month | 350/-               |
| 5       | Restoration of rain damages on Sullah to Harbaral via Majhakra road (Under PDNA) (SH:- Providing and laying CC pavement work in km. 0/550 to 6/600)  | 1,48,410/-     | 3000/-        | Three month | 350/-               |
| 6       | Restoration of rain damages on Thakurdwara Ramnagar colony Raipur Tea Estate Arla (Under PDNA)   | 1,84,709/-     | 3700/-        | Three month | 350/-               |
| 7       | Restoration of rain damages on Sullah to Raipur road (Under PDNA)  | 1,48,825/-     | 3000/-        | Three month | 350/-               |
| 8       | A/R & M/O Nagni Gharana road km. 0/0 to 10/0 (SH:- Providing and fixing dual Directional retro reflective cat eyes studs in between km. 0/0 to 10/00)  | 98,400/-       | 2000/-        | Three month | 350/-               |
| 9       | A/R & M/O Nagni Gharana road km. 0/0 to 10/0 (SH:- Providing and fixing dual Directional retro reflective cat eyes studs in between km. 0/0 to 10/00)  | 99,200/-       | 2000/-        | Three month | 350/-               |
| 10      | A/R & M/O Rud Panyali Lahar Machlaina Parmar Nagar (Rakh) road (SH:- C/O Unlined drain & Maintenance of earthe shoulders in between km. 9/00 to 10/00)   | 99,800/-       | 2000/-        | Three month | 350/-               |
| 11      | A/R & M/O Nagni Gharana road km. 0/0 to 10/0 (SH:- Providing and fixing dual Directional retro reflective cat eyes studs in between km. 2/00 to 4/00)  | 99,200/-       | 2000/-        | Three month | 350/-               |
| 12      | A/R & M/O Nagni Gharana road km. 0/0 to 10/0 (SH:- Providing and fixing dual Directional retro reflective cat eyes studs in between km. 0/00 to 2/00)  | 99,200/-       | 2000/-        | Three month | 350/-               |



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna


On behalf of Governor of Himachal Pradesh

Dated:- 12-02-2026

No. PWD/BWD/TA/NIT/2025-26/ 14564-73

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

**CERTIFICATE**

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-14564-73 dated 12-02-2026.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Schedule of quantity.

Name of Work :- Restoration of Rain Damage on Bhattu Sullah Nanaon upo Kural road. (SH:- Painting & Writing on Bridge, Bidge Pedestal, Rain Shellter, Boards and Kilometers stones etc.)


Estimated Cost :- Rs. 99,770/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

| S. No | Description of Item  | Quantity | Rate      |                         | Unit             | Amount  |
|-------|--|----------|-----------|-------------------------|------------------|---------|
|       |  |          | In figure | In Words                |                  |         |
| 1     | Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.         | 402.60   | 6.00      | Rupees Six Only         | Per Square metre | 2416.00 |
| 2     | Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 23.76    | 60.00     | Rupees Sixty Only       | Per Square Metre | 1426.00 |
| 3     | Painting one coat (excluding priming coat ) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter (With white enemale paint) Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.    | 150.28   | 65.00     | Rupees Sixty Five Only  | Per Square Metre | 9768.00 |
| 4     | Finishing walls with water proofing cement paint of new work (Two or more coats applied @ 3.84 kg/10 sqm) required shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.   | 33.00    | 95.00     | Rupees Ninety Five Only | Per Square metre | 3135.00 |

|                 |  |          |      |                                       |                                  |                 |
|-----------------|--|----------|------|---------------------------------------|----------------------------------|-----------------|
| 5               | Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. |          |      |                                       |                                  |                 |
| i)              | Indian(letters/figures)  | 36900.00 | 2.25 | Rupees Two And Paise Twenty Five Only | Per letter per centimetre height | 83025.00        |
| <b>Total :-</b> |  |          |      |                                       |                                  | <b>99770.00</b> |
|                 | <b>Quoted rates percentage in figures</b>  |          |      |                                       |                                  |                 |
|                 | <b>Quoted rates percentage in words</b>  |          |      |                                       |                                  |                 |

  
 Executive Engineer  
 Bhawana Division  
 HP PWD Bhawana

## Schedule of quantity.


Name of Work :- A/R & M/O Various roads under Bhawarna Section under Bhawarna Sub-Division. (SH:-Painting & Writing on Boards etc.).

Estimated Cost :- Rs. 98,014/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

| S. No           | Description of Item  | Quantity | Rate      |                                       | Unit                             | Amount          |
|-----------------|--|----------|-----------|---------------------------------------|----------------------------------|-----------------|
|                 |  |          | In figure | In Words                              |                                  |                 |
| 1               | Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 21.06    | 60.00     | Rupees Sixty Only                     | Per Square Metre                 | 1264.00         |
| 2               | Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.   |          |           |                                       |                                  |                 |
| 2.1             | Block (letters/figures)  | 21500.00 | 2.25      | Rupees Two And Paise Twenty Five Only | Per letter per centimetre height | 48375.00        |
| 2.2             | Indian(letters/figures)  | 21500.00 | 2.25      | Rupees Two And Paise Twenty Five Only | Per letter per centimetre height | 48375.00        |
| <b>Total :-</b> |  |          |           |                                       |                                  | <b>98014.00</b> |
|                 | Quoted rates percentage in figures   |          |           |                                       |                                  |                 |
|                 | Quoted rates percentage in words   |          |           |                                       |                                  |                 |


  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

**Name of Work :-** Restoration of rain damages on various roads under HPPWD Sub-Division Bhawarna (Section Darang). (SH:- Removal of slips, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

**Estimated Cost :-Rs.99,210/-**  
**Earnest Money :-Rs. 2000/-**  
**Time Limit :- Three Months**

| S. No           | Description of Item   | Quantity | Rate      |                         | Unit              | Amount<br>Rs.   |
|-----------------|---|----------|-----------|-------------------------|-------------------|-----------------|
|                 |   |          | In figure | In Words                |                   |                 |
| 1               | Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.                           | 794.33   | 90.00     | Rupees Ninety Only      | Per Cubic metre   | 71490.00        |
| 2               | Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) ( Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.  | 350.00   | 40.00     | Rupees Forty Only       | Per Running metre | 14000.00        |
| 3               | Maintenance of Earthen shoulder ( Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government. | 392.00   | 35.00     | Rupees Thirty Five Only | Per Square metre  | 13720.00        |
| <b>Total :-</b> |   |          |           |                         |                   | <b>99210.00</b> |
|                 | Quoted rates percentage in figures  |          |           |                         |                   |                 |
|                 | Quoted rates percentage in words  |          |           |                         |                   |                 |


  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

Name of Work :- Restoration of rain damages on Darang Ghanetta Jharet road. (SH :- Construction of U-shape drain with Edge wall in Km 2/400 to 2/427).

Estimated Cost :-Rs. 99,232/-  
Earnest Money :-Rs. 2000/-  
Time Limit :- Three Months

| S. No           | Description of Item  | Quantity | Rate      |  | Unit            | Amount          |
|-----------------|--|----------|-----------|--|-----------------|-----------------|
|                 |  |          | In figure | In Words                                     |                 |                 |
| 1               | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government. | 17.01    | 250.00    | Rupees Two Hundred Fifty Only                | Per Cubic metre | 4253.00         |
| 2               | Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.   | 18.43    | 4950.00   | Rupees Four Thousand Nine Hundred Fifty Only | Per Cubic metre | 91229.00        |
| 3               | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe (White colour pipe) weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.  | 15       | 250.00    | Rupees Two Hundred Fifty Only                | Each            | 3750.00         |
| <b>Total :-</b> |  |          |           |  |                 | <b>99232.00</b> |

  
 Executive Engineer  
 Bhawana Division  
 HP PWD Bhawana

## Schedule of Quantity


Name of Work :- Restoration of Rain damages on Sullah to Harbaral via Majhakra road (Under PDNA).

Estimated Cost :- Rs. 1,48,410/-

Earnest Money :- Rs. 3000/-

Time Limit :- Three Months

| S. No           | Description of Item   | Quantity | Rate      |                            | Unit            | Amount           |
|-----------------|---|----------|-----------|----------------------------|-----------------|------------------|
|                 |   |          | In figure | In Words                   |                 | Rs.              |
| 1               | Providing and laying CC Pavement work in Km 0/550 to 0/600.   |          |           |                            |                 |                  |
| 2               | Providing, laying, Soling 90 to 45mm ( Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 2.00     | 2000.00   | Rupees Two Thousand Only   | Per Cubic metre | 4000.00          |
| 3               | Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.  | 20.63    | 7000.00   | Rupees Seven Thousand Only | Per Cubic metre | 144410.00        |
| <b>Total :-</b> |   |          |           |                            |                 | <b>148410.00</b> |
|                 | Quoted rates percentage in figures  |          |           |                            |                 |                  |
|                 | Quoted rates percentage in words  |          |           |                            |                 |                  |

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

6

Name of Work:- Restoration of Rain damages on Thakurdwara Ramnagar Colony Raipur Tea Estate Arla (under PDNA)

Estimated Cost :- Rs.1,84,709/-

Earnest Money :- Rs. 3700/-

Time Limit :- Three Months

| S. No | Description of Item   | Quantity | Rate      |  | Unit            | Amount<br>Rs. |
|-------|---|----------|-----------|--|-----------------|---------------|
|       |   |          | In figure | In Words                                     |                 |               |
| 1     | C/o E/wall at RD 2/200 to 2/208, U-shape drain at RD 7/900 to 7/940 & P/L CC work at RD 2/510 to 2/525  |          |           |  |                 |               |
| 2     | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government. | 31.36    | 250.00    | Rupees Two Hundred Fifty Only                | Per Cubic metre | 7840.00       |
| 3     | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 ( One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.   | 14.50    | 4950.00   | Rupees Four Thousand Nine Hundred Fifty Only | Per Cubic metre | 71775.00      |
| 4     | Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer –in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.   | 10.08    | 4300.00   | Rupees Four Thousand Three Hundred Only      | Per Cubic metre | 43344.00      |

|                 |   |      |         |                               |                 |                  |
|-----------------|---|------|---------|-------------------------------|-----------------|------------------|
| 5               | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.   | 7.00 | 250.00  | Rupees Two Hundred Fifty Only | Each            | 1750.00          |
| 6               | Providing, laying, Soling 90 to 45mm ( Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 4.80 | 2000.00 | Rupees Two Thousand Only      | Per Cubic metre | 9600.00          |
| 7               | Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.  | 7.20 | 7000.00 | Rupees Seven Thousand Only    | Per Cubic metre | 50400.00         |
| <b>Total :-</b> |   |      |         |                               |                 | <b>184709.00</b> |
|                 | <b>Quoted rates percentage in figures</b>   |      |         |                               |                 |                  |
|                 | <b>Quoted rates percentage in words</b>   |      |         |                               |                 |                  |

Executive Engineer  
Bhawarna Division  
HP PWD Bhawarna

## Schedule of Quantity


Name of Work :- Restoration of rain damages on Sullah to Raipur road (Under PDNA)

Estimated Cost :-Rs. 1,48,825/-

Earnest Money :- Rs. 3000/-

Time Limit :- Three Months

| S. No           | Description of Item   | Quantity | Rate      |  | Unit                | Amount<br>Rs.    |
|-----------------|---|----------|-----------|--|---------------------|------------------|
|                 |   |          | In figure | In Words   |                     |                  |
| 1               | Providing and Laying Interlocking Paver Blocks in Km 1/850 to 1/886.  |          |           |  |                     |                  |
| 2               | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 1.73     | 250.00    | Rupees Two<br>Hundred Fifty Only                 | Per Cubic<br>metre  | 433.00           |
| 3               | Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.  | 2.16     | 6200.00   | Rupees Six<br>Thousand Two<br>Hundred Only       | Per Cubic<br>metre  | 13392.00         |
| 4               | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm (Sixty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.   | 108.00   | 1250.00   | Rupees One<br>Thousand Two<br>Hundred Fifty Only | Per Square<br>metre | 135000.00        |
| <b>Total :-</b> |   |          |           |  |                     | <b>148825.00</b> |
|                 | Quoted rates percentage in figures  |          |           |  |                     |                  |
|                 | Quoted rates percentage in words  |          |           |  |                     |                  |

  
 Executive Engineer,  
 Bhawarna Division,  
 HP PWD Bhawarna.

## Schedule of Quantity

Name of work:- A/R & M/O Nagni Gharana road Km 0/00 to 10/00


Estimate Cost :- Rs. 98400/-

Earnest Money :- Rs. 2000/-

(SH):- Providing and Fixing Dual Directional retro reflective cat eyes studs in between Km 0/00 to 10/00

Time Limit :- Three Months

| S. No          | Description of Item  | Quantity | Rate      |                          | Unit | Amount          |
|----------------|--|----------|-----------|--------------------------|------|-----------------|
|                |  |          | In figure | In Words                 |      |                 |
| 1              | Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government. | 246.00   | 400.00    | Rupees Four Hundred Only | Each | 98400.00        |
| <b>Total:-</b> |  |          |           |                          |      | <b>98400.00</b> |
|                | <b>Quoted rates percentage in figures</b>  |          |           |                          |      |                 |
|                | <b>Quoted rates percentage in words</b>  |          |           |                          |      |                 |

  
Executive Engineer,  
Bhawarna Division,  
HPPWD Bhawarna.

## Schedule of Quantity

Name of work:- A/R & M/D Nagn Channa road Km 000 to 1000


Estimate Cost :- Rs. 99200/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

(S4)- Providing and Fixing Dual Directional retro-reflective cat eyes studs in between Km 000 to 1000

| S. No   | Description of Item  | Quantity | Rate      |                          | Unit | Amount   |
|---------|--|----------|-----------|--------------------------|------|----------|
|         |  |          | In figure | In Words                 |      |          |
| 1       | Providing and Fixing dual Directional retro-reflective cat eyes studs made from high quality ABS plastic stud of size 80-100mm (Ninety one one hundred millimeter) provided with being to roads by hammering made of green life complete to the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all loads, lifts and other incidents. The rate is including entire royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government. | 248.00   | 400.00    | Rupees Four Hundred Only | Each | 99200.00 |
| Total:- |  |          |           |                          |      | 99200.00 |
|         | Quoted rates percentage in Egypth  |          |           |                          |      |          |
|         | Quoted rates percentage in world   |          |           |                          |      |          |


  
 Executive Engineer,  
 Bhawana Division,  
 HPPWD Bhawana.

## Schedule of Quantity

Name of Work :- A/R & M/O Rud Panyali Lahar Machlains Parmar Nagar (Rakh) road (SH:- C/o un-lined drain & Maintenance of Earthen shoulders in between Km 9/00 to 10/00)

Estimate Cost :-Rs. 99,800/-  
Earnest Money :-Rs. 2000/-  
Time Limit :- Two Months

| S. No           | Description of Item   | Quantity | Rate      |                         | Unit              | Amount          |
|-----------------|---|----------|-----------|-------------------------|-------------------|-----------------|
|                 |   |          | In figure | In Words                |                   |                 |
| 1               | Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m ( Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.                    | 920.00   | 40.00     | Rupees Forty Only       | Per Running metre | 36800.00        |
| 2               | Maintenance of Earthen shoulder ( Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government. | 1800.00  | 35.00     | Rupees Thirty Five Only | Per Square metre  | 63000.00        |
| <b>Total :-</b> |   |          |           |                         |                   | <b>99800.00</b> |
|                 | Quoted rates percentage in figures  |          |           |                         |                   |                 |
|                 | Quoted rates percentage in words  |          |           |                         |                   |                 |

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

Name of work:- A/R & M/O Nagni Gharana road Km 0/00 to 10/00


Estimate Cost :- Rs. 99200/-

Earnest Money :- Rs. 2000/-

(SH:- Providing and Fixing Dual Directional retro reflective cat eyes studs in between Km 2/00 to 4/00

Time Limit :- Three Months

| S. No          | Description of Item  | Quantity | Rate      |                          | Unit | Amount<br>Rs.   |
|----------------|--|----------|-----------|--------------------------|------|-----------------|
|                |  |          | In figure | In Words                 |      |                 |
| 1              | Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government. | 248.00   | 400.00    | Rupees Four Hundred Only | Each | 99200.00        |
| <b>Total:-</b> |  |          |           |                          |      | <b>99200.00</b> |
|                | Quoted rates percentage in figures   |          |           |                          |      |                 |
|                | Quoted rates percentage in words   |          |           |                          |      |                 |

  
Executive Engineer,  
Bhawarna Division,  
HPPWD Bhawarna.

## Schedule of Quantity

Name of work:- A/R & M/O Nagni Gharana road Km 0/00 to 10/00


Estimate Cost :- Rs. 99200/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

(SH):- Providing and Fixing Dual Directional retro reflective cat eyes studs in between Km 0/00 to 2/00

| S. No          | Description of Item  | Quantity | Rate      |                          | Unit | Amount          |
|----------------|--|----------|-----------|--------------------------|------|-----------------|
|                |  |          | In figure | In Words                 |      |                 |
| 1              | Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government. | 248.00   | 400.00    | Rupees Four Hundred Only | Each | 99200.00        |
| <b>Total:-</b> |  |          |           |                          |      | <b>99200.00</b> |
|                | Quoted rates percentage in figures   |          |           |                          |      |                 |
|                | Quoted rates percentage in words   |          |           |                          |      |                 |

  
Executive Engineer,  
Bhawarna Division,  
HPPWD Bhawarna.