HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- **13-02-2026 upto 10.00 AM to 11:00 AM.)**
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) **13-02-2026 (3:00 PM to 5.00 PM)**
3. Date of receipt of Tender:- **16-02-2026 at 10.30 AM.**
4. Date of opening of Tender:- **16-02-2026 at 11.30 AM.**

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/o Ambulance Road Mahila Mandal Bhawan to Baba Balaknath Temple via Rajpootan Basti (SH:-P/L 25 mm thick Premix carpet in km 0/00 to 0/100.85) SDP/2024/24.	1,50,609/-	3,500/-	Two Months	Rs. 350/-	Class-D
2	R/R Damages on Various Road under Sub-Division Samirpur (SH:-Repair & Maintenance of earthen shoulder, C/o Unlined Surface drain) (Dho Section)	99,415/-	2,000/-	Two Months	Rs. 350/-	Class-D
3	Restoration of rain Damages on Una Aghar Mandi Road km 67/00 to 79/00) (SH:-C/o R/wall at RD 73/950 to 73/972)	2,55,614/-	5,500/-	Two Months	Rs. 350/-	Class-D
4	A/R & M/O on Various Road under HPPWD Sub-Division Samirpur (SH:- Providing and Laying fixing of Inauguration/Foundation Pedestal i/c Granite stone plate.)	99,600/-	2,000/-	Two Months	Rs. 350/-	Class-D
5	A/R & M/O on various Road under HPPWD Sub-Division Bhoranj (SH:- providing and Laying fixing of inauguration/Foundation Pedestal i/c Granite stone plate.) (Section Patta)	99,800/-	2,000/-	Two Months	Rs. 350/-	Class-D
6	A/R & M/O on various Road under HPPWD Sub-Division Bhoranj (SH:- Providing and Laying fixing of inauguration/Foundation Pedestal i/c Granite stone plate) (section Bhoranj)	99,800/-	2,000/-	Two Months	Rs. 350/-	Class-D
7	A/R & M/O on various Road under HPPWD Sub-Division Bhoranj (SH:- Providing and Laying fixing of inauguration/Foundation Pedestal i/c Granite stone plate) (section Bhareri)	99,600/-	2,000/-	Two Months	Rs. 350/-	Class-D
8	Repair/Restoration on Ludder to Sulgwan via Lagmanwin Hour km 0/00 to 3/550 (SH:-P/L interlocking paver block at RD 0/520 to 0/600) (PDNA)	4,82,720/-	10,000/-	Two Months	Rs. 350/-	Class-D

Scanned with OKEN Scanner

9	Repair/Restoration on Ludder to Sulgwan via Lagmanwin Hour km 0/00 to 3/550 (SH:-P/L interlocking paver block at RD 1/060 to 1/140) (PDNA)	4,82,720	10,000/-	Two Months	Rs. 350/-	Class-D
10	Repair/Restoration on Ludder to Sulgwan via Lagmanwin Road km 0/00 to 5/00 (SH:- P/F W-Beam Metal Crash Barrier at various changes as per site in km 4/800 to 5/00) (PDNA)	4,96,650/-	10,000/-	Two Months	Rs. 350/-	Class-D
11	C/o Link RaodKhatrwar to village Tikkarl Minhasa via Maira, Pidharta km. 0/00 to 3/00 (SH:-Earth filling at RD 0/520 to 0/590 & C/o Wing-wall at RD 0/600 to protect the Abutment)	99,983/-	2,000/-	Two Months	Rs. 350/-	Class-D
12	Restoration on link road Guard Khana to Ward No-3 Harijan Basti Badehar km 0/00 to 1/500 (SH:-C/o Cement concrete pavement at RD 0/124 to 0/248) (PDNA)	4,97,710/-	10,000/-	Two Months	Rs. 350/-	Class-D
13	Restoration on link road Guard Khana to Ward No-3 Harijan Basti Badehar km 0/00 to 1/500 (SH:-C/o Cement concrete pavement at RD 0/00 to 0/124) (PDNA	4,99,708/-	10,000/-	Two Months	Rs. 350/-	Class-D
14	R/R Damages on Executive Engineer Office Building (PWD) Bhoranj (SH:-C/o E/wall at RD 0/00 to 0/013) (RHS)	99,479/-	2,000/-	Two Months	Rs. 350/-	Class-D
15	C/o R-wall to Protect the community Hall Road at Katoh (SH:-C/o R/wall from community Hall side) (VKVNY/2022/1253)	4,79,331/-	10,000/-	Two Months	Rs. 350/-	Class-D
16	Restoration/Repair on Ludder to Sulgwan via Lagmanwin road 0/00 to 5/00 (SH:- P/F W-Beam Metal Crash Barrier at Various changes as per site in km 4/400 to 4/600) (PDNA)	4,96,650/-	10,000/-	Two Months	Rs. 350/-	Class-D
17	R/R on Ludder to Sulgwan via Lagmanwin RD 0/00 to 5/00 (SH:- P/F W-Metal Crash Barrier at various changes as per site in Rd 4/00 to 4/300) (PDNA)	4,96,650/-	10,000/-	Two Months	Rs. 350/-	Class-D
18	Restoration/Repair on Ludder Sulgwan via Lagmanwin road km 0/00 to 5/00 (SH:-C/o V-shape Drain at RD 0/00 to 1/500) (PDNA)	4,62,150/-	10,000/-	Two Months	Rs. 350/-	Class-D
19	R/M of Jijwin Awah Devi via Chamboh road km 0/00 to 9/255 (SH:- C/o R/wall at RD 7/508 to 7/520)	99,990/-	2,000/-	Two Months	Rs. 350/-	Class-D
20	Repair & maintenance of Una Aghar Mandi road km 79/00 to 91/00 (SH:- Dressing and cutting filling road side berms/ shoulder km 84/00 to 85/00 & 85/00 to 86/00) (Section Jahu)	99,746/-	2000/-	Two Months	Rs. 350/-	Class-D
21	Repair & maintenance of ludder Sulgwan road km 0/00 to 5/00 (SH:- Maintenance of earthen at various RDs)	99,830/-	2000/-	Two Months	Rs. 350/-	Class-D
22	R/M road Lapodu to Gasian Mata Mandir Km 0/00 to 0/750 (SH:- C/O R/wall at RD 0/070.50 to 0/076) (PDNA)	99,155/-	2000/-	Two Months	Rs. 350/-	Class-D
23	R/M link road Lapodu to Gasian Mata Mandir km 0/00 to 0/750 (SH:- C/O R/wall at RD 0/082 to 0/087.50) (PDNA)	99,155/-	2000/-	Two Months	Rs. 350/-	Class-D
24	R/M link road Lapodu Gasian Mata Mandir km 0/00 to 0/750 (SH:- C/O R/wall at RD 0/065 to 0/070.50) (PDNA)	99,155/-	2000/-	Two Months	Rs. 350/-	Class-D
25	Restoration of link road Bhareri to Dadu via Forest Rest House in Km 0/00 to 3/00 (SH:-	4,80,369/-	10000/-	Two Months	Rs. 350/-	Class-D

Scanned with OKEN Scanner

	P/L interlocking paver block at RD 0/400 to 0/440 & V-shape drain in km 0/00 to 1/00 (PDNA)					
26	R/R damages on link road Bajroh School to Baroh km. 0/00 to 2/00 (SH:- C/O Crate wire at RD 1/445 to 1/490) (LHS) (PDNA)	4,99,561/-	10000/-	Two Months	Rs. 350/-	Class-D
27	Restoration of link road vety. Hospital Bhareri Amroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/420 ,Vety. Hospital Bhareri to Amroh via Jaroh km 0/00 to 2/420 (SH:- C/O B/wall at RD 1/300 to 1/324, cement Conc. Pavement at RD 1/300 to 1/345) (PDNA)	4,99,776/-	10000/-	Two Months	Rs. 350/-	Class-D
28	Restoration of link road vety. Hospital Bhareri to Amroh via Fakruhi Hanoh km 0/00 to 2/420 (SH:- P/L interlocking paver block and v-shape drain km 0/700 to 0/780) (PDNA)	4,87,748/-	10000/-	Two Months	Rs. 350/-	Class-D
29	R/R damages on link road to vill. Jijwin km 0/00 to 0/600 (SH:- C/O R/wall at RD 0/150 to 0/157)	99,639/-	2000/-	Two Months	Rs. 350/-	Class-D
30	R/R damages on Sangroh to Bakkar Khad via Bhuana road km 0/00 to 3/900) (SH:- C/O R/wall at RD 1/670 to 1/675)	97,516/-	2000/-	Two Months	Rs. 350/-	Class-D
31	Restoration of rain damages on Bassi Bhareri Tatahar road km 0/00 to 11/00)(SH:- Removal of slips at various portions between km 0/700 to 1/500)(PDNA)(Section Bhareri)	4,97,225/-	10000/-	Two Months	Rs. 350/-	Class-D
32	Restoration of rain damages on Bassi Bhareri Tatahar road km 0/00 to 11/00)(SH:- Removal of slips at various portions between km 0/00 to 0/600)(PDNA)(Section Bhareri)	4,97,594/-	10000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Ambulance Road Mahila Mandal Bhawan to Baba Balaknath Temple via Rajpootan Basti .
(SH:- P/L 2.50 cm thick Premix carpet in Km 0/00 to 0/100.85) SDP/2024/24.

Estimated Cost Rs.1,50,609/-
Earnest Money Rs. 3500/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and applying primer coat with bitumen emulsion SS-I on prepared surface and spraying primer at the rate 0.85 kg per sqm using mechanical means as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	383.23	Per Square Meter			
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications On W.B.M. @ 0.75 Kg / sqm as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	383.23	Per Square Meter			
3	2.5 cm premix carpet surfacing with 3 cum of stone chippings 10 mm nominal size per 100 sqm and bitumen emulsion (medium setting min. 65% bitumen contents) complying with IS : 8887, using 96 kg per cum of chippings of road surface, including consolidation with road roller etc complete as per direction of Engineer- in -Charge, including entire carriage of materials in all leads and lifts and other incidentals. The rates are inclusive octori, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government	383.23	Per Square Meter			
4	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface,including rolling and finishing with road roller all complete.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	383.23	Per Square Meter			
	Terms and Condition:-					
	1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Various Road under Sub - Division Samirpur (SH:- Repair & maintenance of earthen shoulder, C/O Unlined Surface drain) (Dho Section).

Estimated Cost Rs 99,415/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1118.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	210.00	Per Running Mtr.			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration of rain Damages on Una Aghar Mandi Road km 67/00 to 79/00) (SH:- C/O R/Wall at RD.73/950 to 73/972) (PDNA)

Estimated Cost Rs 2,55,614/-
Earnest Money Rs. 5500/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	22.84	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	52.94	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.72	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Bhoranj Division

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Various Road under HPPWD Sub- Division Samirpur (SH:- Providing and Laying fixing of Inauguration/Foundation Pedestal i/c Granite stone plate.)

Estimated Cost Rs. 99,600/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Various Road under HPPWD Sub- Division Bhoranj (SH:- Providing and Laying fixing of Inauguration/Foundation Pedestal i/c Granite stone plate.) (Section Patta)

Estimated Cost **Rs. 99,800/-**
Earnest Money **Rs. 2000/-**
Time **2 Months**

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.00	Each			
2	Providing/fixing of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Various Road under HPPWD Sub- Division Bhoranj (SH:- Providing and Laying fixing of Inauguration/Foundation Pedestal i/c Granite stone plate.) (Section Bhoranj)

Estimated Cost Rs. 99,800/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.00	Each			
2	Providing/fixing of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Various Road under HPPWD Sub- Division Bhoranj (SH:- Providing and Laying fixing of Inauguration/Foundation Pedestal i/c Granite stone plate.) (Section Bhareri)

Estimated Cost Rs. 99,600/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of inauguration or foundation stone plague as per approved drawing specification including Z-black Granite stone including letter writing complete. including painting / distempering with Terra Kota colour complete including decoration of pedestal as per the entire specification and direction of Engineer-in - Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Restoration on Ludder to Sulgwan via Lagmanwin Hour Km 0/00 t 3/550 (SH:- P/L Interlocking paver block at RD 0/520 to 0/600) PDNA).

Estimated Cost	Rs 4,82,720/-
Earnest Money	Rs. 10000/-
Time	2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.00	Per Cubic Meter			
2	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	280.00	Per Square Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.20	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Restoration on Ludder to Sulgwan via Lagmanwin Hour Km 0/00 t 3/550 (SH:- P/L Interlocking paver block at RD 1/060 to 1/140) PDNA).

Estimated Cost	Rs 4,82,720/-
Earnest Money	Rs. 10000/-
Time	2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.00	Per Cubic Meter			
2	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	280.00	Per Square Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.20	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration /Repair on Ludder to Sulgwan via Lagmanwin Road 0/00 to 5/00 (S.H :- P/F W-Boam Metal Crash Barrier at various changes as per site in Km 4/800 to 5/00) PDNA).					Estimated Cost	Rs4,96,650/-
					Earnest Money	Rs. 10000/-
					Time	2 month
Sr No	**Description of Items**	**Quantity**	**Unit**	**Rate**	**Rates in Words**	**Amount**
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	129.00	Per running metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Link Road Khatarwar to village Tikkari Minhasa via Maira, Pidharata Km. 0/00 to 3/00 (SH:- Earth filling at RD 0/520 to 0/590 & C/O wing -wall at Rd 0/600 to protect the Abutment)					Estimated Cost	Rs.99,983/-
					Earnest Money	Rs. 2000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavating, supplying and filling of local earth (including royalty) by Mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete as per the direction of Engineer-in-Charge including all incidentals.The rates are inclusive of octroi, royality, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	268.50	Per Cubic meter			
2	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatenng as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.98	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.37	Per Cubic Meter			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration on link road Guard khana to Ward No-3 Harijan Basti Badehar km. 0/00 to 1/500. (SH:- C/O C.Conc.Pavement at RD 0/124to 0/248(PDNA)

Estimated Cost **Rs 4,97,710/-**
Earnest Money **Rs. 10000/-**
Time **2 month**

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.25	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.67	Per Cubic Meter			
5	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.67	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration on link road Guard khana to Ward No-3 Harijan Basti Badehar km. 0/00 to 1/500. (SH:- C/O C.Conc.Pavement at RD 0/00 to 0/124)(PDNA)

Estimated Cost Rs 4,99,708/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.37	Per Cubic Meter			
5	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.82	Per Cubic Meter			
5	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.82	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK :- R/R Damage on Executive Engineer office Building (PWD) Bhoranj (SH:- C/O E/wall at RD 0/00 to 0/013)(RHS)

					Estimated Cost	Rs.99,479/-
					Earnest Money	Rs. 2000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.93	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	18.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.51	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-:C/O R-wall to Protect the Community Hall Road at Katoh) (SH:- C/O R/Wall from Community Hall side) (VKVNY/2022/1253).

Estimated Cost Rs 4,79,331/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	40.65	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	98.42	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	60.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.26	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration /Repair on Ludder to Sulgwan via Lagmanwin road 0/00 to 5/00. (SH:- P/F W-Beam Metal Crash barrier at various changes as per site in Km 4/400 to 4/600) (PDNA).

Estimated Cost Rs 6,98,650/-
Earnest Money Rs. 15000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P C C grade M-10(M- ten)nominal mix 1:3:6 (one cement three sand six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c erecting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	129.00	Per running metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R on Ludeer to sulgwan via Lagmanwin RD 0/00 TO 5/00
(S.H :- P/F W- Metal Crash Barrier at Various changes as per site in RD.4/00 to 4/300 (PDNA)

Estimated Cost Rs 4,96650/-
Earnest Money Rs.10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	129.00	Per running metre			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration /Repair on Ludder Sulgwan via Lagmanwin road km 0/00 to 5/00.(SH:- C/O V-Shape Drain at Rd 0/00 to 1/500) (PDNA)

Estimated Cost Rs 462150/-
Earnest Money Rs. 10000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Construction of V-Shape drain with cement concrete 1:3:6 (one cement: three sand: six graded crushed stone aggregate 20mm (twenty millimeters nominal size) with thickness of concrete 10cm (ten centimeters) and size of drain 45x25 cm(forty five into twenty five centimeters) including cost of from work with steel plate excavation in earth work in all kind of soil and curing complete as per drawing and technical specification as per direction of Engineer-in-Charge including entire carriage of material in all leads and lifts.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1170.00	Per Running Meter			
	Total					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: R/M of Jijwin awah devi via Chamboh road km 0/00 to 9/255 (SH:- C/O R/Wall at RD. 7/508 to 7/520) .

Estimated Cost Rs 99,990/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.93	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.40	Per Cubic Meter			
3	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.60	Per Cubic Meter			
4	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.70	Per Cubic Meter			
5	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.70	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Una Aghar Mandi road Km.79/00 to 91/00 (SH:- Dressing and cutting filling road side berms/ shoulder km .84/00 to 85/00 & 85/00 to 86/00) (Section Jahu).

Estimated Cost Rs 99,745-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1196.00	Per square metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Ludder sulqwan road Km.0/00 to 5/00 (SH:- Maintenance of earthen at variour Rds)

Estimated Cost Rs 99,830/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1197.00	Per square metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: R/M Link road Lapodu to Gasian Mata Mandir km 0/00 to 0/750) (SH:- C/O R/Wall at RD.0/070.50 to 0/076). (PDNA)

Estimated Cost	Rs 99,155/-
Earnest Money	Rs. 2000/-
Time	2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.96	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: R/M Link road Lapodu to Gasian Mata Mandir km 0/00 to 0/750) (SH:- C/O R/Wall at RD.0/082 to 0/087.50). (PDNA)

Estimated Cost Rs 99,155/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.96	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: R/M Link road Lapodu to Gasian Mata Mandir km 0/00 to 0/750) (SH:- C/O R/Wall at RD.0/065 to 0/070.50) (PDNA)

Estimated Cost Rs 99,155/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.96	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road Bhareri to dadu via Forest Rest House in Km.0/00 to 3/00.(SH:- P/L interlocking paver block at RD 0/400 to 0/440 & V-shape drain in Km. 0/00 to 1/000).(PDNA)

Estimated Cost Rs 480369/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.88	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	27.63	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.83	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	255.00	Per Square Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: R/R Damages on Link Road Bajroh School to Baroh Km .0/00 to 2/00. (SH:- C/O Crate Wire Wall at 1/445 to 1/490) L.H.S (PDNA)

Estimated Cost Rs 4,99,561/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of matenals upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	70.31	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm(one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighthing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	140.63	Per Cubic Meter			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.57	Per Cubic Meter			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration of link road vety. Hosital Bhareri amroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/420,Vety. Hospital Bhareri to amroh via Jaroh km 0/00 to 2/420 (SH:- C/O B/Wall at RD 1/300 to 1/324 , Cement Conc. Pavement at RD 1/300 to 1/345.) (PDNA)

Estimated Cost Rs 4,99,776/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of matenals upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the orginal surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrnage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	69.60	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrnage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	71.04	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrnage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	48.00	Each			
4	Providing concrete for plain/ reinforced concrete in P.C.C. grade $M-_{10}$(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.50	Per cubic metre			
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.00	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of link road Voty Hospital Bhareri to Amroh vla Fakruhi Hanoh km 0/00 to 2/420 (SH:- P/L interlocking paver block and v Shape drain km 0/700 to 0/780).(PDNA).

Estimated Cost Rs 487748/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.20	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.00	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	240.00	Per Square Meter			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of rain damages on bassi Bhareri Tatahar Road km 0/00 to 11/00)(S.H :- Removal of slips at Various portions Between km 0/700 to 1/500) PDNA (Section Bhareri)

Estimated Cost Rs 4,97,225/-
Earnest Money Rs. 10,000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302 3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3977.80	Per Cubic metre			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of rain damages on bassi Bhareri Tatahar Road km 0/00 to 11/00)(S.H :- Removal of slips at Various portions Between km 0/00 to 0/600) PDNA (Section Bhareri)

Estimated Cost Rs 4,97,594/-
Earnest Money Rs. 10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3980.75	Per Cubic metre			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Scanned with OKEN Scanner