Tel.01899-299219.
eepwd-chowari@hp.gov.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD-CHW/Tender /2025-26- 13045-13100 Dated:- 19/02/2026

To

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - **Publishing of Tender Notice.**

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letterNo.PWD-CHW/Tender /2025-26 13045-13100 dated 19/2/26 is emergent nature and in public interest.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

HIMACHAL PRADESH
Tel.01899-299219.
eepwd-chowari@hp.gov.in

PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari o behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

1 **Date of issued/sale of tender form against** **27.02.2026**
2 **Cash payment (nonrefundable).** **28.02.2026**

The tender shall be received upto**11.00 AM** on **28.02.2026** and will be opened on the day of **28.02.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **27.02.2026** The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Extension of Kahri Kothi to Kut Read (Portion Kahri to Gunha Nallah) Km.0/00 to 1/500 (SH-C/O R/wall in Wire Crate at Rd. 0/397.50 to 0/402.50)	98042.00	2000.00	Rs. 350/-	One Month	Class-D & C
2	Restoration of rain damage on Shahpur Sihunta Chowari Jot Road Km. 0/00 to 53/00 (SH-C/O B/Wall in Wire Crate at Rd. 46/909.50 to 46/919)	96617.00	2000.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of rain damage on Link Road to Village Raipur Km 0/00 to 1:00 (SH-C/O V-Shape Side Drain at Rd. 0/525 to 0/563 & 0/650 to 0/845)	191040.00	3820.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of rain damage on Raipur to Fagot road Km. 0/00 to 6/350 (SH-Removal of slips in between km. 0/00 to 4/00)	301922.00	6038.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km 25/0 to 40/810 (SH:- Removal of slips in between km. 30/00 to 35/00)	297816.00	5956.00	Rs. 350/-	One Month	Class-D & C
6	Restoration of damage on Garnota (Badela) Pukhru via Padwal Road Km 000 to 6/180 (SH:- C/O R/wall at Rd. 0/0 to 0/006 & 0/026 to 0/031)	289396.00	5788.00	Rs. 350/-	One Month	Class-D & C
7	Restoration of rain damage on Chowari to Jot Road Km. 0:00 to 23/00 (SH-Removal of slips in between km. 0/00 to 5/00)	491838.00	9837.00	Rs. 350/-	One Month	Class-D & C

8	Restoration of rain damage on Village Fakrodu Km. 0/00 to 2/800 (SH:- Removal of slips in between km. 0/00 to 5/00)	497831.00	9957.00	Rs. 350/-	One Month	Class-D & C
9	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH-Removal of slips in between km. 25/00 to 30/00)	456151.00	9123.00	Rs. 350/-	One Month	Class-D & C
10	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 47/00 to 53/00 (SH-Removal of slips in between km. 47/00 to 52/00)	303548.00	6070.00	Rs. 350/-	One Month	Class-D & C
11	11 Restoration of rain damage on various roads under Raipur section (SH-Hiring of Tipper for Shifting Muck debris on various roads	497280.00	9946.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of rain damage on Chowari Mandhiar Baloh Fagot road Km. 0:00 to 13/300 (SH:- Removal of slips in between km. 0/00 to 4/00)	217269.00	4345.00	Rs. 350/-	One Month	Class-D & C
13	Restoration of rain damage on Patka to Dalhousie road Km. 14/00 to 32/00 (SH- Removal of slips in between km. 14/00 to 22/00)	400667.00	80100.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 15/390 to 25/00 (SH-Removal of slips in between km. 15/500 to 25/00)	408099.00	8162.00	Rs. 350/-	One Month	Class-D & C
15	Balance work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH: Removal of formation deficiency in between Km. 1/060 to 1/195)	498022.00	10000.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of rain damage on Link Road to Village Fakrodu Km. 0:00 to 2/700 (SH-C/O B/wall at Rd. 0/185 to 0/191.50 & 0/215 to 0/221)	186580.00	3732.00	Rs. 350/-	One Month	Class-D & C
17	Restoration of Rain damage on Link Road to Village Bighyala Km. 0/00 to 1/730 (SH: C/O B/Wall at RD. 1/450 to 1/466)	186496.00	3730.00	Rs. 350/-	One Month	Class-D & C
18	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH: C/o Retaining wall in WPCC B/w Km. 39/244.50 to 39/247 & 39/248 to 39/250)	50310.00	1000.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of rain damage on Dugrerd to Naloh road Km. 0/00 to 5/630 (SH-Removal of slips in between km. 0/00 to 5/630)	492443.00	9850.00	Rs. 350/-	One Month	Class-D & C
20	Restoration of rain damage on Transformer to Kallar Jolna road Km. 0/00 to 2/700 (SH- Removal of slips in between km. 0/00 to 2/700)	396317.00	7926.00	Rs. 350/-	One Month	Class-D & C
21	Balance work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH. Removal of formation deficiency in between Km. 1/495 to 1/628)	498171.00	10000.00	Rs. 350/-	One Month	Class-D & C

22	Restoration of rain damage on Nanikhed to Samleu Road Km. 0/00 to 30/585 (SH- Removal of slips in between km. 4/00 to 8/600)	445253.00	8900.00	Rs. 350/-	One Month	Class-D & C
23	Restoration of rain damage on Link Road to Village Upper Bakan Kim. 0/00 to 2/050 (SH:-Removal of slips in between lan. 0/00 to 2/050)	439480.00	8800.00	Rs. 350/-	One Month	Class-D & C
24	Restoration of rain damage on Dhalog to Samleta Road Km. 0/00 to 4/900 (SH Removal of slips in between km. 0/00 to 4/500)	498531.00	10000.00	Rs. 350/-	One Month	Class-D & C
25	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuharti Road Km. 15/390 to 25/00 (SH-Removal of slips in between km. 25/500 to 28/400)	442060.00	8800.00	Rs. 350/-	One Month	Class-D & C
26	Restoration of rain damage on Patka to Dalhousie Road Km. 0/00 to 14/00 (SH Removal of alips in berween km. 0/00 to 7/500)	497430.00	10000.00	Rs. 350/-	One Month	Class-D & C
27	Restoration of rain damage on Dukhar to Morthu Road Km. 0/00 to 800 (SH-Removal of slips in between km. 2/00 to 5/500)	421616.00	8400.00	Rs. 350/-	One Month	Class-D & C
28	Balance work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH: Removal of formation deficiency in between Km. 1/785 to 1/935)	499232.00	10000.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of rain damage on Beriyangalla to Taragarh Road Km. 000 to 3/490 (SH- Removal of slips in between km. 0/00 to 3/100)	438914.00	8800.00	Rs. 350/-	One Month	Class-D & C
30	Restoration of Rain damages on Shahpur Sihunta Chowari via Jot Chamba road Kim. 00 to 24/00 (SH:-Construction of Retaining wall at RD. 22/460 to 22/470)	252348.00	5100.00	Rs. 350/-	One Month	Class-D & C
31	Balance work on Silunta Jolna Kotla road Km 0/00 to 5/00 (SH: Formation deficiency in between Km 2/810 to 3/360).	419985.00	10000.00	Rs. 350/-	One Month	Class-D & C
32.	Restoration of rain damage on Patka to Dalhousie road (SH:- Hiring of excavator cum loader for removal of slips Km 32/00 to 45/00).	482258.00	10000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of rain damage on NSLT road (SH:- Hiring of excavator cum loader for removal of slips Km 15/00 to 25/00).	469564.00	9500.00	Rs. 350/-	One Month	Class-D & C

1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.

2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.

3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98042.00	
Earnest Money :- Rs. 2000.00	
Time Limit :-	One Month.

Name of work:- Extension of Kahri Kothi to Kut Road (Portion Kahri to Gunha Nallah) Km.0/00 to 1/500 (SH:- C/O R/wall in Wire Crate at Rd. 0/397.50 to 0/402.50)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.65	400.10	Rupees Four Hundred And Paise Ten Only	Per cum	2261.00
	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (twenty five kilograme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.25	3065.00	Rupees Three Thousand Sixty Five Only	Per cum	95781.00
					Total: -	98042.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

(2)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 96617.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Jot Road Km. 0/00 to 53/00 (SH:- C/O B/Wall in Wire Crate at Rd. 46/909.50 to 46/919)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.04	400.10	Rupees Four Hundred And Paise Ten Only	Per Cum	5617.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (twenty five kilograme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	29.69	3065.00	Rupees Three Thousand Sixty Five Only	Per Cum	91000.00
					Total: -	96617.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 191040.00
Earnest Money :- Rs. 3900.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Link Road to Village Raipur Km. 0/00 to 1/00 (SH:- C/O V-Shape Side Drain at Rd. 0/525 to 0/563 & 0/650 to 0/845).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.99	400.10	Rupees Four Hundred And Paise Ten Only	Per Cum	13999.00
2	Providing and laying mechnical mixed and vibrated concrete for plain / reinforced grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20 millimeter (twenty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, drain and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax,GST or other taxes imposed by the Government.	28.55	6201.10	Rupees Six Thousand Two Hundred One And Paise Ten Only	Per Cum	177041.00
					Total: -	191040.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 301922.00
Earnest Money :- Rs. 6100.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Raipur to Fagot road Km. 0/00 to 6/350 (SH:- Removal of slips in between km. 0/00 to 4/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1919.40	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	301922.00
					Total: -	301922.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 297816.00
Earnest Money :- Rs. 6000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/0 to 40/810 (SH:- Removal of slips in between km. 30/00 to 35/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1893.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	297816.00
					Total: -	297816.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost - Rs. 289396.00
Earnest Money - Rs. 5800.00
Time Limit: - One Months

Name of Work:- Restoration of damage on Garnota (Badela) Pukhru via padwal Road Km. 0/00 to 6/180 (SH:- C/O R/wall at Rd. 0/0 to 0/006 & 0/026 to 0/031).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	9602.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	55.26	4602.00	Rupees Four Thousand Six Hundred Two Only	Per Cubic Metre	254307.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.07	1240.90	Rupees One Thousand Two Hundred Forty And Paise Ninety Only	Per Cubic Metre	7532.00

4	Providing Weepholes in brick masonary / stone masonary / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizental towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals.The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	45	411.00	Rupees Four Hundred Eleven Only	Each	18495.00
					Total: -	**289936.00**
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 491838.00
Earnest Money :- Rs. 9900.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH:- Removal of slips in between km. 0/00 to 5/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3126.75	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	491838.00
					Total: -	491838.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 497831.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Village Fakrodu Km. 0/00 to 2/800 (SH:- Removal of slips in between km. 0/00 to 5/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3164.85	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	497831.00
					Total: -	497831.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 456151.00
Earnest Money :- Rs. 9100.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH:- Removal of slips in between km. 25/00 to 30/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2899.88	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	456151.00
					Total: -	456151.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 303548.00	
Earnest Money :- Rs. 6100.00	
Time Limit :- One Month.	

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 47/00 to 53/00 (SH:- Removal of slips in between km. 47/00 to 52/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1929.74	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	303548.00
					Total: -	303548.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost -	Rs. 497280.00
Earnest Money -	Rs. 10000.00
Time Limit: -	One Months

Name of Work:- Restoration of rain damage on various roads under Raipur section (SH:- Hiring of Hiring of Tipper for Shifting Muck debris on various roads)

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Hiring of tipper having capacity 11 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the conntractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royality ,malkana toll tax sale tax or any other taxes imposed by the Government.	448.00	1110.00	Rupees One Thousand One Hundred Ten Only	Per Cubic Metre	497280.00
					Total: -	497280.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 217269.00
Earnest Money :- Rs. 4400.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/00 to 13/300 (SH:- Removal of slips in between km. 0/00 to 4/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1381.24	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	217269.00
					Total: -	217269.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 400667.00
Earnest Money :- Rs. 8000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Patka to Dalhousie road Km. 14/00 to 32/00 (SH:- Removal of slips in between km. 14/00 to 22/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2547.15	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	400667.00
					Total: -	400667.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 408099.00	
Earnest Money :- Rs. 8200.00	
Time Limit :- One Month.	

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 15/390 to 25/00 (SH:- Removal of slips in between km. 15/500 to 25/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2594.40	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	408099.00
					Total: -	408099.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 498022.00	
Earnest Money :- Rs. 10000.00	
Time Limit :- One Month.	

Name of work: - Balanace work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH: - Removal of formation deficency in between Km. 1/060 to 1/195)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. . Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2675.67	186.13	Rupees One Hundred Eighty Six And Paise Thirteen Only	Per Cubic Metre	498022.00
					Total: -	498022.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 186580.00
Earnest Money :- Rs. 3700.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Link Road to Village Fakrodu Km. 0/00 to 2/700 (SH:- C/O B/wall at Rd. 0/185 to 0/191.50 & 0/215 to 0/221)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.46	400.10	Rupees Four Hundred And Paise Ten Only	Per Cum	7786.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.92	4642.30	Rupees Four Thousand Six Hundred Forty Two And Paise Thirty Only	Per Cum	171394.00
3	Providing Weepholes in brick masonary / stone masonary / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizental towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals.The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.00	411.10	Rupees Four Hundred Eleven And Paise Ten Only	Per Each	7400.00
					Total: -	**186580.00**
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 186496.00	
Earnest Money :- Rs. 3700.00	
Time Limit :-	One Month

Name of work:- Restoration of Rain damage on Link Road to Village Bighyala Km. 0/00 to 1/730 (SH :- C/O B/Wall at RD. 1/450 to 1/466)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.00	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	6402.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.00	4819.95	Rupees Four Thousand Eight Hundred Nineteen And Paise Ninety Five Only	Per Cubic Metre	173518.00
	Providing Weepholes in brick masonary / stone masonary / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizental towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals.The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.00	411.00	Rupees Four Hundred Eleven Only	Per Each	6576.00
					Total: -	186496.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 50310.00
Earnest Money :- Rs. 1000.00
Time Limit :- One Month

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- C/o Retaining wall in WPCC B/w Km. 39/244.50 to 39/247 & 39/248 to 39/250)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.13	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	2053.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.90	4874.40	Rupees Four Thousand Eight Hundred Seventy Four And Paise Forty Only	Per Cubic Metre	48257.00
		50310			**Total: -**	**50310.00**
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 492443.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Dugrerd to Naloh road Km. 0/00 to 5/630 (SH:- Removal of slips in between km. 0/00 to 5/630)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3130.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	492443.00
					Total: -	492443.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 396317.00
Earnest Money :- Rs. 7900.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Transfamer to Kallar Jolna road Km. 0/00 to 2/700 (SH:- Removal of slips in between km. 0/00 to 2/700)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2519.50	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	396317.00
					Total: -	396317.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 498171.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work: - Balanace work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH: - Removal of formation deficency in between Km. 1/495 to 1/628)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. . Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2574.26	193.52	Rupees One Hundred Ninety Three And Paise Fifty Two Only	Per Cubic Metre	498171.00
					Total: -	498171.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 445253.00
Earnest Money :- Rs. 8900.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Removal of slips in between km. 4/00 to 8/600)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2830.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	445253.00
					Total: -	445253.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 439480.00
Earnest Money :- Rs. 8800.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Link Road to Village Upper Bakan Km. 0/00 to 2/050 (SH:- Removal of slips in between km. 0/00 to 2/050)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2793.90	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	439480.00
					Total: -	439480.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 498531.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Dhalog to Samleta Road Km. 0/00 to 4/900 (SH:- Removal of slips in between km. 0/00 to 4/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3169.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	498531.00
					Total: -	498531.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 442060.00
Earnest Money :- Rs. 8800.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 15/390 to 25/00 (SH:- Removal of slips in between km. 25/500 to 28/400)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2810.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	442060.00
					Total: -	442060.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 497430.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Patka to Dalhousie Road Km. 0/00 to 14/00 (SH:- Removal of slips in between km. 0/00 to 7/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3162.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	497430.00
					Total: -	497430.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 421616.00
Earnest Money :- Rs. 8400.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Dukhar to Morthu Road Km. 0/00 to 8/00 (SH:- Removal of slips in between km. 2/00 to 5/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2680.33	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	421616.00
					Total: -	421616.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 499232.00
Earnest Money :- Rs. 10000.00
Time Limit :- One Month.

Name of work: - Balanace work on Link road to Naag Bintru Km. 0/0 to 2/580 (SH: - Removal of formation deficency in between Km. 1/785 to 1/935)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. . Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2737.02	182.40	Rupees One Hundred Eighty Two And Paise Forty Only	Per Cubic Metre	499232.00
					Total: -	499232.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 438914.00
Earnest Money :- Rs. 8800.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Beriyangalla to Taragarh Road Km. 0/00 to 3/490 (SH:- Removal of slips in between km. 0/00 to 3/100)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2790.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cubic Metre	438914.00
					Total: -	438914.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost - Rs. 252348.00
Earnest Money - Rs. 5100.00
Time Limit: - One Month

Name of Work:- Restoration of Rain damages on Shahpur Sihunta Chowari via Jot Chamba road Km. 0/0 to 24/00 (SH: - Construction of Retaining wall at RD. 22/460 to 22/470)

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.70	400.70	Rupees Four Hundred And Paise Seventy Only	Per Cubic Metre	12702.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arrise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46.70	4739.40	Rupees Four Thousand Seven Hundred Thirty Nine And Paise Forty Only	Per Cubic Metre	221330.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.80	1240.90	Rupees One Thousand Two Hundred Forty And Paise Ninety Only	Per Cubic Metre	5956.00

4	Providing Weepholes in brick masonary / stone masonary / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizental towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals.The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30	412.00	Rupees Four Hundred Twelve Only	Each	12360.00
					Total: -	**252348.00**
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					

Executive Engineer
Chowari Division
HP PWD Chowari

BILL OF QUANTITY

Estimate Cost - Rs. 419985.00
Earnest Money - Rs. 8400.00
Time Limit: - One Months

Name of Work:- Balance work on Sihunta Jolna Kotla road Km. 0/00 to 5/00 (SH: - Formation deficency in between Km. 2/810 to 3/360).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Excavation in hilly area in all heights and depths and in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil ,ordinary roack,soft rock ,hard roack chieseling ,wedging out rock (where blasting is probihitted)and their intermediate classification of soil compelet including setting out true to the require lines,grades,width ,cutting and trimming of side slopes and levels as shown on the drawings and as direction of engineer-in-charge at site ,according to the technical specification section 300 and 1600 and sorting out useful material and stacking the same within all leads liftts in acquired width of road and transportation of un-usal materials for filling in roadway camber ,embankement for grade improvements abd disposal of all surplus material to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transpot or mechanical means alongwith its leveling fine dressig and carriage of machineries material,tool ,equipment and safety measures and other incidental necessary to complete the work by contractor .Any loss to the public/private property during the course of execution shall be the absolute responsibilty of the contractor ,which shall have to be compensated by him in all cases.**The removal of slips during the construction period shall be responsibillity of the contractor and nothing extra shall be paid on this account.** The rate are including the octroi royality,Malkana toll tex,sales tax GST or any other taxes imposed by the Govt.	1934.70	217.08	Rupees Two Hundred Seventeen And Paise Eight Only	Per Cubic Metre	419985.00
		Total				**419985.00**

Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDUEL OF QUANTITY	Estimate cost:-469564/--
	Earnest Money:-9500/-
	Time limit:-One Month

Name of work:-Restoration of rain damage on NSLT road (SH:- Removal of slips in Km 15/00 to 25/00).

S.NO	DESCRIPTION OF ITEM	QTY	RATE In No	UNIT	AMOUNT
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidential. The rate including the octori, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2985.15	157.30	Cubic meter	469564.10
				Total	469564
	Rate quoted in (%) above/below				
	Rate quoted in (%) in words				

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI