

Offline

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

No. PWD-Dal/TA/Tender /2025-26 8627-29  
To

Dated: - 06-02-26


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

  
**Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.**


Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle,  
HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive  
Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
**Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie**


**Certificate**

Certified that the tenders called vide this office letter No. PWD-  
/TA/Tender /2025-26:- 8627-27 dated. 06-02-26 is emergent nature and in Public  
interest.

 Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

**Certificate**

Certified that the tenders called vide this office letter No. PWD-  
/TA/Tender /2025-26:- 8627-29 dated. 06-02-26 is emergent nature and in Public  
interest.

 Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- 13.02.2026 onward (between 2:00 p.m.to 4:30.p.m.)

2. Date of issue/sale of tender form against Cash payment (non refundable). 13.02.2026


The tender shall be received up to 3:00 PM on 16.02.2026 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on 13.02.2026

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Construction of Link road from Salla to Bhalei Km. 0/0 to 1/00 (SH: - Construction of 900mm dia Hume pipe Culvert at RD. 0/105).	138709.00	3000.00	350.00	Two Months	D & C
2.	Restoration of rain damage on Link road to village Gandohra Km. 0/0 to 5/510 (Village road) (SH: -Construction of PCC Retaining wall at RD 0/190 to 0/197 & 2/140 to 2/145). (Under PDNA-2023)	240284.00	5000.00	350.00	Two Months	D&C
3.	Restoration of rain damage on Samah to Haddila road Km. 0/0 to 5/510 (Village road) (SH: -Construction of PCC Retaining wall at RD 1/330 to 1/335 & 4/500 to 4/510). (Under PDNA-2023)	365491.00	7500.00	350.00	Two Months	D&C
4.	Restoration of rain damage on various road under Dalhousie Sub. Division (SH:- Removal of slips/Snow on various road under Dalhousie Sub. Division .)	498750.00	10000.00	350.00	One Month	D&C
5	Restoration of rain damage on Link road to village Ruliyani Km. 0/0 to 3/020 (SH:- Removal of slips on Link road to village Ruliyani Km. 0/0 to 3/020.)	98843.00	2000.00	350.00	One Month	D & C
6.	Restoration of rain damage on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (SH:- Removal of slips on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00.)	99764.00	2000.00	350.00	One Month	D&C
7.	Restoration of rain damage on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Removal of slips on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040.)	95648.00	2000.00	350.00	One Month	D&C

8.	Restoration of Rain damage on Patka Chowari Dalhousie road Km. 67/00 to 73/00 (SH: - Removal of Slips/Snow on Km. 67/00 to 73/00).	97213.00	2000.00	350.00	One Month	D&C
9	Restoration of rain damage on Brangal Wangal Mandoh road Km 0/00 to 39/600 (SH:- Construction of Brest wall in wire crate at RD. 35/820 to 35/830).	99760.00	2000.00	350.00	Two Months	D&C
10	Restoration of rain damage on Samah to Haddila road Km. 0/00 to 5/510 (SH:- Removal of slips between Km. 0/00 to 5/510).	99910.00	2000.00	350.00	One Month	D&C
11	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/00 to 39/600 (SH:- Construction of retaining wall in wire crate at RD. 35/840 to 35/850).	99878.00	2000.00	350.00	Two Months	D&C
12	Restoration of rain damage on link road to village Dughar Km. 0/00 to 3/300 (SH:- Removal of slips between Km. 0/00 to 3/300).	98880.00	2000.00	350.00	One Month	D&C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No, Earnest Money, Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.


  
 Executive Engineer,  
 Dalhousie Division,  
 HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 8630 - 8650

Dated:- 06-02-26

**Copy forwarded to the following for information and necessary action please:-**

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

  
 Executive Engineer,  
 Dalhousie Division,  
 HPPWD, Dalhousie

**Schedule of qty**

Estimated Cost: - Rs. 138709.00

Earnest Money :- Rs. 3000.00

Time Limit :- Two Months

Name of work: - Construction of Link road from Salla to Bhalei Km. 0/0 to 1/00 (SH: - Construction of 900mm dia Hume pipe Culvert at RD. 0/105).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	27.71			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:4:8 (one cement is to four sand isto eight graded crushed stone aggregate with nominal mix in open foundations complete as per drawing and technical specifications clauses 802, 803, 1202 & 1203 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	2.47			Per Cubic Metre	
3	Providing and laying plain cement concrete 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 milliMetre (forty milliMetre) nominal size including the cost of form work and curing complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	12.14			Per Cubic Metre	
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete grade M-15 (M-fifteen) 1:2.5:5 (One cement isto two point five sand isto five graded crushed stone aggregate 40 mm (forty millimetre) nominal size) in sub structure including curing complete and cost of form work as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	1.20			Per Cubic Metre	

5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure grade M-20 (M-Twenty) nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40 mm (Forty milimeter) nominal size) and curing complete including pumping or bailing out water, dewatering removal of slush as required at site including the cost of form work as per drawing and MORD technical specification sections 802,803,1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	0.25			Per Cubic Metre	
6	Providing and laying (to level or slope) 900 mm dia (nine hundred milliMetre diaMetre) reinforced cement concrete light duty non pressure pipes IS Class NP-2 (two) for culverts as per design in single row on concrete cradle bedding of plain cement concrete grade M-15 (fifteen) in single row including providing and fixing collar with cement mortar 1:2 (One cement isto two sand), but excluding the cost of excavation, protection works, back filling, concrete cradle bedding and masonry work in head walls and parapets etcetera complete as per drawings and M.O.R.D. technical specifications clause 1108 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	7.50			Per Running Metre	
					<b>Total: -</b>	

  
 Executive Engineer  
 Dalhousie Division,  
 RPFWD, Dalhousie  


**Schedule of qty**

Estimated Cost: - Rs. 240284.00

Earnest Money :- Rs. 5000.00

Time Limit :- Two Months

Name of work: -Restoration of rain damage on Link road to village Gandohra Km. 0/0 to 5/510 (Village road) (SH: -Construction of PCC Retaining wall at RD 0/190 to 0/197 & 2/140 to 2/145). (Under PDNA-2023)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	24.48			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	42.84			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	6.60			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	18.00			Each	
					<b>Total: -</b>	

  
**Executive Engineer**  
 Dalhousie Division,  
 HPP/MD, Dalhousie

## Schedule of qty

Job No. 03 TS No. 155

Estimated Cost: - Rs. 365491.00

Earnest Money :- Rs. 7500.00

Time Limit :- Two Months

**Name of work: -Restoration of rain damage on Samah to Haddila road Km. 0/0 to 5/510 (Village road) (SH: -Construction of PCC Retaining wall at RD 1/330 to 1/335 & 4/500 to 4/510). (Under PDNA-2023)**

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	36.75			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	64.45			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	9.90			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc extndng through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tencial specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	27.00			Each	
					<b>Total: -</b>	

  
**Executive Engineer**  
 Dalhousie Division,  
 HPPWD, Dalhousie

## Schedule of qty

Job No. 04 TS 179

Estimated Cost: - Rs. 498750.00

Earnest Money :- Rs. 10000.00

Time Limit :- One Month


Restoration of rain damage on various road under Dalhousie Sub. Division (Sh:- Removal of slips/Snow on various road under Dalhousie Sub. Division .)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips/snow in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	475.00			Per Hour	
					<b>G. Total:-</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

  
Executive Engineer  
Dalhousie Division,  
HPPWD, Dalhousie  
SC

Job No. 05 TS 175

**Schedule of qty**



Estimated Cost: - Rs. 98843.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Restoration of rain damage on Link road to village Ruliyani Km. 0/0 to 3/020 (SH:- Removal of slips on Link road to village Ruliyani Km. 0/0 to 3/020.)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of Slips/Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as per directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	791.50			Per Cubic Metre	
					Total	

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie  


Job No.6 TS 176

## Schedule of qty

Estimated Cost: - Rs. 99764.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Restoration of rain damage on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (SH:- Removal of slips on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00.)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of Slips/Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as per directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	798.87			Per Cubic Metre	
					<b>Total</b>	

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie  


Job No. 07 TS 177

**Schedule of qty**

Estimated Cost: - Rs. 95648.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Restoration of rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Removal of slips on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040.)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of Slips/Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as per directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	765.92			Per Cubic Metre	
					<b>Total</b>	

  
Executive Engineer  
Dalhousie Division,  
HPPWS Dalhousie

Job No. 08 TS 178

## Schedule of qty


Estimated Cost: - Rs. 97213.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Patka Chowari Dalhousie road Km. 67/00 to 73/00 (SH: - Removal of Slips/Snow on Km. 67/00 to 73/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of Slips/Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as per directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	778.45			Per Cubic Metre	
					<b>Total</b>	

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie  
*SK*

**Schedule of qty**


Estimated Cost: - Rs. 99760.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Restoration of rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Brest wall in wire crate at RD. 35/820 to 35/830).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	18.75			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (Twenty Five kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.26	←		Per Cubic Metre	
					<b>Total: -</b>	

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie

**Schedule of qty**

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Samah to Haddila Km. 0/0 to 5/510 (SH: - Removal of slips between Km. 0/00 to 5/510).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					<b>G. Total:-</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

  
Executive Engineer  
Dalhousie Division,  
HPPWD, Dalhousie  
SL


Job No. 14 TS 171

## Schedule of qty

Estimated Cost :- Rs.	99878.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Month

Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SI: - Construction of Retaining wall in wire crate at RD. 35/840 to 35/850).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	18.95			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (Twenty Five kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.26			Per Cubic Metre	
<b>Total: -</b>						

  
 Executive Engineer  
 Dalhousie Division  
 M.F.P.W.D. Dalhousie  
 SK

**Schedule of qty**

Estimated Cost: - Rs.

98880.00

Earnest Money :- Rs.

2000.00

Time Limit :-

One Month

Name of work: -Restoration of rain damage on Link road to village Dughar Km. 0/0 to 3/300 (SI: - Removal of slips between Km. 0/00 to 3/300 ).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					<b>G. Total:-</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

  
Executive Engineer  
Dalhousie Division,  
HPPWD, Dalhousie  
SK