

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26
To

12379-99


Dated 20/2/26

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla


Subject:- Tender Notice

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

- Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla - 2 for favour of information please.
- Copy to the Engineer-in-Chief HPPWD Shimla for information please.
- Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.
- Copy to the Superintending Engineer Dehra Circle HPPWDD Dehra for favour of information please.
- Copy to Notice Board
- Copy to All the head of Branches
- Copy to All the Contractors working under Dehra Division


Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER


Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 25.02.2026 upto 5.00 PM
2. Date and time of issue of tender form: 27.02.2026 upto 5.00 PM
3. Date and time of receipt of tenders: 28.02.2026 upto 11.00 AM
4. Date and time of opening of tenders: 28.02.2026 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain damages on Kaloha Pargapur Dhalaiara Dada Siba Sansarpur Terrace Road Km 9/00 t 22/200 (SH;- Providing and laying & interlocking Paver Block 80mm thick 10/998 t0 11/00 & Hume Pipe Culvert at Rd 11/00	Rs.264864	Rs5300	Three Months	Rs 350/-
1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): Copy of Registration/Latest renewal of enlistment.				
(i)	PAN (Permanent Account No.)				
(ii)	Registration under GST No.				
(iii)	EPF(Employee Provident Fund Account No.)				
(iv)	The proof ownership/hire/lease, buying of required machinery for micro surfacing works.				
(v)					
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				


Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P

106

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of rain damages on Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace road in Km 9/000 to 22/200 (SH:- Providing and laying & interlocking paver block 80mm thick 10/988 to 11/000 & Hume Pipe Culvert at RD 11/000).

Estimate Cost :- Rs. 2,64,864.00
Earnest Money :- Rs. 5,300.00
Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	41.60 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	12,064.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	19.59 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	96,971.00

df

No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	2.77 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	11,219.00
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete <i>in open foundation</i> Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in open foundation etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	2.75 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	15,950.00
5	Providing and laying ISI marked factory made chartered edge Cement Concrete paver blocks having thickness 80mm (Eighty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	68.40 Square metre	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square metre	78,660.00

Handwritten signature or mark.

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
6 Providing and laying (to level or slope) 900mm (Nine Hundred millimeter) diameter ISI marked reinforced cement concrete medium duty non pressure pipes I S class NP-3 as per design for culverts on type 'A' (concrete cradle) bedding of M-15 (M-fifteen) grade cement concrete in single row including providing and fixing collar with cement mortar 1:2 (one cement isto two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets etcetera as per drawing and MORRD Technical specification as clause 1106 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, Toll tax, sale tax or any other taxes imposed by the Government	10.00 Running metre	5000.00	Rupees Five Thousand Only	Per Running metre	50,000.00
TOTAL					2,54,864.00
% Above/below					
Quoted Amount in Figures					
Quoted Amount in Words					

Percentage bid of quantity checked and approved for Rs. 2,54,864.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra