HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26- 11609-29 Dated 10/2/26
To

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla

Subject:- **Tender Notice**

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla - 2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer Dehra Circle HPPWDD Dehra for favour of information please.

Copy to Notice Board

Copy to All the head of Branches

Copy to All the Contractors working under Dehra Division

Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the **Executive Engineer Dehra Division HPPWD.,** Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 16.02..2026 upto 5.00 PM
2. Date and time of issue of tender form: 17.02.2026 upto 5.00 PM
3. Date and time of receipt of tenders: 18.02.2026 upto 11.00 AM
4. Date and time of opening of tenders: 18.02.2026 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dada Siba Sansarpur Terrace Road 9/00 to 22/200 (SH;- Painting and writing on km stone culverts bridge sign boards & Rain Shelter etc in Dhaliara section)	Rs.99845.00	Rs.2,000/-	Three Months	Rs 350/-
2	Restoration of Rain Damages on Upper Pragpur to Karol Via Dadari in km 2/00 to 3/300 (SH;- C/O R/wall at Rd 3/225 to 3/237) PDNA	Rs.99896.00	Rs.2,000/-	Three Months	Rs 350/-
3	Restoration of Rain Damages on Upper Pragpur to Karol Via Dadari in km 2/00 to 3/300 (SH;- C/O R/wall at Rd 3/240 to 2/252) PDNA	Rs99896.00	Rs.2,000/-	Three Months	Rs 350/-
4	A/R & M/o to Non Residential Building at Hanuman Chowk Dehra Tehsil Dehra Distt Kangra (H.P) (SH:- Wood work Concrete work Sanitary work etc)	Rs.98660.00	Rs2000/-	Three Months	Rs 350/-
5	C/O Ambulance road from Bilan Bala baba Mandhir to Main Road ward No 4 Post office Kheran GP Kherain km 0/0to 0/300 (Sh;- Providing and laying 80mm thick interlocking paver block at Rd 0/239 to 0/262.30 VKV/2025/425) Deposit	Rs 79604.00	Rs.2000/-	Three Months	Rs 350/-
6	C/O Ambulance road from Bilan Bala baba Mandhir to Main Road ward No 4 Post office Kheran GP Kherain km 0/0to 0/300 (Sh;- Providing and laying 80mm thick interlocking paver block at Rd 0/210 to 0/237.50 VKV/2025/425) Deposit	Rs 80090.00	Rs 2000/-	Three Months	Rs 350/-
7	C/O Ambulance road from Bilan Bala baba Mandhir to Main Road ward No 4 Post office Kheran GP Kherain km 0/0to 0/300 (SH;- Providing and laying 80mm thick interlocking paver block at Rd 0/070 to 0/115 VKV/2025/425) Deposit	Rs89614.00	Rs.2000.00	Three Months	Rs 350/-
8	Restoration Rain Damages on Jawalimukhi Dehra Raja k talab road in km 22/00 to 39/180 (SH;- Painting & Writing on Bridges Culvers Providing & Fixing precast kilometer Stone) PDNA	Rs99845.00	Rs.2000.00	Three Months	Rs 350/-

1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): Copy of Registration/Latest renewal of enlistment.
(i)	PAN (Permanent Account No.)
(ii)	Registration under GST No.
(iii)	EPF(Employee Provident Fund Account No.)
(iv)	The proof ownership/hire/lease, buying of required machinery for micro surfacing works.
(v)	
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).
4	The offer of the tender shall remain valid upto 30 days after the opening.

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P

(451)

PERCENTAGE BILL OF QUANTITY

Estimated Cost: Rs. 99845/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Name of Work: Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace Road 9/00 to 22/200 (SH:- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc in Dhaliara Section) PDNA

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	24.56 Square metre	23.60	Rupees Twenty Three And Paise Sixty Only	Per square metre	580.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	90.00	Rupees Ninety Only	Per square metre	2153.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	75.64 Square metre	90.00	Rupees Ninety Only	Per square metre	6808.00
4	Writing letter in figures of any surface with black Japan Paint (stops, comas, hyphens and the like not to be measured and paid seprately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	21000.00 Per.Cm height per letter	2.95	Rupees Two And Paise Ninety Five Only	Per centimetre height per letter	61950.00
5	Painting index hands normal size or arrows(up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00 Figure	59.50	Rupees Fifty Nine And Paise Fifty Only	Per figure	16660.00
6	Finishing wall with water proofing cement paint of approved brand and manufacture (Nerolac Surksha/Apex exterior) and of approved shade on decorated wall surfaces (two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, other foreign matter and sand papered smooth including applying of putty as required for making the surface smooth complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	98.61 Square metre	70.00	Rupees Seventy Only	Per square metre	6903.00
7	White washing with lime on two coats on parapet walls and tree trunks including preparationof surface by cleaning scraping etc. as per technical specification clause 1915 complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	416.58 Square metre	11.50	Rupees Eleven And Paise Fifty Only	Per square metre	4791.00
	TOTAL					**99845.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Prosecute Bill & Quantity check & Approved for Rs 99845/-

Executive Engineer,
HPPWD Dehra ,
Division Dehra.

438

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99896.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Upper Pragpur to Karol via Dadari in Km 2/00 to 3/300 (SH:- Construction of Retaining wall at RD.3/225 to 3/237) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.56 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,192.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	20.88 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	84,564.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,500.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.52 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	8,640.00
	TOTAL					**99,896.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Below Quantity checked & approved

Executive Engineer,
Dehra Division,
HPPWD Dehra

437

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99896.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Upper Pragpur to Karol via Dadari in Km 2/00 to 3/300 (SH:- Construction of Retaining wall at RD.3/240 to 3/252) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.56 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,192.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	20.88 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	84,564.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,500.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.52 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	8,640.00
	TOTAL					**99,896.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BLUW quantity checked & approved by R [illegible]

Executive Engineer,
Dehra Division,
HPPWD Dehra

DC

436

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98,660.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Three Months.

Name of Work:- A/R & M/O to Non Residential Building at Hanuman Chowk Dehra Tehsil Dehra District Kangra (H.P) (SH:- Wood work,Conc. Work, Sanitary work etc).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	0.10 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	495.00
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in foundation and plinth above plinth level upto all floor level in cement mortar 1:4 (one cement isto four sand) and curing complete as per approved drawing, design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of Royality, Malkhana, Octroi, GST, Toll Tax, Sale tax or any other taxes imposed by the Government.	1.364 Cubic metre	7200.00	Rupees Seven Thousand Two Hundred Only	Per Cubic metre	9,821.00
3	Providing and fixing G.I.Pipes complete with GI fittings and clamps i/c cutting and making good the walls etc.complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	17.00 Running metre	290.00	Rupees Two Hundred Ninety Only		4,930.00
4	Providing and laying size of Tile 600x600 mm (Six hundred into Six hundred millimetre) vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (Twenty millimetre) thick cement mortar 1:4 (One cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etetera, complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royality, Malkhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government.	1.00 Square metre	1127.95	Rupees One Thousand One Hundred Twenty Seven And Paise Ninety Five Only	Per Square metre	1,128.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Providing and fixing 12mm (twelve milimetre) thick in wall lining flat pressed three layer (medium density) particle board or graded wood Prelaminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed arrangement and screws etc. complete :as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royality, Malkhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government.	0.54 Square metre	1154.00	Rupees One Thousand One Hundred Fifty Four Only	Per Square metre	623.00
6	Providing and fixing 18mm (Eighteen milimetre) thick in wall lining flat pressed three layer (medium density) particle board or graded wood Pre laminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed arrangement and screws etc. complete :as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royality, Malkhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government.	1.35 Square metre	1315.90	Rupees One Thousand Three Hundred Fifteen And Paise Ninety Only	Per Square metre	1,776.00
7	Providing and fixing 6mm (Six milimetre) plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in- charge (Frame work shall be paid for separately).complete :as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royality, Malkhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government.	3.24 Square metre	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	3,078.00
8	Providing and fixing PVC pipe complete with CPVC clamps including cutting and making good the walls 15mm (Fifteen millimetre) dia complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	16.10 Running metre	950.00	Rupees Nine Hundred Fifty Only	Per Running metre	15,295.00
9	Providing and fixing PVC Plastic /Rubber pipes complete with CPVC clamps including cutting and making good the walls 15mm (Fifteen millimetre) dia complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	57.00 Running metre	690.00	Rupees Six Hundred Ninety Only	Per Running metre	39,330.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
10	Providing and fixing IS:8931 PVC Plastic Tap standard design and of approved make conforming complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.00 Number	450.00	Rupees Four Hundred Fifty Only	Each	900.00
11	Providing and fixing PVC water storage tank of ISI marked G.I. inlet and outlet connection 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting upto all heights above ground level 1000 litres net capacity tankas per direction of 11 Engineer in Charge.including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royality, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government..	1.00 Number	10000.00	Rupees Ten Thousand Only	Each	10,000.00
12	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls complete, including painting of fittings and brackets, cutting and making good the wall wherever required of size 600x450x200mm (Six hundred into four hundred fifty into two hundred millimetre) etc. complete including carriage of material with in all leads, lifts and other incidentals The rate is including Sales tax, GST, Toll tax or any other taxes imposed by the Government.	1.00 Number	2257.60	Rupees Two Thousand Two Hundred Fifty Seven And Paise Sixty Only	Each	2,258.00
13	Providing and fixing anodized aluminium Handles ISI marked anodized(anodic coating not less then grade AC 10 as per IS 1868) transparent or dyed to required colour or 13 shade, with necessary screws etc complete transparent or dyed to required colour and shade with necessary screws etc completed complete as per drawing as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royality, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	2.00 Numbers	202.55	Rupees Two Hundred Two And Paise Fifty Five Only	Each	405.00
14	Providing and fixing G.I. Sockets 15mm dia complete as per drawing as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royality, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	9.00 Numbers	55.00	Rupees Fifty Five Only	Each	495.00
15	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, GST, Toll Tax Sale tax or any other taxes imposed by the Government.	2.00 Numbers	2643.00	Rupees Two Thousand Six Hundred Forty Three Only	Each	5,286.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
16	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	2.00 Numbers	1420.00	Rupees One Thousand Four Hundred Twenty Only	Each	2,840.00
	TOTAL					**98,660.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity Checked and approved for Rs. 98,660.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra.

(457)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.79604.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Months.

Name of work:- C/o Ambulance road from Bilan Bala Baba Mandir to Main road ward No.4 Post office Kherian GP Kherian Km. 0/00 to 0/300 (SH:- Providing and laying 80mm thick interlocking paver block at RD. 0/239 to 0/262.30)VKV/2025/425 Deposit

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	2.83 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	16,414.00
2	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 80mm (Eighty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	55.92 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	63,190.00
	TOTAL					**79,604.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill Quantity checked & approved for Rs 79604/-

Executive Engineer
Dehra Division
HPPWD Dehra (Kangra)

454

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.80090.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Months.

Name of work:- C/o Ambulance road from Bilan Bala Baba Mandir to Main road ward No.4 Post office Kherian GP Kherian Km. 0/00 to 0/300 (SH:- Providing and laying 80mm thick interlocking paver block at RD. 0/210 to 0/237.50)VKV/2025/425 Deposit

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	2.68 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	15,544.00
2	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 80mm (Eighty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	57.12 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	64,546.00
	TOTAL					**80,090.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill of quantity checked & approved for Rs 80090/-

Executive Engineer,
Dehra Division,
HPPWD Dehra

458

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.89614.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Two Months.

Name of work:- C/o Ambulance road from Bilan Bala Baba Mandir to Main road ward No.4 Post office Kherian GP Kherian Km. 0/00 to 0/300 (SH:- Providing and laying CCP at RD. 0/070 to 0/115)VKV/2025/425 Deposit

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.73 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,372.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	6.16 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	24,948.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix 1:1.5:3 (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.24 Cubic metre	6850.00		Per Cubic metre	63,294.00
	TOTAL					**89,614.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked
& approved for Rs 89614/-

Executive Engineer,
Dehra Division,
HPPWD Dehra

460

PERCENTAGE BILL OF QUANTITY

Estimated Cost: Rs. 99845/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Name of Work: Restoration of Rain Damages on Jawalmukhi Dehra Jawali Raja Ka talab road in km 22/000 to 39/180.(SH:-Painting & writing on bridges ,culverts , Providing & fixing precast Kilometer Stone). PDNA

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	667.86 Square metre	11.15	Rupees Eleven And Paise Fifteen Only	Per square metre	7447.00
2	Finishing walls with water proofing cement paint of required shade :Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litrs/10 sqm complete including cost of Priming coat.complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	667.86 Square metre	59.20	Rupees Fifty Nine And Paise Twenty Only	Per square metre	39537.00
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. including cost of Priming coat.complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	26.25 Square metre	110.05	Rupees One Hundred Ten And Paise Five Only	Per square metre	2889.00
4	Writing letter in figures of any surface with black Japan Paint (stops, comas, hyphens and the like not to be measured and paid seprately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, GST,sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2500.00 Per.Cm height per letter	2.65	Rupees Two And Paise Sixty Five Only	Per centimetre height per letter	6625.00
5	Providing and erecting reinforcement concrete mechanically mixed and vibrated Grade M-15 (M-fifteen), in ordinary kilometer stone (precast) of standed design as per IRC :8 fixing in position including painting and printing etcetera as per Drawing and MORD technical specification section 1700 including hauling of materials materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	7.00 Number	3571.50	Rupees Three Thousand Five Hundred Seventy One And Paise Fifty Only	Each	25001.00
6	Providing and erecting reinforcement concrete mechanically mixed and vibrated Grade M-15 (M-fifteen), in 200 mtr (two hundred metre) stone (precast) of standed design as per IRC :8 fixing in position including painting and printing etcetera as per Drawing and MORD technical specification section 1700 including hauling of materials materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	35.00 Number	500.00	Rupees Five Hundred Only	Each	17500.00
	TOTAL					**98999.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill Quantity Checked & appd for Rs 98999/-

Executive Engineer,
HPPWD Dehra ,
Division Dehra.