

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2025-26- 22232-66

Dated:- 20-02-2026.

To

✓ The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025-300858 dated 09-10-2025 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534



HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhama on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **28.02.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **27.02.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **26.02.2026 up to 4:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhama must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	A/R & M/O rest house building at Sunni Distt. Shimla H.P.(SH: C/O Porch at Rest house Sunni). (Roofing work thereof).	96768 /-	2000/-	One Month	Rs.350/-
2	A/R & M/O rest house building at Sunni Distt. Shimla H.P.(SH: C/O Porch at Rest house Sunni).	98650 /-	2000/-	One Month	Rs.350/-
3	A/R & M/O to various roads under Shoghi Sub Division (SH: Providing & Fixing of typical informatory boards and village board).	99400 /-	2000/-	15 days	Rs.350/-
4	R/R damages on Banuti Pahal road Km. 0/00 to 16/150 (SH: C/O R/Wall at Rds.0/217 to 0/222).	65177 /-	1000/-	One Month	Rs.350/-
5	A/R & M/O Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 10/795 to 10/799.30).	98325 /-	2000/-	One Month	Rs.350/-
6	A/R & M/O Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 10/840 to 10/844.30).	98427/-	2000/-	One Month	Rs.350/-
7	R/R damages on link road Hiranagar to Upperli Fatechi road Km. 0/00 to 0/780 (SH: C/O R-Wall at Rds. 0/496.30 to 0/499.60).	99603 /-	2000/-	One Month	Rs.350/-

8	C/O link road from Anandpur to Kahala Lohala road Km. 0/00 to 1/500 (SH: C/O R-Wall at Rds. 0/005.50 to 0/010).MMGSY	94604 /-	2000/-	One Month	Rs.350/-
9	C/O link road from Kufridhar to Shanol Km. 0/00 to 2/120 (SH: Formation Cutting in earth work in Km. 0/630 to 0/682).	99281 /-	2000/-	One Month	Rs.350/-
10	C/O link road from Kufridhar to Shanol Km. 0/00 to 2/120 (SH: Formation Cutting in earth work in Km. 1/720 to 1/915).	93092 /-	2000/-	One Month	Rs.350/-
11	A/R & M/O of link road to Village Khatmol Km. 5/500 to 10/000 (SH: Repair of earthen shoulder, Trimming of grass and clearing of drain in Km. 5/500 to 10/000).	96757 /-	2000/-	One Month	Rs.350/-
12	S/R of Health Sub Centre buiilding at Ogli Tehsil Sunni, Distt. Shimla H.P. (SH: C/O PCC Breast Wall) Balance work, Deposit Work.	97852 /-	2000/-	One Month	Rs.350/-
13	S/R of Health Sub Centre buiilding at Ogli Tehsil Sunni, Distt. Shimla H.P. (SH: C/O PCC Breast Wall and cement plaster work) Deposit Work.	98156 /-	2000/-	One Month	Rs.350/-
14	S/R to CHC building at Jalog Tehsil Sunni, Distt. Shimla H.P. (SH: C/O PCC Boundary Wall) Deposit Work.	99925 /-	2000/-	One Month	Rs.350/-
15	S/R to CHC building at Jalog Tehsil Sunni, Distt. Shimla H.P. (SH: C/O PCC Breast wall and Boundary Wall) Deposit Work.	99955 /-	2000/-	One Month	Rs.350/-
16	A/R & M/O Shoghi Salana Sari road Km. 0/00 to 12/200 (SH: Trimming of Grass between Km. 0/00 to 12/120).	99990 /-	2000/-	One Month	Rs.350/-
17	R/R damages on Anandpur to Tara Mata Mandir road Km. 0/00 to 2/200 (SH: C/O R/Wall at Rds. 2/110.50 to 2/116).	93584 /-	2000/-	One Month	Rs.350/-
18	A/R & M/O Hanuman Mandir to Trari road Km. 0/00 to 2/395 (SH: Providing correction with WBM G-III Km. 1/500 to 2/395).	99984 /-	2000/-	One Month	Rs.350/-
19	A/R & M/O Rest House at Tara Devi (SH: C/O Wire Crate for protection work on back side of rest house).	99706 /-	2000/-	One Month	Rs.350/-
20	A/R & M/O Rest House at Tara Devi (SH: C/O R/Wall on back side of Rest house building).	99458 /-	2000/-	One Month	Rs.350/-
21	A/R & M/O Shoghi Kanawan kanhechi to Ohri road Km. 0/00 to 14/200 (SH: Trimming of Grass between Rds. 0/00 to 12/120).	99990 /-	2000/-	One Month	Rs.350/-
22	A/R & M/O various roads under Shoghi Sub Division (SH: Trimming of Grass on Totu Taradevi bypass road between Km. 0/00 to 4/105, Trimming of Grass on Phayal Dawnti via Shamleeg road between Km. 0/00 to 4/135 & Trimming of Grass on Phayal Rampuri via Matholi road between Km. 0/00 to 3/880).	99990 /-	2000/-	One Month	Rs.350/-
23	A/R & M/O of PWD Rest house at Taradevi Distt. Shimla (SH: P/F tiles flooring, Walls & Sanitary fitting, etc. work in old VIP set).	98464 /-	2000/-	One Month	Rs.350/-
24	R/R damages on link road to village Dishti road Km. 0/00 to 3/00 (SH: C/O PCC R/Wall at Rds. 2/750 to 2/754).	98190 /-	2000/-	One Month	Rs.350/-
25	A/R & M/O Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O Catchpit a/w curtain wall at Rd. 0/075 and C/O V-shape drain Km. 0/00 to 0/075).	99686 /-	2000/-	One Month	Rs.350/-
26	C/O proposed link road Patyar Ghatru via Sitri Jayan Berti Nallah (0/00 to 3/600 Km.) under Dhami sub division HPPWD collecting data preparation of KML file, Digital Map with co-ordinates & SHP file i/c online submission of Forest case (SH: Preparation of FRA case in all respect).	70000 /-	1500/-	One Month	Rs.350/-
27	C/O proposed link road from Mandhorghat to Golan Km. 0/00 to 1/810 under Dhami sub division HPPWD (SH: Collecting data preparation of KML file, Digital Map with co-ordinates & SHP file i/c online submission of Forest case).	99000 /-	2000/-	One Month	Rs.350/-
28	A/R & M/O Rest house at Sunni Distt. Shimla H.P.(SH: Providing wood work and minor repair works thereof) Job I.	99787 /-	2000/-	One Month	Rs.350/-
29	A/R & M/O Shimla Mandi road Km. 39/200 to 52/200 (SH: Trimming of grass, Maintenance of earthen shoulders, Maintenance of drain, Maintenance of culvert & white washing in Km. 47/500 to 49/000).	99608 /-	2000/-	One Month	Rs.350/-
30	R/R damages on link road to village Neen Km. 0/00 to 2/000 (SH: C/O B/Wall at Rds. 0/242 to 0/257).	99815 /-	2000/-	One Month	Rs.350/-

31	A/R & M/O Rest house at Sunni Distt. Shimla H.P.(SH: Providing and Fixing sanitary works and minor repair works thereof) Job No.2.	99036 /-	2000/-	One Month	Rs.350/-
32	A/R & M/O various Jhullas over Satluj river at various locations in Sub-Tehsil Jalog, Distt. Shimla H.P. (SH: Thigtening of wire rope).	98020 /-	2000/-	One Month	Rs.350/-
33	A/R & M/O Bag to Kayalu road Km. 0/00 to 10/500 (SH: Construction and Maintenance of unlined drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance of Hume Pipe culvert in Km. 0/00 to 5/00).	99035 /-	2000/-	One Month	Rs.350/-
34	A/R & M/O Kadharghat to Palag Srikedi road Km. 0/00 to 7/00 (SH: Maintenance of drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance of Hume Pipe culvert in Km. 0/00 to 7/00).	99676 /-	2000/-	One Month	Rs.350/-
35	A/R & M/O Bathora to Panewat road Km. 0/00 to 3/500 (SH: Construction and Maintenance of unlined drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance of Hume Pipe culvert in Km. 0/00 to 3/500).	99607 /-	2000/-	One Month	Rs.350/-
36	A/R & M/O Slapper Tattapani Sunni Luhri road portion Km. 86/00 to 104/000 (SH: Maintenance of drain, Maintenance of berms/shoulders, Maintenance of Hume Pipe culvert in Km. 86/00 to 104/00).	99716 /-	2000/-	One Month	Rs.350/-
37	R/R damages on Hari Devi Seri Bhaloh road Km. 0/00 to 3/600 (SH: C/O R/Wall at Rds.1/330 to 1/335.75).	99248 /-	2000/-	One Month	Rs.350/-
38	S/R to Distt. Court Complex at Chakkar Distt. Shimla (SH: P/F Aluminium frame work at ADR centre & Block A of Distt. Court complex).	99682 /-	2000/-	One Month	Rs.350/-
39	R/R damages on Ghanahatti Kalihatti Arki road Km. 0/00 to 8/060 (SH: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catchpit/pot hole etc. in Km. 0/00 to 8/00).	98550 /-	2000/-	One Month	Rs.350/-
40	A/R & M/O on Shimla Mandi road Km. 39/200 to 52/200 (SH: Trimming of grass, Maintenance of earthen shoulder, Maintenance of drain, Maintenance of culvert & white washing in Km. 49/000 to 50/500).	99979 /-	2000/-	One Month	Rs.350/-
41	A/R & M/O Rest house at Taradevi (SH: C/O wire Crate for protection work on back side of rest house).	99185 /-	2000/-	One Month	Rs.350/-
42	R/R damages on Anandpur to Kot road Km. 0/00 to 8/00 (SH: Removal of slips at various Rds.) Job No. 2.	99898 /-	2000/-	One Month	Rs.350/-
43	R/R damages on Anandpur to Kot road Km. 0/00 to 8/00 (SH: Removal of slips at various Rds.) Job No. 1.	99294 /-	2000/-	One Month	Rs.350/-
44	R/R damages on Chauri Ki ghatti to Yan via Bhad road Km. 0/00 to 9/600 (SH: Removal of slips at various Rds.).	99814 /-	2000/-	One Month	Rs.350/-
45	A/R & M/O PWD Rest House at Taradevi (SH: Providing Furnishing items in HPPWD Rest House).	99450 /-	2000/-	One Month	Rs.350/-
46	R/R damages on Ambulance road Taradevi to Duggal Cottage road Km. 0/00 to 1/280 (SH: P/L Kharanja stone soling in various reaches).	99717 /-	2000/-	One Month	Rs.350/-
47	R/R damages on Dargi Macharyana Judloo road Km. 0/00 to 11/900 (SH: C/O R-Wall at Rds. 2/855 to 2/860.50).	99318/-	2000/-	One Month	Rs.350/-
48	A/R & M/O on Kadrain Nalawan road Km. 0/00 to 3/00 (SH: Curve cutting in various Rds. in Km. 2/500 to 3/00).	99973 /-	2000/-	One Month	Rs.350/-
49	A/R & M/O Dargi Macharyana Judloo road Km. 0/00 to 11/900 (SH: C/O R/Wall at Rd. 3/590 to 3/594).	99453/-	2000/-	One month	Rs.350/-
50	C/O link road from Mandhorghat to Mahila Mandal Bhawan Pipal Ka Ped Km. 0/00 to 0/630 (SH: Formation cutting in Km. 0/045 to 0/075, 0/150 to 0/180 and 0/255 to 0/300).	99339/-	2000/-	One month	Rs.350/-
51	R/R damages on Okhroo Nehra via Keru road Km. 0/00 to 2/000 (SH: Removal of slip in various Rds. between Km. 0/00 to 2/00C/O R/Wall at Rds. 1/167 to 1/170.80).	99834/-	2000/-	One Month	Rs.350/-
52	R/R damages on Hiranagar Sharog road Km. 0/00 to 5/00 (SH: C/O R-Wall at Rds. 0/692 to 0/693.50).	65323/-	1400/-	One Month	Rs.350/-
53	C/O Ambulance road to Uparli Fathachi Km. 0/00 to 0/750 (SH: C/O B/Wall at Rd. 0/736 to 0/739.50).	96835/-	2000/-	One Month	Rs.350/-

54	R/R damages on Banuti to Dayla road Km. 0/00 to 1/00 (SH: C/O wire crate wall at Rds. 0/985 to 1/000). Job No. IV.	99855/-	2000/-	One Month	Rs.350/-
55	A/R & M/O CHC Old & New building at Dhami, Distt. Shimla (SH: P/F scaffolding of bamboos for painting work on exterior walls upto all story height in CHC New building) Job No. IV.	94350/-	2000/-	One Month	Rs.350/-
56	R/R damages on Khairi Lohali road Km. 0/00 to 2/220 (SH: C/O R/Wall at Rds. 1/167 to 1/170.80).	98510/-	2000/-	One Month	Rs.350/-
57	A/R & M/O various roads under sub division Totu (SH: P/F of high intensity retro reflective alol weather multi colour taps/ sheets of approved shade on exsisting W-Metal Beam Crash Barriers).	98280/-	2000/-	One month	Rs.350/-
58	A/R & M/O Printing Press Building of Ghora Chowki Shimla (SH: Dismantling old sewerage line press colony and providing new Geverage line and Cerami Floor tiles in Block-A) Deposit Work.	79693/-	1600/-	One month	Rs.350/-
59	A/R & M/O of PWD Rest house at Taradevi Distt. Shimla (SH: P/F tiles flooring, Walls & Sanitary fitting, etc. work in Dinning hall old building).	99605 /-	2000/-	One Month	Rs.350/-
60	R/R damages on Hari Devi Seri Bhaloh road Km. 0/00 to 3/600 (SH: C/O R/Wall at Rds.1/336 to 1/341.75).	99248 /-	2000/-	One Month	Rs.350/-
61	R/R damages on Hiranagar Sharog road Km. 0/00 to 5/00 (SH: C/O R-Wall at Rds. 0/691 to 0/692).	88218/-	1800/-	One Month	Rs.350/-
62	R/R damages on link road to village Dishti road Km. 0/00 to 3/00 (SH: C/O PCC R/Wall at Rds. 2/754 to 2/758).	98156 /-	2000/-	One Month	Rs.350/-
63	A/R & M/O Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 10/800 to 10/804.30).	98376 /-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhami

Certificate

Certified that the tenders called vide this notice inviting tender for 63 (Sixty three) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhami.

Schedule Of Quantity						Estimated Cost:- 96,768.00	
Name Of Work :- A/R & M/O Rest House building at Sunni Distt. Shimla (HP) (SH:- Construction of Porch at Rest House Sunni) <i>for Roofing work thereat</i>						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing polycarbonatd tranparent sheet 5mm thick in roofing with galvanised J or L hooks bolts and nuts with G.I Limpe and bitumen rubber washer complete with all accessories as required as per direction of Engineer in Charge.	40.32	Sqm	2400.00	Rupees Two Thousand Four Hundred Only	Per Square metre	96768
Total Rs.							96768
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. *San*



Schedule Of Quantity						Estimated Cost:- 98,650.00	
Name Of Work :- A/R & M/O Rest House building at Sunni Distt. Shimla (HP) (SH:- Construction of Porch at Rest House Sunni)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	1.22	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	435
2	Providing and laying cement concrete 1:2:4 (one cement: two sand: four graded stone aggregate twenty millimetre nominal size) and curring complete excluding the cost of form work in foundation and plinth and curing complete mechanical mixed and vibrated for compacting reinforced concrete as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials ,labour ,tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	1.22	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per cubic metre	7808
3	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material in all leads and lifts as per direction of the Engineer in charge.	732.16	Kg.	123.48	Rupees One Hundred Twenty Three and Paise Forty Eight Only	Per Kilogram	90407
Total Rs.							98650
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.





Schedule of quantity.

Name of work A/R & M/O to various road under Sub Division Shoghi (SH: Providing and fixing of typical informatory boards and village board .

E/Cost 99400.00
E/Money 2000.00
Time 15 days

Sr. No	Description	Qty	Rates in	Unit	Amount
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over aluminum sheeting, 1.5 mm thick supported on a mild steel angle iron post 50 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification . board size 600mmx450mm Deprecation and palace sign with size 1 Direcation and pleace sign board (1200mm x900mm)	10	7000	each	70000
2	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over aluminum sheeting, 1.5 mm thick supported on a mild steel angle iron post 50 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification . board size 600mmx450mm Deprecation and palace sign with size 1 Village board 900x600	6	4900	each	29400
TOTAL					99400


ASSISTANT ENGINEER,
HPPWD, SUB-DIVISION,
SHOGHI


Executive Engineer
Shimla Sub-Division
H.P.P.W.D. Shimla



SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Banuti Pahal Road Km. 0/00 to 16/150 (Sh: Construction of Retaining wall at Rd. 0/217 to 0/222) Estimated Cost: - Rs 65177 /- only
 Earnest Money : - Rs. 1000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	2.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	630.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	4.05	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1444.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1 : 4 : 8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	13.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	59800.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8, (I) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.55	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2147.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge	6.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1156.00
0						Total:	65177.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall at Rd. 10/795 to 10/799.30)		Estimated Cost : - Rs 98325 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month				
S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.35 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1715.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.10 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2610.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v).20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	9.60 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1632.00
0					Total:	98325.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
100001, Shimla

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall at Rd. 10/840 to 10/844.30)				Estimated Cost: - Rs 98427 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month		
S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.35 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1715.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.10 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2610.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1734.00
0					Total:	98427.00

Amount Quoted by the Contractor in Percentage					Rs.
--	--	--	--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages Link Road Hiranagar to Upperli Fatechi Road Km. 0/00 to 0/780 (Sh: Construction of Retaining wall at Rd. 0/496.30 to 0/499.60)

Estimated Cost. - Rs 99603 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
				4	5		
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	4.75	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1109.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.54	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1975.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand. 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.05	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92230.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1292.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.56	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2997.00
0						Total:	99603.00

Amount Quoted by the Contractor in Percentage		Rs.
---	--	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule Of Quantity				Lehals		Estimated Cost:- 94,604.00	
Name Of Work :- Construction of Link road, from Anandpur to Kahala road km 0/00 to 1/500 (SH:- C/O R/wall at Rd 0/005.50 to 0/010) (mmgsy)						Earnest Money:- 2,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	3.52	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	822
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.72	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	2039
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14 8 (1 Cement 4 sand; 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	17.77	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	85296
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I Including carnage of material within all leads and lifts	4.95	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	4167
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	12.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	2280
Total Rs.							94604
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhara

SCHEDULE OF QUANTITY

Name of Work: - Construction of Link Road from Kufridhar to Shanol Km. 0/00 to 2/120 (Sh: Formation Cutting in earth work in Km. 0/630 to 0/682)

Estimated Cost: - Rs 99281 /- only

Earnest Money : - Rs. 2000 /-only

Time- One Month

S.No.	Sub head and items of work	Qty.		Rate	Unit	Amount	
1	2	3	In figure	In words	6	7	
1	<p>Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 21.27 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreases in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.</p>	425.37	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	99281.00
						Total:	99281.00
Amount Quoted by the Contractor in Percentage							

Executive Engineer,
 Shimla Rural Division,
 HPPWD Dhami

SCHEDULE OF QUANTITY

Name of Work: - Construction of Link Road from Kufridhar to Shanol Km. 0/00 to 2/120 (Sh: Formation Cutting in earth work in Km. 1/720 to 1/915)						Estimated Cost: - Rs 93092 /- only	
						Earnest Money : - Rs. 2000 /-only	
						Time- One Month	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 19.94 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreases in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	398.85	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	93092.00
						Total:	93092.00
Amount Quoted by the Contractor in Percentage							

Executive Engineer,
Shimla Rural Division,
HPPWD Dhami

ET

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Link Road to village Khatnol Km.5/500 to 10/00 (Sh: Repair of Earthen shoulder, i. ! trimming of grass and clearing of drain in Km. 5/500 to 10/000)

Estimated Cost: - Rs 96757 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	1500.00 Sqm	16.50	Rupees Sixteen and Paise Fifty Only	Per Square Meter	24750.00
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	3000.00 Rmt.	4.00	Rupees Four Only	Per Running Meter	12000.00
3	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	15000.00 Sqm	4.00	Rupees Four Only	Per Square Meter	60000.00
0					Total:	96750.00

ct	Amount Quoted by the Contractor in Percentage	Rs.
----	---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami



Schedule Of Quantity						Estimated Cost:- 97,852.00	
Name Of Work :- Repair & Up-gradation of Health Sub Centre Building at Ogli Tehsil Sunni, Distt. Shimla, HP(SH:- C/o PCC Breast Wall) Deposit Work						Earnest Money:- 2,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:3.6 nominal mix (1 Cement 3 sand 6 graded crushed stone aggregate 20mm nominal size).	18.29	Cum	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per Cubic metre	97852
Total Rs.							97853
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dharti



Schedule Of Quantity						Estimated Cost:- 98,156.00	
Name Of Work :- Special Repair & Up-gradation of Health Sub Centre Building at Ogli , Tehsil Sunni, Distt Shimla, HP. (SH:- C/O PCC Breast wall and cement plaster work) Desposit Work						Earnest Money:- 2,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	7.27	Cum	191.39	Rupees One Hundred Ninety One and Paise Thirty Nine Only	Per Cubic metre	1391
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in Charge	10.92	Cum	292.33	Rupees Two Hundred Ninety Two and Paise Thirty Three Only	Per Cubic metre	3192
3	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge (i) Cement Concrete 1:3:6 nominal mix (1 Cement 3 sand 6 graded crushed stone aggregate 20mm nominal size)	16.14	Cum	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per Cubic metre	86349
4	20 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement 4 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	24.00	Sqm	301.00	Rupees Three Hundred One Only	Per Square metre	7224
Total Rs.							98156
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm.



Schedule Of Quantity						Estimated Cost:- 99,925.00	
Name Of Work :- S/R to CHC building at Jalog , Tehsil Sunni Distt Shimla HP (SH:- C/O PCC Work Boundary Wall) Deposit Work						Earnest Money:- 2,000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:3:6 nominal mix (1 Cement 3 sand 6 graded crushed stone aggregate 20mm nominal size)	8.85	Cum	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per Cubic metre	48233
2	15 mm cement plaster on the rough side of single or half brick wall of mix 1:5 (1 cement 5 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	124.56	Sqm	295.00	Rupees Two Hundred Ninety Five Only	Per Square metre	36745
3	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty as required for metting the surface	124.56	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square metre	14947
Total Rs.							99925
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhams



Schedule Of Quantity						Estimated Cost:- 99,955.00	
Name Of Work :- S/R to CHC building at Jalog , Tehsil Sunni Distt Shimla HP						Earnest Money:- 2,000.00	
(SH:- C/O PCC Breast wall and Boundary Wall) Deposit Work						Time:- One Month.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	2			In figures	In words	7	8
1	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 502, 503, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:3:6 nominal mix (1 Cement:3 sand :6 graded crushed stone aggregate 20mm nominal size).	17.03	Cum	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per Cubic metre	92814
2	12 mm cement plaster on the rough side of single or half brick wall of max. 1:3 cement :3 fine sand complete including carriage of material in all beds and lifts as per direction of the Engineer in Charge.	14.80	Sqm	295.00	Rupees Two Hundred Ninety Five Only	Per Square metre	4366
3	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete stone plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for mending the surface.	14.80	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square metre	1776
4	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.	4.44	Sqm	225.00	Rupees Two Hundred Twenty Five Only	Per Square metre	999
Total Rs.							99955
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharami.



Schedule Of Quantity

Name of work:- A/R & M/O Shoghi Salana Sari road km 0/00 to 12/200. (SH:-Trimming of Grass between RD 0/00 to 12/120.)

Estimated Cost:-99,990.00

Earnest Money:- 2,000.00

Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of Grass and weeds from the shoulders/berms and disposing of the same to the suitable locations as per technical specifications Clause 1914 including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	18180.00	Cum	5.50	Rupees five and paise fifty only	Per square metre	99990.00
						Total:-	99990.00
Amount Quoted by the Conctrator in percentage		Rs.					
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami



Schedule of Quantity

Name of work: R/R Damages on Ananadpur to Tara Mata Mandir km 0/000 to 2/200. Estimated Cost: 93,584/- only
 (SH : C/O R/wall at RD 2/110.50 to 2/116). Earnest Money: 2000/-only.
 Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer -in- Charge	3.52	Per Cum	233.40	Two hundred thirty three rupee forty Paise only	Per Cum	822.00
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of side and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer -in- Charge	5.72	Per Cum	356.50	Three hundred fifty six rupees fifty paise only	Per Cum	2039.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	17.77	Per Cum	4800.00	Four thousand eight Hundred rupees only	Per Cum	85296.00
4	Back filling behind Abutment wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	4.95	Per Cum	841.80	Eight hundred forty one rupees eighty paise only	Per Cum	4147.00
5	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift	7.00	No	180.00	One hundred eighty rupees only	Each	1260.00
						Total	93584.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhanni

Schedule Of Quantity

Name of work:- A/R & M/O Hanuman Mandir to Trari road Km 0/00 to 2/395. (SH: Providing correction with WBM G-III in Km 1/500 to 2/395)

Estimated Cost:-99,984.00

Earnest Money:- 2,000.00

Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading -III as per Technical Specification Clause 405. By Mechanical means.	44.44	Cum	2250.00	Rupees twenty two hundred and fifty only.	Per cubic metre	99984.00
						Total:-	99984.00
Amount Quoted by the Conctrator in percentage		Rs.					
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam



Schedule Of Quantity

Name of work:- A/R & M/O Rest House at Tara Devi. (SH: C/O Wire Crate for protection work on back side of rest house.)

Estimated Cost:-99,706.00

Earnest Money:- 2,000.00

Time:- One Month.


S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 1/c setting out.construction of shoring and bracing removal of stums and other deleterious materials and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in tranches with excavated suitable material.	3.68	Cum	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	1312.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia. G.I wire conforming to IS:280 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10% extra for laps and joint laid with stone boulder weighing not less than 25 kg each as per drawing and technical specification clause 1301	30.63	Cum	3212.35	Rupees three thousand two hundred twelve and paise thirty five only	Per cubic metre	98594.00
Amount Quoted by the Conctrator in percentage						Total:-	99706.00
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.		Rs.					

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharami.



Schedule Of Quantity

Name of work:- A/R & M/O Rest House at Tara Devi. (SH:- C/O R/wall on back side of rest house building.)						Estimated Cost:-99458.00	
						Earnest Money:- 2000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Earthwork in excavation in hilly area by manual/mechanical means i/c cutting and trimming and side slope for structures as per drawing and technical specification clause 305.1 and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	4.07	Cum	233.40	Rupees Two hundred thirty three and Paise forty only	Per cubic metre	949.00
2	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	4.94	cum	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	1761.00
3	Providing and laying Plain cement concrete 1:4:8(one cement isto four sand isto eight graded crushed stone aggregate 20 milimetre(twenty milimetre) nominal size for plain /reinforced concrete in open foundation and plinths or similar works complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	18.716	Cum	4800.00	Rupees Four thousand six hundred only	Per cubic metre	89839.00
4	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	4.23	Cum	841.80	Rupees Eight hundred forty one and eighty Paise only	Per cubic metre	3561.00
5	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	18.60	Rmt	180.00	Rupees One hundred eighty only	Per running metre	3348.00
						Total:-	99458.00
Amount Quoted by the Conctrator in percentage						Rs.	
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							


Executive Engineer,
Shimla Rural Division,
HPPWD, Dhana

Schedule Of Quantity


**Name of work:- A/R & M/O Shoghi Kanawan Kanhechi to Ohri road km 0/00 to 14/200. (SH:-
Trimming of Grass between RD 0/00 to 12/120.)**

Estimated Cost:-99,990.00

Earnest Money:- 2,000.00

Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of Grass and weeds from the shoulders/berms and disposing of the same to the suitable locations as per technical specifications Clause 1914 including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	18180.00	Cum	5.50	Rupees five and paise fifty only	Per square metre	99990.00
						Total:-	99990.00
	Amount Quoted by the Conctrator in percentage	Rs.					
	Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.						


Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam.



Schedule Of Quantity

Name of work:- A/R & M/O various roads under Shoghi sub division. (SH:-Trimming of Grass on Totu Taradevi bypass road between Km 0/00 to 4/105, Trimming of Grass on Phayal Dawnti via Shamleeg road between Km 0/00 to 4/135 & Trimming of Grass on Phayal Rampuri via Matholi road between Km 0/00 to 3/880.)

Estimated Cost:-99,990.00

Earnest Money:- 2,000.00

Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of Grass and weeds from the shoulders/berms and disposing of the same to the suitable locations as per technical specifications Clause 1914 including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	18180.00	Cum	5.50	Rupees five and paise fifty only	Per square metre	99990.00
						Total:-	99990.00
Amount Quoted by the Conctrator in percentage		Rs.					
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi.



SCHEDULE OF QUANTITY


Name of Work:- Annual Repair & Maintenance of PWD Rest House at Tara Devi District Shimla H.P. (SH: Providing and fixing tiles flooring,Walls & Sanitary fitting, etc work in Old VIP Set)				Estimated Cost: - Rs 98464 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month			
S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
				4	5		
1	2	3		4	5	6	7
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. complete including carriage of materials within all leads and lifts as per the direction of Engineer in Charge. For thickness of tiles 10 mm to 25 mm	20.16	Sqm	31.20	Rupees Thirty One and Paise Twenty Only	Per Square Metre	629.00
2	P/F Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete. including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	5.00	Sqm	1354.00	Rupees One Thousand Three Hundred Fifty Four Only	Per Square Metre	6770.00
3	P/F 1st quality ceramic glazed wall tiles conforming to IS 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps & dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) & jointing with grey cement slurry @3.3kg/sqm including pointing in white cement mixed with pigment of matching shade complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	20.16	No.	1447.00	Rupees One Thousand Four Hundred Forty Seven Only	Per Square Metre	29172.00
4	Providing and fixing one piece white vitreous china pedestal type water closet (European type W.C pan) No. 92657 (S-220) with seat and lid, 10 litre low level dual flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of material upto all leads and lifts as per the direction of Engineer in Charge : Size 620x370x745mm	1.00	No.	15639.00	Rupees Fifteen Thousand Six Hundred Thirty Nine Only	Each	15639.00
6	Providing and fixing C.P. Brass Jet of Hindware Cat No. F-160193 with 1.2 metre long to European type W.C. of quality and make as approved by Engineer - in - charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	1104.00	Rupees One Thousand One Hundred Four Only	Each	1104.00
7	Providing and fixing white vitreous china wash basin size 55x40x83cm cat. No. 10008 VIKING with Pedestal No. 11003 of Hindware including making all connections including the cost of all fittings including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	3973.00	Rupees Three Thousand Nine Hundred Seventy Three Only	Each	3973.00
8	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour. Waste coupling 31 mm dia of 79 mm length and 62mm breadth weighing not less than 45 gms including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	534.00	Rupees Five Hundred Thirty Four Only	Each	534.00
9	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. Semi rigid pipe 32 mm dia	1.00	No.	592.00	Rupees Five Hundred Ninety Two Only	Each	592.00

10	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :-15 mm nominal bore with 45cm length.	5.00	No.	259.00	Rupees Two Hundred Fifty Nine Only	Each	1295.00
11	Providing and fixing C.P brass soap dish Hindware cat. No. F580004 with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	1102.00	Rupees One Thousand One Hundred Two Only	Each	2204.00
12	Providing & fixing 125mm dia C.P/ S.S grating for floor of approved quality and colour. Square type including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	420.00	Rupees Four Hundred Twenty Only	Each	840.00
13	P/F 600x450mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	2121.00	Rupees Two Thousand One Hundred Twenty One Only	Each	2121.00
14	Providing and fixing 46 x 13cm Acrylic/glass shelf of JAL Cat. No. 36552 with edges round off, complete including all fitting & fixtures and carriage of material within all leads and lifts as per direction of the Engineer in Charge.	1.00	No.	2203.00	Rupees Two Thousand Two Hundred Three Only	Each	2203.00
15	Providing and fixing C.P. brass toilet paper holder of Hindware Cat. No. F102009 including the cost of fittings complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	No.	1182.00	Rupees One Thousand One Hundred Eighty Two Only	Each	1182.00
16	Providing and fixing 600mm size C.P. brass/S.S towel Rod Hindware cat. No. F102012 (heavy duty ISI marked IS:8931 & 8934) complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	1210.00	Rupees One Thousand Two Hundred Ten Only	Each	1210.00
17	P/F high pressure PVC spigot & socket, waste and ventilating pipe ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i) 110 mm dia	10.00	Rmt	1087.00	Rupees One Thousand Eighty Seven Only	Per Running Meter	10870.00
18	Providing and fixing (Finolex) PVC floor traps ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts:-110mm x 90mm	2.00	No.	408.00	Rupees Four Hundred Eight Only	Each	816.00
19	P/F PVC plain bend ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i) 110 mm dia	4.00	No.	248.00	Rupees Two Hundred Forty Eight Only	Each	992.00
20	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts:- 110MM Dia	2.00	No.	268.00	Rupees Two Hundred Sixty Eight Only	Each	536.00
21	P/F C.P. brass bib cock with wall flange Hindware cat. No.F690004 of approved quality conforming to IS standards & weighing not less than 690 gms including carriage of material upto all leads and lifts as per the direction of Engineer in Charge : 15 mm nominal bore	1.00	No.	1122.00	Rupees One Thousand One Hundred Twenty Two Only	Each	1122.00
22	Providing and fixing 15mm dia C.P. brass Angle Stop Cock with flange of Hindware Cat. No. F690043 (heavy duty ISI marked IS:8931 & 8934) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	5.00	No.	950.00	Rupees Nine Hundred Fifty Only	Each	4750.00

23	P/F C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931, 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	4008.00	Rupees Four Thousand Eight Only	Each	4008.00
24	Providing and fixing CP Brass Single lever wall mixer of quality & make as approved by Engineer in charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (a) 15 mm nominal dia	1.00	No.	5902.00	Rupees Five Thousand Nine Hundred Two Only	Each	5902.00
0						Total:	98464.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi



SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Link road to village Dishti Road Km. 0/00 to 3/00 (Sh: Construction of PCC R-wall at Rd. 2/750 to 2/754) Estimated Cost: - Rs 98190 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.68 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	626.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	4.16 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1483.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.68 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	85928.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	5.76 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4849.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	31.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	5304.00
0					Total:	98190.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

Schedule Of Quantity

Name of work:- A/R & M/O Shoghi Mehli road km 0/00 to 12/375. (SH:- C/O catchpit a/w curtain wall at RD km 0/075 and C/O V-shape drain b/w Km 0/00 to 0/075.)

Estimated Cost:-99,686.00

Earnest Money:- 2000.00

Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.03	cum	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	3576.00
2	Providing and laying Plain cement concrete 1:3:6 (one cement isto four sand isto six graded crushed stone aggregate 20 milimetre(twenty milimetre) nominal size for plain /reinforced concrete in open foundation and plinths or similar works complete as per drawings and technical specifications MORD clause 802.803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	17.70	Cum	5300.00	Rupees Five thousand three hundred only	Per cubic metre	93810.00
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	20.00	Sqm	115.00	Rupees One hundred fifteen only	Per square metre	2300.00
						Total:-	99686.00
Amount Quoted by the Conctrator in percentage		Rs.					
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural-Division,
HPPWD, Dhamsi.



SCHEDULE OF QUANTITY

Name of Work: - Construction of Proposed link road Patyar Ghatru via Sitri Jayan Berti Nallah (0/00 to 3/600 Km.) under Dhamsi Sub Division HPPWD Collecting Data Preparation of KML file, Digital Map with co-ordinates & SHP file i/c online submission of Forest case. (SH: -Preparation of FRA case in all respect)					Estimated Cost: - Rs 70000/- only	
					Earnest Money : - Rs. 1500/-only	
					Time: -	One Month
S. No.	Sub head and items of work	Qty.	Rate in		Unit	Amount
			figures	In words		
1	2	3	4	5	6	7
1	Preparation of Geo refrence digital map and Collecting the data from proposed site including field visits Preparation of Kml file, Geo coordinates along with making of Habitations to be benefited by construction of project and dumping area of proposed site. Making The alignment in soft copy and submission in hard copy.Preperation of Forest case(FRA) proposed road in Dhamsi Sub Division.Preperation of Folders complete in all respect and submit to the department as per the direction of Engineer- in- charge.	1 No.	70000.00	Rupees Seventy Thousand Only	Each	70000.00
					Total:	70000.00

Amount Quoted by the Contractor in precentage Rs.


 EXECUTIVE ENGINEER
 SHIMLA RURAL DIVISION
 HPPWD, DHAMI

SCHEDULE OF QUANTITY

Name of Work: - Construction of Proposed link road from Mandhorghat to Golan KM 0/0 to 1/810. under Dhami Sub Division HPPWD (SH:- Collecting Data Preparation of KML file, Digital Map with co-ordinates & SHP file i/c online submission of Forest case).					Estimated Cost: - Rs 99000/- only		
					Earnest Money : - Rs. 2000/-only		
					Time: -	One Month	
S. No.	Sub head and items of work	Qty.		Rate in		Unit	Amount
				figures	In words		
1	2	3	4	5	6	7	
1	Preperaton of Forest case Proposed road in Dhami sub division under the shimla rural Division HP.PWD Shimla Preperation of 5 Sets of FCA Check list in hard copy Online submission of forest case with scanning of all papers and converting the same into PDF files as per requirement for online submission and monitoring and one time resubmission of case as per the direction of Engineer- in- charge.Collecting the data from site Preparation of Kml file, Digital map with coordinates ,Toposheet and Shp file as per the FCA Guide line of MOEF hard copy and soft copy including fild visits as per the direction of engineer-in-charge	1	No.	99000.00	Rupees Ninety Nine Thousand Only	Each	99000.00
						Total:	99000.00

Amount Quoted by the Contractor in precentage	Rs.
---	-----

EXECUTIVE ENGINEER
SHIMLA RURAL DIVISION
HPPWD, DHAMI

Schedule of Quantity

Name of Work : A/R & M/O HPPWD Rest House at Sunni Shimla HP. (SH : Providing wood work and minor repair works thereof)(Job-I)					Estimated Cost:	99787.00	/- only
					Earnest Money:	1996.00	/- only
					Time: - One month		
S. No	Description of Work	Nos of Qty		Rate	Unit	Amount	
1	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead : Of sectional area 40 square centimetres and above	0.31	Cum	3299.00	Three thousand two hundred ninety nine rupees only	Per cubic meter	1036.00
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :Of area beyond 3 sq. metres	9.12	Sqm	346.00	Three hundred forty six rupees only	Per Square meter	3156.00
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.31	Cum	142230.00	One Lakh forty two thousand two hundred thirty rupees only	Per cubic meter	44669.00
4	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately)2nd class deodar wood	9.12	Sqm	3817.00	Three thousand eight hundred seventeen only	Per Square meter	34811.00
5	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm. for doors, windows and clerestory windows with hinges and necessary screws including all leads and lifts and as directed by theEngineer-in-Charge.	3.66	Sqm	4403.00	Four thousand four hundred three rupess only	Per Square meter	16115.00
						Total	99787.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor himself							

Executive Engineer
Shimla Rural Division
HP.PWD, Dhisai



SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Shimla Mandi Road km 39/200 to 52/200 (SH:- Trimming of grass , Maintenance of Eathen Shoulders , Maintenance of drain ,Maintenance of Culverts & white Washing in Km 47/500 to 49/000						Estimated cost:-	99,608.00
						Earnest money:-	2000.00
						Time:-	One Month
Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.	
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2925	Per Sqm	4.50	Rupees Four and Paise Fifty Only	13163.00	
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3000	Per Sqm	24.95	Rupees Twenty Four and Paise Ninety Five Only	74850.00	
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	1200	Rmt	4.50	Rupees Four and Paise Fifty Only	5400.00	
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only	5250.00	
5	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge.	27	Per Sqm	35.00	Rupees Thirty Five Only	945.00	
						Total:-	99608.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self and bills will be submitted							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhansi



Schedule Of Quantity						Estimated Cost:- 99,815.00	
Name of Work :- R/R damages on link road to Neen km 0/00 to 2/000 (SH:- C/O B/wall at RD 0/242 to 0/257)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	29.66	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6923
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	3.67	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1308
3	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.56	Cum	2650.00	Rupees Two Thousand Six Hundred Fifty Only	Per cubic metre	91584
Total Rs.							99815
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharti



Schedule of Quantity

Name of Work : A/R & M/O HPPWD Rest House at Sunni Shimla HP. (SH : Providing and fixing sanitary works & minor repair works thereof (Job-II)								Estimated Cost:	99036.00	/- only
								Earnest Money:	1981.00	/- only
								Time: - One month		
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount			
		3	4	In Figure	In word			5	6	7
1	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm. for doors, windows and clerestory windows with hinges and necessary screws including all leads and lifts and as directed by the Engineer-in-Charge.	5.46	Sqm	4403.00	Four thousand four hundred three rupees only	Per square meter	24040.00			
1	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	36.48	Sqm	139.00	One hundred thirty nine rupees only	Per Square meter	5071.00			
2	Providing and fixing aluminium sliding door bolts. ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868). transparent or dyed to required colour or shade. with nuts and screws etc. complete :300x16 mm as per the directions of Engineer-in-Charge including carriage of materials with in all leads. lifts and other incidentals .	8.00	Nos.	322.00	Three hundred twenty two rupees only	Nos.	2576.00			
3	Providing and fixing aluminium tower bolts. ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. as per the directions of Engineer-in-Charge including carriage of materials with in all leads. lifts and other incidentals . 200x10mm (Two hundred x ten millimeter)	32.00	Nos.	110.00	One hundred ten rupees only	Nos.	3520.00			
4	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete as per the directions of Engineer-in-Charge including carriage of materials with in all leads. lifts and other incidentals.	24.00	Nos.	69.00	Sixty nine rupees only	Nos.	1656.00			
5	Providing and fixing 100mm (One hundred millimeter) bright finished brass floor door stopper with rubber cushion screws etc. to suit shutter thickness complete as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	6.00	Nos.	249.00	Two hundred forty nine rupees only	Nos.	1494.00			
6	Providing and fixing 10.00 ltr. (ten litre) capacity PVC low level flushing cistern Hind ware sleek ultra design No 186575 size 42 X 39 X 14 cm (forty two into thirty nine into fourteen centimetre) or equivalent with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float,with push button,couplings for connections with inlet, outlet and overflow pipe. 40mm (forty millimetre) dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carriage of materials within all leads and lifts :-	2.00	No.	2204.00	Two thousand Two hundred four rupees only	No.	4408.00			
7	Providing and fixing 15 mm (Fifteen millimetre) dia C.P. Brass pillar tap with Capstan head 15 mm dia of Jaguar as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. .	6.00	No.	586.00	Five hundred eighty six rupees only	No.	3516.00			

9	Providing and fixing 15 mm (Fifteen millimetre) dia C.P. Brass angle cock as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. .	6.00	No.	447.00	Four hundred forty seven rupees only	No.	2682.00
10	Providing and fixing finishing bright finished or/and black enamelled iron (Helical door spring 150mm)	5.00	No.	164.00	One hundred sixty four rupees only	No.	820.00
11	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm. 78 mm wide and effective height of 88 mm, weighing not less than 170 gms	4.00	No.	607.00	Six hundred seven rupees only	No.	2428.00
12	Providing and fixing wooden plank ceiling with tongued and grooved jointing and wood screws (frame work and cover fillets to be measured and paid for separately) 1st class deodar wood	1.43	Sqm	2546.00	Two thousand five hundred forty six rupees only	Per Square meter	3641.00
13	Polishing two coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler.	1.43	Sqm	186.00	One hundred fifty three rupees only	Per Square meter	266.00
14	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	83.70	Kg	118.00	One hundred eighteen rupees only	Per Kilogram	9877.00
15	Providing and fixing one hole basin mixing faucet :	4.00	Each	3066.00	Three thousand sixty six rupees only	Each	12264.00
16	Providing and fixing mixer for kitchen sink with easted bottom swinging spout at top. .	1.00	Each	3917.00	Three thousand nine hundred seventeen rupees only	Each	3917.00
17	Providing and fixing wall mixing faucet for shower and bath hand shower with angular and rest holder.	4.00	Each	4215.00	Four thousand two hundred fifteen rupees only	Each	16860.00
					Total		99036.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor himself							

Executive Engineer
Shimla Rural Division
HP.P.W.D., Dhara



Schedule Of Quantity						Estimated Cost:- 98,020.00	
Name Of Work :- A/R & M/O Various Jhullas over Satluj river at various locations in Sub-Tehsil Jalog, Distt. SHimla HP (SH:- Tightening of wire rope)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Tightening of wire rope of Jhulla by using Chain and Pulley System including providing and fixing steel accessories like U-bolts, Clamps, suspenders & rope grips, also providing & applying grease and including carriage of materials, labour, tool & plant with in all leads and lifts as per direction of Engineer-in-Charge	5.00	Nos	19604.00	Rupees Nineteen Thousand Six Hundred Four Only	Per Cubic metre	98020
Total Rs.							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dikari



Schedule of Quantity


Name of Work :- A/R & M/O Bag to Kayalu road Km 0/00 to 10/500 (SH: Construction and Maintenance of unlined drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance Of Hume Pipe Culvert in Km 0/00 to 5/000) Estimated Cost:- 99035.00 Only.
 Earnest Money: 2000.00 Only.
 Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2			5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2100.00	Rmt	4.00	Rupees Four Only	Rmt	8400.00
2	Trimmmg ot grass and weeds from the shoulders/berms and disposing offthe same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2355.00	Sqm	4.00	Rupees Four Only	Sqm	9420.00
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2677.50	Sqm	16.00	Rupees Sixteen Only	Sqm	42840.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	5.00	Nos.	1600.00	Rupees One Thousand Six Hundred Only	Nos.	8000.00
5	Construction of unlined surface drain of average cross sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and technical specification clause 307. Excavated material to be used in embankment at site.	405.00	Rmt.	75.00	Rupees Sventy Five Only	Rmt.	30375.00
						Total	99035.00
Amount procured by the contractor in percentage		Rs.					
Conditions:- All the Machinerries/materials will be procured by the contractor himself and bills will be submitted							

Executive Engineer
 Shimla Rural Division
 HPPWD Dhami

Schedule of Quantity

Name of work - A/R & M/O Kadharghat to palag serikedi Km 0/00 to 7/00 (SH: Maintenance of drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance Of Hume Pipe Culvert in Km 0/00 TO 7/00)					Estimated Cost:- 99676.00 Only.		
					Earnest Money: 2000.00 Only.		
					Time: - One month		
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2325.00	Rmt	4.00	Rupees Four Only	Rmt	9300.00
2	Trimmmg ot grass and weeds from the shoulders/berms and disposing offthe same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	3816.00	Sqm	4.00	Rupees Four Only	Sqm	15264.00
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	3094.50	Sqm	16.00	Rupees Sixteen Only	Sqm	49512.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	16.00	Nos.	1600.00	Rupees One Thousand Six Hundred Only	Nos.	25600.00
					Total		99676.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machinerries/materials will be procured by the contractor himself and bills will be submitted						


 Executive Engineer
 Shimla Rural Division
 HPPWD Dhanji

Schedule of Quantity

Name of Work :- A/R & M/O Bathora to Panewat road km 0/00 to 3/500 (SH: Construction and Maintenance of unlined drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance Of Hume Pipe Culvert in Km 0/00 to 3/500)

Estimated Cost:- 99607.00 Only.
Earnest Money: 2000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge..	1830.00	Rmt.	4.00	Rupees Four Only	Rmt.	7320.00
2	Trimmmg ot grass and weeds from the shoulders/berms and disposing ofthe same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1461.00	Sqm	4.00	Rupees Four Only	Sqm	5844.00
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2523.00	Sqm	16.00	Rupees Sixteen Only	Sqm	40368.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	7.00	Nos.	1600.00	Rupees One Thousand Six Hundred Only	Nos.	11200.00
5	Construction of unlined surface drain of average cross sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and technical specification clause 307. Excavated material to be used in embankment at site.	465.00	Rmt.	75.00	Rupees Sventy Five Only	Rmt.	34875.00
					Total		99607.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineris/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
 Shimla Rural Division
 HPPWD Dhara

Schedule of Quantity

Name of Work : A/R & M/O Slapper Tattapani Sunni Luhri road portion Km 86/00 to 104/000 (SH: Maintenance of drain, Maintenance of berms/shoulders, Maintenance of Hume Pipe Culvert in between Km 86/00 to 104/000) Estimated Cost:- 99716.00 Only.
 Earnest Money: 2000.00 Only.
 Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
				5	6		
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	4935.00	Rmt	4.00	Rupees Four Only	Rmt	19740.00
2	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	3598.50	Sqm	16.00	Rupees Sixteen Only	Sqm	57576.00
3	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	14.00	Nos.	1600.00	Rupees One Thousand Six Hundred Only	Nos.	22400.00
					Total		99716.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
 Shimla Rural Division
 HPPWD Dhansi

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hari Devi Seri Bhaloh Road In km. 0/00 to 3/600 (Sh: Construction of R-wall at Rd. 1/330 to 1/335.75)

Estimated Cost: - Rs 99248 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.99 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	698.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.84 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2438.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.78 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90988.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.31 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3628.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.80 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1496.00
0					Total:	99248.00

Rs. _____

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 99682.00
 Earnest Money Rs. :- 2000.00
 Time:- One Month.

S/R to District Court Complex at Chakker Distt. Shmls. (S.H. providing & fixing aluminium frame work at ADR Centre & Block-A of District Court Complex).

S.No.	Items of work	Quantity		Rate		Unit	Amount
		3	4	5	6 in words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 microns) including carriage of material within all leads and lifts.	45.03	Kg	680.00	Rupees Six Hundred Eighty Only	Per/Kilogram me	30620.00
2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts.	50.92	Kg	690.00	Rupees Six Hundred Ninety Only	Per/Kilogram me	35135.00
3	Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.50 mm dia. wire and 1.4mm wide aperture with matching wood beading.including carriage of material within all leads and lifts.	1.78	Sqm	550.00	Rupees Five Hundred Fifty Only	Per square metre	979.00
4	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	8.05	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	10868.00



5	Providing & fixing 4 mm thick laminated Aluminium Composite Panell (ACP SHEETS) in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge.	4.35	Sqm	2200.00	Rupees Two Thousand Two Hundred Only	Per square metre	9570.00
6	Providing and fixing bright finished Godrej make hydraulic door closer of Godrej make or equivalent with screws etc. complete including carriage of materials in all leads and lifts.	3.00	No	2500.00	Rupees Two Thousand Five Hundred Only	Each	7500.00
7	Providing and fixing 100x58x1.90 mm size M.S. pressed butt hinges bright finished with necessary screws etc. complete including carriage of materials within all leads and lifts.	15.00	No	70.00	Rupees Seventy Only	Each	1050.00
8	Providing and fixing anodized aluminum sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. completed within all leads, lifts of materials and other incidentals:- (i) 250 X 16 mm size	3.00	No	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
9	Providing and fixing aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etc. complete including carriage of materials within all leads and lifts. 150x10mm size	12.00	No	105.00	Rupees One Hundred Five Only	Each	1260.00
10	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete including carriage of materials within all leads and lifts. 150mm size	12.00	No	75.00	Rupees Seventy Five Only	Each	900.00
11	Providing and fixing 100mm bright finished brass floor door stopper with rubber cushion scerws etc. tosuit shutter thickness complete. including carriage of materials within all leads, lifts and other incidentals.	3.00	No	250.00	Rupees Two Hundred Fifty Only	Each	750.00
						Total	99682.00
Quoted rate in figure.							
Quoted rate in words							
Conditions:-							
1	Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.						
2	Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.						

Executive Engineer
Rural Division Dhami
HP. PWD. Shimla



SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ghanahatti Kalihatti Arki Road In km. 0/00 to 8/060 (Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catchpit / pot hole etc. in Km., 0/00 to 8/00)

Estimated Cost: - Rs 98550 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	Hiring of Excavater -cum-loader for removal of slips including cost od fuel oil libricants wages of operational staff any repair during operation will be carried out at his risk cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor and including all leads and lifts & work shall be executed as per the direction of Engineer-in-Charge.	90.00 Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550.00
0					Total:	98550.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhoni

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Shimla Mandi Road km 39/200 to 52/200 (SH:- Trimming of grass , Maintenance of Eathen Shoulders , Maintenance of drain ,Maintenance of Culverts & white Washing in Km 49/000 to 50/500					Estimated cost:-	99,979.00
					Earnest money:-	2000.00
					Time:-	One Month
Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3000	Per Sqm	4.50	Rupees Four and Paise Fifty Only	13500.00
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3150	Per Sqm	24.95	Rupees Twenty Four and Paise Ninety Five Only	78593.00
3	The maintenance of drains include erosion, repair, cleaning, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907, including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	900	Rmt	4.50	Rupees Four and Paise Fifty Only	4050.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only	3500.00
5	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	96	Per Sqm	35.00	Rupees Thirty Five Only	336.00
					Total:-	99979.00
Amount Quoted by the Contractor in Percentage						
Note :- All the material will procured by the contractor him self and bills will be submitted						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhampur.



Schedule Of Quantity

Name of work:- A/R & M/O Rest House at Tara Devi. (SH: C/O Wire Crate for protection work on back side of rest house.)					Estimated Cost:-99,185.00		
					Earnest Money:- 2,000.00		
					Time:- One Month.		
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 I/c setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in tranches with excavated suitable material.	3.66	Cum	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	1305.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia. G.I wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10% extra for laps and joint laid with stone boulder weighing not less than 25 kg each as per drawing and technical specification clause 1301	30.47	Cum	3212.35	Rupees three thousand two hundred twelve and paise thirty five only	Per cubic metre	97880.00
						Total:-	99185.00
Amount Quoted by the Conctrator in percentage		Rs.					
Conditions:-(i) All the materials will be pro cured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhapli.



Schedule Of Quantity

Work:- R/R damages on Anandpur to Kot road Km 0/00 to 8/00 (SH: Removal of slips at
as Rds) Job No.2

Estimated Cost:-99,898.00

Earnest Money:- 2,000.00

Time:- One Month.

No.	Description of Work	No. of Qty.			Rate		Unit	Amount
		3	4	5	In figures	In words		
					6	7		
1	Removal of slips in all kinds of soil i/c saturated soil but excluding boulder and rocky portion requiring blasting upto a distance of 20.00 mtrs disposing of unserviceable materials, stacking serviceable materials and neatly dressing the surface including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	1109.98	Cum	90.00		Rupees ninety only	Per square metre	99898.00
							Total:-	99898.00
Amount Quoted by the Conctrator in percentage		Rs.						
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.								

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhampur

Schedule Of Quantity

of work:- R/R damages on Anandpur to Kot road Km 0/00 to 8/00 (SH: Removal of slips at
as Rds) Job No.1

Estimated Cost:-99,294.00

Earnest Money:- 2,000.00

Time:- One Month.

No.	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Removal of slips in all kinds of soil i/c saturated soil but excluding boulder and rocky portion requiring blasting upto a distance of 20.00 mtrs disposing of unserviceable materials, stacking serviceable materials and neatly dressing the surface including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	3	4	5	6	7	8
		1103.27	Cum	90.00	Rupees ninety only	Per square metre	99294.00
	Amount Quoted by the Conctrator in percentage					Total:-	99294.00
	Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami.



Schedule Of Quantity

of work:- R/R damages on Chauri Ki Ghatti to Yan via Bhad road Km 0/00 to 9/600 (SH: 101) (Removal of slips at various Rds)

Estimated Cost:- 99,814.00

Earnest Money:- 2,000.00

Time:- One Month.

No.	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Removal of slips in all kinds of soil i/c saturated soil but excluding boulder and rocky portion requiring blasting upto a distance of 20.00 mtrs disposing of unserviceable materials, stacking serviceable materials and neatly dressing the surface including carriage of material with in all leads and lifts as per the Direction of Engineer-In-Charge.	3	4	5	6	7	8
		1109.04	Cum	90.00	Rupees ninety only	Per square metre	99814.00
Total:-							99814.00
Amount Quoted by the Contractor in percentage		Rs.					
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi.



Schedule Of Quantity

& M/O PWD Rest house house at TaraDevi (SH:- Providing Furnishing Items in H.P.P.W.D. rest house.)

Estimated Cost:- 99450.00


Earnest Money:- 2000.00

Time:- One Month.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Providing & placing Door Matary Bed Sheed single superior quality in approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	15	Nos	750.00	Rupess Seven hundred & fifty only.	Nos	11250.00
2	Providing & placing Door Matt superior quality in approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	12	Nos	650.00	Rupess six hundred & fifty only.	Nos	7800.00
3	Providing & placing entrance Door Matt full size superior quality in approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	2	Nos	1000.00	Rupess One Thousand only.	Nos	2000.00
4	Providing & placing Curtain superior quality in approved colour/shade complete in all lead & lift as per the direction of Engineer in Charge.	28	Nos	2800.00	Rupess Two Thousand & eight hundred only.	Nos	78400.00
Total							99450.00

Amount Quatated by the Contractor in Percentage.

Note:- All the material will procured by the contractor him self.


 Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhami.



Schedule Of Quantity						Estimated Cost:- 99,717.00	
Name of Work :- Restoration of rain damages on Ambulance road Taradevi to Duggal Cottage Km 0/00 to 1/280 (SH:- P/L Kharanja stone soling in various reaches)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S No	Description of Work	No of Qty		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading and consolidation of binding material moorums or earth etc complete as per HPPWD specification 150 mm spread thickness (finished work i/c material and labour) including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	46.38	Cum	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Cubic metre	99717
Total Rs.							99717
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhansi.



SCHEDULE OF QUANTITY


Name of Work:- Restoration of Rain damages on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: Construction of Retaining wall at Rd. 2/855 to 2/860.50)

Estimated Cost: - Rs 99318 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.81 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	656.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.61 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2000.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.69 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90574.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.05 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	5093.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.85 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	995.00
0					Total:	99318.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami

SCHEDULE OF QUANTITY

Name of Work: - Annual Repair & Maintenance of Kadrain Nalawan Road Km. 0/00 to 3/00 (Sh: Curve cutting various RDs. in km. 2/500 to 3/000)	Estimated Cost: - Rs 99973 /- only
	Earnest Money : - Rs. 2000 /-only
	Time- One Month

S.No.	Sub head and items of work	Qty.		Rate	Unit	Amount	
1	2	3		In figure	In words	6	
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 25.64 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreases in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	256.34	Cum	390.00	Rupees Three Hundred Ninety Only	Per cubic metre	99973.00
						Total:	99973.00
Amount Quoted by the Contractor in Percentage							

Executive Engineer,
Shimla Rural Division,
HPPWD Dhani

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & maintenance on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: C/o R/wall at Rd. 3/590 to 3/594)
 Estimated Cost: - Rs 99453 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
				figures		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.78 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	649.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	7.10 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2531.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-602, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.38 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	89148.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	5.98 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	5034.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	12.30 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2091.00
0					Total:	99453.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami



SCHEDULE OF QUANTITY


Name of Work: - Construction of Link Road from Mandhorghat to Mahila Mandal Bhawan Pipal Ka Ped km. 0/00 to 0/630 (Sh: Formation Cutting in Km. 0/045 to 0/075, 0/150 to 0/180 and 0/255 to 0/300)						Estimated Cost: - Rs 99339 /- only	
						Earnest Money : - Rs. 2000 /-only	
						Time- One Month	
S.No.	Sub head and items of work	Qty.		Rate	Unit	Amount	
1	2	3		In figure	In words	6	7
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side.which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 13.86 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decreas in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	462.04	Cum	215.00	Rupees Two Hundred Fifteen Only	Per cubic metre	99339.00
						Total:	99339.00
Amount Quoted by the Contractor in Percentage							

Executive Engineer,
Shimla Rural Division,
HPPWD Dhamsi

SCHEDULE OF QUANTITY

Name of Work: - Restoration of rain damages on Okhroo Nehra Via Keru Road Km. 0/00 to 2/00 (SH:- Removal of slip in various Rds. Between km. 0/00 to 2/00)					Estimated Cost: - Rs 99834/- only		
					Earnest Money : - Rs. 2000/-only		
					Time: -		One Month
S. No.	Sub head and items of work	Qty.		Rate in		Unit	Amount
				figures	In words		
1	2	3	4	5	6	7	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materails/unserviceable materials up to dumping site arranged by the contractor at his own risk and cost with in all all leads and lifts as per the direction of Engineer-in-Charge & as per technical specifiction 302.3.5 and 1611.	1050.89	Cum	95.00	Rupees Ninty five Only	Per Cubic Metre	99834.00
						Total:	99834.00

Amount Quoted by the Contractor in precentage	Rs.
---	-----


 EXECUTIVE ENGINEER
 SHIMLA RURAL DIVISION
 HPPWD, DHAMI

Schedule Of Quantity						Estimated Cost:- 65,323.00	
Name Of Work :- Restoration of Rain Damages on Hiranagar Sharog Road						Earnest Money:- 1,400.00	
km 0/00 to 5/00 (SH:- C/O R/wall at Rd 0/692 to 0/693.50)						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	2.16	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	504
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	2.93	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	1045
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand, 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	13.06	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	62688
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1990 volume-I. Including carriage of material within all leads and lifts	1.62	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	1364
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	3.80	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	722
Total Rs.							65323
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dharam



Schedule Of Quantity						Estimated Cost:- 96,835.00	
Name Of Work :- C/O Ambulance road to Uparli Fatechi Km0/00 to 0/750 (SH:- C/O B/wall at Rd 0/736 to 0/739.50)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	193	Cum	233 40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	450
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	273	Cum	356 50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	973
3	Providing and Laying cement concrete for plain / reinforced concrete in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8:1 (1 Cement 4 sand & graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	1964	Cum	4800 00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	94272
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	600	Rmt	190 00	Rupees One Hundred Ninety Only	Per running metre	1140
Total Rs.							96835
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhanji



SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banuti to Dayla Road In km. 0/00 to 1/00 (Sh: Constructin of Wire crate wall at Rd. 0/985 to 1/00) JOB NO. IV							Estimated Cost: - Rs 99855 /- only
							Earnest Money : - Rs. 2000 /-only
							Time: - One Month
S.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3	4	4	5		
1	2	3	4	4	5	6	7
1	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimeter) dia GI wire conforming to IS:280 (two hundred eighty) and IS 4626 (four thousnad eight hundred twenty six) in 100 mm x 100 mm (one hundred into one hundred millimeter) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawingj and technical specifications clause 1301, (one thousand three hundred one) including carriage of all labour equipement and material to various location through all modes of transportation in all leads lifts all incidental charge.	27.34	Cum	3560.00	Rupees Three Thousand Five Hundred Sixty Only	Per Running Metre	97330.00
2	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2525.00
0						Total:	99855.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of CHC Old and New Building at Dhami, District Shimla (Sh: Providing and fixing scaffolding of bamboos for painting work on exterior walls upto all story height in CHC New Building) Job No. IV

Estimated Cost: - Rs 94350 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Providing scaffolding for all kind of works in multistorey buildings up to all height with Bamboo complete tied with rope on joints and pedistal of CGI Sheet etc in all respect (Face area of scafolding up to top pedestal height shall be measured and paid for) including carriage of materials within all leads and lifts as per direction of the Engineer-in-charge	754.80 Sqm	125.00	Rupees One Hundred Twenty Five Only	Per Square Meter	94350.00
					Total:	94350.00
0						

Amount Quoted by the Contractor in Percentage					Rs.	
--	--	--	--	--	------------	--

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Khairi Lohali Road Km. 0/00 to 2/220 (Sh: Construction of Retaining wall at Rd. 1/167 to 1/170.80)

Estimated Cost: - Rs 98510 /- only
 Earnest Money: - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.84 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1596.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	7.14 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2545.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.10 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92460.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.44 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	1212.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	4.10 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	697.00
0					Total:	98510.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	-----

Note : (i) All the material will procured by the contractor him self.


Executive Engineer
 Shimla Rural Division
 HPPWD, Dhama

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & maintenance on various Road under Sub Division Totu (Sh: (SH:- Providing & fixing of high intensity retro reflective all weather multi colour taps/sheets of approved shade on exsisting W-Metal Beam Crash Barriers)							Estimated Cost: - Rs 98280 /- only
							Earnest Money : - Rs. 2000 /-only
							Time: - One Month
S. No.	Sub head and Items of work	Qty.	Rate figures		Unit	Amount	
1	2	3	4	5	6	7	
1	Providing & fixing of high intensity reflective all weather proof multi colour taps/sheet size 300 min x 450 mm of approved shade and quality, fixed over on front face of longitudinal channel rail of W-Metal beam crash barrier with mechanical means with high visibility from long distance in fog prone area, black spot point and narrow curve etc. including rubbing and fixing the sheet etc. as per HPPWD specification including carriage of materials by all modes of transportation in all leads and lifts, compete in all respect and as per direction of the Engineer-in-charge.	117.00 Rmt.	840.00	Rupees Eight Hundred Forty Only	Per cubic metre	98280.00	
0					Total:	98280.00	

Amount Quoted by the Contractor in Percentage		Rs.
--	--	-----

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 79,693.00	
Name Of Work :- A/R & M/O Printing press building of Ghora Chowki Shimla (SH:- Dismantling old sewerage line near press colony and providing new Geverage line and Cerami Floor tiles in block-A) (Deposit work)						Earnest Money:- 1,600.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Demolishing cement concrete Manually/ by mechanical means including disposal of material within all leads as per direction of Engineer-in-charge nominal concrete 1;3:6 or richer mix (i/c equivalent design mix) Including carriage of material within all leads and lifts.	0.39	Cum	1280.00	Rupees One Thousand Two Hundred Eighty Only	Per Cubic metre	499
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work up to plinth level 1:3:6 (1 Cement 3 coarse sand: 6 graded stone aggregate 20mm nominal size).	0.39	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic metre	2184
3	Providing and laying ceramic floor tiles of 300mm x 300mm sizes (thickness to be specified by the manufacturer) with water absorption less then 0.08% and conforming to IS: 15622, of approved make in all colours and shades , laid on 20mm thick cement mortar 1:4 (1cement 4 coarse sand) jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigment etc complete.	1.30	Rmt	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per running metre	1885
4	Providing and fixing high pressure PVC Finolex (Type-B) spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. complete including carriage of materials within all leads and lifts. 150mm	30.00	Rmt	850.00	Rupees Eight Hundred Fifty Only	Per Cubic metre	25500
4.01	Providing and fixing high pressure PVC Finolex (Type-B) spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. complete including carriage of materials within all leads and lifts. 110mm	20.00	Rmt	650.00	Rupees Six Hundred Fifty Only	Per running metre	13000
4.02	Providing and fixing high pressure PVC Finolex (Type-B) spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. complete including carriage of materials within all leads and lifts. 75mm	10.00	Rmt	425.00	Rupees Four Hundred Twenty Five Only	Per running metre	4250
5	Providing and laying PVC Plain bend ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 150mm dia	4.00	No	450.00	Rupees Four Hundred Fifty Only	Each	1800
5.01	Providing and laying PVC Plain bend ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 110mm dia	2.00	No	350.00	Rupees Three Hundred Fifty Only	Each	700

5.02	Providing and laying PVC Plain bend ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 75mm dia	6.00	No	275.00	Rupees Two Hundred Seventy Five Only	Each	1650
6	Providing and laying PVCcollars ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 150mm dia	5.00	No	350.00	Rupees Three Hundred Fifty Only	Each	1750
6.01	Providing and laying PVCcollars ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 110mm dia	5.00	No	275.00	Rupees Two Hundred Seventy Five Only	Each	1375
6.02	Providing and laying PVCcollars ISI marked including fixing with approved adhesive etc . Complete including carriage of materials within all leads and lifts :- 75mm dia	4.00	No	225.00	Rupees Two Hundred Twenty Five Only	Each	900
7	Constructing masonry chamber 30x30x50 cm inside in brick work in cement mortar 1:4 (1 cement 4 coarse sand) for stop cock with C.I surface box 100x100x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement 2 coarse sand 4 graded stone aggregate 20 mm nominal size) i/c necessary excavation , foundation concrete 1:5:10 (1cement 5 fine sand 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement 3 coarse sand) 12mm thick finished with a floating coat of neat cement complete as per standard design : 18.32.1 with common brunt clay F.P.S (non modular) bricks of class designation 7.5	8.00	No	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Each	15600
8	Providing and fixing white vitreous china pedestal type water closet 9 European type) with seat and lid 10 litre low level white vitreous china flushing cistern & C.P flush bend with fitting & C.I brackets 40mm flush bend overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete including painting of fittings and brackets cutting and making good the walls and floors wherever required	1.00	No	5500.00	Rupees Five Thousand Five Hundred Only	Each	5500
9	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P Brass hinges and rubber buffers : 1 SOLID TYPE : a white plastic seat and cover . Cera.	1.00	No	550.00	Rupees Five Hundred Fifty Only	Each	550
10	Providing and fixing 8mm dia C.P / S.S Jet with flexible tube upto 1 metre long with S.S traingular plate to European type W.C of quality and make as approved by Engineer-in-charge	1.00	No	675.00	Rupees Six Hundred Seventy Five Only	Each	675
11	Providing and fixing CP Brass Bib cock with flange of approved colour and quality sieko make in all leads and lifts complete	1.00	No	925.00	Rupees Nine Hundred Twenty Five Only	Each	925
12	Providing and fixing CP Brass Angle cock with flange of approved colour and quality sieko make in all leads and lifts complete	1.00	No	950.00	Rupees Nine Hundred Fifty Only	Each	950

Total Rs.						79693
Amount Quoted by the Contractor in Percentage						
Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla, Rural Division,
HP, PWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of PWD Rest House at Tara Devi District Shimla H.P. (SH: Providing and fixing tiles flooring,Walls & Sanitary fitting, etc work In Dinning Hall Old Building)

Estimated Cost: - Rs 99605 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.		Rate		Unit	Amount
				4	5		
1	2	3				6	7
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. complete including carriage of materials within all leads and lifts as per the direction of Engineer in Charge. For thickness of tiles 10 mm to 25 mm	28.50	Sqm	31.20	Rupees Thirty One and Paise Twenty Only	Per Square Meter	889.00
2	P/F Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete. including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.42	Sqm	1354.00	Rupees One Thousand Three Hundred Fifty Four Only	Per Square Meter	3270.00
3	P/F 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps & dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) & jointing with grey cement slurry @3.3kg/sqm including pointing in white cement mixed with pigment of matching shade complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	21.09	Sqm	1447.00	Rupees One Thousand Four Hundred Forty Seven Only	Per Square Meter	30510.00
4	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) NO. 20118 EWC SUPERB S with seat and lid, 10 litre low level white P.V.C. cistern NO. 511856 of Hindware with dual flushing system, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	10088.00	Rupees Ten Thousand Eighty Eight Only	Each	10088.00
5	Providing and fixing C.P. Brass Jet of Hindware Cat No. F-160193 with 1.2 metre long to European type W.C. of quality and make as approved by Engineer - in - charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	1104.00	Rupees One Thousand One Hundred Four Only	Each	1104.00
6	Providing and fixing white vitreous china wash basin size 55x40x83cm cat. No. 10008 VIKING with Pedestal No. 11003 of Hindware including making all connections including the cost of all fittings including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	3973.00	Rupees Three Thousand Nine Hundred Seventy Three Only	Each	7946.00
7	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour. Waste coupling 31 mm dia of 79 mm length and 62mm breadth weighing not less than 45 gms including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	534.00	Rupees Five Hundred Thirty Four Only	Each	1068.00
8	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. Semi rigid pipe 32 mm dia	3.00	No.	592.00	Rupees Five Hundred Ninety Two Only	Each	1776.00



9	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.-15 mm nominal bore with 45cm length.	4.00	No.	259.00	Rupees Two Hundred Fifty Nine Only	Each	1036.00
10	Providing and fixing C.P brass soap dish Hindware cat. No. F580004 with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3.00	No.	1102.00	Rupees One Thousand One Hundred Two Only	Each	3306.00
11	Providing & fixing 125mm dia C.P/ S.S grating for floor of approved quality and colour. Square type including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3.00	No.	420.00	Rupees Four Hundred Twenty Only	Each	1260.00
12	P/F 600x450mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	2121.00	Rupees Two Thousand One Hundred Twenty One Only	Each	4242.00
13	Providing and fixing 46 x 13cm Acrylic/glass shelf of JAL Cat. No. 36552 with edges round off, complete including all fitting & fixtures and carriage of material within all leads and lifts as per direction of the Engineer in Charge.	2.00	No.	2203.00	Rupees Two Thousand Two Hundred Three Only	Each	4406.00
14	Providing and fixing C.P. brass toilet paper holder of Hindware Cat. No. F102009 including the cost of fittings complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	No.	1182.00	Rupees One Thousand One Hundred Eighty Two Only	Each	1182.00
15	Providing and fixing 600mm size C.P. brass/S.S towel Rod Hindware cat. No. F102012 (heavy duty ISI marked IS:8931 & 8934) complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	1210.00	Rupees One Thousand Two Hundred Ten Only	Each	1210.00
16	P/F high pressure PVC spigot & socket, waste and ventilating pipe ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i) 110 mm dia	10.00	Rmt	1087.00	Rupees One Thousand Eighty Seven Only	Per Running Meter	10870.00
17	Providing and fixing (Finolex) PVC floor traps ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts:-110mm x 90mm	3.00	No.	408.00	Rupees Four Hundred Eight Only	Each	1224.00
18	P/F PVC plain bend ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i) 110 mm dia	3.00	No.	248.00	Rupees Two Hundred Forty Eight Only	Each	744.00
19	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts:- 110MM Dia	2.00	No.	268.00	Rupees Two Hundred Sixty Eight Only	Each	536.00
20	P/F C.P. brass bib cock with wall flange Hindware cat. No.F690004 of approved quality conforming to IS standards & weighing not less than 690 gms including carriage of material upto all leads and lifts as per the direction of Engineer in Charge : 15 mm nominal bore	1.00	No.	1122.00	Rupees One Thousand One Hundred Twenty Two Only	Each	1122.00
21	Providing and fixing 15mm dia C.P. brass Angle Stop Cock with flange of Hindware Cat. No. F690043 (heavy duty ISI marked IS:8931 & 8934) including carriage of materials within all leads and lifts.	4.00	No.	950.00	Rupees Nine Hundred Fifty Only	Each	3800.00

22	1/2" C.P. brass angle valve for basin mixer and shower points of approved quality conforming to IS 8531 1/2 mm nominal bore including carriage of material lifts of leads and fits as per the direction of Engineer in Charge	2.00	No	4008.00	Rupees Four Thousand Eight Only	Each	8016.00
0						Total	99606.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self


 Executive Engineer
 Sharda Rural Division
 H.P.W.D. Dabra

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hari Devi Seri Bhaloh Road in km. 0/00 to 3/600 (Sh: Construction of R-wall at Rd. 1/336 to 1/341, 75)

Estimated Cost - Rs 99248 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.		Rate		Unit	Amount
				4	5		
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	2.99	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	698.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.84	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2438.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.78	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90988.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.31	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3628.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v).20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1496.00
0						Total:	99248.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD/Dhami

Schedule Of Quantity						Estimated Cost:- 88,218.00	
Name Of Work :- Restoration of Rain Damages on Hiranagar Sharog Road						Earnest Money:- 1,800.00	
km 0/00 to 5/00 (SH:- C/O R/wall at Rd 0/691 to 0/692)						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	2.88	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	672
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	3.90	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	1390
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14 8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	17.42	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	83616
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1990 volume-I Including carriage of material within all leads and lifts	2.16	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	1818
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	3.80	No	190.00	Rupees One Hundred Ninety Only	Each	722
Total Rs.							88218
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhansi.



SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Link road to village Dishti Road Km. 0/00 to 3/00 (Sh: Construction of PCC R-wall at Rd. 2/754 to 2/758)

Estimated Cost: - Rs 98156 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.68 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	626.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	4.16 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1483.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.68 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	85928.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	5.76 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4849.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	31.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	5270.00
0					Total:	98156.00

Amount Quoted by the Contractor in Percentage		Rs.
--	--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of R-wall at Rd. 10/800 to 10/804.30)				Estimated Cost: - Rs 98376 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month			
S. No.	Sub head and items of work	Qty.		Rate figures	Unit	Amount	
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.35	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1715.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.08	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92368.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3 8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.10	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2610.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	9.90	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1683.00
0						Total:	98376.00
Amount Quoted by the Contractor in Percentage						Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhama