

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2025-26- 17752

Dated:- 20.2.2026

To

✓ The Executive Engineer(IT) Cell,
HP.PWD,Nirman Bhawan, Nigam Vihar,
HP.PWD,Shimla-2.


Subject: Regarding publication of Tender notice on department website.

Sir,

With reference to the notification issued by the Secretary (PW) to the Government of Himachal Pradesh No. PBW(B) A(3)I/2024 dated 03/01/2024 , further corrigendum on dated 08/01/2025 and Under Secretary (PW) to the Government of Himachal Pradesh No. PWD-B-A0(3)/1/2024-241828 dated 02-02-2026 . Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

Certified that the work mentioned in the Tender Notice are urgenet in nature.

DA:- As above


Executive Engineer,
Dharampur Division,
HP.PWD. Dharampur.

H.P.P.W.D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

TENDER SCHEDULE:

- | | | |
|-----------|--|---------------------------------|
| 1 | Date and time of receipt of application for the tender form : | 25-02-2026 upto 4.00 PM |
| 2 | Date and time of issue of tender form : | 26-02-2026 upto 4.00 PM |
| 3 | Date and time of receipt of tenders: | 27-02-2026 upto 11.00 AM |
| 4. | Date and time of opening of tenders: | 27-02-2026 upto 11.30 AM |

The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.


Sr. No	Name of Works	Estimated Cost (in Rs)	EMD (in Rs.)	Time Limit	Cost of Tender Form	Eligible class of Contractor
01.	Restoration of Rain damages on Trohla Richhli Manudhar Road Km. 0/0 to 4/900(SH:- C/O R/all in PCC 1:5:10 at RD 0/525 to 0/545)PDNA2023	2,30,555/-	4,700/-	Two months	350/-	"D"
02	Restoration of Rain damages on Baroti Rakhera Kandapattan Road Km. 0/0 to 6/500(SH:- Construction of Toe wall in 1:3:6 below existing R/wall at RD 4/150 to 4/165 below GHS Rakhera in Nallah)PDNA2023	3,45,930/-	7,000/-	Two Months	350/-	"D"
03	Restoration of Rain damages o Sanour to Fihar Road Km. 0/0 to 6/0(SH:- Removal of Slips at various RD)	95,497/-	2,000/	Two Months	350/-	"D"
04	Restoration of Rain damages on Longni to Sari Road Km. 0/0 to 6/0 (SH:- Removal of slips at various RD).PDNA2023	94,661/-	1,900/-	Two Months	350/-	"D"
05	Construction of New Link Road in Village Sarskan to House of Sh. Bhoop. Singh and Sh. Balam Ram (SH:- Formation cutting 3/5 mtrs wide in Km. 0/0 to 0/300)	3,00,418/-	6,100/-	Two months	350/-	"D"
06	Construction of Link raod to Bhora Ra Nallah From Curu Balh Km. 0/0 to 1/0 (SH:- Formation cutting 3/5 mtr wide in Km. 0/0 to 0/250) Under Deposit SDP	2,99,253/-	6,000/-	Two months	350/-	"D"
07	Restoration of Rain Damages on Cholthara Kothi via Rasain Bhalwan Km. 0/0 to 17/345(SH:- Construction of B/wall at RD 17/200 to 17/215) Under Head PDNA2023 S. NO. 14	4,90,830/-	9,900/-	Two months	350/-	"D"
08.	A/R & M/O various Roads under HPPWD Sub Division Marhi (SH:- P/L 53 to 22.4mm for pot holes)	49,558/	1,000/-	Two Months	350/-	"D"
09.	A/R & M/O various roads under HPPWD Sub-Division Mandap (SH:- P/L 53 to 22.4mm for pot holes)	49,235/-	1,000/-	Two Months	350/-	"D"
10	Construction of Mahila Mandal Bhawan Lavanpur in Tehsil Dharampur Distt. Mandi (HP) (SH:- Providing and laying plaster work, doors and window and painting work etc.) Under Deposit	1,92,182/-	3,900/-	Two months	350/-	"D"

SDP/2018/150						
11.	Restoration of rain damages on Dabrot to Paryal road Km. 0/0 to 7/0 (SH:- P/L CCpavement at RD 6/328 to 6/332 and 6/620 to 6/635)	75,494/-	1,600/-	Two Months	350/-	"D"
12	R/R Damages on various road under section Sidhpur HPPWD Sub-Division Dharampur (SH:- Removal of slips & maintenance of berms in various roads)	4,76,909/-	10,000/-	Two Months	350/-	"D"
13.	Restoration of Rain damages on various roads under Gorat Section HPPWD Sub Division Marhi(SH:- Deployment/Hiring of Excavator cum loader for removal of land slide/slips)	4,89,600/-	9,800/-	Two Months	350/-	"D"
14	Restoration of rain damages on 40.00mtrs span bridge over Nallad Khad Longni to sari Road Km. 0/0 to 6/500(SH:- Construction of protection wall at River bed level at Abutment) PDNA 2023 S.No. 3265	4,15,249/-	8,400/-	Two Months	350/-	"D"
15	Restoration of rain damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km. 8/765 to 20/0(SH:- Removal of formation deficiency in Km. 9/075 to 9/135)	1,34,649/-	3,000/-	Two Months	350/-	"D"
16	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km. 8/765 to 20/0(SH:- C/O wire crate wall at RD 12/920 to 12/940)	4,54,100/-	10,000/-	Two Months	350/-	"D"
17	Restoration of Rain damages on various roads under HPPWD Sub Division Marhi(SH:- Deployment/Hiring of excavator cum loader for removal of land slide/ slips)	4,93,125/-	9,900/-	Two Months	350/-	"D"
18	Restoration of Rain damages on various Road under Kamlah Section HPPWD Sub-Division Marhi (SH:- Deployment/ Hiring of excavator cum loader for removal of land slide/ slips in various RD's)	4,97,250/-	10,000/-	One months	350/-	"D"
19	Restoration of Rain damages on various road under kamlah Section HPPWD Sub-Division Marhi (SH:- Hiring of tipper for removal of land slides/ slips at various RDs)	91,500/-	1,900/-	Two months	350/-	"D"
20	Restoration of Rain damages on various Roads under HPPWD Sub Division Dharampur (SH:- Deployment/ Hiring of Tipper for removal of land slide/slips)	97,650/-	2,000/-	Two Months	350/-	"D"
21	Restoration of rain damages on various roads under HPWD Sub Division Dharampur(SH:- Removal of slips and maintenance of berms in various Roads)	4,04,303/-	8,100/-	Two Months	350/-	"D"
22.	Restoration of Rain Damages on various Road under Dharampur Section HPPWD Sub-Division Dharampur (SH:- Deployment/Hiring of Excavator cum loader and Hiring of Tipper for removal of land slide/slips)	4,67,625/-	10,000/-	Two Months	350/-	"D"
23.	Restoration of Rain damages on Dharampur to sandhole via Seoh (Proton Mayoh Km. 0/0 to 3/0 and Dharampur to Kalswai Km. 0/0 to 2/110 and Dharampur to Shivdwals via Gujjar Nalla(SH:- Hiring of Excavator cum loader and Tipper for removal of land slide/ slips)	3,12,000/-	6,300/-	Two Months	350/-	"D"

24.	Restoration of Rain damages on various Roads Baroti section HPPWD Sub-Division Mandap (SH:- Hiring of excavator cum loader and Hiring of Tipper for removal of alnd slide/slips)	4,46,250/-	10,000/-	Two Months	350/-	"D"
25.	Restoration of Rain damages on various Roads under Marhi Section HPPWD Marhi (SH:- Deployment/Hiring of excavator cum loader & Hiring of tipper for removl of land slide/slips)	2,32,600/-	5,000/-	Two Months	350/-	"D"
26.	Restoration of rain damages on various roads under HPPWD Sub Division Mandap (SH:- Deployment/Hiring of excavator cum loader for removal of land slide/slips)	3,06,000/-	6,500/-	Two Months	350/-	"D"

Terms and Conditions:-

- 1 The contractors/firms should posses the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (Vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under-signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.
4. The contractor will give affidavit that he has not two or more works in hand for execution, failing which the application shall be rejected.
5. The offer of the tender shall remain valid upto 60 days after the opening.
6. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).



Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

No.PW-DPD-CB-Tender/2025-26/ 17753-52

Dated:- 2012.2026

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer, Hamirpur Zone HP.PWD, Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur.
3. The Executive Engineer (IT) O/o Engineer-In Chief HPPWD Shimla through email-eeict-pwd-shi@hp.gov.in & ee-pwd-hp@nic.in for uploading the same on HPPWD web portal.
4. Notice Board.
5. A/B, D/B. Of this office.


Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

183
68

①

DRAFT SCHEDULE OF QUANTITY

Restoration of Rain Damages on Trohla Richhli Manudhar road in 0/0 to 4/900 (Sh:- Construction of PCC 1:5:10 at RD 0/525 to 0/540)

Estimated cost :- 230555
Earnest Money:- 4700

Time Limit Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.15	250	Rupees Two Hundred Fifty Only	Per Cubic metre	6038
Providing and laying cement concrete 1:5:10 (One cement: Five sand: Ten graded crushed stone aggregate 40mm (Forty millimeters) Nominal size as per PWD specification in all heights and curing complete including cost of form work in retaining wall/breast walls with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.25	4375	Rupees Four Thousand Three Hundred SeventyFive Only	Per Cubic metre	206719
Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall and return wall with 100mm (One Hundred millimetres) dia PVC pipe extending through the full width of structure with slope of 1:20 (One vertical twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.00	175	Rupees One Hundred SeventyFive Only	Per Running metre	2625
Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3 with in all leads lifts and technical specifications including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.85	850	Rupees Eight Hundred Fifty Only	Per Cubic metre	15173
				Total	230555

Draft schedule of quantity approved
RS. 230 555 / Vides No. 183/2018/26

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

193
84

2

DRAFT SCHEDULE OF QUANTITY

Restoration of Rain damages on Baroti Rakhera Kandapattan road km 0/0 to 6/500 (Sh:- Construction of in 1:3:6 below existing R/wall at RD 4/150 to 4/165 below GHS Rakhera in Nallah)PDNA 2023)

Estimated cost :- 345930
Earnest Money:- 7000
Time Limit Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site with in all leads lifts and technical specifications with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	53.86	250	Rupees Two Hundred Fifty Only	Per Cubic metre	13465
Providing and laying cement concrete 1:3:6 (One cement: three sand: six graded/crushed stone aggregate 40mm (Forty millimetre) nominal size) and curing complete including the cost of from work in foundation and plinth including carriage of materials within all leads and lifts and other incidentals charges. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	67.85	4900	Rupees Four Thousand Nine Hundred Only	Per Cubic metre	332465
				Total	345930

*Draft schedule of quantity approved
Rs. 345930 of vide No 193/2023*

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

213/94

3

DRAFT SCHEDULE OF QUANTITY

Work :- Resoration of rain damages on Sanour to Fihar road km 0/0 to 6/0 (SH:- Removal of slips at various Rd.s)

Estimated cost :- 95497

Earnest Money:- 2000

Time Limit Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials including carriage of surplus material to dumping site in all roads and lifts through all mode of transportation as per technical specification 302.3.5 and 1611 and as per direction of Engineer - in -Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1005.23	95	Rupees NinetyFive Only	Per Cubic metre	95497
Total					95497

*Draft schedule of quantity approved
RS.954977 vide s.no. 94/2025-26*

[Signature]
Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharanpur

214
95

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on Longni to Sari road km 0/0 to 6/0 (SH:- Removal of slips at various Rd.s)

Estimated cost :- 94661
Earnest Money:- 1900
Time Limit Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials including carriage of surplus material to dumping site in all roads and lifts through all mode of transportation: as per technical specification 302.3.5 and 1611 and as per direction of Engineer - in - Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	996.43	95	Rupees NinetyFive Only	Per Cubic metre	94661
Total					94661

*Draft schedule of quantity approved
Rs. 94661 H.Vide No. 214/2015-26*

[Signature]
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

217/96

5

DRAFT SCHEDULE OF QUANTITY

Work: -Construction of new link road in village Sarskan to house of Sh. Bhoop singh and Sh. Balam Ram (Information cutting 3/5 mtrs wide in km 0/0 to 0/300

Estimated cost :-	300418	
Earnest Money:-	6100	
Time Limit	Two Months	
Rates	Unit	Amount
In Figure	In words	
4	5	7
231.75	Rupees Two Hundred ThirtyOne Paise SeventyFive Only	Per Cubic metre.
3	1296.30	300418
Total		300418

Description of item/Sub Head

2

Excavation in earthwork in hilly area all heights and depths, in all kind of soil by manual /mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Road, August, 2004 and clause 1603.1 and 1603.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. Recovery for stones whether useful or not for 216.05Cum @ Rupees 300 (Three Hundred only per cubic metre) shall be done on prorata basis from each running bill of this item.

Draft schedule of quantity approved
 RS.300418/- Vide s.no. 217/96

Executive Engineer,
 Dharampur Division
 H.P.W.D., Dharampur



212
93

6

DRAFT SCHEDULE OF QUANTITY						
Name of work:- Construction of link road to Bhora Ra Nallah from Chuhru Balh km 0/0 to 1/0 (SH:- Formation cutting 3/5 Mtr wide in km 0/0 to 0/250) under Deposit SDP/2024/569						
S.N	Description of item/Sub Head	Quantity	In Fig.	Time Limit		One Month Amount
				Rates	Unit	
		y		In words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Road, August, 2004 and clause 1603.1 and 1603.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. Recovery for stones whether usefull or not for 216.66 Cum @ Rupees 300.00 (One Hundred seventy only per cubic metre) shall be done on prorata basis from each running bill of this item.	1299.97	230.20	Rupees Two Hundred Thirty Paise Twenty Only	Cum	299253

Draft schedule of quantity approved 18.2.92531
Wd 87 No 212/2025-26

[Signature]
Executive Engineer
Dharampur Division,
H.P.P.W.D Dharampur

218
81

7

DRAFT SCHEDULE OF QUANTITY

Work:- Resoration of rain Damages on Cholthara to Kothi via Rasain Bhalwan km 0/0 to 17/345 Kothi (Sh:-
uction of B/wall at Rd 17/200 to 17/215) under Head PDNA 2023.SNo. 14

Estimated cost :- 490830
Earnest Money:- 9900
Time Limit Two Months

Description of item/Sub Head	Quantity	Rates			Unit	Amount
		In Figure	In words	Unit		
2	3	4	5	6	7	
Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	37.20	250	Rupees Two Hundred Fifty Only	Per Cubic metre	9300	
Providing and laying cement concrete plain/ reinforced concrete 1:3:6 (One cement: three sand: six graded stone aggregate) 40 mm (Forty millimetre) in open foundation complete as per drawing and technical specification clause 302,803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP,PWDD technical specification with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	97.20	4900	Rupees Four Thousand Nine Hundred Only	Per Cubic metre	476280	
Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutment,wing wall and return wall with 100mm (One Hundred millimetres) dia PVC pipe extending through the full width of structure with slope of 1:20 (One vertical twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614.709,1204.3.7 including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	30.00	175.00	Rupees One Hundred SeventyFive Only	Per Running metre	5250	
Total					490830	

Draft schedule of quantity approved
Rs.490830-Vide Mo.2.18/2025-26

[Signature]
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

191
69

8

DRAFT SCHEDULE OF QUANTITY

Range of Work :-A/R & M/O various roads under HPPWD Sub Division Marhi (SH :- P/L 53 to 22.4 mm for pot

Description of item/Sub Head	Quantity	Estimated cost :-		Two Months Amount
		Earnest Money :-		
		In Figure	In words	
2 Providing, laying, spreading and compacting stone aggregate of specific sizes 53-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel, roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by Mechanical means as per technical Specification Clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 23.05	4 2150.00	5 Rupees Two Thousand One Hundred Fifty Only	7 49558
Total:-			49558	

Draft amount approved by Rs 49558/- vide S.O 191

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

190
72

DRAFT SCHEDULE OF QUANTITY

Item of Work :- A/R & M/O various roads under HPPWD Sub Division Mandap (SH :- P/L 53 to 22.4 mm for pot

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Two Months Amount
		Earnest Money :-			
		In Figure	In words		
2 Providing, laying, spreading and compacting stone aggregate of specific sizes 53-22.4mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by Mechanical means as per technical Specification Clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 22.90	4 2150.00	5 Rupees Two Thousand One Hundred Fifty Only	6 Per Cubic Metre	7 49235
				Total:-	49235

DNIT amount approved for Rs 49235/- vide Sr no 190

[Signature]
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

197
73

10

DRAFT SCHEDULE OF QUANTITY

of work:- Construction of Mahila Mandal Bhawan Javanpur in Tehsil Dharampur Distt. Mandi (H.P.) (SH:-
Laying and Laying Plaster work ,doors and window and painting work etcetra) under deposit SDP/2018/150

Description of item/Sub Head	Quantity	Estimated cost :-		Two month	
		Earnest Money:-		Amount	
		In Figure	In words	Unit	Amount
Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory window including black enamelled iron butt hinges with necessary screws.40mm (Forty millimetres) thick lnd class Deodar wood including carriage of materials within all leads and lifts and other incidentals charges.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	6.46	4500	Rupees Four Thousand Five Hundred Only	Per Square metre	29070
Providing fixing 35mm (Thirty five millimetres) thick 2nd class (second class) deodar wood wire gauge shutters using galvanized M.S. wire gauge I.S gauge designation 85G with wire of dia 0.56mm (zero point fifty six millimetres for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials within all leads and lifts and other incidentals charges.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	4.78	3187.6	Rupees Three Thousand One Hundred EightySeven Paise Sixty Only	Per Square metre	15237
Providing and laying vitrified floor tiles in different size (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero percent)and conforming to IS 15622 of approved make in all colours and shades, laid on 20mm(twenty millimetre) thick cement mortar 1:4 (One cement : four sand) jointing with grey cement slurry @ 3.3kg / sqm (Three point three kilogramper square metre) including pointing in white cement mixed with pigment of matching shade complete.within all leads and lifts and other incidentals charges.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	35.54	1490	Rupees One Thousand Four Hundred Ninety Only	Per Square metre	52955
White glazed tiles 6 mm(six millimetre) thick in skirting risers of steps and dado 12 mm (Twelve millimetre) thick cement mortar 1:3 (one cement : three sand) and jointed with cement slurry. as directed by the Engineer-in-Charge including entire carriage of material with in all leads and lifts and including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Govt.	21.3	1300	Rupees One Thousand Three Hundred Only	Per Square metre	27690
Providing and applying white cement based putty of average thickness 1 mm,(One millimetre) of approved brand and manufacturer JK wall putty/ Birla white Putty make over the plastered wall surface to prepare the surface even and smooth complete upto all floor level including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , ST or other taxes imposed by the Government.	110.35	75	Rupees SeventyFive Only	Per Square metre	8276
mm (six millimetre) cement plaster to ceiling with cement mortar 1:3 (one cement : three sand) including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	36.35	198.3	Rupees One Hundred NinetyEight Paise Thirty Only	Per Square metre	7208
mm (Fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering up to floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) upto any floor level including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	138.15	259.95	Rupees Two Hundred FiftyNine Paise NinetyFive Only	Per Square metre	35912

Sub

Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on un-decorated wall surfaces (Two coats) applied 3.84 km²/10sqm (three point eight fourkilogramme per ten square metre) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials within all leads and lifts and other incidentals charges.

Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer of required shade and colour complete as per manufacturer specification including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.

Finishing with delux multi surface paint system for interior and exterior using primer as per manufacture specification including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.

Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm(zero point nine litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm(zero point seven five litre per ten square metre) of approved brand and manufacture of ICI (Dulux Gloss), Nerolac, Berger (Luxol High Gloss), Asian Paints (Premium Apollite Gloss), Shallimar. make including cleaning of all dirt, dust and other foreign matter sand papering and stopping complete upto all floor levels in all heights/ depth.

50.88	95	Rupees NinetyFive Only	Per Square metre	4834
110.35	90	Rupees Ninety Only	Per Square metre	9932
11.24	95	Rupees NinetyFive Only	Per Square metre	1068
Total				192182

*Draft schedule of quantity approved
Rs.192182/- vide No. 197/2025-28*

[Signature]
Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

196

11

DRAFT SCHEDULE OF QUANTITY

Work :- Resoration of rain damages on Dabrot to paryal road km 0/0 to 7/0 (SH:-
) at concrete pavement at RD 6/328 to 6/332 and 6/620 to 6/635)

Estimated cost :- 75494
 Earnest Money:- 1600
 Time Limit Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2 Stone soling properly hand packed filling interstices with kharanja stone and consolidating complete to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 100mm (One hundred millimetre) spread thickness (finished work) including materials and labour) including carriage of materials within all leads and lifts and other incidentals charges. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 8.84	4 1190.00	5 Rupees One Thousand One Hundred Ninety Only	6 Per cubic Metre	7 10520
Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre) nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mn2 and minimum cement not less than 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14- days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll	8.84	7350.00	Rupees Seven Thousand Three Hundred Fifty Only	Per cubic Metre	64974
				Total	75494

*Draft schedule of quantity approved
 Rs. 75494/- Vides no. 196/2024*

[Signature]
 Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur

199
57

12

DRAFT SCHEDULE OF QUANTITY

Work :- R/R Damages on various road under section Sidhpur HPPWD Sub Division Dharampur (SH:-
of slips & maintenance of berms in various roads)

Estimated cost :- 476909
Earnest Money:- 10000

Time Limit Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2	3	95	Rupees NinetyFive Only	6	7
Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all leads and lifts/ soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer - in -Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	273.60			Per Cubic Metre	25992
Maintenance of Earthen shoulder Stripping excess soil from the shoulder surface to achieve the approved level as per drawings and Technical Specification Clause 1903 The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27579.00	16.35	Rupees Sixteen Paise ThirtyFive Only	Per Square metre metre	450917
				Total:-	476909

By approved For

DRAFT Schedule of Rs 476909 / - vide SN 199

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur.

20607

14

Work :- Restoration of rain Damages on 40.00 Mtr. Span Bridge over Nallad Khad on Longni to Sari road km 0/0
(SH:- Construction of protection wall at River bed level at Abutment) PDNA 2023 S.No. 3265

Estimated cost :- 415249
Earnest Money:- 8400

Time Limit
Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	3	4	5	6	7
Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	74.60	250	Rupees Two Hundred Fifty Only	Per Cubic metre	18650
Providing and laying cement concrete plain/ reinforced concrete 1:3:6 (One cement : three sand: six graded stone including form work for plain/ reinforced concrete work as per drawing and HP,PWDD technical specification with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	79.51	4900	Rupees Four Thousand Nine Hundred Only	Per Cubic metre	389599
Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutment,wing wall and return wall with 100mm (One Hundred millimetres) dia PVC pipe extending through the full width of structure with slope of 1:20 (One vertical twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614.709,1204.3.7 including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	40.00	175.00	Rupees One Hundred SeventyFive Only	Per Running metre	7000

Total 415249

*Draft schedule of quantity approved
PS-415249/-vide No. 206/2023*

Executive Engineer,
Dharanpur Division
H.P.W.D.,Dharampur

12/54

15

DRAFT SCHEDULE OF QUANTITY

of Work :- Restoration of Rain damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 8/765 to 20/0
Removal of formation deficiency in Km 9/075 to 9/135)

Estimated cost :-	134649
Earnest Money:-	3000
Time Limit	Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	3	4	5	6	7
Excavation in earthwork in hilly area all heights and depths, in all kind of soil by manual /mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Road, August, 2004 and clause 1603.1 and 1603.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. Recovery for stones whether usefull or not for 103.97 Cum @ Rupees 300.00 (Three Hundred only per cubic metre) shall be done on prorata basis from each running bill of this item. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	479.86	280.60	Rupees Two Hundred Eighty Paise Sixty Only	Per Cubic Metre	134649
				Total	134649

Draft schedule of quantity approved for Rs 134649/-

Sr No 159

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

53

16

DRAFT SCHEDULE OF QUANTITY

Work :- R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 8/765 to 20/0 (SH :- C/O
ate wall at RD 12/920 to 12/940)

Estimated cost :-
Earnest Money :-
Time Limit

454100
10000
Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and as per direction of Engineer-in-charge complete. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 47.40	250.00	Rupees Two Hundred Fifty Only	Per Cubic Metre	7 11850
Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	145.00	3050.00	Rupees Three Thousand Fifty Only	Per Cubic Metre	442250
Total:-					454100

Draft schedule of Quantity approved for Rs 454100/

vide Sr No 158

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

155

72

DRAFT SCHEDULE OF QUANTITY

**Name of Work :- Restoration of rain damages on various roads under HPPWD Sub Division Marhi (SH :-
 xment/Hiring of Excavator cum loader for removal of land slide/slips)**

S.No	Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount	
			In Figure	In words			Two Months
2	Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	315.00	1275.00	Rupees One Thousand Two Hundred SeventyFive Only	Per Hours	401625	
	Deployment/Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic ft Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge with in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt	30.00	3050.00	Rupees Three Thousand Fifty Only	Perdays	91500	
Total:-						493125	

Draft schedule of qty approved For
Rs 493125/-
vide S.No. 154/202826
 Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur

176
60

DRAFT SCHEDULE OF QUANTITY

Description of item/Sub Head	Quantity	Rates			Unit	Amount
		In Figure	In words			
		4	5	6		
<p>Work:- Restoration of Rain Damages on various Road under Kamlah Section HPPWD Sub Division H :- Deployment/ Hiring of excavator cum loader for removal of land slide/slips in various RDs)</p> <p>Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff . Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Govt.</p>	3	1275	Rupees One Thousand Two Hundred SeventyFive Only	Per Hours	497250	
				Total	497250	

*Draft schedule of quantity approved for
 RS. 497250/- vide S.M.No. 176/201524*

S
 Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur

175
59

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of Rain Damages on various Road under Kamlah Section HPPWD Sub Division
At:- Hiring of Tipper for removal of land slides /slips at Various Rd,s)

Estimated cost :- 91500
Earnest Money:- 1900

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		Time Limit Two Months			
		In Figure	In words		
2 Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	3050.00	Rupees Three Thousand Fifty Only	Per Day	91500
		4	5	6	7
				Total	91500

*Draft schedule of quantity approved
Rs. 91500/- Vicksan No 175/2025-26*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

134
69

70

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads under HPPWD Sub Division Dharampur (Sh:-
Payment /Hiring of Tipper for removal of land slide /slips)

Estimated cost :- 97650
Earnest Money:- 2000
Time Limit Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	3	4	5	6	7
Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Day	97650
				Total	97650

*Draft schedule of quantity approved
for Rs. 97650 vide No. 134/2025-26*

[Signature]
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

186
82

21

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads under HPPWD Sub Division Dharampur (SH:-
of Slips and maintenance of berms in various roads)

Estimated cost :- 404303

Earnest Money:- 8100

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		Time Limit Two Months			
		In Figure	In words		
2	3	4	5	6	7
Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials up to all leads and lifts as per technical specification 302.3.5 and 1611 as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	306.00	95.00	Rupees NinetyFive Only	Per Cubic metre	29070
Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 and as per direction of Engineer - in -Charge.	22950.00	16.35	Rupees Sixteen Paise ThirtyFive Only	Per Cubic metre	375233
Total					404303

*Draft schedule of quantity approved
As. No 4303/- vide no. 186/2015-28*

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

Called

201
59

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads of under Dharampur Section HPPWD Sub
Dharampur (SH :- Deployment/Hiring of Excavator cum loader and Hiring of Tipper for removal of land

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		In Figure	In words		
	3	4	5	6	7
2 Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	295.00	1275.00	Rupees One Thousand Two Hundred SeventyFive Only	Per Hour	376125
Deployment/Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic ft Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge with in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	30.00	3050.00	Rupees Three Thousand Fifty Only	Per day	91500
Total:-					467625

Draft schedule of Quantity approved For
Rs 467625/- vide S.O No 201
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

75
165

23

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on Dharampur to Sandhole via Seoh (Portion Mayoh km 0/0 to Dharampur to Kalswai km 0/0 to 2/110 and Dharampur to Shidwala via Gujjar Nal (SH:- Hiring of Cum loader and Tipper for removal of land slides /slips)

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Deployment / Hiring of Excavator cum loader 0.90 cum (Zero point nine zero cubic metre) bucket capacity @ 20.00 (Twenty) cubic metre per hour for removal of slips, Road side berms, katch drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable materials from the road surface including cost of fuel oil lubricant and wages of staff , any repair /breakage during operation will be carried out by the contractor /owner at his own risk .shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3	1275.00	Rupees One Thousand Two Hundred SeventyFive Only	Per Hour	7 280500
Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	10.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Day	31500
				Total	312000

Draft schedule for quantity approved
RS.349250 / Vides No. 165.
2025-26

Executive Engineer,
 Dharampur Division
 H.P.W.D., Dharampur

39/181

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads under Baroti Section HPPWD Sub Division Mandap
 Hiring of Excavator Cum loader for removal of land slides /slips)

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		Time Limit			
2 Development / Hiring of Excavator cum loader 0.90 cum(Zero point nine zero cubic metre) bucket capacity @ 20.00(Twenty) cubic metre per hour for removal of slips, Road side berms, katch drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable materials from the road surface including cost of fuel oil lubricant and wages of staff , any repair /breakage during operation will be carried out by the contractor /owner at his own risk .shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3	4 1275.00	5 Rupees One Thousand Two Hundred SeventyFive Only	6 Per Hour	7 446250
Total					446250

Draft schedule of quantity approved as 446250 vide S/N No 181/2025-26

Executive Engineer,
 Dharampur Division
 H.P.W.D., Dharampur

181

DRAFT SCHEDULE OF QUANTITY

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		Earnest Money:-			
		In Figure	In words		
<p>Deployment/Hiring of Excavator cum loader & Hiring of Tipper for removal of land slide/slips)</p> <p>2</p> <p>Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.</p>	142.00	1300.00	Rupees One Thousand Three Hundred Only	Per Hours	184600
<p>Deployment/Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic ft Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge with in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.</p>	15.00	3200.00	Rupees Three Thousand Two Hundred Only	Per day	48000
				Total:-	232600

Draft Schedule of Quantity approved for Rs 232600/- vide S.No.181/2025-26

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

149
61

26

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub Division Mandap (SH :-
Deployment/Hiring of Excavator cum loader for removal of land slide/slips)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		Earnest Money:-			
		In Figure	In words		
2 Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	3 240.00	4 1275.00	5 Rupees One Thousand Two Hundred SeventyFive Only	6 Per Hours	7 306000
Total:-					306000

Draft schedule of quantity approved
As 306000/- vide S.No 149/202526

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur