

Himachal Pradesh  
Public Works Department

No PW/DD/CB/Tender/2025-26:-

10499-10506

Dated:- 13/02/2026

To

✓  
The Executive Engineer (I T Cell),  
O/o the Engineer-In- Chief,  
Nigam Vihar HPPWD Shimla-2

Subject: -

Publication of Tender Notice .

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sect. (PW) to the Govt. of Himachal Pradesh letter No PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.

*Chander Sheel*  
Executive Engineer,  
Dharamshala Division,  
HPPWD Dharamshala.

Copy forwarded for information to:-

1. The Superintending Engineer 5<sup>th</sup> Circle HPPWD Palampur.
2. All the Assistant Engineer working under this Division.
3. Copy to Ab/ DB of this Division.
4. Notice Board.

Executive Engineer,  
Dharamshala Division,  
HPPWD Dharamshala.



Office of Executive Engineer Dharamshala Division HPPWD Dharamshala  
Himachal Pradesh Public Works Department Dharamshala -176215  
Phone No.01892-224946 Fax 222065 E-mail [ee-dha-hp@nic.in](mailto:ee-dha-hp@nic.in)

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Dharamshala Division, HPPWD Dharamshala on emergent basis for the below mentioned works from the approved and eligible contractors enlisted in HPPWD so as to reach in his office on or before 17.02.2026 upto 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the tender opening committee and intending contractors/firms or their authorized representatives. The tender documents can be had from this office against cash payment/Non refundable) on 16.02.2026 between 2:00 PM to 5:00 PM and the applications for issue of tender forms shall be received upto 12:30 PM on 16.02.2026.

The Earnest Money in the shape of NSC's / FDR's Deposit/Bank Guarantee at Call of any of the Post office/Bank duly pledged in favour of XEN HPPWD, Dharamshala must be accompanied with the tender documents. Please note that no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will summarily be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserves the right to reject any tender or all tenders without assigning any reasons. The contractors should be registered as a dealer GST Tax Act.2018 and also produce the clearance certificate from the Excise and Taxation department and the contractor will also have to attach the labour employer licence from the labour office with the application. The tender documents shall only be issued to those contractors/firms who will produce the photo copy of their enlistment/renewal, if happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue:-

Sr. No.	Name of Work	Estimated cost in Rs.	EMD	Time limit	Cost of Tender form
1.	Restoration of rain damages on Dharamshala to Jule via Aghanjar Mahadev to Slate Godown road km 0/000 to 22/500 in Tehsil Dharamshala, Distt. Kangra H.P. (SH:- Consturction of breast wall at RD 13/380 to 13/394 ( 2nd step)	59466.00	1200.00	Two Months	350/-
2.	Restoration of rain damages on link road Anil Gas Agency Dari to GPS Kand in Km 0/000 to 2/500 in Tehsil Dharamshala, Distt. Kangra H.P. (SH:- C/P PCC Retaining wall at RD 1/385 to 1/389)	98578.00	2000.00	Two Months	350/-
3.	Annual repair and maintenance of link road Fatehpur to Matt Road km 0/000 to 2/500 in Dharamshala, Distt. Kangra H.P. (SH:- C/O U-shape drain at RD 4/800 To 4/850 and parapet 3 Nos. at R.D 4/840)	87520.00	1800.00	Two Months	350/-
4.	Repair of Jeepable road link road to Sh. Sudesh Kumar and other house G.P. Rakkar in Tehsil Dharamshala, Distt. Kangra H.P. (Deposit work) (SH:- Providing and laying interlocking paver block at RD 0/420 to 0/430)	61303.00	1200.00	Two Months	350/-
5.	Annual Repair and maintenance of various roads under Meledoganj section Sub division No. 1 HPPWD Dharamshala in Distt. Kangra H.P. (SH:-Painting and writing letters, figures on sign board and kilometres stôhe etcetera.)	99800.00	2000.00	One Month	350/-
6.	Repair and Maintenance of Residential Accommodation HPPWD Colony at Dharamshala, Distt. Kangra H.P. (SH:-Providing and laying tile flooring and steel work other minor repair work in Type-III quarter No. S-13 and N-2)	66491.00	1400.00	Two Months	350/-
7.	Repair and Mainteance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P. (SH:-Providing and laying Tile flooring, Painting, Distempering and Sanitary Installation etc in Type-III quarter No. 9 of Assistant Town Planner near B.E.d College Dharamshala)	95110.00	2000.00	Two Months	350/-
8.	Repair and Maintenance of Residential Accommodation HPPWD Colony at Dharamshala, Distt. Kangra H.P. (SH:-Painting and distempering, Sanitary Installation and other minor repair work in Type- IV quarter No.3)	49037.00	1000.00	Two Months	350/-
9.	Repair and Maintenance in General Pool Accommodation at Dharamshala, Distt. Kangra H.P. (Deposit work) (SH:-Providng and fixing Cup board and Sanitary Installation etc. in Type-IV quarter No.6 of AC to Divisional Commissioner at Chelian )	44072.00	900.00	Two Months	350/-
10.	Repair and Mainteance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P. (SH:-Providing and laying Tile flooring and sanitary Installation etc. in Type-III quarter No. 23 of Distt. Language Officer near B.E.d College Dharamshala)	99982.00	2000.00	Two Months	350/-
11.	Repair and Mainteance of office of Superintending of Police ( State Vigilance & Anti-Corruption Bureau) in the Complex of Mini Secretariat Building at Dharamshala, Distt. Kangra H.P. (SH:- Painting & distempering and other minor repair work etcetera)	43807.00	900.00	Two Months	350/-
12.	Repair and Mainteance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P. (SH:-Shifting of Sewerage line back side of quarter No. 17, Type- III near B.Ed college)	66215.00	1400.00	Two Months	350/-
13.	Repair and Maintenance of Residential accommadation of Additional Distt. Judge -2 at Khara Danda road Dharamshala, Distt. Kangra H.P (Sh:- Providing and fixing curtain rod, Aluminium and steel work and other minor repair work etc.)	38766.00	800.00	Two Months	350/-

14.	Repair and Maintenance of residential accommodation <b>IPS residence</b> at Depot Bazar Dharamshala, Distt. Kangra H.P. (SH:-Painting and Distempering work etc.)	53145.00	1100.00	Two Months	350/-
15.	Repair and maintenance of Residential accommodation of (Kothi No. A- 9 ) <b>Additional District &amp; Session Judge</b> at Dharamshala, Distt. Kangra H.P. (SH:- Providing and fixing pre-painted sheet roofing, painting work and water supply & Sanitary work etc.)	97526.00	2000.00	Two Months	350/-
16.	Repair and Maintenance of Residential Accommodation HPPPWD Colony at Dharamshala, Distt. Kangra H.P. (SH:-Providing and fixing wood work, distempering, painting and other minor repair work in Type- II quarter No J-11)	98387.00	2000.00	Two Months	350/-
17.	Repair and Maintenance of Residential Accommodation of District and Session Judge Kangra at Dharamshala, Distt. Kangra H.P. (SH:- Providing and fixing roofing and wood work etcetera in Type- VI accommodation for <b>District and session Judge</b> )	93280.00	1900.00	Two Months	350/-
18.	Repair and Maintenance of Type- V Residence District and Session Judge Kangra at Dharamshala, Distt. Kangra H.P. (SH:- Painting and distempering to Type- V residence of <b>District and Session Judge (Family court)</b> )	84230.00	1700.00	Two Months	350/-
19.	Construction of Judiciary at Dharamshala, Distt. Kangra H.P. (Deposit work) (SH:- Construction of Steel <del>rack</del> in record room on ground and first floor)	99638.00	2000.00	Two Months	350/-
20.	Repair and Maintenance of Residential building ( Kothi No. A-1) for <b>Chairman Waqf Board Tribunals</b> at Chilgari Dharamshala, Distt. Kangra H.P. (SH:-Providing and fixing PVC 2 Nos. water tank (1000 Ltr. Each)	25900.00	2000.00	Two Months	350/-
21.	Repair and Maintenance of Court room of <b>Senior Civil Judge cum Chief Judicial Magistrate</b> (Court-4) in Judicial Court Complex (Old Block) at Dharamshala, Distt. Kangra H.P. (SH:- Providing and Fixing wall panelling etc. .)	88151.00	1500.00	Two Months	350/-
22.	Repair and Maintenance of Court room of <b>Senior Civil Judge cum Chief Judicial Magistrate</b> (Court-4) in Judicial Court Complex (Old Block) at Dharamshala, Distt. Kangra H.P. (SH:- Providing and Fixing Carpeting, Distempering & painting and other minor repair work etc.)	73781.00	1500.00	Two Months	350/-
23.	Repair and Maintenance of Residential building of <b>Civil Judge cum JMFC-1</b> at Khara Danda road Dharamshala, Distt. Kangra H.P. (Sh:- Distempering and painting and other minor repair work etc.)	63144.00	1300.00	Two Months	350/-
24.	Repair and Maintenance of Deputy Commissioner State Taxation & Excise residence at Chilgari Dharamshala, Distt. Kangra H.P. ( <b>Deposit work</b> ) (SH:- Providing and fixing wood work & sanitary work etcetera)	69125.00	1400.00	Two Months	350/-
25.	Repair and Maintenance of Deputy Commissioner office building at Dharamshala, District Kangra H.P. (SH:- Balance work for Construction of Sewerage Chamber and cleaning of manhole / chamber of sewerage pipe work etcetera)	93837.00	1900.00	Two Months	350/-
26.	Repair and Maintenance Residential Accommodation HPPPWD Colony Darnu at Dharamshala, Distt. Kangra H.P. (SH:-Providing and fixing Aluminium work, distempering, painting and other minor repair work in Type- IV quarter No.-1)	99600.00	2000.00	Two Months	350/-

Certified that above work for Sr. No 1 to 25 are urgent nature and require immediate execution.

*Chander Sheel*  
Executive Engineer,  
Dharamshala Division,  
HPPWD Dharamshala

On behalf of Governor of Himachal Pradesh.

No. PWD-DD/CB/M-34/-2025-26:-

10507-30

Dated 13/02/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ) HP.PWD Dharamshala.
2. The Superintending Engineer, 5th Circle HP.PWD, Palampur.
3. The Deputy Commissioner Kangra at Dharamshala.
4. The Commissioner Dharamshala Municipal Corporation.
5. All the Executive Engineer, working under Kangra Zone.
6. The SDM & Tehsildar Dharamshala.
7. The BDO Dharamshala /Rait.
8. All the Assistant Engineers working under this Division.
9. All the Head of the Branches in this office.
10. All the Contractors working under this Division.
11. Notice Board.

*Chander Sheel*  
Executive Engineer,  
Dharamshala Division,  
HPPWD Dharamshala

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 59466.00  
 Earnest Money :-Rs.1200.00  
 Time Limit :- Two Months.

**Name of work:-** Restoration of rain damages on Dharamshala to jule via Aghanjar Mahadev to slate Godown road km 0/0 to 22/500 in Tehsil Dharamshala, Distt. Kangra H.P.(SH :- Construction of breast wall at RD. 13/380 to 13/394 (2nd step).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water for all type of structure, in R/wall / B/wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths including cost of form work and curing complete for 14 (fourteen) days as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax,GST or any other taxes imposed by the Government.	10.92 Cubic metre	5050.00	Rupees Five Thousand Fifty Only	Per Cubic metre	55146.00
2	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetres) diameters P.V.C. pipe extending through the full width of the structure with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specifications Clause 614, 709, 1204.3.7, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government..	12.00 Numbers	360.00	Rupees Three Hundred Sixty Only	Each	4320.00
	<b>Total</b>					<b>59466.00</b>
			(Amount to be quoted by the contractor in figure)			
			(Amount to be quoted by the contractor in words)			

  
 Executive Engineer,  
 HPPWD (B&R) Division,  
 DHARAMSALA

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 98578.00  
 Earnest Money :-Rs.2000.00  
 Time Limit :- Two Month.

Name of work:- Restoration of rain damages on Link road Anil Gas agency Dari to GPS Kand in Km.0/0 to 2/500 in Tehsil Dharamshala, Distt. Kangra H.P. (SH:- C/o PCC Retaining wall RD.1/385 to 1/389).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantum of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as direction of Engineer-in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	11.30 Cubic metre	360.00	Rupees Three Hundred Sixty Only	Per Cubic metre	4,068.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate) 40 mm (forty millimetre) nominal size in retaining wall including the cost of centering, shuttering and finishing complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	18.62 Cubic metre	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per Cubic metre	90,307.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetres) diameters P.V.C. pipe extending through the full width of the structure with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specifications Clause 614, 709, 1204.3.7, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government..	6.00 Numbers	360.00	Rupees Three Hundred Sixty Only	Each	2160.00

275

5

4	Back filling behind abutment, wing wall and return wall complete as per drawing & Technical Specification Clause-1204.3.8 Granular material and as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.15 cubic metre	950.00	Rupees Nine Hundred Fifty Only	Per Cubic metre	2,043.00
<b>Total</b>						<b>98,578.00</b>
Quoted rate in figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 HPPWD (B&R) Division,  
 DHARAMSALA

SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 87,520.00

Earnest Money :-Rs. 1800.00

Time Limit :- Two Month.

**Name of work:-** Annual repair and maintenance of link road Fatehpur to Matt road Km 0/0 to 5/00 in Tehsil Dharamshala Dist. Kangra HP (SH:- C/o U-shape drain at RD 4/800 to 4/850 and parapet 3nos at RD. 4/840).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantity of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as directed by Engineer-In-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	34.80 Cubic metre	360.00	Rupees Three Hundred Sixty Only	Per Cubic metre	12528.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:3:6 (One cement into three sand into six graded crushed stone aggregate 20mm (twenty millimeter) nominal size), on ground or under water for all type of structure, in drain edge wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths including cost of form work and curing complete for 14 (fourteen) days as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax,GST or any other taxes imposed by the Government.	13.76 Cubic metre	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per Cubic metre	74992.00
		<b>Total</b>				<b>87520.00</b>
			<b>(Amount to be quoted by the contractor in figure)</b>			
			<b>(Amount to be quoted by the contractor in words)</b>			

  
 Executive Engineer,  
 HPPWD (B&R) Division,  
 DHARAMSALA


141

SCHEDULE OF QUANTITY

Estimate Cost :- Rs.61373.00  
Earnest Money :-Rs.1200.00  
Time Limit :- Two Month.

Name of work:- Repair of Jeepable road link road to Sh. Sudesh Kumar and other house G.P. Rakkar in Tehsil Dharamshala, Distt. Kangra H.P. (Deposit work) (SH:- Providing and laying Interlocking paver block at Rd. 0/470 to 0/430)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate) 40 mm (forty millimetre) nominal size.in all type of structure and retaining wall including the cost of centering, shuttering and finishing complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	3.05 Cubic metre	5050.00	Rupees Five Thousand Fifty Only	Per Cubic metre	15,403.00
2	Providing and laying 60mm Sixty millimetres) thick inter locking paver blocks heavy duty precast cement concrete of NTC or as approved by the HPPWD inter locking paver blocks vibro compacted upto M-50 (M-Fifty) grade including border or kurb block Grey or coloured over sub-base of concrete withn 25mm (Twenty five millimetres) thick average thickness of cement mortar 1:4 (One cement : Four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub-base concrete floor to be paid for separately) as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, maikana and all type of taxes imposed by the Government.	34.00 Square metre	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square metre	45,900.00
<b>Total</b>						<b>61,303.00</b>
						(Amount to be quoted by the contractor in figure)
						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 HPPWD (P&R) Division,  
 DHARAMSALA

356

## Schedule of Quantity

ESTIMATED COST:- Rs. 99800.00  
 EARNEST MONEY:- Rs. 2000.00  
 TIME LIMIT : One month

NAME OF WORK :- Annual Repair and maintenance of various roads under Mcleodganj section Sub division No. 1 HPPWD Dharamshala in Distt. Kangra H.P.  
 SUB HEAD :- Painting and writing letters, figures on sign board and kilometres stone etcetera.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4		5	6
1	Painting two coats (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter enamel paint other than white, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	94.35 Square metres	90.00	Rupees ninety and paise zero only	Per square metre	8492.00
2	Painting two coats (excluding priming coat) on previously painted concrete/ masonry/plastered surfaces with enamel paint of approved brand and manufacture for use on floors to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering as required, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	50.65 Square metres	85.00	Rupees eighty five and paise zero only	Per square metre	4305.00
3	Writing letters or figures on any surface with Synthetic enamel paint ( other than white) stops, comas, hyphens and the like not to be measured and paid separately) in Block letters/figures, including entire carriage of materials, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2867.66 Centi-metres	2.10	Rupees two decimal ten zero only	Per Centi metre	6022.00
4	Writing letters or figures on any surface with Synthetic enamel paint ( other than white) stops, comas, hyphens and the like not to be measured and paid separately) in Indian letters/ figures, including entire carriage of materials , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	37665.66 Centi-metres	2.15	Rupees two decimal one five only	Per Centi metre	80981.00
<b>TOTAL:-</b>						<b>99800.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

*Chandrasekhar*  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 66491.00  
 EARNEST MONEY :- ₹ 1400.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Repair and maintenance of residential accommodation HPPWD colony at Dharamshala Distt. Kangra H.P.

SUB-HEAD :- Providing and laying flooring tile, Steel work and other minor repair work etc. in type- III quarters No. S-13 and N-2

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Steel work Tata/ Sail in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes, within all leads, lifts of materials and other. Incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	211.79 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	22238.00
2	Providing 0.63 mm ( zero decimal sixty three millimetres) thick with zinc coating not less than 275 gm/ m <sup>2</sup> ( two hundred seventy five gram per square metre) corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required, within all leads, lifts of materials and other. Incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	16.14 Square metres	1200.00	Rupees One Thousand Two Hundred Only	Per square metre	19368.00
3	Providing flushing 38cm( thirty eight centimetres) overall in 0.63mm ( Zero decimal sixty three millimetres) thick plain G.I. sheet fixed with galvanised iron. J or L hooks, bolts and nuts, G.I. limpet washer and bitumen washers complete bent to shape and fixed in walls with cement mortar 1:3 (one cement isto three sand) with all accessories within all leads, lifts of materials and other. Incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	18.90 Running metres	650.00	Rupees Six Hundred Fifty Only	Per running metre	12285.00

1	2	3	4	5	6	7
4	<p>Providing and fixing 1st quality ceramic glazed wall tiles 300x450mm ( three hundred into four hundred fifty ) of Kajaria / Johnson / Nitco / Orient / Bell / Somany / AGI conforming to IS : 15622 (thickness to be specified by the manufacturer ) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm ( twelve milimetres) thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 ( at the rate three decimal three) kilogram per square metres including pointing in white cement mixed with pigment of matching shade complete, within all leads, lifts of materials and other. Incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	12.00 Square metres	1050.00	Rupees One Thousand Fifty Only	Per Square metre	12600.00
<b>TOTAL :-</b>						<b>66491.00</b>
<b>Quated Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure )</b>
<b>Quated Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala.

**DRAFT SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 95110.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Repair and Maintenance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P.  
**SUB-HEAD :-** (SH):-Providing and laying Tile flooring, Painting, Distemping and Sanitary Installation etc in Type-III quarter No. 9 of Assistant Town Planner near B.E.d College Dharamshala)

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Demolition above G.L. upto floor two level including disposal of unserviceable materials within 20 metres lead un-reinforced cement concrete upto 15cm ( fifteen centimetres) thickness, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.45 Cubic metres	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic metre	608.00
2	Providing and laying in position cement concrete of specified grade including the cost of form work in foundation and plinth 1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm ( forty millimetres) nominal size), as per approved drawing, design and specification including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	0.45 Cubic metres	5050.00	Rupees Five Thousand Fifty Only	Per Cubic metre	2273.00
3	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 mtr. (fifty metres ) lead of area 3 sqm (three square metre ) and below , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	70.00	Rupees Seventy Only	Each	140.00
4	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked including fixing with approved adhesive etc. complete including entire carriage of materials as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.					
i	75mm (One hundred ten millimetres) diameter	1.40 Running metres	350.00	Rupees Three Hundred Fifty Only	Per running metre	490.00
ii	100mm (One hundred millimetre) diametres	1.20 Running metres	400.00	Rupees Four Hundred Only	Per running metre	480.00

1	2	3	4	5	6	7
5	Providing and fixing P.V.C Plain bend of Supreme/Finolex/Vectus/Relpipe (reliance) including fixing with approved adhesive complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	200.00	Rupees Two Hundred Only	Each	400.00
	i) 110mm (One hundred ten millimetre) diametres	2.00 Numbers	150.00	Rupees One Hundred Fifty Only	Each	300.00
	ii) 75mm (seventy five millimetre) diametres	1 Number	520.00	Rupees Five Hundred Twenty Only	Each	520.00
6	Providing and fixing 110 x 90 mm ( one hundred ten into ninety millimetre) nominal size/diameter P.V.C. floor trap ISI marked of Finolex, Relpipe (Reliance), Vectus ISI marked Confirming to BIS-14735-99 of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floor etcetera complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.69 Square metres	1325.00	Rupees One Thousand Three Hundred Twenty Five Only	Per square metre	6214.00
7	Providing and laying 300X300 mm (three hundred into three hundred millimetre) antiskid Ceramic tile of Orient/RAK/Kajaria/Somany/Johnson/ Bell in flooring on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.05 Square metres	1050.00	Rupees One Thousand Fifty Only	Per square metre	13703.00
8	Providing and laying 300X450 mm (three hundred into four hundred fifty millimetre) ceramic white Glazed tile of Kajaria/ Swastik / Somany / Bell / AGL/Johnson in skirting risers of steps and dados on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					

1	2	3	4	5	6	7
9	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	8500.00	Rupees Eight Thousand Five Hundred Only	Each	8500.00
10	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass angle valve of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931 as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
11	Providing and fixing 15mm (Fifteen millimetres) nominal bore uplasticsed PVC connection pipe with brass union 45cm (Forty five Centimetres) length of Finolex , Relpipe (Reliance ) , Vectus as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	500.00
12	Providing and fixing 100mm (One hundred millimetre) diametres C.P. Grating of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal for gully floor or Nahni trap , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	100.00	Rupees One Hundred Only	Each	300.00
13	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) old wood and wood based surface with enamel paint other than white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	68.58 Square metres	90.00	Rupees Ninety Only	Per square metre	6172.00

1	2	3	4	5	6	7
14	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	250.75 Square metres	75.20	Rupees Seventy Five And Paise Twenty Only	Per Square metre	18856.00
15	Providing and applying white cement based putty of Birla / JK average thickness 1 mm ( one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	37.61 Square metres	73.50	Rupees Seventy Three And Paise Fifty Only	Per square metre	2764.00
16	Providing and laying 15 mm ( fifteen millimetre) nominal bore to wall ceiling and floor galvanised mild steel tubes (Medium grade) of Tata/Jindal tube fitting and clamps including making good the wall, ceiling and floor complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	2.60 Running metres	450.00	Rupees Four Hundred Fifty Only	Per running metre	1170.00
17	Providing and fixing 15 mm ( fifteen millimetre) nominal bore C.P. brass bib tap of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of approved quality conforming to IS:8931 as approved by Engineer - in - charge and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
18	Providing and fixing 32 mm (Thirty two millimetres) diametres P.V.C. waste pipe for wash basin and sink including P.V.C. fittings complete Semi rigid pipe 30mm ( thirty two millimetres) diametres complete, within all leads, lifts of material and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	190.00	Rupees One Hundred Ninety Only	Each	380.00
19	Providing and laying cement concrete 1:2:4 (one cement isto two Sand isto four graded stone aggregate 20mm ( twenty millimetres) nominal size) and curing complete mechanically mixed and vibrated excluding cost of form work in foundation and plinth as per approved specification, drawing and design complete upto floor all level, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1.20 Cubic metres	6650.00	Rupees Six Thousand Six Hundred Fifty Only	Per cubic metre	7980.00

1	2	3	4	5	6	7
20	Providing and fixing factory made PVC door frame single rebate of any clours of size 50x47mm with a wall thickness of 5mm made out of extruded 5mm rigid PVC foam sheet heat bend & mitred at corners and jointed with 2 Nos. of 150mm long brackets of 15mmx15mm M.S. square tube, the vertical door profiles to be reinforced with 19mmx19mm M.S. square tube of 19 gauge EPDM rubber gasket weather seal to be provided throughout the frame i/c fixing of door frame to wall with M.S. screws 100long with wooden or rawl plugs emedded in masonry complete as per approved shade within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	9.50 Running metres	580.00	Rupees Five Hundred Eighty Only	Per running metre	5510.00
21	Providing and fixing to existing door frames, 30mm (Thirty millimetres) thick factory made PVC panelled door shutter consisting of frame made out of M.S. tubes of 19 (Nineteen) gauge thickness and size of 19mm x19mm (Nineteen into nineteen millimetres) for styles and 15mmx15mm (Fifteen into fifteen millimetres) for top & bottom rails, code 9.120 of Rajshri M.S. frame shall have a coat of steel primers of approved make and manufacture M.S. frame covered with 5mm (Five millimetres) thick heat moulded PVC "C" channel of size 30mm (Thirty millimetres) thickness, 70mm (Seventy millimetres) width out of which 50mm (Fifty millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapped in 45 (Forty five ) degree angle on either side forming style and 5mm (Five millimetres) thick, 95mm (Ninety five millimetres) wide, PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered in 45 (Forty five) degree on the inner side to form top and bottom rail and 115mm (One hundred fifteen) wide PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered on both side to form lock rail, top, bottom and lock rail shall be provided either side of the panel 10mm (Ten millimetres) thick, 20mm (Twenty millimetres) wide cross PVC sheet be provided as gap insert for top rail and bottom rail paneling of 5mm thick both side PVC Sheet to be fitted in the M.S. frame welded/sealed to the style & rails, joints mitred and jointed with solvent cement adhesive i/c fixing of PVC shutter with existing frame with M.S. butt hinges 100x50x1.90mm ( One hundred into fifty into one decimal ninety millimetres) size with necessary screws etc complete as directed by the Engineer-in-Charge.within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Square metres	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per square metre	9450.00
22	Providing and fixing 250x16mm (Two hundred fifty into Sixteen millimetres) size Pilot/sheel anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	200.00	Rupees Two Hundred Only	Each	400.00
23	Providing and fixing 100x10mm ( one hundred into ten millimetres) size aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etc.Tower bolts (Barrel type) as approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4 Numbers	150.00	Rupees One Hundred Fifty Only	Each	600.00

1	2	3	4	5	6	7
24	Providing and fixing 125mm (One hundred twenty five millimetre) size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	4.00 Numbers	125.00	Rupees One Hundred Twenty Five Only	Each	500.00
TOTAL :-						95110.00

*DNIT Checked and approved for  
₹ 95110 Ten only*

*Chandrasekhar*  
Executive Engineer,  
Dharamshala Division,  
HPPWD Dharamshala

**SCHEDULE OF QUANTITY**

Estimate Cost :- Rs. 49037.00  
 Earnest Money :-Rs. 1000.00  
 Time Limit :- Two Months.

Name of work:- Repair and Maintenance of residential accommodation HPPWD colony at Dharamshala District Kangra H.P. (Sub Head :- Painting, distemping & sanitary installation and other minor repair work etc. in Type-IV Qtr. No. 3).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Dismantling tile work in flooring and roofing work by manually/ by mechanical means including stacking of flooring and roofing and disposal of unserviceable material at suitable as per the direction of Engineer - in-charge. including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.(Note :- usefull material obtain after dismantling / Demolising will be stacked at suitable place as per the direction of the Engineer - in -charge and handed over to the department).	5.09 Square metre	90.00	Rupees Ninety Only	Per Square metre	458.00
2	Providing and laying Ceramic glazed wall tiles of Kajaria /Johnson / Nitco /Orient /Bell of size 300x300 mm (three hundred into four hundred fifty millimetres)or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetres) thick cement mortar 1:3 (1 Cement: 3 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm at the rate of three point three kilogramme per square metre) including grouting the joints with white cement and matching pigments etc., complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST and any other taxes imposed by the Government.	5.09 Square metre	1050.00	Rupees One Thousand Fifty Only	Per Square metre	5345.00
3	Wall painting with acrylic emulsion paint of Asians Paints /Nerolac suraksha /Berger paint approved brand and manufacture to give an even shade, two or more coats , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	258.72 Square metre	105.00	Rupees One Hundred Five Only	Per Square metre	27166.00
4	Painting woodwork with premium enamel of Asian/Nerolac Paint to give an even shade, Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	69.72 Square metre	110.00	Rupees One Hundred Ten Only	Per Square metre	7669.00

5	Painting Steel work with premium enamel of Asian/Nerolac Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.80	Square metre	100.00	Rupees One Hundred Only	Per Square metre	480.00
6	Providing and applying white cement (Birla white/JK) based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	25.87	Square metre	73.00	Rupees Seventy Three Only	Per Square metre	1889.00
7	Providing and fixing 15mm (fifteen millimetres) nominal bore C.P. brass bib cock tap of continental series of Jajuar/Contess series of Hindware/ Ocean series of Cera/ Vintage series of Kerovit and Hindon series of Jal complete within all leads, lifts including carriage of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	2.00	Numbers	1050.00	Rupees One Thousand Fifty Only	Each	2,100.00
8	Providing and fixing 15 mm nominal bore C.P. brass angle valve of Continental series of Jaquar /classik series of Hindware /floralseries of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to 8931complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government	2.00	Numbers	1050.00	Rupees One Thousand Fifty Only	Each	2,100.00
9	Providing and fixing 32 mm dia P.V.C.flexible waste pipe of Finolex , Relipee (Reliance ) , Vectus for sink or wash basin including P.V.C. waste fittings complete within all leads, lifts including carriage of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of toll taxes, GST and any other taxes imposed by the Government	2.00	Numbers	290.00	Rupees Two Hundred Ninety Only	Each	580.00

10	Providing and fixing 600x450mm (Six hundred into four hundred fifty) beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	Numbers	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	1,250.00
	<b>Total</b>						49037.00
	Quoted rate in figure (%)						
	Quoted rate in Words (%)						

  
 Executive Engineer,  
 HPPWD (B&R) Division,  
 DHARAMSALA.

354

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 44072.00  
 EARNEST MONEY :- ₹ 900.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Repair and Maintenance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P. (Deposit work)  
 SUB-HEAD :- Providing and fixing Cup board and sanitary installation work etcetera in Type-IV quarter No. 6 of AC to BC at Chellan  
 Divisional Commr. & Jno. 1

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and installation 3 L ( three Litres) capacity Instant Geyser (Cat-A) of stationary storage type Electric water heater (Geyser) of various sizes by means of Expansion-bolts with nuts and washers, including embedding of expansion bolts in the wall, providing and fixing of Non-return valve, Dead weight safety valve, 2 No (two numbers) C.P. connection rods 18" (eighteen inch ) long, making good the damages, electrical connections, safety valve connections, testing and commissioning etc. as required:- Makes: Racold/Bajaj/Havells, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	3800.00	Rupees Three Thousand Eight Hundred Only	Each	3800.00
2	Providing and fixing 15L ( fifteen Litres) KENT Supreme Alkaline - B Aquaguard Water Purifier approved quality with necessary screws etcetera complete in all respect, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	11000.00	Rupees Eleven Thousand Only	Each	11000.00
3	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	63.38 Square metres	125.00	Rupees One Hundred Twenty Five Only	Per square metre	7923.00
4	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade One or more coats on new work , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	20.00 Square metres	95.00	Rupees Ninety Five Only	Per square metre	1900.00

1	2	3	4	5	6	7
5	Complete box of cupboard of 25mm (Twenty five millimetres) thick water proof termite resistant commercial board Uniply / Green ply /Kit ply /Dura ply / Marino (ISI Marked ) for shutter including 19mm thick shutter. Back side of cupboard shall be 6 to 8 mm (six to eight millimetre) thick water proof ply. The shutter from all side shall also have 6mm (six millimeter) thick hard board edging/ Topping to be finished with 1mm (one millimeter) thick mica lamination of Century / Greenlam / Action Tesa / Merinolam approved shade of office including fixing handles be provided in wood colour with nickel plated piano hinges with screws etcetera within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	4.01 Square metres	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per square metre	19449.00
					<b>TOTAL :-</b>	<b>44072.00</b>
<b>Quoted Rate in Figure (%)</b>						
<b>Quoted Rate in Words (%)</b>						
<b>(Amount to be quoted by the contractor in Figure )</b>						
<b>(Amount to be quoted by the contractor in words)</b>						

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWP Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99982.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and Maintenance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P.  
SUB-HEAD :- (SH:-Providing and laying Tile flooring and sanitary Installation etc. in Type-III quarter No. 23 of Distt. Language Officer near B.E.d College Dharamshala)


S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Demolition above G.L. upto floor two level including disposal of unserviceable materials within 20 metres lead un-reinforced cement concrete upto 15cm ( fifteen centimetres) thickness, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.41 Cubic metres	1400.00	Rupees One Thousand Four Hundred Only	Per Cubic metre	1974.00
2	Providing and laying in position cement concrete of specified grade including the cost of form work in foundation and plinth 1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm ( forty millimetres) nominal size), as per approved drawing, design and specification including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	1.41 Cubic metres	5050.00	Rupees Five Thousand Fifty Only	Per Cubic metre	7121.00
3	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 mtr. (fifty metres) lead of area 3 sqm (three square metre) and below, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	70.00	Rupees Seventy Only	Each	140.00
4	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked including fixing with approved adhesive etc. complete including entire carriage of materials as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.					0.00
i	75mm (One hundred ten millimetres) diameter	2.20 Running metres	350.00	Rupees Three Hundred Fifty Only	Per running metre	770.00
ii	100mm (One hundred millimetre) diameters	3.00 Running metres	400.00	Rupees Four Hundred Only	Per running metre	1200.00

1	2	3	4	5	6	7
5	<p>Providing and fixing P.V.C Plain bend of Supreme/Finolex/Vectus /Relpipe (reliance) including fixing with approved adhesive complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	2.00 Numbers	200.00	Rupees Two Hundred Only	Each	400.00
i	110mm (One hundred ten millimetre) diametres	3.00 Numbers	150.00	Rupees One Hundred Fifty Only	Each	450.00
ii	75mm (seventy five millimetre) diametres	3 Numbers	520.00	Rupees Five Hundred Twenty Only	Each	1560.00
6	<p>Providing and fixing 110 x 90 mm ( one hundred ten into ninety millimetre) nominal size/diameter P.V.C. floor trap ISI marked of Finolex , Relpipe (Reliance ) , Vectus ISI marked Confirming to BIS-14735-99 of self cleaning design including fixing with approved adhesive , cost of cutting and making good the wall and floor etcetera complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	4.69 Square metres	1325.00	Rupees One Thousand Three Hundred Twenty Five Only	Per square metre	6214.00
7	<p>Providing and laying 300X300 mm (three hundred into three hundred millimetre) antiskid Ceramic tile of Orient/RAK/Kajaria/Somany/Johnson/ Bell in flooring on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	16.80 Square metres	1050.00	Rupees One Thousand Fifty Only	Per square metre	17640.00
8	<p>Providing and laying 300X450 mm (three hundred into four hundred fifty millimetre) ceramic white Glazed tile of Kajaria/ Swastik / Somany / Bell / AGL/Johnson in skirting risers of steps and dados on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>					

1	2	3	4	5	6	7
9	<p>Providing and fixing 10mm (Ten millimetres) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundred into six hundred into ten millimetres) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm (Twelve millimetres) thick cement mortar 1:3 (One cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.</p>	7.23 Square metres	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square mere	9761.00
10	<p>Repairs to plaster of thickness 12 mm (twelve millimetres) to 20 mm ( twenty millimetres) in patches of area 2.50 ( two decimal five zero ) sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete With cement mortar 1:4 (one cement isto four fine sand) as per direction of Engineer-in-Charge as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	2.34 Sqaure metres	290.00	Rupees Two Hundred Ninety Only	Per square metre	679.00
11	<p>Providing and fixing 18 mm ( Eighteen millimetre) thick polished Grey / Cheema Pink Granite having semi round nosing gang saw cut, mirror polished, premoulded and prepolished, machine cut for work top of Toilet shelves, water trough and Kitchen works top over 20 mm ( twenty millimetre) thick base of cement mortar 1:4 (one cement isto four coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etcetera complete , as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.</p>	2.30 Square metres	5650.00	Rupees Five Thousand Six Hundred Fifty Only	Per Square metre	12995.00
12	<p>Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	1.00 Number	8500.00	Rupees Eight Thousand Five Hundred Only	Each	8500.00

1	2	3	4	5	6	7
13	Providing and fixing wash basin 610x 450 mm ( six hundred ten into four hundred fifty millimetres) of Cera / Hindware / Jaquar of star white/snow shade with single 15 mm C.P. brass pillar tap with C.I. brackets, 32 mm (thirty two millimetres) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require., as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
14	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass angle valve of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931 as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
15	Providing and fixing 15mm (Fifteen millimetres) nominal bore uplasticsed PVC connection pipe with brass union 45cm (Forty five Centimetres) length of Finolex , Relpipe (Reliance ) , Vectus as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	500.00
16	Providing and fixing 100mm (One hundred millimetre) diametres C.P. Grating of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal for gully floor or Nahni trap , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	100.00	Rupees One Hundred Only	Each	300.00
17	Providing and fixing Second class deodar wood 40mm (forty millimetres) thick shutters panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) , as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Square metres	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per Square metre	15750.00

1	2	3	4	5	6	7
18	Providing and fixing 125mm (One hundred twenty five millimetre) size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	4.00 Numbers	125.00	Rupees One Hundred Twenty Five Only	Each	500.00
19	Supplying and fixing 4mm ( four millimetre) glass panes ( weight not less than 10.0 kg per sqm ( ten decimal zero kilogram per squaremetres) with putty and nails including removal of broken glass panes wherever necessary, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.55 Square metres	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square metre	633.00
20	Providing and fixing 15mm (Fifteen millimetres) nominal bore C.P. brass ball valve of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal and approved quality, High or low pressure, with plastic floaters complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	2 Numbers	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
21	Providing and laying 15 mm ( fifteen millimetre) nominal bore to wall ceiling and floor galvanised mild steel tubes (Medium grade) of Tata/Jindal tube fitting and clamps including making good the wall, ceiling and floor complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	5.60 Running metres	450.00	Rupees Four Hundred Fifty Only	Per running metre	2520.00
21	20mm ( twenty millimetre) nominal bore	2.50 Running metres	450.00	Rupees Four Hundred Fifty Only	Per running metre	1125.00
<b>TOTAL :-</b>						<b>99982.00</b>
<b>Quoted Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure )</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala


SCHEDULE OF QUANTITY

Estimate Cost :- Rs. 43807.00  
 Earnest Money :-Rs. 900.00  
 Time Limit :- Two Months.

Name of work:- Repair and maintenance of office of the Superintendent of Police State vigilance & Anti corruption Bureau North range Dharamshala District Kangra  
 (Sub Head :- Painting and distemping and other minor repair work etc.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Wall painting with acrylic emulsion paint of Asians Paints /Nerolac suraksha /Berger paint approved brand and manufacture to give an even-shade; two or more coats , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, maikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	88.93	105.00	Rupees One Hundred Five Only	Per Square metre	9338.00
2	Providing and applying white cement (Birla white/JK) /based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, maikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.60	73.00	Rupees Seventy Three Only	Per Square metre	701.00
3	Providing and fixing blinds curtain with all necessary fitting including entire carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, maikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	8.31	2800.00	Rupees Two Thousand Eight Hundred Only	Per Square metre	23268.00

4	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) continental series of Jaquar / Contess plus series of Hindware / Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal with seat and lid, ( Single piece ) with manually controlled device including jet conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	Number	10500.00	Rupees Ten Thousand Five Hundred Only	Each	10,500.00
	<b>Total</b>						43807.00
	Quoted rate in figure (%)		(Amount to be quoted by the contractor in figure)				
	Quoted rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 HPPWD (B&R) Division,  
 DHARAMSALA

352

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 66215.00  
 EARNEST MONEY :- ₹ 1400.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Repair and Maintenance of General Pool Accommodation at Dharamshala, Distt. Kangra H.P.

**SUB-HEAD :-** Shifting of Sewerage line back side of quarter, Providing and Fixing sanitary installation and other minor repair work etc. in quarter No. 17, Type-III near B.Ed college.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Demolition above G.L upto floor level including disposal of unserviceable materials within 20 metres lead un-reinforced cement concrete upto 15cm ( fifteen centimetres) thickness, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.60 Cubic metres	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per cubic metre	750.00
2	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms; depth upto any depth including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm (twenty centimetres) in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated within all leads, lifts and other incidental and as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.00 Running metres	319.60	Rupees Three Hundred Nineteen And Paise Sixty Only	Per Running metres	4155.00
3	Providing and fixing 110mm ( one hundred ten millimetre) diametres high pressure PVC spigot and socket, waste and ventilating pipes ISI marked of Finolex , Relpipe (Reliance ), Vectus including fixing with approved adhesive etcetera Complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.00 Running metres	490.50	Rupees Four Hundred Ninety And Paise Fifty Only	Per Running metre	6377.00
4	Providing and fixing 110mm (One hundred ten millimetre) diametres P.V.C Plain bend of of Supreme/Finolex/Vectus /Relpipe (reliance) including fixing with approved adhesive complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	380.00	Rupees Three Hundred Eighty Only	Each	760.00

1	2	3	4	5	6	7
5	<p>Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (one cement isto four coarse sand) C.I. cover with frame (light duty) 455x610 mm ( four hundred fifty five into six hundred ten millimetres) internal dimensions, total weight of cover with frame to be not less than 38 kg ( thirty eight kilogram) (weight of cover 23 kg ( twenty three kilogram) and weight of frame 15 kg ( fifteen kilogram), R.C.C. top slab with 1:1.5:3 mix (one cement isto one decimal five Fine sand isto three graded stone aggregate 20 mm ( twenty millimetres) nominal size), foundation concrete 1:5:10 (one cement isto five fine sand isto ten graded stone aggregate 40 mm ( forty millimetres) nominal size), inside plastering 12 mm ( twelve millimetres) thick with cement mortar 1:3 (one cement isto three coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etcetera complete as per standard design Inside dimensions 455x610 mm ( four hundred fifty five into six hundred ten millimetres) and 45 cm ( forty five centimetres) deep for single pipe line with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 ( seven decimal five), within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	1 Number	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Each	6250.00
6	<p>Providing and laying cement concrete 1:3:6 (1 Cement : 3 Sand : 6 graded stone aggregate 40mm nominal size ) bedding for stoneware pipes of the following internal diameters,necessary form work and curing complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	13.00 Running metres	750.00	Rupees Seven Hundred Fifty Only	Per Running metre	9750.00
7	<p>Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement isto 2 coarse sand isto 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement isto 3 coarse sand). For pipes 100 to 250 mm ( one hundred to two hundred fifty millimetres )diameter finished with a floating coat of neat cement and making necessary channels for the drain etc. complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	1 Number	550.00	Rupees Five Hundred Fifty Only	Each	550.00
8	<p>Cleaning brick masonry manhole / Chambers Inside size 800x800x1000mm ( Eight hundred into eight hundred into one thousand millimetres) and 900cm ( Nine hundred millimetres) deep, as per directions and entire satisfaction of the Engineer-in-Charge including disposal of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, maikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.</p>	2 Numbers	5000.00	Rupees Five Thousand Only	Each	10000.00

1	2	3	4	5	6	7
9	Providing and laying cement concrete 1:2:4 (one cement iso two Sand iso four graded stone aggregate 20mm ( twenty millimetres) nominal size) and curing complete mechanically mixed and vibrated including cost of form work in foundation and plinth as per approved specification, drawing and design complete upto floor all level, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	0.60 Cubic metres	6650.00	Rupees Six Thousand Six Hundred Fifty Only	Per cubic metre	3990.00
10	Providing and fixing 15 mm ( fifteen millimetre) nominal bore C.P. brass stop cock (concealed) Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal of standard design and of approved make conforming to IS : 8931 , within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Numbers	1200.00	Rupees One Thousand Two Hundred Only	Each	1200.00
11	Providing and fixing 15mm (Fifteen millimetres) nominal bore P.V.C. unplasticised connection pipe with PTMT nuts , collar and bush of approved quality and colour brass union 30/ 45cm (Thirty or Forty five Centimetres) length complete and within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Numbers	150.00	Rupees One Hundred Fifty Only	Each	150.00
12	Providing and fixing white vitreous china pedestal type water closet (European type) No 20087 (S - 10 ) Size 57 X 35 X 39 cm ( fifty seven into thirty five into thirty nine centimetre) with ISI Marked white solid plastic seat and lid, 10 (ten) litre low level white PVC flushing cistern (sleek Plus) having dual flush system Hindware, Cera, Jaquar of star white / Snow white shade and as shown in the drawing / as per details & C.P. flush bend with fittings & C.I. brackets, 40 mm ( forty millimetres) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	1 Number	9899.40	Rupees Nine Thousand Eight Hundred Ninety Nine And Paise Forty Only	Each	9899.00
13	Providing and fixing 32 mm ( thirty two millimetre) dia P.V.C. flexible waste pipe of Finolex / Relpipe (Reliance ) / Vectus for sink or wash basin including P.V.C. waste fittings complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Numbers	230.00	Rupees Two Hundred Thirty Only	Each	230.00

1	2	3	4	5	6	7
14	Providing and fixing 8 mm ( eight millimetre) diameter C.P. / S.S. Jet of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal with flexible tube telephonically upto 1.5 mtr. (one decimal five metre) long complete with C.P./ S.S. Jet holder stand for telephonically jet spray within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any	1 Number	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
15	Providing and fixing 15 mm ( fifteen millimetre) nominal bore C.P. brass angle valve of Continental series of Jaquar / Contess plus series of Hindware / Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	1350.00	Rupees One Thousand Three Hundred Fifty Only	Each	2700.00
16	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass bib cock of Continental series of Jaquar / Contess plus series of Hindware / Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of approved quality conforming to IS:8931 as approved by Engineer - in - charge and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	1150.00
17	Brick work using Second Class common burnt clay F.P.S. ( non modular) bricks of class designation 7.5 ( seven decimal five) in super-structure above plinth level up to floor V level in all shapes and size in cement mortar 1:6 (One cement isto Six sand) and curing complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	0.73 Cubic metres	7850.00	Rupees Seven Thousand Eight Hundred Fifty Only	Per Cubic metre	5731.00
18	15mm (Fifteen millimetres) thick cement plaster in single coat on fair side of brick/concrete/ stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi,	6.89 Square metres	250.00	Rupees Two Hundred Fifty Only		1723.00
<b>TOTAL :-</b>						<b>66215.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

  
 Chandrashell  
 Executive Engineer  
 Dharamshala Division,  
 HPPWD Dharamshala


**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 38766.00  
 EARNEST MONEY :- ₹ 800.00  
 TIME LIMIT : One Month

**NAME OF WORK :-** Repair and Maintenance of Residential accommodation of Additional Distt. Judge -2 at Khara Danda road Dharamshala, Distt. Kangra H.P.  
**SUB-HEAD :-** (Sh:- Providing and fixing curtain rod, Aluminium and steel work and other minor repair work etc.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 1 Steel work welded in built up sections/ framed work, of Tata/ Sail including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 245.06 Kilograms	4 105.00	5 Rupees One Hundred Five Only	6 Per Kilogram	7 25731.00
2	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on new steel work, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	33.20 Square metres	90.00	Rupees Ninety Only	Per Square metre	2988.00
3	Providing and fixing aluminium work for shutter of doors, windows, ventilators and galazed partitions with extrusion built up standard tubulars and other sections of Jindal / Hindalco approved make conforming to IS :733 and IS : 1285 anodised aluminium ( anodised transparent of dyed to required shade accordingly to IS :1868, minimum coating to grade AC 15) ( AC- fifteen), fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber / neoprene gasket etcetra. Aluminium section shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat, angle, Aluminium snap beading for glazing/ paneling, C.P. brass / stainless steel screws, all complete as per architectural drawing and the directions of Engineer-in-charge ( Glazing, paneling and dash fasteners to be paid for separately) including providing and fixing hinges/ pivots and making provision for fixing of fitting wherever required including the cost of EPDM rubber/ neoprene gasket required all complete as per architectural drawings design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes	8.12 Kilograms	650.00	Rupees Six Hundred Fifty Only	Per Kilogram	5278.00

1	2	3	4	5	6	7
4	Providing and fixing 125mm (One hundred twenty five millimetre) size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	2.00 Numbers	125.00	Rupees One Hundred Twenty Five Only	Each	250.00
5	Providing and fixing 150x10mm (One hundred fifty into Ten millimetres) size aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etc. Tower bolts (Barrel type) as approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4 Numbers	170.00	Rupees One Hundred Seventy Only	Each	680.00
6	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4 mm ( fou milimetre) thickness (weight not less than 10.00 kg/ sqm ( ten decimal zero kilogram per squaremetre), as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.70 Square metres	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per square metre	875.00
7	Providing and Fixing 20mm Chromium plated stainless steel curtain rod having wall thickness of 1.25mm ( one decimal twenty five millimetre) with tow chromium plated bracket fixed with C.P. screws and PVC sleeves etc , wherever necessary complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes	7.80 Running metres	380.00	Rupees Three Hundred Eighty Only	Per Running metre	2964.00
				<b>TOTAL :-</b>		<b>38766.00</b>
				<b>(Amount to be quoted by the contractor in Figure )</b>		
				<b>(Amount to be quoted by the contractor in words)</b>		

  
 Executive Engineer  
 Dharamshala Division,  
 HPPWP Dharamshala

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 53145.00  
 EARNEST MONEY :- ₹ 1100.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and Maintenance of Residential Accommodation I.P.S. Residence at Depot Bazar in Tehsil Dharamshala, Distt. Kangra H.P.  
 SUB-HEAD :- Distemping & Painting work etc.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	190.02 Square metres	105.00	Rupees One Hundred Five Only	Per square metre	19952.00
2	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade One or more coats on new work, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	107.77 Square metres	95.00	Rupees Ninety Five Only	Per square metre	10238.00
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm ( zero decimal ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm ( zero decimal seventy five litre per ten square metre) of approved brand and manufacture, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	104.26 Square metres	110.00	Rupees One Hundred Ten Only	Per Square metre	11469.00
4	Finishing walls with Acrylic Smooth exterior paint of Asian / Dulux / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm ( one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm ( two decimal twenty kilogram per ten squaremetre), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	66.59 Square metres	130.00	Rupees One Hundred Thirty Only	Per Square metre	8657.00

1	2	3	4	5	6	7
5	Providing and applying white cement based putty of Birla / JK average thickness 1 mm ( one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	38.49 Square metres	73.50	Rupees Seventy Three And Paise Fifty Only	Per square metre	2829.00
<b>TOTAL :-</b>						<b>53145.00</b>
<b>Quoted Rate in Figure (%)</b>						
<b>Quoted Rate in Words (%)</b>						
<b>(Amount to be quoted by the contractor in Figure )</b>						
<b>(Amount to be quoted by the contractor in words)</b>						

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97526.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Repair & Maintenance of Residential Accommodation of (Kothi No. A-9) Additional District & Session Judge at Chilgari Dharamshala, Distt. Kangra H.P.  
 SUB-HEAD :- Providing and fixing pre-painted sheet roofing, painting work and water supply & sanitary work etcetera

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing and laying 300X450 mm (three hundred fifty millimetre) ceramic Glazed tile of Kajaria/ Swastik / Somany / Bell / AGL/Johnson in skirting risers of steps and dados on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 1.70 Square metres	4 1050.00	5 Rupees One Thousand Fifty Only	6 Per square metre	7 1785.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with pre-painted iron J or L hooks, bolts and nuts with pre-painted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.55 Square metres	1490.00	Rupees One Thousand Four Hundred Ninety Only	Per square metre	9760.00
3	Structural steel work of Tata / Sail riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	190.00 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	19950.00
4	Providing and fixing 6 mm ( sixty millimetre) thick Cement bonded wood particle board as per IS:14276 and ISI Marked IS No 12823 Action Tesa / Kitlam / Greenlam / Merinolam / Vistapla in multipurpose cement board (High pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately) , as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Square metres	850.00	Rupees Eight Hundred Fifty Only	Per Square metre	2550.00

1	2	3	4	5	6	7
5	Providing and fixing factory made PVC door frame single rebate of any clours of size 50x47mm with a wall thickness of 5mm made out of extruded 5mm rigid PVC foam sheet heat bend & mitred at corners and jointed with 2 Nos. of 150mm long brackets of 15mmx15mm M.S. square tube, the vertical door profiles to be reinforced with 19mmx19mm M.S. square tube of 19 gauge EPDM rubber gasket weather seal to be provided throughout the frame i/c fixing of door frame to wall with M.S. screws 100long with wooden or rawl plugs entedded in masonry complete as per approved shade within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.85 Running metres	530.32	Rupees Five Hundred Thirty And Paise Thirty Two Only	Per Running metre	2572.00
6	Providing and fixing to existing door frames, 30mm (Thirty millimetres) thick factory made PVC panelled door shutter consisting of frame made out of M.S. tubes of 19 (Nineteen) gauge thickness and size of 19mm x19mm (Nineteen into nineteen millimetres) for styles and 15mmx15mm (Fifteen into fifteen millimetres) for top & bottom rails, code 9.120 of Rajshri M.S. frame shall have a coat of steel primers of approved make and manufacture M.S. frame covered with 5mm (Five millimetres) thick heat moulded PVC "C" channel of size 30mm (Thirty millimetres) thickness, 70mm (Seventy millimetres) width out of which 50mm (Fifty millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapped in 45 (Forty five ) degree angle on either side forming style and 5mm (Five millimetres) thick, 95mm (Ninety five millimetres) wide, PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered in 45 (Forty five) degree on the inner side to form top and bottom rail and 115mm (One hundred fifteen) wide PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered on both side to form lock rail, top, bottom and lock rail shall be provided either side of the panel 10mm (Ten millimetres) thick, 20mm (Twenty millimetres) wide cross PVC sheet be provided as gap insert for top rail and bottom rail paneling of 5mm thick both side PVC Sheet to be fitted in the M.S. frame welded/sealed to the style & rails, joints mitred and jointed with solvent cement adhesive i/c fixing of PVC shutter with existing frame with M.S. butt hinges 100x50x1.90mm ( One hundred into fifty into one decimal ninety millimetres) size with necessary screws etc complete as directed by the Engineer-in-Charge.within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.50 Square metres	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per square metre	4725.00
7	Providing and fixing 250x16mm (Two hundred fifty into Sixteen millimetres) size Pilot/steel anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	250.00	Rupees Two Hundred Fifty Only	Each	250.00
8	Providing and fixing 150x10mm (One hundred fifty into Ten millimetres) size aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etc.Tower bolts (Barrel type) as approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	90.00	Rupees Ninety Only	Each	180.00

1	2	3	4	5	6	7
9	Providing and fixing 125mm (one hundred twenty five millimetres) Aluminium Pilot/sheet or equivalent anodized transparent or dyed to required colour and shade and of approved make with necessary screws etc. handles with the necessary screws etc. complete. within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	125.00	Rupees One Hundred Twenty Five Only	Each	250.00
10	Finishing wall with Apex weather proof exterior grade emulsion of Asians Paints /Nerolac suraksha /Bergur paint Exterior Emulsion as per approved shade approved design (Apexultima) on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	14.38 Square metres	130.00	Rupees One Hundred Thirty Only	Per Square metre	1869.00
11	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.77 Square metres	105.00	Rupees One Hundred Five Only	Per square metre	1026.00
12	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	8500.00	Rupees Eight Thousand Five Hundred Only	Each	8500.00
13	Providing and fixing wash basin with Pedestal and C.I. brackets, 15 mm C.P. brass single hole basin mixer, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Flat back wash basin size 550x 400 mm ( five hundred fifty into four hundred millimetre) of Cera / Hindware / Jaquar of star white/snow white shade with single 15 mm C.P. brass single hoel basin mixer, as directed by Engineer-in-charge all kind of soil within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	4500.00	Rupees Four Thousand Five Hundred Only.	Each	4500.00

1	2	3	4	5	6	7
14	Providing and fixing 32 mm ( thirty two millimetres) dia P.V.C. flexible waste pipe of Finolex , Relpipe (Reliance ) , Vectus for sink or wash basin including P.V.C. waste fittings complete. as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	190.00	Rupees One Hundred Ninety Only	Each	190.00
15	Providing and fixing 600x450 mm ( six hundred into four hundred fifty millimetres) beveled edge mirror of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of superior glass (of approved quality) complete with 6 mm ( six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
16	Providing and fixing 600x120x5mm ( six hundred into one hundred twenty into five millimetres) glass shelf with edge round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40mm ( forty millimetres) long screws, rawl plugs etc complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	750.00	Rupees Seven Hundred Fifty Only	Each	750.00
17	Providing and fixing 8 mm (eight millimetres) dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	500.00	Rupees Five Hundred Only	Each	500.00
18	Providing and fixing 100mm (One hundred millimetre) diametres C.P. Grating of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal for gully floor or Nahni trap , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	100.00	Rupees One Hundred Only	Each	200.00
19	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass bib cock of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of approved quality conforming to IS:8931 as approved by Engineer - in - charge and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	1350.00	Rupees One Thousand Three Hundred Fifty Only	Each	2700.00

1	2	3	4	5	6	7
20	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass angle valve of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovit & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931 as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	3 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
21	Providing and fixing 15mm (Fifteen millimetres) nominal bore uplasticsed PVC connection pipe with brass union 45cm (Forty five Centimetres) length of Finolex , Relpipe (Reliance ) , Vectus as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	150.00	Rupees One Hundred Fifty Only	Each	300.00
22	Providing and fixing 20 mm ( twenty millimetre) nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	8.25 Running metres	450.00	Rupees Four Hundred Fifty Only	Per Running metre	3713.00
23	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and all type of taxes imposed by the Government.	15.60 Running metres	350.00	Rupees Three Hundred Fifty Only	Per Running metres	5460.00
24	Providing and placing on terrace (at all floor levels) polyethylene water storage tank of Supreme / Finolex/ Vectus IS : 12701 marked, having 1000/500 ( one thousand and five hundred) litres capacity with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	500 Litres	11.50	Rupees Eleven And Paise Fifty Only	Per Litre	5750.00

1	2	3	4	5	6	7
25	Providing and fixing 110 x 90 mm ( one hundred ten into ninety millimetre) nominal size/diameter P.V.C. floor trap ISI marked of Finolex , Relpipe (Reliance ) , Vectus ISI marked Confirming to BIS-14735-99 of self cleaning design including fixing with approved adhesive , cost of cutting and making good the wall and floor etcetera complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	520.00	Rupees Five Hundred Twenty Only	Each	1040.00
26	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked of Finolex , Relpipe (Reliance ) , Vectus including fixing with approved adhesive etcetera Complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
	i) 110mm ( one hundred ten millimetre) diameters	20.40 Running metres.	490.00	Rupees Four Hundred Ninety Only	Per Running metre	9996.00
	ii) 75mm (seventy five millimetre) diameters	3.55 Running metres	400.00	Rupees Four Hundred Only	Per Running metre	1420.00
27	Providing and fixing PVC (polyvinyl chloride) Single equal branch with oval access door, insertion rubber washer 3 mm (Three millimetres) thick bolts and nuts ISI marked complete including fixing with approved adhesive etcetera complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	250.00
28	Providing and fixing P.V.C Plain bend of Supreme/Finolex/Vectus /Relpipe (reliance) including fixing with approved adhesive complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material, within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
	i) 110mm (One hundred ten millimetre) diameters	2.00 Numbers	200.00	Rupees Two Hundred Only	Each	400.00
	ii) 75mm (seventy five millimetre) diameters	1.00 Numbers	150.00	Rupees One Hundred Fifty Only	Each	150.00

1	2	3	4	5	6	7
29	Providing and fixing 110mm ( one hundred ten millimetre) diametres PVC (polyvinyl chloride) door bend with oval access door, insertion rubber washer 3 mm (three millimetre) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	350.00	Rupees Three Hundred Fifty Only	350.00	350.00
30	Providing and fixing P.V.C. ISI marked of Finolex, Relipipe (Reliance), Vectus Collar ISI marked conforming to IS No-14735-99 including fixing with approved adhesive complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	150.00	Rupees One Hundred Fifty Only	Each	300.00
ii)	110mm ( one hundred ten millimetre) diametres	2.00 Numbers	90.00	Rupees Ninety Only	Each	180.00
31	Providing and fixing chromium plated soap dish of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of jal with C.P. Brass brackets fixed to wooden cleats with C.P. Brass screws complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	210.00	Rupees Two Hundred Ten Only	Each	210.00
32	Providing and fixing 15mm (Fifteen millimetres) nominal bore C.P. brass full way valve with wheel, of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	1250.00
					<b>TOTAL :-</b>	<b>97526.00</b>
		<b>Quoted Rate in Figure (%)</b>				<b>(Amount to be quoted by the contractor in Figure )</b>
		<b>Quoted Rate in Words (%)</b>				<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98387.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and maintenance of HPPWD Residential Building Colony at Dharamshala, Distt. Kangra H.P.  
 SUB-HEAD :- Providing and Fixing wood work, Painting and distempereing, sanitary installation and other minor repair work etc in Type - II quarters No. J-11

S. No	Description of items	Quantity		RATES		Unit	Amount
		In fig	In words	In fig	In words		
1	Repairs to plaster of thickness 10 mm to 15 mm ( ten millimetres to fifteen millimetres) in patches of area 2.5 ( two decimal five) sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:6 (one cement isto six fine sand) as per direction of Engineer-in-charge In cement mortar as per direction of Engineer-in-charge in cement mortar within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3	10.30 Square metres	4	290.00	6	2987.00
2	Wall painting with Premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC ( Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	175.30	Square metres	105.00	Rupees One Hundred Five Only	Per square metre	18407.00
3	Providing and applying white cement based putty of Birla / JK average thickness 1 mm ( one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	50.00	Square metres	73.50	Rupees Seventy Three And Paise Fifty Only	Per square metre	3675.00
4	Painting wood work with Deluxe Multi Surface Paint of required shade two or more coat applied @ 0.90 ltr/10 sqm ( zero decimal ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm ( zero decimal seventy five litre per ten square metre) of approved brand and manufacture, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.00	Square metres	95.00	Rupees Ninety Five Only	Per Square metre	8550.00

1	2	3	4	5	6	7
5	Painting with Deluxe Multi surface paint of Asian / Dulax / Berger / Nerolac Suraksha paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm ( zero decimal ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm ( zero decimal eighty litre per ten square metre) of approved brand and manufacture , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	32.00 Square metres	90.00	Rupees Ninety Only	Per Square metre	2880.00
6	Complete box of cupboard of 25mm (Twenty five millimetres) thick water proof termite resistant commercial board Uniply / Green ply /Kit ply /Dura ply / Marino (ISI Marked ) for shutter including 19mm thick shutter. Back side of cupboard shall be 6 to 8 mm (six to eight millimetre) thick water proof ply. The shutter from all side shall also have 6mm (six millimeter) thick hard board edging/ Topping to be finished with 1mm (one millimeter) thick mica lamination of Century / Greenlam / Action Tesa / Merinolam approved shade of office including fixing handles be provided in wood colour with nickel plated piano hinges with screws etcetera within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	2.80 Square metres	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per Square metre	13580.00
7	Providing and fixing 15 mm ( fifteen millimetres) mixer for Kitchen sink with top / bottom swinging spout of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required, as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Each	4650.00
8	Providing and fixing PVC wall corner box with necessary fittings complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Number	1050.00	Rupees One Thousand Fifty Only	Each	2100.00
9	Providing and fixing 600x450 mm ( six hundred into four hundred fifty milimetres) beveled edge mirror of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal superior glass (of approved quality) complete with 6 mm ( six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	1050.00	Rupees One Thousand Fifty Only	Each	1050.00

1	2	3	4	5	6	7
10	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China wash basin size 550x400 mm ( five hundred fifty into four hundred millimetre) of Cera / Hindware / Jaquar of star white/snow white shade , as directed by Engineer-in-charge all kind of soil within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Each	3850.00
11	Providing and fixing white vitreous china Pedestal for wash basin completely recessed at the back for the reception of pipes and fittings, as directed by Engineer-in-charge all kind of soil within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Each	1950.00
12	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink of Diamond / Unik Kitchen sink with drain board 510x1040 mm ( five hundred ten into one thousand forty millimetre) bowl depth 250 mm ( two hundred fifty millimetre) with C.I. brackets and stainless steel plug 40 mm ( forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	1 Number	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Each	5250.00
13	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass angle valve of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS:8931 as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
14	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth at plinth level in Cement Mortar 1:6 (one cement isto six sand) including levelling with cement concrete 1:6:12 ( one cement isto six sand isto twelve graded stone aggregate 20mm (twenty millimetre) nominal size including entire carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.05 Cubic metres	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	9533.00
15	Providing and fixing 8 mm (eight millimetres) dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to Euroopean type W.C. of quality and make, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Numbers	850.00	Rupees Eight Hundred Fifty Only	Each	850.00

1	2	3	4	5	6	7
16	Providing and laying 1:2:4 (1 cement isto 2 coarse sand isto 4 graded stone aggregate 20 mm (Twenty millimetres nominal size) in position cement concrete of specified grade including the cost of centering and shuttering all work up to plinth level as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.50 Cubic Metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic metre	15625.00
<b>TOTAL :-</b>						<b>98387.00</b>
<b>Quoted Rate in Figure (%)</b>						
<b>Quoted Rate in Words (%)</b>						

  
 Dharamshala Division,  
 HPPWD Dharamshala

372

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 93280.00  
 EARNEST MONEY :- ₹ 1900.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Repair and Maintenance of Residential Accommodation of District and session Judge Kangra at Dharamshala, Distt. Kangra H.P.  
**SUB-HEAD :-** Providing and fixing roofing and wood work etcetera in Type- VI accommodation for District and Session Judge.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 1.66mm to 2.00 mm (One decimal six six millimeters to two decimal zero millimeters) thick fixed in eaves board / fascia / soffits / ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately), as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	13.55 Square metres	1500.00	Rupees One Thousand Five Hundred Only	Per square metre	20325.00
2	Structural steel work of Tata / Sail riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	100.00 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilograms	10500.00
3	Providing and fixing 40mm (Forty millimetres) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of IS gauge designation 85 G with wire of 0.63mm (Zero decimal sixty three millimetres) diameters for doors, windows and clerestory windows including bright finished /black anameled iron hinges with screws within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	3.69 Square metres	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per square metre	15683.00

1	2	3	4	5	6	7
4	Providing and fixing 19mm (Nineteen millimetres) thick water proof termite resistant commercial board with hard wood edging Centuary/ Alpro or equivalent in shelves/box for cup-board including shelves and shutter back side of the cup board butt joints and fixing with nails and screws etcetera complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.76 Square metres	2050.00	Rupees Two Thousand Fifty Only	Per Square metre	13858.00
5	Providing and fixing 15 mm ( fifteen millimetre) nominal bore C.P. brass bib cock of Continental series of Jaquar / Contess plus series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of approved quality conforming to IS:8931 as approved by Engineer - in - charge and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	7 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	8050.00
6	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on old work (wood & steel work) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	261.73 Square metres	95.00	Rupees Ninety Five Only	Per square metre	24864.00
<b>TOTAL :-</b>						<b>93280.00</b>
<b>Quoted Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure )</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD, Dharamshala

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84230.00  
 EARNEST MONEY :- ₹ 1700.00  
 TIME LIMIT : Two Months

and maintenance

NAME OF WORK :- Repair of Type- V Residence District and Session Judge Kangra at Dharamshala, Dist. Kangra H.P.  
 SUB-HEAD :- Painting and distemping to Type- V residence of District and session Judge (Family Court)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	294.35 Square metres	105.00	Rupees One Hundred Five Only	Per square metre	30907.00
2	Finishing wall with Apex weather proof exterior grade emulsion of Asians Paints /Nerolac suraksha /Berqur paint Exterior Emulsion as per approved shade approved design (Apexultima) on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	247.67 Square metres	130.00	Rupees One Hundred Thirty Only	Per Square metre	32197.00
3	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on old work (steel work), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	222.38 Square metres	95.00	Rupees Ninety Five Only	Per square metre	21126.00
<b>TOTAL :-</b>						<b>84230.00</b>
						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala

355

**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 99638.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT :- Two Months

**NAME OF WORK :-** Construction of Judiciary at Dharamshala, Distt. Kangra H.P. (Deposit work)  
**SUB-HEAD :-** Construction of Steel rack in record room on ground and first floor

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Steel work welded in built up sections/ framed work, of Tata/ Sail including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 914.00 Kilograms	4 105.00	5 Rupees One Hundred Five Only	6 Per Kilograms	7 95970.00
2	Painting two or more coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing of Asian paint/ Nerolac/Berger of approved shade to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter enamel paint other than white, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	36.50 Square metres	100.50	Rupees One Hundred And Paise Fifty Only	Per square metre	3668.00
<b>TOTAL :-</b>						<b>99638.00</b>
<b>Quoted Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure)</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

*Chandrasekhar*  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala.

350

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 25900.00  
EARNEST MONEY :- ₹ 600.00  
TIME LIMIT : One Month

NAME OF WORK :- Repair and Maintenance of Residential building ( Kothi No. A-1) for Chairman Waqf Board Tribunals at Chilgari Dharamshala, Distt. Kangra H.P.  
SUB-HEAD :- Providing and fixing PVC 2 Nos. water tank (1000 Ltr. Each)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and placing on terrace (at all floor levels) polyethylene water storage tank having Tripple layer of Reipipe (Reliance) / Vectus IS : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank , within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	2000 Litres	11.50	Rupees Eleven And paise Fifty Only	Per Litre	23000.00
2	Providing and fixing 15mm (Fifteen millimetres) nominal bore C.P. brass ball valve of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal and approved quality, High or low pressure, with plastic float complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	2 Numbers	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
3	Providing and fixing 15mm (Fifteen millimetre) diametre nominal bore G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.10 Running metres	200.00	Rupees Two Hundred Only	Per Running metre	1220.00
4	Providing and fixing 15mm (Fifteen millimetre) diametre nominal bore G.I./M.I Union of following sizes (where not included in the items ) complete in all respect as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00 Numbers	190.00	Rupees One Hundred Ninety Only	Each	380.00
<b>TOTAL :-</b>						<b>25900.00</b>
(Amount to be quoted by the contractor in Figure )						
(Amount to be quoted by the contractor in words)						

Chander Sheela  
Executive Engineer  
Dharamshala Division,  
HPRWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 88151.00  
 EARNEST MONEY :- ₹ 1500.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and Maintenance of Court room of Senior Civil Judge cum Chief Judicial Magistrate (Court-4) in Judicial Court Complex (Old Block) at Dharamshala, Distt. Kangra H.P.

S. No.	SUB-HEAD :- Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing and Fixing wall panelling etc.	3	4	5	6	7
1	Providing and fixing 12mm ( twelve millimetres) thickness WPC (Wood Plastic Composite) Louvers Panneling / lining ( 7.7" x 116" =2.95 x0.20 mtr.( seven decimal seven inch into one hundred sixteen inch equal two decimal ninety five into zero decimal two zero metre) with make of approved shade Area 7.7" x116" x0.20 M= 0.590 Sqm ( seven decimal seven inch into one hudred sixteen inch into zero decimal two zero metre equal to zero decimal five nine zero squarmetre) for interior side/ including cutting and fixing in position. The WPC also Eco wood wall pannel, not easy to deform moisture- proof, insect and fire resistance in all type of decorative colours, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government. *	30.93 Square metres	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	Per Square metre	88151.00
<b>TOTAL :-</b>						<b>88151.00</b>
Quated Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quated Rate in Words (%)						(Amount to be quoted by the contractor in words)

*Chandrasekhar*  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 73781.00  
 EARNEST MONEY :- ₹ 1500.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Repair and Maintenance of Court room of Senior Civil Judge cum Chief Judicial Magistrate (Court-4) in Judicial Court Complex (Old Block) at Dharamshala, Distt. Kangra H.P.

**SUB-HEAD :-** Providing and Fixing Carpeting, Distempering & painting and other minor repair work etc.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	218.78 Square metres	105.00	Rupees One Hundred Five Only	Per Square metre	22972.00
2	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on old work (wood & steel work), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	84.23 Square metres	90.00	Rupees Ninety Only	Per square metre	7581.00
3	Polishing two coats with melamine polish of required shade on previous wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust, and sand papered smooth and including a coat of wood filler as per specification, drawing, design and direction by the Engineer in charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.67 Square metres	325.00	Rupees Three Hundred Twenty Five Only	Per square metre	11918.00
4	Providing and fixing Carpeting complete as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	23.93 Square metres	500.00	Rupees Five Hundred Only	Per Square metre	11965.00
5	Providing and Fixing 20mm Chromium plated stainless steel curtain rod having wall thickness of 1.25mm (one decimal twenty five millimetre) with tow chromium plated bracket fixed with C.P. screws and PVC sleeves etc, wherever necessary complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.04 Running metres	380.00	Rupees Three Hundred Eighty Only	Per Running metre	3435.00

1	2	3	4	5	6	7
6	Providing and fixing curtain for door and window as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.00 Nos	605.00	Rupees Six Hundred Five Only	Each	9680.00
7	Supplying and fixing 4mm ( four millimetre) glass panes ( weight not less than 10.0 kg per sqm ( ten decimal zero kilogram per squaremetres) with putty and nails including removal of broken glass panes wherever necessary , as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.93 Square metres	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square metre	1070.00
8	Providing Second class Deodar wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position. within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	0.015 Cubic metres	110000.00	Rupees One Lakh(s) Ten Thousand Only	Per cubic metre	1650.00
9	Steel work welded in built up sections/ framed work, of Tata/ Sail including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00 kilograms	105.00	Rupees One Hundred Five Only	Per Kilograms	2100.00
10	Providing and fixing 20 mm ( twenty millimetre) nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Running metres	470.00	Rupees Four Hundred Seventy Only	Per Running metre	1410.00
<b>TOTAL :-</b>						<b>73781.00</b>
<b>Quoted Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure )</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Chandrashekhar  
 Executive Engineer,  
 Dharamsaba Division,  
 HPPWD Dharamshala

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 63144.00  
 EARNEST MONEY :- ₹ 1300.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and Maintenance of Residential building of Civil Judge cum JMFC-1 at Khara Danda road Dharamshala, Distt. Kangra H.P.

SUB-HEAD :- (Sh:- Distemping and painting and other minor repair work etc.)

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with plastic emulsion paint of Nerolac/Asian paint/ Berger of approved brand and manufacture on decorated wall surface one or two coat on old work to give an even shade including thoroughly brushing the surface clean of all dirt grease, loose of scale and sand papered smooth, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	374.09 Square metres	105.00	Rupees One Hundred Five Only	Per Square metre	39279.00
2	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on old work (wood & steel work) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	150.95 Square metres	90.00	Rupees Ninety Only	Per square metre	13585.00
3	Providing and applying white cement based putty of Birla / JK average thickness 1 mm ( one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	56.11 Square metres	73.50	Rupees Seventy Three And Paise Fifty Only	Per square metre	4124.00
4	Finishing wall with Apex weather proof exterior grade emulsion of Asians Paints /Nerolac suraksha /Bergur paint Exterior Emulsion as per approved shade approved design (Apexultima) on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	49.24 Square metres	125.00	Rupees One Hundred Twenty Five Only	Per Square metre	6155.00
<b>TOTAL :-</b>						<b>63144.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chundeshwari  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWD, Dharamshala

## SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 69125.00

EARNEST MONEY :- ₹ 1400.00

TIME LIMIT : Two Months

NAME OF WORK :- Repair and maintenance of Deputy Commissioner State Taxation &amp; Excise residence at Chilgari, Distt. Kangra H.P. (Deposit work)


SUB-HEAD :- Providing and fixing wood work and sanitary installation etcetera

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 4mm ( Four millimetre) float glass panes ( weight not less than 10 kg per sqm ( ten kilogram per squaremetres) with putty and nails including removal of broken glass panes wherever necessary , as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.48 Square metres	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square metre	5152.00
2	Providing and fixing 40mm (Forty millimetre) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of IS gauge designation 85 G with wire of 0.56mm (Zero decimal five six millimetre) diameters for doors, windows and clerestory windows including bright finished /black enameled iron hinges with screws, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.82 Square metres	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per square metre	3485.00
3	Providing and fixing 8 mm (eight millimetres) dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. with C.P./ S.S. Jet holder stand for jet sprayof quality and make as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Number	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
4	Providing and fixing 20 mm ( twenty millimetre) nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	21.35 Running metres	450.00	Rupees Four Hundred Fifty Only	Per Running metre	9608.00
5	Providing and fixing Single socketed pipes on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm ( ten millimetre) gap for thermal expansion, as per direction of Engineer-in-charge in cement mortar as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.					

1	2	3	4	5	6	7
5.i	110mm (one hundred ten millimetre) diameter	6.00 Running metres	450.00	Rupees Four Hundred Fifty Only	Per Running metre	2700.00
5.ii	75mm (Seventy five millimetre) diameter.	5.50 Running metres	400.00	Rupees Four Hundred Only	Per Running metre	2200.00
6	Providing and fixing C.P. brass towel ring, trapezoidal Shape 215mm (two hundred fifteen millimetres) long, 200mm wide with minimum distance of 37mm (thirty seven millimetres) from wall face with concealed fittings arrangement of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour and with not less than 88 gms (eighty eight gram), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	2 Numbers	550.00	Rupees Five Hundred Fifty Only	Each	1100.00
7	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetres) beveled edge mirror of Continental series of Jaquar / Contess plus series of Hindware / Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	1050.00	Rupees One Thousand Fifty Only	Each	2100.00
8	Providing and fixing P.V.C. glass shelf with necessary fitting complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	750.00	Rupees Seven Hundred Fifty Only	Each	1500.00
9	Providing and fixing P.V.C. wall corner shelf with necessary fitting complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	500.00	Rupees Five Hundred Only	Each	1000.00
10	Providing and fixing bath shower of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	450.00	Rupees Four Hundred Fifty Only	Each	450.00

1	2	3	4	5	6	7
11	Providing and fixing Bend 87.5° ( eighty seven decimal five degree) 110mm ( one hundred ten millimetre) bend on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm ( ten millimetre) gap for thermal expansion as per direction of Engineer-in-charge in cement mortar as per direction of Engineer-in-charge in cement mortar within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.					
11.i	110mm ( one hundred ten millimetre)	6 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	1500.00
11.ii	75mm (Seventy five millimetre)	6 Numbers	200.00	Rupees Two Hundred Only	Each	1200.00
12	Providing and fixing chromium plated soap dish holder of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal with C.P. Brass brackets fixed to wooden cleats with C.P. Brass screws complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1 Number	250.00	Rupees Two Hundred Fifty Only	Each	250.00
13	Providing and fixing white vitreous china water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	8250.00	Rupees Eight Thousand Two Hundred Fifty Only	Each	16500.00
14	Providing and fixing one hole basin mixing Faucet of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	Each	2850.00
15	Providing and fixing 15 mm ( fifteen millimetres) nominal bore C.P. brass stop cock (concealed) Continental series of Jaquar / Contess plus series of Hindware / Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal of standard design and of approved make conforming to IS:8931 as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	11 Numbers	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	12650.00

1	2	3	4	5	6	7
16	Providing and fixing two hole basin mixing Faucet of Continental series of Jaquar / Classik series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1 Number	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Each	3650.00
17	Providing and fixing 32 mm ( thirty two millimetres) dia P.V.C. flexible waste pipe of Finolex , Relipipe (Reliance ) , Vectus for sink or wash basin including P.V.C. waste fittings complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2 Numbers	190.00	Rupees One Hundred Ninety Only	Each	380.00
<b>TOTAL :-</b>						<b>69125.00</b>
<b>Quoted Rate in Figure (%)</b>						
<b>Quoted Rate in Words (%)</b>						
<b>(Amount to be quoted by the contractor in Figure)</b>						
<b>(Amount to be quoted by the contractor in words)</b>						

  
 Executive Engineer,  
 Dharamshala Division,  
 HPPWDP Dharamshala

638

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 93837.00  
 EARNEST MONEY :- ₹ 1900.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Repair and Maintenance of Deputy Commissioner office building at Dharamshala, District Kangra H.P.

SUB-HEAD :- Balance work for construction of sewerage chamber and cleaning of manhole / chamber of sewerage pipe etcetera

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Brick work using Second Class common burnt clay F.P.S. ( non modular) bricks of class designation 7.5 ( seven decimal five) in super-structure above plinth level up to floor V level in all shapes and size in cement mortar 1:6 (One cement isto Six sand) and curing complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	1.47 Cubic metres	7850.00	Rupees Seven Thousand Eight Hundred Fifty Only	Per Cubic metre	11540.00
2	Providing in laying mechanically mixed and vibrated concrete for plain cement concrete in open foundations complete in road work as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 using P.C.C. grade M-10 (M-Ten) nominal mix (1:3:6) (One cement : Three sand : Six graded crushed stone aggregate 20mm (twenty millimetres) nominal size) in or under water and curing complete including pumping or bailing out water complete for all heights/depths including the cost of form work, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	0.51 Cubic Metres	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per Cubic metre	2780.00
3	15mm (Fifteen millimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arising internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand), as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	6.45 Square metres	270.00	Rupees Two Hundred Seventy Only	Per square metre	1742.00
4	Providing and fixing 110mm (One hundred ten millimetre) diameters P.V.C pipe of Supreme/Finolex/Vectus /Relpipe (reliance) including fixing with approved adhesive complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	11.50 Running metres	450.00	Rupees Four Hundred Fifty Only	Per Running metre	5175.00

1	2	3	4	5	6	7
5	Cleaning brick masonry manhole / Chambers Inside size 800x800x1000mm ( Eight hundred into eight hundred into one thousand millimetres) and 900cm ( Nine hundred Centimetre) deep, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	11 Numbers	5500.00	Rupees Five Thousand Five Hundred Only	Each	60500.00
6	Providing and fixing 455x610 mm ( four hundred fifty five and six hundred ten millimetres) R.C.C rectangular man hole cover including R.C.C. work and steel work, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	11.00 Numbers	1100.00	Rupees One Thousand One Hundred Only	Each	12100.00
<b>TOTAL :-</b>						<b>93837.00</b>
<b>Quoted Rate in Figure (%)</b>						
<b>Quoted Rate in Words (%)</b>						

  
 Executive Engineer  
 Dharamshala Division,  
 HPPWD Dharamshala

359

SCHEDULE OF QUANTITY

ESTIMATED ₹ 99600.00  
 EARNEST ₹ 2000.00  
 TIME LIMIT Two Months

NAME OF WORK :- Repair and Maintenance of residential accommodation HPPPWD Colony Darnu at Dharamshala, Distt. Kangra H.P.

SUB-HEAD :- Providing and fixing Aluminium work, distemping, painting and other minor repair work in Type- IV quarter No.1

S. No	Description of items	Quantity	RATES			Unit	Amount
			In fig	In words	In words		
1	2	3	4	5	6	7	
1	Providing and fixing aluminium Frame work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) ) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	31.21 Kilogramms	600.00	Rupees Six Hundred Only	Per Kilogram	18726.00	
2	Providing and fixing aluminium work for shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) ) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	34.10 kilogramms	650.00	Rupees Six Hundred Fifty Only	Per Kilogram	22165.00	
3	Providing and fixing factory made PVC door frame single rebate of any clours of size 50x47mm with a wall thickness of 5mm made out of extruded 5mm rigid PVC foam sheet heat bend & mitred at corners and jointed with 2 Nos. of 150mm long brackets of 15mmx15mm M.S. square tube, the vertical door profiles to be reinforced with 19mmx19mm M.S. square tube of 19 gauge EPDM rubber gasket weather seal to be provided throughout the frame i/c fixing of door frame to wall with M.S. screws 100long with wooden or rawl plugs emedded in masonry complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	5.60 Running metres	520.30	Rupees Five Hundred Twenty And Paise Thirty Only	Per Running metre	2914.00	

1	2	3	4	5	6	7
4	<p>Providing and fixing to existing door frames, 30mm (Thirty millimetres) thick factory made PVC panelled door shutter consisting of frame made out of M.S. tubes of 19 (Nineteen) gauge thickness and size of 19mm x19mm (Nineteen into nineteen millimetres) for styles and 15mmx15mm (Fifteen into fifteen millimetres) for top &amp; bottom rails, code 9.120 of Rajshri M.S. frame shall have a coat of steel primers of approved make and manufacture M.S. frame covered with 5mm (Five millimetres) thick heat moulded PVC "C" channel of size 30mm (Thirty millimetres) thickness, 70mm (Seventy millimetres) width out of which 50mm (Fifty millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered in 45 (Forty five ) degree angle on either side forming style and 5mm (Five millimetres) thick, 95mm (Ninety five millimetres) wide, PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered in 45 (forty five) degree on the inner side to form top and bottom rail and 115mm (One hundred fifteen) wide PVC sheet out of which 75mm (Seventy five millimetres) shall be flat and 20mm (Twenty millimetres) shall be tapered on both side to form lock rail, top, bottom and lock rail shall be provided either side of the panel 10mm (Ten millimetres) thick, 20mm (Twenty millimetres) wide cross PVC sheet be provided as gap insert for top rail and bottom rail paneling of 5mm thick both side PVC sheet to be fitted in the M.S. frame welded/sealed to the style &amp; rails, joints mitred and jointed with solvent cement adhesive 1/3 fixing of PVC shutter with existing frame with M.S. butt hinges 100x50x1.90mm ( One hundred into fifty into one decimal ninety millimetres) size with necessary screws etc complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the</p>	1.54 Square metres	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per square metre	4851.00
5	<p>Providing and fixing 12mm (Twelve millimetre) thick Phenol Bonded (Both Sides) Prelaminated BWP Grade Partical Board in Matt Finish Flat pressed three layer or graded wood partical board conforming to IS No. 12823 of action Tesa/ Greenlam/ Merinolam/Xitlam/Vista as per ISI and approved shade Grade-I type-II in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetra complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	1.26 Square metres	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	1701.00
6	<p>Providing and fixing aluminium sheet 1mm ( one millimetres) thick in expansion joints vertically fixed with screws or nails complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	0.43 Square metres	1150.00	Rupees One Thousand One Hundred Fifty	Per square metre	495.00
7	<p>Providing and fixing aluminium composite panel ACP. Panel Sheets 6mm ( six millimetre) thick within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	1.23 Square metres	1375.00	Rupees One Thousand Three Hundred	Per square metre	1691.00
8	<p>Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm ( one decimal four millimetre) in both directions with wire of dia. 0.63 mm ( zero decimal sixty three millimetre) all complete With 12 mm ( twelve millimetres) mild steel U beading within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	2.80 Square metres	1050.00	Rupees One Thousand Fifty Only	Per square metre	2940.00
9	<p>Providing and fixing 40mm (Forty millimetre) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of IS gauge designation 85 G with wire of 0.56mm (Zero decimal five six millimetre) diameters for doors, windows and clerestory windows including bright finished /black enameled iron hinges with screws, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.</p>	1.60 Square metres	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per square metre	6800.00

1	2	3	4	5	6	7
10	Providing and fixing 250x16mm (Two hundred fifty into Sixteen millimetres) size Pilot/sheel anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etcetera, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	3 Numbers	200.00	Rupees Two Hundred Only	Each	600.00
11	Providing and fixing 150x10mm (One hundred fifty into Ten millimetres) size aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etcetera Tower bolts (Barrel type), within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	26 Numbers	150.00	Rupees One Hundred Fifty Only	Each	3900.00
12	Providing and fixing 125mm (One hundred twenty five millimetres) size aluminium Pilot/sheel or equivalent anodized transparent or dyed to required colour and shade and of approved make with necessary screws etc. handles with the necessary screws etcetera complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	26 Numbers	125.00	Rupees One Hundred Twenty Five Only	Each	3250.00
13	Providing and fixing 20 mm ( twenty millimetre) diametre chromium plated stainless steel curtain rod having wall thickness of 1.25mm ( one decimal twenty five millimetre) with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etcetera wherever necessary complete, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	13.75 Running metres	350.00	Rupees Three Hundred Fifty Only	Per Running metre	4813.00
14	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre ( fifty grams per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	165.80 Square metres	105.00	Rupees One Hundred Five Only	Per Square metre	17409.00
15	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on old work (wood & steel work) , within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	77.32 Square metres	95.00	Rupees Ninety Five Only	Per square metre	7345.00
<b>TOTAL :-</b>						<b>99600.00</b>
<b>Quated Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure )</b>
<b>Quated Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Dharamshila Division,  
 HPPW, Dharamshila