Office of the
Executive Engineer
Electrical Division, HP PWD Una
Tel: +911975223484, Fax: +911975223484
E-mail: ee-eleu-hp@nic.in

No.PW/EDU/CB//TA/Tender/2025-26/- 9436-55 **Dated** 20/02/26

To

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar
Shimla-171002

Subject: - Regarding publication of Tenders Notice.

Sir,

"JAI HIND"

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification no. PBW-(B)1/2020 dated 16.07.2021 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

Executive Engineer,
Electrical Division,
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 2nd Electrical Circle, HPPWD, Dharamshala.
2. The Assistant Engineer, Electrical Sub Division, HP PWD Una/Hamirpur & Bilaspur.
3. All the contractors working under the control of this Division.
4. All the Head of Branches in this office.
5. Notice Board.

Executive Engineer,
Electrical Division
HPPWD, Una

Office of the
Executive Engineer
Electrical Division, HP PWD Una
Tel: +911975223484, Fax: +911975223484
E-mail: ee-eleu-hp@nic.in

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer, Electric Division HPPWD Una, in form No.6 & 8 on behalf of Governor of H.P. for the following works from the contractors of appropriate cla enlisted with HPPWD (Electrical). The tenders shall be opened on dated **12/02/2026** in the presence of contractors/firms or th authorized representative who wish to be present.

The copy of **Valid enlistment** and renewal certificate along with GST No., Pan No., a EPF No. shall be attached with application form. The offer of the tender shall remain open **75 days** from the date of opening of t tenders. The undersigned reserves the right to reject/cancel the tenders without assigning any reason. The tender form will be issued only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

TIME SCHEDULE OF TENDER

1.	Last date of receipt of application	:-	28/02/2026 up to 1.00 P.M.
2.	Date of sale of tenders	:-	28/02/2026 up to 5.00 P.M.
3.	Last date of receipt of bids	: -	02/03/2026 up to 11.30 A.M.
4.	Date of bid opening	: -	02/03/2026 up to 1.00 P.M.

Sr. No.	Name of work	Estimated Cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time Limit	Eligible Cla of Contract
1	Multipurpose Hall on Retail lab at Shri MA GSSS Bharari, Tehsil Ghumarwin, Distt. Bilaspur (HP) (SH:- Providing E.I. therein)	64,522/-	1,300/-	350/-	Six Months	Class-D,C
2	Running and Operation of Bolero Camper HP20J-5483 in Electrical Division HPPWD, Una Distt. Una (HP) (SH:- Providing skilled driving services (w.e.f. for Four months from awarded date)	97,234/-	1,950/-	350/-	Four Months	Class-D,C
3	Providing and Installation of 1.8/2.0 ton (Split type) Air conditioner in the Server room of the Court complex at Ghumarwin Tehsil Ghumarwin Distt. Bilaspur (H.P) (SH:- Chargeable to ADA building Ghumarwin)	85,740/-	1,700/-	350/-	One month	**Specialized Job**
4	Providing services of 1 No. T/mate/Helper for attending complaints/Running and Operation of Electrical Service/ Repair & Maintenance of E.I. in various Govt. N.R. buildings under ESD Una Distt. Una (HP) (w.e.f. Four months from awarded date)	81,720/-	1,600/-	350/-	Four Months	Class-D,C
5	A/R & M/O Various Govt. Non-residential building under ESD Bilsapur (Swarghat Section) (SH:- Replacement of damaged Electrical accessories, cables)	99,368/-	2,000/-	350/-	Three months	Class-D,C

GENERAL TERMS AND CONDITIONS:-

1. The earnest money in the shape of NATIONAL Saving Certificate time deposit account in any of the post office in HP/FDR or any bank duly pledged in favour of Executive Engineer, HPPWD., Electrical Division Una accompanied with the application for receipt of tender form along with cost of form.
2. The Contractor/Firm should be submitted the all above-mentioned documents (photocopy to be self-attested) with the application for obtaining the tender documents.
3. In case office happens to be closed on any of the above mentioned dates, the bids will be opened on the next working day at same time and venue.
4. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which tenders are likely to be rejected.
5. No Person/persons shall be allowed to give the documents with regard to tender unless he/they hold/holds the power of attorney duly registered under law.
6. The tender of those contractors who are registered under H.P. Central Sales Tax Act 1969, GST and who have been cleared all the dues on account of tax will be entertained.
7. The competent authority on behalf of Governor of H.P. reserves the right to reject any or all the tenders received without assigning any reason.
8. The eligible Contractors/Firm should performance certificate for specialized jobs as required.
9. The tendered amount should be within the limit of (+) 5% to (-) 30% as per notification No. PBW(B)A(3)1/2020-1 dated 07.10.2021 shall be applicable for Bid price lower than-10% and more than + 5%. If the Contractors/Firms has quoted bid price lower than 10% the performance guarantee will be deposited before the award of work as per terms & condition of above said notification.

"HIM SUCHANA AVAM JANSAMPARK"

Executive Engineer,
Electrical Division
HPPWD, Una

Job No 1

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 64,522/-
Earnest money:- Rs. 1300/-
Time Limit:- Six months.

Name of work :-Multipurpose Hall on Retail lab at PM SHIRI MA GSSS Bharari Tehsil Ghumarwin ,Distt.Bilaspur(H.P.)(SH: Providing E.I. there in)

S. No.	Description	Quantity	Rate In Fig.	In Words.	Unit	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed heavy class PVC conduit having wall thickness minimum 2 mm with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required Make :Plaza/Anchor/Finolex/L&T.					
i	GroupC	18	1143	Rupees One thousand one hundred forty three only.	Point	20574
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required .Make:-Plaza/ Anchor/ Finolex/L&T .					
i	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	20	198	Rupees One hundred ninety eight only.	p/mtr	3960
ii	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	15	311	Rupees Three hundred eleven only.	p/mtr	4665
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.Make:-Anchor/SSK/Legrand.					
i	5/6 amps switch	2	42	Rupees Forty two only.	each	84
ii	3pin 5/6 amps socketoutlet	2	57	Rupees Fifty seven only.	each	114
4	Supplying and fixing two rotary stepped type electronic fan regulator on the existing switch box including connections etc. as required.Make:-Anchor/SSK/Legrand.	6	257	Rupees Two hundred fifty seven only.	each	1542
5	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLS on including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings) Make :- L&T/Anchor Roma/ABB as approved by Engineer-in - charge	6	265	Rupees Two hundred sixty five only.	each	1590

6	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLS on including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.Make :- L&T/Anchor Roma/ABB as approved by Engineer-in -charge	1	406	Rupees Four hundred six only.	each	406
7	Supplying and fixing PVC batten/ angle holder including connections etc. as required.Make:-Anchor/SSK/Legrand	1	88	Rupees Eighty eight only.	Each	88
8	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Make L&T/ABB/Hager/Anchor as approved by Engineer-in -charge					
i	Single pole.6 Amp Cat-A.	3	239	Rupees Two hundred thirty nine only.	each	717
ii	Single pole.16 Amp Cat-A.	1	239	Rupees Two hundred thirty nine only.	each	239
9	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make :-L&T/ABB/Hager/Anchor as approved by Engineer-in -charge					
i	40 Amps. Cat-A.	1	530	Rupees Five hundred thirty only.	each	530
10	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)Make L&T/ABB/Hager/Anchor as approved by Engineer-in -charge					
i	MCBDB 8 WAY D/Door	1	1703	Rupees One thousand seven hundred three only.	Each	1703
11	Providing and fixing 6 SWG (4 mm dia.) G.I. wire on surface or in recess for loop earthing as required.	15	60	Rupees Sixty only.	p/mtr	900
12	Providing, Installation, testing and commissioning of Ceiling fan including wiring the down rods of standard length (up to 30 cm) with 16/0.20 mm twin twisted flexible, cotton braided, copper cable, including providing and fixing phenolic laminated sheet cover on the fan box and earthing etc. as required:Make:- Usha/Orient/Crompton as approved by Engineer-in-charge(Five year warranty)					
i	Ceiling Fan 1200 mm sweep	6	2438	Rupees Two thousand four hundred thirty eight only.	each	14628

13	Providing and fixing LED Batten Light of IP40 Led fixture 40 W+/- 1W with Surface Mounted 4 Feet with Polycarbonate diffuser with Extruded aluminium housing having minimum system lumen output 1000 lumens and system lumen efficacy of 100 lm/W with P.F.>0.95 with THD<20% ,CRI 80 .The LED with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects. Make:- JAQUAR/Philips/Panasonnic/Wipro, as approved by Engineer-in-Charge (Five YEAR WARRANTY)	9	714	Rupees Seven hundred fourteen only.	Each	6426
14	Supplying and fixing LED. Lamp 9 watts E-27 base in the existing batten holder/pendent holder . Make:- Wipro /Havells/Jaquar	1	138	Rupees One hundred thirty eight only.	Each	138
15	Supplying and fixing street light LED 25 watt with G.I bracket die cast Aluminium housing with frame and toughened glass, pipe mounting 5700k, (Five YEAR WARRANTY) and it should be compatible with specification e.i. Power Factor > .9, Harmonic Distortion<10% and efficacy >100 Lumens per watt, suitable for input voltage: AC 220-240 V, 50/60Hz, complete with all accessories, connections, testing and commissioning etc. Make - Jaquar/Panasonic /Philips/wipro or as approved by Engineer-in-Charge (Five Year warranty)	2	2729	Rupees Two thousand seven hundred twenty nine only.	each	5458
16	Providing and Fixing 6SWG Service wire	20	38	Rupees thirty only.	MTR	760
	Total:-					64522

DNIT checked and approved for Rs 64,522/- only (Rs Sixty four thousand five hundred Twenty two only)

Executive Engineer
Electrical Division
H.P.P.W.D.Una-174303

Assistant Engineer
Electrical Sub Division
HPPWD Bilaspur (H.P.)

Job No. 2

DRAFT SCHEDULE OF QUANTITY		
	Estimated cost:- Rs. 97,234/-	
	Earnest money:- Rs. 1,950/-	
	Time Limit:- Four months.	

Name of work:- Running and operation of Bolero Camper HP-20-J-5483 in Electrical Division HP.PWD Una Distt. Una (H.P) (SH:- Providing Skilled driving services (w.e.f for Four months from awarded date)

Sr. No.	Description of Items	Quantity		Rate In Fig.	In Words.	Unit	Amount
1	Providing Services on temporary basis driving for Bolero Camper HP-20-J-5483 in Departmentally vehicle during working hours (9.30Am to 5.30PM) or as when required by the Officer-in-charge.	4	Months 122 days	797	Rupees Seven hundred Ninety Seven only.	P/day	97234
	TOTAL						97234

DNIT checked and approved for 97,234/- only
(Rs Ninty Seven thousand Two hundred thirty four only)

Executive Engineer
Electrical Division
H.P.P.W.D. Una-174303

ASSISTANT ENGINEER
Electrical Sub Division
H.P.P.W.D. UNA

DRAFT SCHEDULE OF QUANTITY

Job No. 03

Estimated cost:- Rs.85,740/-

Earnest money:- Rs. 1700/-/-

Time Limit:- One month.

Name of Work:-Providing and Installation of 1.8/2.0 Ton (Split type) Air conditioner in the Server Room of the Court complex at Ghumarwin Tehsiol Ghumarwin Distt. Bilaspur (H.P). (SH:- Chargeable to ADA building Ghumarwin)

Sr. No.	Description	Quantity	Rate In Fig.	In Words.	Unit	Amount
2	Supplying and fixing 1.8/2.0 ton invertor split type air conditioner Hot and Cold with five year warranty advanced filter ,E saver mode , quit mode, dual display ,auto clean ,anti bacteria filter jet Cool on/off timer sleep mode compressor cord less remote complete in all respect as per comprising to ISI with latest amendment suitable to operate on 230 volt /240 volt +_ 10 % AC supply capable to perform the function of cooling dehumidification air circulation ventilation and fitting in size of nominal cooling capacity and drain pipe 20mm dia approximately 3 mtrs long of2 Nos copper pipe with isulator for inlet and outlet approximately 3 mtr. long and outdoor uni of split type A.,C including carrigae of material with in all leads and lift.Make -Daikin (model:FTHT60)/ O Genral/ Mitsubsi as approved by the Engineer -in-Charge.	1	72692	Rupees Seventy two thousand six hundred ninety two only.	Each	72692
2	Providing and fixing of M.S. power coated stand (Heavy duity) including grouting for outdoor unit complete in all respect and as approved by the Engineer-in-charge.	1	550	Rupees Five hundred fifty only.	Each	550
3	Providing and fixinmg of following size of PVC conduit alongwith accessories in surface/recess including painting in case of surface conduit , or cutting the wall and making good the same of recessed conduit as required.	10	60	Rupees Sixty only.	P/Mtr.	600

4	Supplying and fixing of voltage Stablizer upto 2.0ton AC having specification input voltage range 130-300, digital display, under voltage Protection, over voltage protection, including connections, testing and commissioning etc. as required. Make:- Miroctech/ V-guard/ Godrej as approved by the Engineer-in-charge. (Three year warranty).	1	6198	Rupees Six thousand one hundred ninety eight only.	Each	6198
5	Supplying and fixing Copper pipe with insulator and 2.5sq.mm wire	3	1400	Rupees One thousand four hundred only.	P/Mtr.	4200
6	Air Conditioner Installation charges.	1	1500	Rupees One thousand five hundred only.	Each	1500
TOTAL						85740

DNIT checked and approved for Rs 85,740/- only (Rs Eighty five thousand seven hundred forty only)

Assistant Engineer
Electrical Sub Division
HPPWD. Bilaspur (H.P.)

Executive Engineer
Electrical Division
H.P.P.W.D. Una

Job No. 4

	DRAFT SCHEDULE OF QUANTITY					
					Estimated cost:- Rs.81,720/-	
					Earnest money:- Rs. 1,600/-	
					Time Limlit:- Four months.	

Name of work:- Providing services of 1 No. T/mate/Helper for attending complaints/Running and Operation of Electrical Service/ Repair & Maintenance of E.I. in various Govt.N.R.buildings under ESD Una Distt.Una (HP) (w.e.f. Four months from awarded date)

S. No.	Description of Items	Quantity	Unit	Rate In fig.	In Words.	Amount
1	Engagement of 1 No. temporary basis T/mate/Helper for various N/R building in Distt. Una as per instruction of Engineer-In-Charge.	4 Months (120 Days)	P/day	681	Rupees Six Hundred eighty one only.	81720
	TOTAL					**81720**

DNIT checked and approved for Rs 81,720/- only (Rs Eighty one thousand seven hundred twenty only)

Executive Engineer
Electrical Division
H.P.P.W.D.Una-174303

ASSISTANT ENGINEER
Electrical Sub Division
H.P.P.W.D. UNA

Job No. 5

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs.99368/-

Earnest money:- Rs.2000/-

Time Limit:- Three months.

Name of work:- A/R & M/O Various Govt. Non Residential buildings under ESD Bilaspur (swarghat Section) (SH:-Replacement of damaged Electrical accessoirs, cables).

S. N.	Description of Items	Qty	Rate	Unit	Rate in words	Amount
1	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc.as required.Make:- Anchor/L&T/Legrand					
1.1	5 amp Piano switch	30	42	each	Rupees Fourty Two Only	1260
1.2	5 amp Piano socket	25	57	each	Rupees Fifty Seven Only	1425
2	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.Make:- Anchor/L&T/Legrand					
2.1	15 amp Piano switch	8	116	each	Rupees One Hundred Sixteen Only	928
2.2	15 amp Piano socket	8	123	each	Rupees One Hundred Twenty Three Only	984
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVCconduit as required. ANCHOR FINOLEX/PALAZA					
3.1	2x1.5sq.mm	80	71	P/Mtr	Rupees.One Hundred Ninty Eight Only	5680
3.2	2x4 sq.mm	30	153	P/Mtr	Rupees.Three Hundred Eleven Only	4590
4	Providing and Fixing of LED fixture 600mmX600mm 36 Watt +/- 1W Recess mounted fixture with HET Plastic diffuser with minimum system lumen efficacy of 100 lm/W with CRCA housing having P.F.>0.95 with THD<10% ,CRI 80.The LED with Useful life of 50000 Hrs at L70. The LEDs used in the luminaire shall have CCT of 5700 K with CRI of minimum 80. The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.Make Philips/Wipro/Panasonic/Jaquar or as approved by Engineer-in-Charge.(five year warranty)					

4.1	LED Panel 2'x2' 36 watt Makes:- Panasonic	5	3397	each	Rs. Three Thousand Three Hundred Ninety Seven Only	16985
5	Providing and installation of following type of LED retrofit Lamp B-22 holder base with polycarbomate diffuser and aluminium heat sink including connections, testing and commissioning etc. as required.:Make JAQUAR, wipro,Philips or its equivalent as approved by Engineer-in-Charge	20	154	each	Rs. One Hundred Fifty Four Only	3080
7	Providing and Fixing of IP20 LED fixture of 18 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing,pressure die cast heat sink and P.F.>0.95 with THD<10% ,CRI 80.The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.	10	1821	each	Rs. One Thousand Eight Hundred Twenty One Only	18210
8	Providing, Installation, testing and commissioning of Glazed LED 10 Watt Batten 600mm long(Mirror Light) High quality design aluminum extruded decorative end caps as per best satisfaction of Engineer-in-Charge. Make: , Wipro Cat No L20-111-XXX-65NE3), or its equivalent or as approved by Engineer in charge.	8	552	each	Rs. Five Hundred Fifty Two Only	4416
9	Providing and fixing LED Batten Light of IP40 Led fixture 40 W+/- 1W with Surface Mounted 4 Feet with Polycarbonate diffuser with Extruded aluminium housing having minimum system lumen output 1000 lumens and system lumen efficacy of 100 lm/W with P.F.>0.95 with THD<20% ,CRI 80 .The LED with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.	12	2417	each	Rs. Two Thousand Four Hundred SeventeenOnly	29004
10	Providing and installation of stationary storage type Electric water heater (Geyser) five year warranty of various sizes by means of expansion-bolts with nuts and washers, includingembedding of expansion-bolts in the wall, making good the damages, electricalconnections, testing etc. complete as required. Make:- Usha (Model 35L SWH MISTY WITH KIT), Bajaj, Recold as approved by Er-in-charge					
10.1	25 Liter capacity water heater as per Usha price list Jan./2023	1	12806	each	Rs. Twelve Thousand Eight Hundred Six Only	12806
	Total					99368

DNIT Checked and approved for Rs. 99,368/- only.
(Rupees Ninety nine thousand three hundred Sixty eight only).

Executive Engineer
Electrical Division
H.P.P.W.D. Una-174303

ASSISTANT ENGINEER
ELECTRICAL SUB-DIVISION
HPPWD BILASPUR