

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-

20355-62

Dated:- 24/2/2026

To,

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 05.03.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 06.03.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 07.03.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 08.03.2026 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1.	R/O (Repair of) Road near house of Rakesh Kumar Puran Chand Ward No.4 GP Barot Under SDF (D.C. Deposit)(SH:- Providing and laying Interlocking paver block pavement at R.D. 0/00 to 0/033).	Rs.56987/-	Rs.1200/-	One month	350/-	Class D&C
2.	R/O (Repair of) Road near house of Krishan Kumar Tara Chand Ward No.3 G.P. Barot Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028)	Rs.57019/-	Rs.1200/-	One month	350/-	Class D&C
3.	R/O (Repair of) Road near house of BantaSingh etc. Ward No.3 G.P. Barot Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028)	Rs.57019/-	Rs.1200/-	One month	350/-	Class D&C
4.	R/O (Repair of) Road Pond to Sarvan Singh house Ward No.3 G.P. Barot Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/026)	Rs.57019/-	Rs.1200/-	One month	350/-	Class D&C
5.	R/O (Repair of) Jagdish Singh house towards Rajinder house Ward No.7 G.P. Sunet Under SDF (D.C. Deposit) (SH:- Providing and laying interlocking paver block pavement at RD 0/0 to 0/034)	Rs.56996/-	Rs.1200/-	One month	350/-	Class D&C
6.	R/O (Repair of) from Mandir Gate to Harbans Land village Bhatoli G.P. Diyana Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/023.40)	Rs.57019/-	Rs.1200/-	One month	350/-	Class D&C
7.	R/O (Repair of) from Maira Palli link road to Narjeev Singh Shed G.P. Lohara Under SDF (D.C. Deposit) (SH:- Providing and laying interlocking paver block pavement at RD 0/0 to 0/013.50)	Rs.57000/-	Rs.1200/-	One month	350/-	Class D&C
8.	R/O (Repair of) Drain and other work from Kripal Singh house to Anil Ashwani etc. in Ward no.6 G.P. Lohara Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain at RD 0/00 to 0/067)	Rs.57001/-	Rs.1200/-	One month	350/-	Class D&C
9.	Repair of Main road to Adrash Model School Village Junat G.P. Baroona Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement in length = 25.00 mtr.)	Rs.56361/-	Rs.1200/-	One month	350/-	Class D&C
10.	Repair of Main road towards Kishori Lal house Ward No.7 Lalwana GP Khatiar Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement in length = 21.50 mtr.)	Rs.56877/-	Rs.1200/-	One month	350/-	Class D&C
11.	Repair of path drain from main path to Bashan, Sanju, Ram Lal etc. ward No.5 GP Sathana Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement in length = 21.50 mtr.)	Rs.56877/-	Rs.1200/-	One month	350/-	Class D&C
12.	Repair of Tiled path 35mtr. Sandol Singh land to Shiv Ram house ward No.5 Under SDF (D.C. Deposit)	Rs.57227/-	Rs.1200/-	One month	350/-	Class D&C
13.	Repair of from Jeetu house towards Lal Chand and Birbal etc. house alongwith retaining wall Under SDF (D.C. Deposit)	Rs.57640/-	Rs.1200/-	One month	350/-	Class D&C

14	Repair of from Main road to Rakesh, Rajesh house in Village Rey G.P. Rey Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement in length = 24.00 mtr.)	Rs.57150/-	Rs.1200/-	One month	350/-	Class D&C
15	Repair of path from Mohd. Rafiq house to Yousuf Alis house in Ward No.7 Muslim Basti Rey Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement)	Rs.56936/-	Rs.1200/-	One month	350/-	Class D&C
16	Restoration of rain damages on link road Dehri Sakoh Padehar road km. 0/00 to 2/500 (SH:- Construction of U-shape drain at R.D.0/150 to 0/193)	Rs.99985/-	Rs.2000/-	One month	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

7


SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Road near house of Rakesh Kumar Puran Chand Ward No.4 GP Barot Under SDF (D.C. Deposit) (SH:- Providing and laying Interlocking paver block pavement at R.D. 0/00 to 0/033).

Estimated cost:- Rs.56987/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.96 Cubic meter.	3880.20	Rupees Three Thousand Eight Hundred Eighty And Paise Twenty Only	Per cubic meter	15366.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	39.60 Square meter	845.60	Rupees Eight Hundred Forty Five And Paise Sixty Only	Per Square meter.	33486.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping of bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.49 Cubic meter.	5459.60	Rupees Five Thousand Four Hundred Fifty Nine And Paise Sixty Only	Per cubic meter	8135.00
					Total:-	56987.00

Amount quoted by the contractor in % Above/Below


 Civil Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (J&K)

5

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Road near house of Krishan Kumar Tara Chand Ward No.3 G.P. Barot Under SDF (D.C. Deposit)
(SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028)

Estimated cost:- Rs.57019/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50 Cubic meter.	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per cubic meter	57019.00
Amount quoted by the contractor in % Above/Below						Total:- 57019.00

Executive Engineer
 Faizpur Division I.P.P.W.D.
 Faizpur Dist. Kanya H.


SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Road near house of BantaSingh etc. Ward No.3 G.P. Barot Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028)

Estimated cost:- Rs.57019/- only
 Earnest Money : Rs.1200/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50 Cubic meter.	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per cubic meter	57019.00
					Total:-	57019.00

Amount quoted by the contractor in % Above/Below


 Engineer
 Fatehpur Division HPFWD
 Fatehpur Distt. Kangra (H.P.)

5

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Road Pond to Sarvan Singh house Ward No.3 G.P. Barot Under SDF (D.C. Deposit)
(SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/026)

Estimated cost:- Rs.57019/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity		Rate		Unit	Amount
		In words	In figures	In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per	Cubic meter	57019.00
Total:-							57019.00
Amount quoted by the contractor in % Above/Below							

[Signature]
 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Dist. Kangra (H.P.)

5

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Jagdish Singh house towards Rajinder house Ward No.7 G.P. Sunet Under SDF (D.C. Deposit) (SH:- Providing and laying interlocking paver block pavement at RD 0/0 to 0/034)

Estimated cost:- Rs.56996/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	1.02 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	346.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.74 Cubic meter.	3880.20	Rupees Three Thousand Eight Hundred Eighty And Paise Twenty Only	Per cubic meter	14512.00
3	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	36.74 Square meter	850.40	Rupees Eight Hundred Fifty And Paise Forty Only	Per Square meter.	31244.00
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1.2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.04 Cubic meter.	5340.20	Rupees Five Thousand Three Hundred Forty And Paise Twenty Only	Per cubic meter	10894.00
					Total:-	56996.00

[Signature]

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra


8

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) from Mandir Gate to Harbans Land village Bhatoli G.P. Diyana Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/023.40)

Estimated cost:- Rs.57019/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50 Cubic meter.	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per cubic meter	57019.00
					Total:-	57019.00
			Amount quoted by the contractor in % Above/Below			


 Executive Engineer
 Panchayat Division APPWD
 Panchayat, Kangra (H.P.)

(T)


SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) from Maira Palli link road to Narjeev Singh Shed G.P. Lohara Under SDF (D.C. Deposit)
(SH:- Providing and laying interlocking paver block pavement at RD 0/0 to 0/013.50)

Estimated cost:- Rs.57000/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	0.39 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	132.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.64 Cubic meter.	3880.20	Rupees Three Thousand Eight Hundred Eighty And Paise Twenty Only	Per cubic meter	14124.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm (eighty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	35.60 Square meter	1050.40	Rupees One Thousand Fifty And Paise Forty Only	Per Square meter.	37394.00
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.98 Cubic meter.	5459.60	Rupees Five Thousand Four Hundred Fifty Nine And Paise Sixty Only	Per cubic meter	5350.00
					Total:-	57000.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur, Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Drain and other work from Kripal Singh house to Anil Ashwani etc. in Ward no.6 G.P. Lohara Under SDF (D.C. Deposit) (SH:- Construction of U-shape drain at RD 0/00 to 0/067)

Estimated cost:- Rs.57001/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	14.07 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4777.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification sections 800, 900 & 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.14 Cubic meter.	4688.00	Rupees Four Thousand Six Hundred Eighty Eight Only	Per cubic meter	52224.00
					Total:-	57001.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (t) f


9

SCHEDULE OF QUANTITY

Name of work:- ~~Construction~~ Repair of Main road to Adrash Model School Village Junat G.P. Baroona Under SDF (D.C. Deposit) Estimated cost:- Rs.56361/- only
 (SH:- Providing and laying Cement Concrete Pavement inlength = 25.00 mtr.) Earnest Money : Rs.1200/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.64 Cubic meter.	1695.10	Rupees One Thousand Six Hundred Ninety Five And Paise Ten Only	Per cubic meter	4475.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.52 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	51886.00
Total:-						56361.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)


SCHEDULE OF QUANTITY

Name of work:- Repair of Main road towards Kishori Lal house Ward No.7 Lalwana GP Khatiar Under SDF (D.C. Deposit)
(SH:- Providing and laying Cement Concrete Pavement in length = 21.50 mtr.)

Estimated cost:- Rs.56877/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.52 Cubic meter.	1695.10	Rupees One Thousand Six Hundred Ninety Five And Paise Ten Only	Per cubic meter	7662.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.03 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	49215.00
Total:-						56877.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra


51

SCHEDULE OF QUANTITY

Name of work:- Repair of path drain from main path to Bashan, Sanju, Ram Lal etc. ward No.5 GP Sathana Under SDF (D.C. Deposit) Estimated cost:- Rs.56877/- only
 Earnest Money : Rs.1200/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.52 Cubic meter.	1695.10	Rupees One Thousand Six Hundred Ninety Five And Paise Ten Only	Per cubic meter	7662.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.03 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	49215.00
Total:-						56877.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra

12


SCHEDULE OF QUANTITY

Name of work:- Repair of Tiled path 35mtr. Sandol Singh land to ShivRam house ward No.5 Under SDF (D.C. Deposit)

Estimated cost:- Rs.57227/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	57227.00
Total:-						57227.00

Amount quoted by the contractor in % Above/Below


 Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

185

SCHEDULE OF QUANTITY

Name of work:- Repair of from Jeetu house towards Lal Chand and Birbal etc. house alongwith retaining wall Under SDF (D.C. Deposit)

Estimated cost:- Rs.57640/- only

Earnest Money : Rs.1200/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge.Including carriage of materials within all leads and lifts and other incidental .	4.86 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	1650.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	9.00 Cubic meter.	3950.20	Rupees Three Thousand Nine Hundred Fifty And Paise Twenty Only	Per cubic meter	35552.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	20438.00
					Total:-	57640.00

Amount quoted by the contractor in % Above/Below

[Signature]
Executive Engineer
Pachor Division HPPWD

SCHEDULE OF QUANTITY

Name of work:- Repair of from Main road to Rakesh, Rajesh house in Village Rey G.P. Rey Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement in length = 24.00 mtr.)

Estimated cost:- Rs.57150/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.50 Cubic meter.	1700.00	Rupees One Thousand Seven Hundred Only	Per cubic meter	7650.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00 Cubic meter.	5500.00	Rupees Five Thousand Five Hundred Only	Per cubic meter	49500.00
					Total:-	57150.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. (Kangra H.P.)

15

515
2025-26


SCHEDULE OF QUANTITY

Name of work:- Repair of path from Mohd. Rafiq house to Yousuf Alis house in Ward No.7 Muslim Basti Rey Under SDF (D.C. Deposit) (SH:- Providing and laying Cement Concrete Pavement)

Estimated cost:- Rs.56936/- only
Earnest Money : Rs.1200/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate. watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.59 Cubic meter.	1694.00	Rupees One Thousand Six Hundred Ninety Four Only	Per cubic meter	7775.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.02 Cubic meter.	5450.20	Rupees Five Thousand Four Hundred Fifty And Paise Twenty Only	Per cubic meter	49161.00
Total:-						56936.00

Amount quoted by the contractor in % Above/Below



 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

18

SCHEDULE OF QUANTITY

Sr. No		Description of items	Quantity	Rate		Unit	Amount
				In words	In figures		
Name of work:- Restoration of rain damages on link road Dehri Sakoh Padehar road km. 0/00 to 2/500 (SH:- Construction of U-shape drain at R.D.0/150 to 0/193)							
Estimated cost:- Rs.99985/- only Earnest Money : Rs.2000/- only							
1		Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	26.57	350.00	Rupees Three Hundred Fifty Only	Per cubic meter	9300.00
2		Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.10	4350.10	Rupees Four Thousand Three Hundred Fifty And Paise Ten Only	Per cubic meter	70037.00
3		Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement into two sand into four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.55	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic meter	8138.00
4		Supplying fitting and placing HYSD bar reinforcement in foundation complete as per drawing and MORD technical specifications clause 1000 and 1202 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any floor level as per the direction of Engineer-in-charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	139.00	90.00	Rupees Ninety Only	Per kilogra mme	12510.00
						Total:-	99985.00

Amount quoted by the contractor in % Above/Below


 Civil Engineer
 Padehar Division, HP (PWD)
 Patnitop Distt. Kangra