

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-
To,

17064-17091 Dated:- 9/02/2026

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 16.02.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 16.02.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 17.02.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 18.02.2026 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1.	Construction of retaining wall near the house of Ranjeet Singh Village Jharoli Under (SDF) DC Deposit (SH:- Construction. of Retaining wall at RD 0/0 to 0/035	Rs. 75,998/-	Rs.1600/-	One month	350/-	Class D&C
2.	Re- Construction of retaining wall from Ratan Lal , Nand Lal ke Khet se Chaman Lal ke Ghar Tak Ward No. 4 Under (SDF) DC Deposit (SH:- Construction of Retaining wall at RD 0/0 to 0/022	Rs. 94,298/-	Rs.1900/-	One month	350/-	Class D&C
3.	Construction of retaining wall near the house of Parkash Singh Village Chandrahad in G.P. Ther (Under MLALAD) Deposit Work (SH;- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028). Balance Work.	Rs. 52,733/-	Rs.1100/-	One month	350/-	Class D&C
4	Construction of Pucca Path from Magar Singh house House to Kulveer House in village Badnad in G.P Bagroli (Under SDP) Deposit work (SH:-Construction of Retaining wall at RD. 0/0 to 0/010 and P/L Cement concrete pavement at RD. 0/0 to 0/024)	Rs.69,523/-	Rs.1400/-	One month	350/-	Class D&C
5.	Construction of retaining wall near the house of Veer Singh, Joginder Sing Rakesh etc. in Village Khudial G.P. Kutwasi Under MLALAD (Deposit Work) (SH:- Construction of PCC Retaining wall at RD 0/0 to 0/14.50)	Rs. 95,000/-	Rs.1900/-	One month	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh


DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near house of Ranjeet Singh village Jharoli Under (SDDMF) (SH:- Construction of retaining wall at R.D. 0/0 to 0/035) (D.C. Deposit)

Estimated cost:- Rs.75998/- only
 Earnest Money : Rs.1600/- only
 Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.55 Cubic meter.	315.60	Rupees Three Hundred Fifteen And Paise Sixty Only	Per cubic meter	3645.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken.stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.11 cubic meter	3410.50	Rupees Three Thousand Four Hundred Ten And Paise Fifty Only	Per cubic meter	65175.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00 Numbers	299.10	Rupees Two Hundred Ninety Nine And Paise Ten Only	Each	7178.00
					Total:-	75998.00

Amount quoted by the contractor in % Above/Below


 Assistant Engineer
 Fatehpur Division H.P.P.P.P.
 Fatehpur Distt. Kangra (P.S.)

SCHEDULE OF QUANTITY

Name of work:- Re construction of Retaining wall from Ratan Lal, Nand Lal, Ke Khet se Chaman Lal Ke Ghar Tak Ward No.4
 Under (SDF) (SH:- Construction of retaining wall at R.D. 0/0 to 0/022) (D.C. Deposit)

Estimated cost:- Rs.94298/- only
 Earnest Money : Rs.1900/- only
 Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.58 Cubic meter.	318.90	Rupees Three Hundred Eighteen And Paise Ninety Only	Per cubic meter	2736.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.97 cubic meter	3430.50	Rupees Three Thousand Four Hundred Thirty And Paise Fifty Only	Per cubic meter	85660.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00 Numbers	295.10	Rupees Two Hundred Ninety Five And Paise Ten Only	Each	5902.00
					Total:-	94298.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra


SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Parkash Singh village Chandrahad in G.P. Ther (under MLALAD) Deposit work. (SH:- Providing and laying Cement Concrete Pavement at RD 0/0 to 0/028). Balance work

Estimated cost:- Rs.52733/- only
Earnest Money : Rs.1100/- only
Time limit:- one month

Sr.No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government. Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.00	650.20	Rupees Six Hundred Fifty And Paise Twenty Only	Per cubic meter	18206.00
2		6.30	5480.40	Rupees Five Thousand Four Hundred Eighty And Paise Forty Only	Per cubic meter	34527.00
Total:-						52733.00

Amount quoted by the contractor in % Above/Below



 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (Pa)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Magar Singh house to Kulveer house in village Bdanad GP Bagroli Under
SDP Deposit Work (SH):- Construction of Retaining wall at R.D.0/0 to 0/010 and providing and laying cement concrete
pavement at RD 0/0 to 0/024)

Estimated cost:- Rs.69523/- only
Earnest Money : Rs.1400/- only
Time limit:- One month


Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	2.30 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	781.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.50 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	19527.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1600.00
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00 Cubic meter.	5290.60	Rupees Five Thousand Two Hundred Ninety And Paise Sixty Only	Per cubic meter	47615.00
					Total:-	69523.00


 Engineer
 Kanchpur Division HPPWD
 Patelput Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Sr. No		Description of items	Quantity		Rate		Unit	Amount
			In words	In figures	In words	In figures		
Name of work:-Construction of Retaining wall near the house of Veer Singh, Joginder, Rakesh etc.in village Khudial GP Kutwasi Under MLALAD (Deposit work) (SH:- Construction of P.C.C. Retaining wall at RD 0/0 to 0/14.50)								
Estimated cost:- Rs.95000/- only Earnest Money : Rs.1900/- only Time limit:- one month								
1		Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.75 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3989.00	
2		Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.23 cubic meter	3450.30	Rupees Three Thousand Four Hundred Fifty And Paise Thirty Only	Per cubic meter	87051.00	
3		Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	3960.00	
							Total:-	95000.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)