

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NO.PW- GHD-EA-I- /Tender/2026-
To

139 66-70

Dated:-

21-02-2026

**The Executive Engineer (IT-Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.
Email:-ee-pwd-hp@nic.in**

SUBJECT: -

Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before **23.02.2026**.

DA:-As above.

**Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin**
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.

**Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.**
On behalf of Governor of Himachal Pradesh

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **02-03-2026 up to 11.00 AM(if holiday then next working day)**. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 28-02-2026 up to 4.00 P.M and the application for issue of tender form shall be **received on 28-02-2026 up to 11.30 AM(if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Restoration of rain damages on Sumari to Lower Bhapral road km 0/00 to 9/00 (SH: Providing and laying Stone soling at link road Badon at km 1/150 and Badog at km 3/850 under PDNA year 2023.	Rs. 135920/-	Rs.2800/-	Rs.350/-	One Month
2.	Restoration of rain damages on Kandroun Panoh Takrera Ghumarwin road km 0/00 to 8/300 (SH: C/o Link road village Tarountra Hume Pipe Culvert at RD 0/553 under PDNA 2023.	Rs. 270927/-	Rs.5500/-	Rs.350/-	One Month
3.	Restoration of rain damages on Bhadhagat Kotla Sohni Devi road km 0/00 to 5/500 (SH: Boulder filling and earth filling behind retaining wal at Rd 0/470 to 0/495, at Rd 0/503 to 0/511, at Rd 0/284 to 0/291, at RD 0/317 to 0/325 at Rd 0/373 to 0/388 at Rd 2/101j to 2/114 at RD 2/164 to 2/179, at RD 4/400 to 4/430, at RD 4/433 to 4/451 and at RD 4/870 to 4/886 under PDNA Year 2023.	Rs.181879/-	Rs.3700/-	Rs.350/-	One Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,
Ghumarwin Division
HP.PWD, Ghumarwin

Draft Schedule of Quantity

Estimated Cost:- Rs.	1,35,920.00
Earnest Money:- Rs.	2,800.00
Time :-	One month

Name of Work:- Restoration of rain damages on Sumari to Lower Bhapral road km 0/00 to 9/00 (SH:-Providing and laying Stone soling at link road Badon at km 1/150 and Badog at Km 3/850)(Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre)spread thickness (finished work including materials and labour)as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.69	Per cubic metre	1550.00	Rupees One Thousand Five Hundred Fifty Only	135920
Total :-						135920

Draft Schedule of Quantity No 449 for the year 2025-26 approved for Rs 1,35,920/- only (one lakh thirty five thousand nine hundred twenty Rs)

Executive Engineer,
Ghumarwin Division,
HP PWD, Ghumarwin.

(Signature)

Draft Schedule of Quantity

Estimated Cost:- Rs. 2,70,927.00
Earnest Money:- Rs. 5,500.00
Time:- One month

Name of Work:- Restoration of rain damages on Kandror Panoh Takrera Ghumarwin road km 0/00 to 8/300 (SHI:- C/o link road village Tarountra Hume Pipe Culvert at RD 0/553) .(Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and MORD technical specification 2014 clause 305 (Three zero five) and as per direction of the Engineer-in-Charge. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.50	Per Cubic metre	250.00	Rupees Two Hundred Fifty Only	7375
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : (C.C. 1:3:6)(One cement is to three Coarse sand is to six crushed graded stone aggregate) 20 mm (twenty millimeter) nominal size.The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.06	Per cubic metre	5400.00	Rupees Five Thousand Four Hundred Only	48924
3	Providing and laying reinforced cement concrete hume pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One Cement: two Sand) but including cost of excavation, protection work, back filling ,concrete and masonry work in head walls and parapet as per MORD Technical Specification 2014 Clause 1108. 900mm dia (Nine hundred millimetre) dia including entire carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Per running metre	3800.00	Rupees Three Thousand Eight Hundred Only	28500
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement is to two sand) but including excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 600mm (six hundred millimetre) dia as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Per running metre	2000.00	Rupees Two Thousand Only	15000
5	Back filling with granular material behind retaining walls, abutment wing wall and return wall complete as per drawings and MORD technical specification 2014 Clause 1204.3.8 and as per direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.80	Per Cubic metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	92250

6	Filling in foundation trenches as per drawing and MORD technical specification Clause 305.3.9 earth filling and as per directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	242.70	Per cubic metre	325.00	Rupees Three Hundred Twenty Five Only	78878
Total :-						270927

Draft Schedule of Quantity No 452 for the year 2025-26 approved for Rs 2,70,927/only. (Two lakh Seventy Thousand Nine Hundred Twenty Seven only.)

Executive Engineer,
Ghumarwin Division,
P.W.D., Ghumarwin.


Draft Schedule of Quantity

Estimated Cost:- Rs.	1,81,879.00
Earnest Money:- Rs.	3,700.00
Time :-	One month

Name of Work:- Restoration of rain damages on Bhadhaghat Kotla Sohni Devi road km 0/00 to 5/500(SH:- Boulder filling & earth filling behind Retaining wall at RD 0/470 to 0/495, at RD 0/503 to 0/511, at RD 0/284 to 0/291, at RD 0/317 to 0/325, at RD 0/313 to 0/388, at RD 2/101 to 2/114, at RD 2/164 to 2/179, at RD 4/400 to 4/430, at RD 4/433 to 4/451 and at RD 4/870 to 4/886) .(Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Boulder filling dry hand packed tightly in wire crates vertical bunds with sloping face (wire crates to be measured separately) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	71.89	Per Cubic Metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	89863.00
2	Filling in foundation trenches as per drawing and MORD technical specification Clause 305.3.9 earth filling and as per directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	287.55	Per cubic metre	320.00	Rupees Three Hundred Twenty Only	92016.00
Total						181879

Draft Schedule of Quantity at Sr. No 438 for the year 2025-26 approved for Rs 1,81,879/- only


 Executive Engineer,
 Ghumarwin Division,
 PWD, Ghumarwin.