

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NO.PW- GHD-EA-I- /Tender/2026-
To

13353-56 Dated:- 10-02-2026

The Executive Engineer (IT-Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.
Email:-ee-pwd-hp@nic.in


SUBJECT: - Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 11.02.2026.


DA:-As above.


Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.


Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
E-Mail id- ee-ghu-hp@nic.in
Phone No.01978-255281

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **17-02-2026 up to 11.00 AM(if holiday then next working day)**. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 16-02-2026 up to 4.00 P.M and the application for issue of tender form shall be **received on 16-02-2026 up to 11.30 AM(if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	C/o Motorable road (about 300 mtr) from main road to the house os Puppy Kumar S/o Sh. Sukh Ram Village Barota PO Luharwin (VKV/2025/51(SH: ROFD at RD 0/010 to 0/080 .	Rs. 49800/-	Rs.1000/-	Rs.350/-	One Month
2.	C/o Health Sub Center building at Chokhna, Tehsil Ghumarwin Distt Bilaspur HP (SH: Providing and laying M.S.Grill Cement Concrete 1:4:8, 1:1.5:3 ,steel,half brick, 15mm plaster and plinth protection (Deposit works).	Rs. 95809/-	Rs.2000/-	Rs.350/-	One Month
3.	Restoration of rain damages on Bhager Panol Sunhani road km 0/00 to 3/d300 (SH: Removal of slips at Various RD's under PDNA year 2023.	Rs.265074/-	Rs.5400/-	Rs.350/-	One Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,
Ghumarwin Division
HP.PWD, Ghumarwin

Draft Schedule of Quantity

Estimated Cost:- Rs. 49,800.00

Earnest Money:- Rs. 1,000.00

Time :- One month

Name of Work:- Construction of Motorable road (About 300 metre) from main road to the House of Sh. Puppy Kumar S/o Sh. Sukh Ram Village Barota P.O. Luharwin Mohal : Barota (VKV/2025/51) (SH:- R.O.F.D. at RD 0/010 to 0/080) (Deposit VKVNY).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Cuting in earth work for road formation in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary oil ,soft rocks,hard rocks,chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required lines,graded with cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the M.O.R.D. technical specification clause 1603.1 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of unuseful material for filling in road,ways,camber, embankments for grade improvements and disposal of all in useful materials to required width of the road or approved dumping sites by Engineer-in-charge through all modes of transportation including head load or animals transport or mechanical means,along with its leveling fine dressing using machineries,materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and/or labour if required.Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge.The rate includes, octroi, Malkana , Toll tax , Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	204.10	Per cubic metre	244.00	Rupees Two Hundred Forty Four Only	49800.00
Total						49800

Draft Schedule of Quantity at Sr.No. 436 for
the year 2025-26 approved for Rs 49,800/- only

Executive Engineer,
Ghugrana Division,
R.P.W.D., Ghumarwin.

(Signature)

Draft Schedule of Quantity

Estimated Cost:- Rs. 95,809.00
Earnest Money:- Rs. 2,000.00
Time :- One Month

Name of Work:- Construction of Health Sub Center building at Chokhna. Tehsil Gumarwin Distt. Bilaspur (H.P.) (SH:- Providing and laying M.S. Grill. Cement Concrete 1:4:8 . 1:1.5:3. steel. Half brick. 15 mm plaster and Plinth Protection. (Deposit work).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing and fixing M.S. grills of required patterns in wooden/M.S. steel frames of windows etc. with M.S. flats, square, or round bars with round headed bolts and nuts or by screws plain grill including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge and as per HP.PWD Specification 1990 vol-I clause 12.4.10.9. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	442.430	Per kilogram	90.00	Rupees Ninety Only	39819
2	Centering and shuttering including strutting, propping etc. and removal of form for Suspended Moors, roofs, landing, balconies and access platform including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.88	Per Cubic Metre	280.00	Rupees Two Hundred Eighty Only	2206
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation complete as per drawing and MORD technical specification clauses 802, 803, 1202 & 1203. Nominal Mix 1:4:8 (one cement is to four sand is to eight crushed graded stone aggregate 40mm) (forty millimeter) .The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.78	Per cubic metre	5000.00	Rupees Five Thousand Only	8900
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement M-25 (M-twenty five): 1:1.5:3 (one cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty millimetre nominal size)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.52	Per cubic metre	7300.00	Rupees Seven Thousand Three Hundred Only	11096
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete work including cost of binding wire upto all floor level TMT of grade Fe-500D or more steel bars including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	182.00	Per kilogram	90.00	Rupees Ninety Only	16380
6	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level . Cement mortar 1:4 (1 cement :4 coarse sand)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2	Per Square Metre	900.00	Rupees Nine Hundred Only	1800

7	15 mm(fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:4 (One cement is to four coarse sand) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rate includes, octroi, Malkana, Toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.91	Per Square Metre	250.00	Rupees Two Hundred Fifty Only	6728
8	Providing under layer for plinth protection of 75 mm (seventy five millimeter) thick Unconsolidated bed dry brick/stone aggregate 40mm (forty millimeter) nominal size well rammed and consolidated grouted with fine sand including preparing of ground including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same and as per HP.PWD Specification 1990 vol-I clause 9.2.1.	15.31	Per square metre	260.00	Rupees Two Hundred Sixty Only	3981
9	Making plinth protection 50mm(fifty millimetre) thick of cement concrete 1:3:6 (One cement is to three coarse sand (zone - III) six crushed graded stone aggregate 20 mm (twenty millimetre) nominal size over 75mm (seventy five millimetre) thick bed of dry brick ballast 40 mm (forty millimetre) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.31	Per Square metre	320.00	Rupees Three Hundred Twenty Only	4899
Total:-						95,809.00

*Draft Schedule of Quantity at Sr. No 395 - for
the year 2025-26 approved for Rs 95,809/- only*

Executive Engineer,
Ghumarwin Division,
AP, PWD, Ghumarwin.
[Signature]

Draft Schedule of Quantity				Estimated Cost:- Rs.		
				2,65,074.00		
				Earnest Money:- Rs.		
				5,400.00		
				Time :-		
				One month		
Name of Work:- Restoration of rain damages on Bhager Panol Sunhani road km 0/00 to 3/300 (SH:- Removal of slips at various RD's) (Under PDNA Year 2023).						
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of material with in all leads and lifts as per technical specification 302.3.5 and 1611. The dumping site for throwing debris be arranged by the contractor at his own level and no debris be thrown in the forest land or along the nallah, culverts etc. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. Any damage occurred to government or private property during execution of work will be the sole responsibility of the contractor. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2208.95	Per cubic metre	120.00	Rupees One Hundred Twenty Only	265074
	Total					265074

Draft Schedule of Quantity at Sr. No. 435 for the year 2025-26 approved for Rs 2,65,074/only

Executive Engineer,
Ghumarwin Division,
P.P. PWD, Ghumarwin.