

Himachal Pradesh  
Public Works Department

\*\*\*\*

No. PWH/HD/CB/T-I/2025-26  
To

11247-49

Dated: - 16-02-2025

The Executive Engineer (IT Cell)  
Nirman Bhawan, Nigam Vihar,  
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una (HP).


Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una (HP).

## Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/  
1/2025-26-11247-49 dated 16/2/2026 are required to be carried out immediately being emergent nature of  
in public interest.

  
Executive Engineer,  
Haroli Division, HPPWD  
Haroli Dist. Una HP).

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
" NOTICE INVITING TENDERS "

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: -
2. Date of issue/sale of tender forms against cash payment(non-refundable): -
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

23/02/2026  
25/02/2026  
28/02/2026

up to 10.30 (AM).  
up to 3.00 PM  
up to 10.30 AM  
at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-X) under MMGSY	59049	2000/-	One Month	350/-	Class- C & D
2	Balance work for the C/O 4 Nos. class room at G.S.S. at Singan Tehsil Haroli Distt. Una (SH:-Painting, dressing & polishing of kota stone etc.) Deposit work	99584	2000/-	One Month	350/-	Class- C & D
3	Repair of pot hole on link road Singan to HP Boundary km. 0/00 to 1/300(SH:- Repair of pot hole at RD. 0/00 to 1/300)	97062	2000/-	One Month	350/-	Class- C & D
4	C/O link road from House of Chamba devi RD. 0/00 to 1/200(SH:-C/O Retaining wall at RD. 1/179.30 to 1/188.60 LHS)	98726	2000/-	One Month	350/-	Class- C & D
5	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-VIII) under MMGSY	99258	2000/-	One month	350/-	Class- C & D
6	Balance work for theC/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O B/wall near Septic Tank Phase-II) Deposit Work	99797	2000/-	One month	350/-	Class- C & D
7	Repair of pot hole on link road Chak Khad to Khad Khas via Tand Tand Paneda km. 0/00 to 2/240(SH:-Patch work at RD. 0/400 to 0/590)	99247	2000/-	One Month	350/-	Class- C & D
8	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-VII) under MMGSY	98974	2000/-	One Month	350/-	Class- C & D
9	Repair of pot hole on Ajouli Santoshgarh Polian road km. 0/00 to 17/400 (SH:-Reapir of pot hole at RD. 13/00 to14/00)	99301	2000/-	15 day	350/-	Class- C & D
10	Repair of pot hole on Ajouli Santoshgarh Polian road km. 0/00 to 17/400 (SH:-Reapir of pot hole at RD. 14/00 to15/00)	98431	2000/-	One Month	350/-	Class- C & D
11	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-VI) under MMGSY	99849	2000/-	One Month	350/-	Class- C & D
12	Balance work for the C/O 4 Nos. class room at G.S.S. at Singan Tehsil Haroli Distt. Una (SH:-Painting, of School building)Phase-I Deposit work	99856	2000/-	One Month	350/-	Class- C & D
13	Repair of pot hole on link road to shamshanghat Nangal Khurd from Jaijon modh to Tahliwal chowk road km. 0/00 to 1/320(SH:- Repair of pot holes at RD. 0/00 to 1/320)	99845	2000/-	One Month	350/-	Class- C & D
14	Repair of pot hole on Ajouli Santoshgarh Polian road km. 0/00 to 17/400 (SH:-Reapir of pot hole at RD. 15/00 to16/00)	97559	2000/-	One Month	350/-	Class- C & D

15	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/553.50 to 2/565)	97812	2000/-	One Month	350/-	Class- C & D
16	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/542.10 to 2/553.50)	97812	2000/-	One Month	350/-	Class- C & D
17	Repair of pot holes on link road to village Khad km. 0/00 to 2/240 (SH:-Patch work at RD. 1/572 to 1/744)	99589	2000/-	One Month	350/-	Class- C & D
18	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-I) under MMGSY	99536	2000/-	One Month	350/-	Class- C & D
19	Balance work for the C/O 4 Nos. class room at G.S.S. at Singan Tehsil Haroli Distt. Una (SH:-Painting work in class room, dressing & polishing of kota stone etc.)Phase-II Deposit work	99585	2000/-	One Month	350/-	Class- C & D
20	Repair of pot hole on link road to village Nangal Khurd from Jaijon modh to Tahliwal chowk road km. 0/00 to 2/00(SH:-Repair of pot hole at RD. 0/00 to 2/00)	97108	2000/-	One Month	350/-	Class- C & D
21	Repair of pot hole on link road Chak Khad to Khad Khas via Tand Tand Paneda km. 0/00 to 2/240(SH:-Patch work at RD. 0/600 to 0/790)	99241	2000/-	One Month	350/-	Class- C & D
22	Repair of pot hole on Umrli Beetan Goua road km. 0/00 to 3/200(SH:-Repair of pot hole at RD. 2/00 to 3/200)	99301	2000/-	One Month	350/-	Class- C & D
23	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-II) under MMGSY	98974	2000/-	One Month	350/-	Class- C & D
24	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/530.50 to 2/542.10)	99528	2000/-	One Month	350/-	Class- C & D
25	C/O link road from House of Chamba devi RD. 0/00 to 1/200(SH:-C/O Retaining wall at RD. 1/170 to 1/179.30 LHS)Deposit Work	98886	2000/-	One Month	350/-	Class- C & D
26	Repair of pot hole on link road Petrol Pump Bhadsali to Una Hoshiarpur road to Pandoga lower to Har Sainia Abadi km. 0/00 to 2/00(SH:-Patch work at RD. 0/300 to 0/915)	99408	2000/-	One Month	350/-	Class- C & D
27	Repair of pot hole on link road Ispur to Pandoga via Kyarian km. 0/00 to 2/175 (SH:-Patch work at RD. 1/300 to 1/780)	99538	2000/-	One Month	350/-	Class- C & D
28	Repair of pot hole on Jaijon Modh to Tahliwal chowk via Bhai ka Modh road km. 0/00 to 17/500 (SH:-Repair of pot holes at RD. 28/500 to 29/500 & 33/00 to 34/00)	99550	2000/-	One Month	350/-	Class- C & D
29	Repair of pot hole on Ajouli Santoshgarh Polian road km. 0/00 to 17/400 (SH:-Reapir of pot hole at RD. 4/00 to 8/00)	99550	2000/-	One Month	350/-	Class- C & D
30	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/519 to 2/530.50)	98670	2000/-	One Month	350/-	Class- C & D
31	C/O link road from House of Chamba devi RD. 0/00 to 1/200(SH:-C/O Retaining wall at RD. 1/188.60 to 1/194.30 RHS)	98970	2000/-	15 day	350/-	Class- C & D

32	Repair of pot hole on Una Rampur Haroli Jaijon road km. 0/00 to 23/00(SH:-Repair of pot hole at RD. 16/200 to 16/234)	98906	2000/-	One Month	350/-	Class- C & D
33	Repair of pot hole on Una Rampur Haroli Jaijon road km. 0/00 to 23/00(SH:-Repair of pot hole at RD. 16/234 to 16/268.10)	99197	2000/-	One Month	350/-	Class- C & D
34	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/507.60 to 2/519)	97812	2000/-	One Month	350/-	Class- C & D
35	Balance work for the Improvement of Collage infrastructure at SDWG Govt. Collage Beetan Tehsil Haroli Distt. Una (HP)(SH:-Leveling work of play Ground)Phase-I	99352	2000/-	One Month	350/-	Class- C & D
36	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/496 to 2/507.60)	99528	2000/-	One Month	350/-	Class- C & D
37	Repair of pot hole on Una Rampur Haroli Jaijon road km. 0/00 to 23/00(SH:-Repair of pot hole at RD. 16/302.30 to 16/336.60)	99589	2000/-	One Month	350/-	Class- C & D
38	Repair of pot holes on link road to village Khad km. 0/00 to 2/240 (SH:-Patch work at RD. 1/400 to 1/570)	99679	2000/-	One Month	350/-	Class- C & D
39	Repair of pot hole on Panjwar Bathri road km. 0/00 to 34/00(SH:-Patch work at RD. 0/00 to 3/00)	99399	2000/-	One Month	350/-	Class- C & D
40	C/O link road from House of Chamba devi RD. 0/00 to 1/200(SH:-C/O Retaining wall at RD. 1/194.30 to 1/200 RHS)Deposit Work	99450	2000/-	One Month	350/-	Class- C & D
41	Repair of pot hole on Panjwar Bathri road km. 0/00 to 34/00(SH:-Patch work at RD. 3/00 to 6/00)	99107	2000/-	One Month	350/-	Class- C & D
42	Balance work for the Upgradation of link road Umrli Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/481.50 to 2/496)	98670	2000/-	One Month	350/-	Class- C & D
43	Repair of pot hole on Una Rampur Haroli Jaijon road km. 0/00 to 23/00(SH:-Repair of pot hole at RD. 15/400 to 16/200)	99550	2000/-	One Month	350/-	Class- C & D
44	Balance work for the Improvement of Collage infrastructure at SDWG Govt. Collage Beetan Tehsil Haroli Distt. Una (HP)(SH:-Leveling work of play Ground)Phase-II	99792	2000/-	One Month	350/-	Class- C & D
45	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-III) under MMGSY	99258	2000/-	One Month	350/-	Class- C & D
46	Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O B/wall near Septic Tank Phase-I) Deposit Work	99957	2000/-	One Month	350/-	Class- C & D
47	Repair of pot hole on Panjwar Bathri road km. 0/00 to 34/00(SH:-Patch work at RD. 6/00 to 9/00)	99688	2000/-	One Month	350/-	Class- C & D
48	Repair of pot hole on Una Rampur Haroli Jaijon road km. 0/00 to 23/00(SH:-Repair of pot hole at RD. 16/268.10 to 16/302.30)	99392	2000/-	One Month	350/-	Class- C & D
49	Balance work for the Improvement of Collage infrastructure at SDWG Govt. Collage Beetan Tehsil Haroli Distt. Una (HP)(SH:-Leveling work of play Ground re-painting of existing stage shed and main gate)Phase-IV	98699	2000/-	One Month	350/-	Class- C & D

50	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-IV) under MMGSY	98071	2000/-	One Month	350/-	Class- C & D
51	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-IX) under MMGSY	97787	2000/-	One Month	350/-	Class- C & D
52	Repair of pot hole on link road to village Pandoga from Gagret road km. 0/00 to 2/640(SH:-Patch work at RD. 0/300 to 0/915)	99394	2000/-	One Month	350/-	Class- C & D
53	Repair of pot hole on link road to Co-Operative society Haroli via GSSS Haroli km. 0/00 to 2/225(SH:-Repair of pot hole at RD. 0/00 to 1/00)	98193	2000/-	One Month	350/-	Class- C & D
54	Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O B/wall near rain harvesting Tank Phase-V) Deposit Work	98542	2000/-	One Month	350/-	Class- C & D
55	Balance work for the Upgradation of link road Umrals Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/461.50 to 2/473.10)	99528	2000/-	One Month	350/-	Class- C & D
56	C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH:-C/O R/wall alongwith Mandir Phase-V) under MMGSY	98662	2000/-	One Month	350/-	Class- C & D
57	Balance work for the Upgradation of link road Umrals Dhillwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC pavement in main road at RD. 2/473.10 to 2/484.50)	97812	2000/-	One Month	350/-	Class- C & D
58	Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-P/F collapsible steel shutter & water storage tanks) Deposit Work	99926	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

**SPECIAL CONDITION: -**


1. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
2. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
3. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
4. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
5. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
6. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer  
HPPWD Division Haroli  
Distt.Una(HP).Pin Code-177220  
Email: [ee-harolli-hp@hp.gov.in](mailto:ee-harolli-hp@hp.gov.in)  
On behalf of Governor of Himachal Pradesh

①

**Schedule of quantity**

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-X)under MMGSY						Estimated Cost: Rs	₹ 59,049
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	4.38	Cum.	170.00	Rupees one hundred seventy Only	745	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	16.77	Cum.	3300.00	Rupees three thousand three hundred only	55341	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510	
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	4.46	Cum.	550.00	Rupees five hundred fifty only	2453	
Total:						59049	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							
						Executive Engineer	

**SCHEDULE OF QUANTITY**

Name of Work : Balance work for the C/O 4 Nos class room at G.S.S. at Singan Tehsil Haroli Distt. Una (SH: -painting , dressing & polishing of Kota stone) -Deposit work.

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Finishing walls with Acrylic Smooth exterior paint of (Neolac/Assian/Dulux/Berger) Jensen and Nicholson (J&N) GFolden Paint Aqualac make required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) upto any floor/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	281.25	Per square metre	75.00	Rupees seventy five only	21094
2	Painting steel work with deluxe multi surface paint system for interiors and exterior using Steel work with Delux Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	143.00	Per square metre	80.00	Rupees eighty only	11440
3	Providing and fixing glazing with glass panes of 4 mm thickness (weight not less than 10 kg/ sqm in aluminium door, window, ventilator shutters make it Hindal Co., Jindal Indian aluminium Co. and including carriage with PVC/ neoprens gasket etcetera complete upto any floor level/height complete Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	14.40	Per square metre	850.00	Rupees eight hundred fifty only	12240
4	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, complete including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.00	Per square metre	4200.00	Rupees four thousand two hundred only	16800
5	Dressing and polishing of marble/ granite/kota stone complete as per per direction of Engineer in Charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018 2) The rates shall be inclusive of all types of taxes including GST etcetera)	205.46	Per square metre	185.00	Rupees one thousand eighty five only	38010
	Percentage quoted rate in Figures				<b>Total:</b>	<b>99584</b>
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

**Schedule of quantity**

Name of work:-Repair of pot hole on Link road Singan to HP Boundary km. 0/00 to 1/300		Estimated Cost: Rs	Time:-	₹ 97,062		
(SH: Repair of pot hole at Rd. 0/00 to 1/300)		Earnest Money:-				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.09	cum	1300	Rupees One Thousand Three Hundred Only	20914
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	214.50	sqm	55.00	Rupees FiftyFive Only	11798
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	214.50	sqm	300.00	Rupees Three Hundred Only .	64350
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97062
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					



**Executive Engineer,**  
H.P.P.W.D. Division Haroli

**Schedule of quantity**

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs	₹ 98,726			
(SH: C/O Retaining wall at Rd. 1/179.30 to 1/188.60 Lhs)		Time:-	One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	
					Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.09	Cum.	160.00	Rupees One Hundred Sixty Only	1295
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.85	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	91917
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One Hundred Sixty Only	2240
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.95	Cum.	550.00	Rupees Five Hundred Fifty Only	3274
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	98726
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)31/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)31/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					
	<b>Executive Engineer, H.P.P.W.D. Division Haroli Distt. Una (H.P.)</b>					

5

**Darft Schedule of quantity**

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-VIII) under  
M&GSY

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-VIII) under		Estimated Cost: Rs		Amount			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.38	Cum.	170.00	Rupees one hundred seventy Only	1255	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.29	Cum.	3300.00	Rupees three thousand three hundred only	93357	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510	
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.52	Cum.	550.00	Rupees five hundred fifty only	4136	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018						Total:	99258
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							

603

**SCHEDULE OF QUANTITY**

Name of work : Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una ( SH:C/O breast wall near Septic Tank - Phase-II ) - D/work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
				Estimated Cost		
						99797
						2000
						One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royakly, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.22	Per cubic metre	160.00	Rupees One hundred sixty only	675
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.73	Per cubic metre	3400.00	Rupees three thousand three hundred only	97682
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only	1440-
					<b>Total:</b>	<b>99797</b>
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/20212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	<b>Percentage quoted rate in Figures</b>					
	<b>Percentage quoted rate in words</b>					
	<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>					

  
**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (HP)**

638

SCHEDULE OF QUANTITY

Name of work : Repair of pot hole on link road Chak Khad to Khad Khas via Tand Paneda Km 0/00 to 2/240 (SH: Patch work at RD 0/400 to 0/590)		Estimated Cost	99247			
		Earnest Money	2000			
		Time limit	One month			
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	6.42	Per cubic metre	1400.00	Rupees One three hundred fifty only	8988
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals The rate including octroi royalty,malkhana toll taxes,GST , labour cess or taxes imposed by the Government	85.55	Per square metre	55.00	Rupees Fifty five only	4705
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	285.18	Per square metre	300.00	Rupees Three hundred only	85554
				<b>Total:</b>		<b>99247</b>
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

**Schedule of quantity**

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-VII) under MMGSY							Estimated Cost: Rs	₹ 98,974
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.36	Cum.	170.00	Rupees one hundred seventy Only	1251		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.21	Cum.	3300.00	Rupees three thousand three hundred only	93093		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510		
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.49	Cum.	550.00	Rupees five hundred fifty only	4120		
					Total:	98974		
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17/2/0212 dated 7.8.2018							
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31/2020 dated 22.07.20							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

645

Schedule of quantity

Name of work:- Repair of pot hole on Ajouli Santoshgarh Polian road Km. 0/00 to 17/400

(SH: Repair of pot hole at Rd. 13/00 to 14/00)

Name of work:- Repair of pot hole on Ajouli Santoshgarh Polian road Km. 0/00 to 17/400		Estimated Cost: Rs		₹ 99,301			
(SH: Repair of pot hole at Rd. 13/00 to 14/00)		Time:-		One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.46	cum	1300		Rupees One Thousand Three Hundred Only	21396
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	219.45	sqm	55.00		Rupees FiftyFive Only	12070
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	219.45	sqm	300.00		Rupees Three Hundred Only	65835
	<b>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</b>					Total	99301
	<b>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</b>						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be r3jected						

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt Una (H.P.)

10

646

Schedule of quantity

Name of work:-Repair of pot hole on Ajouli Santoshgarh Polian road Km. 0/00 to 17/400		Estimated Cost: Rs		₹ 98,431		
(SH: Repair of pot hole at Rd. 14/00 to 15/00)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	
					Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. 1/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.31	cum	1300	Rupees One Thousand Three Hundred Only	21209
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mcchemical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	217.53	sqm	55.00	Rupees FiftyFive Only	11964
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	217.53	sqm	300.00	Rupees Three Hundred Only	65258
					Total	98431
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,  
H.P.P.W.D. Division Haridif  
Distt. Una (H.P.)

4

Schedule of quantity

Name of Work :-C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-VI) under

MMGSY		Estimated Cost: Rs		Amount		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.43	Cum.	170.00	Rupees one hundred seventy Only	1263
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.46	Cum.	3300.00	Rupees three thousand three hundred only	93918
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.56	Cum.	550.00	Rupees five hundred fifty only	4158
				Total:		99849
				Percentage quoted rate in Figures		
				Percentage quoted rate in words		
				Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.		

Executive Engineer

12

**SCHEDULE OF QUANTITY**

Name of Work : Balance work for the C/O 4 Nos class room at G.S.S. at Singan Tehsil Haroli Distt. Una (SH: painting of school building ) - Deposit work. *phmet*

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
				Time limit		
					Estimated Cost	99856
					Earnest Money	2000
					Time limit	One Month
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	735.62	Per square metre	11.00	Rupees eleven only	8092
2	Providing and applying white cement (Birla white/JK) wall putty based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level /any height including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	147.12	Per square metre	62.00	Rupees sixty two only	9121
3	Applying priming coats with primer of approved brand and manufacturer, having low VOC (Volatile Organic Compound) content With water thinnable cement primer on wall surface having VOC content less than 50 including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	735.62	Per square metre	51.00	Rupees fifty one only	37517
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC contents less than 50grms /litre of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	523.78	Per square metre	73.00	Rupees seventy three only	38236
5	Painting wood work delux multi surface paint of approved brand and manufacture on wood work (hard and soft wood) two or more coat applied i.e. 0.90 litre per ten square metre over and under coat of primer including priming coat of approved primer including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	86.12	Per square metre	80.00	Rupees eighty only	6890
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The rates shall be inclusive of all types of taxes including GST etcetera)					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					
					Total:	99856

Executive Engineer  
Haroli Division,  
HPPWD Haroli

13

633

Schedule of quantity

Name of work:-Repair of pot hole on Link road to Shamshanghat Nangal Khurd from Jaijon modh to Tahliwal chowk road Km. 0/00 to 1/320		Estimated Cost: Rs		Time:-		₹ 99,845	
(SH: Repair of pot hole at Rd. 0/00 to 1/320)		1/320		2000		One month	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.35	cum	1300	Rupees One Thousand Three Hundred Only	19949	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	225.06	sqm	55.00	Rupees FiftyFive Only	12378	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	225.06	sqm	300.00	Rupees Three Hundred Only	67518	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				Total	99845	
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

647

12

**Schedule of quantity**

Name of work:-Repair of pot hole on Ajouli Santoshgarh Polian road Km. 0/00 to 17/400		Estimated Cost: Rs		₹ 97,559			
(SH: Repair of pot hole at Rd. 15/00 to 16/00)		Time:-		One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.17	cum	1300	Rupees One Thousand Three Hundred Only	21021	
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	215.60	sqm	55.00	Rupees FiftyFive Only	11858	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	215.60	sqm	300.00	Rupees Three Hundred Only	64680	
<b>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</b>						Total	<b>97559</b>
<b>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</b>							
Percentage quoted rate in figures							
Percentage quoted rate in words							
<b>Note -Rate quoted in figures &amp; words are mandatory by the contractor, other wise the tender will be rejected</b>							

15

Schedule of quantity							Estimated Cost: Rs	₹ 97,812
Name of work:- Balance work for the Upgradation of link road Umralli Dhilwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400.							Time:-	One month
( SH: P/L CC Pavement in main road at Rd. 2/553.50 to 2/565).							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealent, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501.. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.05	CUM.	6500.00	(Rupees Six thousand five hundred only)	97812		
					Total:	97812		

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018  
 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20

Percentage quoted rate in Figures  
 Percentage quoted rate in words  
 Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. H.

16

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umralli Dhilwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400.		Estimated Cost: Rs	₹ 97,812			
(SH: P/L CC Pavement in main road at Rd. 2/542.10 to 2/553.50).		Time:-	One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.05	CUM.	6500.00	(Rupees Six thousand five hundred only)	97812
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt of HP vide letter No.PBW(B)@17/02/12 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20						
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						
<b>Total:</b>						<b>97812</b>

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

639

17

SCHEDULE OF QUANTITY									
Name of work : Repair of pot hole on link road to village Khad Km 0/00 to 2/240 (SH: Patch work at RD 1/572 to 1/744)									
S. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost	Earnest Money	Time limit	AMOUNT
				Figures	Words				
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 400* including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	9.84	Per cubic metre	1400.00	Rupees One three hundred fifty only	99589	2000	One month	13776
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government	131.15	Per square metre	55.00	Rupees Fifty five only				7213
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government..	262.00	Per square metre	300.00	Rupees Three hundred only				78600
						<b>Total:</b>			<b>99589</b>
<b>Percentage quoted rate in Figures</b>									
<b>Percentage quoted rate in words</b>									
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>									

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

**Schedule of quantity**

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-I) under MMGSY

S.NO		DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Estimated Cost: Rs	Amount
1		Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.40	Cum.	170.00	Rupees one hundred seventy Only		1258
2		Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.37	Cum.	3300.00	Rupees three thousand three hundred only		93621
3		Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only		510
4		Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.54	Cum.	550.00	Rupees five hundred fifty only		4147
							Total:	99536
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018								
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

74

Schedule of quantity

Name of work :- Balance work for the C/o 4 Nos class room at Govt. Sr. Sec. School at Singan Tehsil Haroli Distt. Una.

Name of work :- Balance work for the C/o 4 Nos class room at Govt. Sr. Sec. School at Singan Tehsil Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,585		
[Sub Head:Painting work in class room , dressing & polishing of Kota stone ] Phase-II (C/P/work)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	525.00	Per Square metre	11.00	Rupees Eleven only	5775
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	105.00	Per Square metre	62.00	Rupees sixty two only	6510
3	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface :Water thinnable cement primer. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	525.00	Per Square metre	51.00	Rupees fifty one only	26775
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	525.00	Per Square metre	73.00	Rupees seventy three only	38325
5	Dressing and polishing of Marble/Granite/Kota stone complete as per direction of Engineer in Charge The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	120.00	Per Square metre	185.00	Rupees One hundred eighty five only	22200
				NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018		
				2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20		
				Percentage quoted rate in Figures		
				Percentage quoted rate in words		
				Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.		
				Total:		99585

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

20

632

Schedule of quantity


Name of work:-Repair of pot hole on Link road to Village Nangal Khurd from Jaijon modh to Tahlwal chowk road Km. 0/00 to 2/00		Estimated Cost: Rs		₹ 97,108			
(SH: Repair of pot hole at Rd. 0/00 to 2/00)		Time:-		One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.98	cum	1300	Rupees One Thousand Three Hundred Only	2000	9068
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	248.00	sqm	55.00	Rupees FiftyFive Only		13640
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	248.00	sqm	300.00	Rupees Three Hundred Only		74400
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		97108
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

M

640

(2)

SCHEDULE OF QUANTITY							Estimated Cost	99241
Name of work : Repair of pot hole on link road Chak Khad to Khad Khas via Tand Paneda Km 0/00 to 2/240 (SH: Patch work at RD 0/600 to 0/790)							Earnest Money	2000
S. No.	Description of work	Quantity	Unit	RATE IN		One month AMOUNT		
				Figures	Words			
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.42	Per cubic metre	1400.00	Rupees One thousand four hundred only	8988		
2	Providing and applying eventy a primer coat with bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seveny kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty,maikhana toll taxes,GST ,labour cess or taxes imposed by the Government	85.55	Per square metre	55.00	Rupees Fifty five only	4705		
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904 2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	285.16	Per square metre	300.00	Rupees Three hundred only	85548		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/20212 dated 7.8.2018						Total:	99241	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt.of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

  
 Exedutive Engineer  
 Haroli Division  
 HP.PWD.,Haroli

648

22

## Schedule of quantity

Name of work:-Repair of pot hole on Umralli Beetan Goua road Km. 0/00 to 3/200		Estimated Cost: Rs		₹ 99,301		
(SH: Repair of pot hole at Rd. 2/00 to 3/200)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density, j/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.46	cum	1300	Rupees One Thousand Three Hundred Only	21396
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	219.45	sqm	55.00	Rupees FiftyFive Only	12070
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	219.45	sqm	300.00	Rupees Three Hundred Only	65835
	<b>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</b>				Total	99301
	<b>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021</b>					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.R.)

23

Schedule of quantity

Name of Work :- C/O retaining wall Near Sheetia Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-II) under MMGSY						Estimated Cost: Rs	₹ 98,974
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.36	Cum.	170.00	Rupees one hundred seventy Only	1251	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.21	Cum.	3300.00	Rupees three thousand three hundred only	93093	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510	
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.49	Cum.	550.00	Rupees five hundred fifty only	4120	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018						Total:	98974
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

214


Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umralli Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400.		Estimated Cost: Rs	Time:-			
( SH: P/L CC Pavement in main road at Rd. 2/530.50 to 2/542.10).		₹ 99,528	One month			
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.31	CUM.	6500.00	(Rupees Six thousand five hundred only)	99528
					Total:	99528
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

25

Schedule of quantity

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs		₹ 98,886		
(SH: C/O Retaining wall at Rd. 1/170 to 1/179.30 Lhs)		Time:-		One month		
		Earnest Money:-				
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.09	Cum.	160.00	Rupees One Hundred Sixty Only	1295
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.85	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	91917
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.00	Each	160.00	Rupees One Hundred Sixty Only	2400
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.95	Cum.	550.00	Rupees Five Hundred Fifty Only	3274
				Total		98886
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						
				 <b>Executive Engineer,</b> <b>H.P.W.D. Division Harohi</b> <b>Distt. Una (H.P.)</b>		

641

26

SCHEDULE OF QUANTITY				Estimated Cost	99408	
Name of work : Repair of pot hole on link road Petrol Pump Bhadsali to Una Hoshiarpur road to Pandoga lower to Har Sania Abadi Km 0/00 to 2/00 (SH: Patch work at RD 0/300 to 0/915)				Earnest Money	2000	
				Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400 11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, maikhana , toll tax, GST, labour cess or other taxes imposed by the Government...	7.03	Per cubic metre	1400.00	Rupees One thousand four hundred only	9842
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentials. The rate including octroi royalty, maikhana toll taxes, GST, labour cess or taxes imposed by the Government	93.79	Per square metre	55.00	Rupees Fifty five only	5158
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2 503 and 508.1 including carriage of materials within all leads and lifts and other incidential. The rate includes sale tax octroi, royalty, maikhana , toll tax, GST, labour cess or other taxes imposed by the Government...	281.36	Per square metre	300.00	Rupees Three hundred only	84408
				<b>Total:</b>		<b>99408</b>
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

Executive Engineer  
Haroli Division  
HP.PWD., Haroli

642

27

SCHEDULE OF QUANTITY									
Name of work : Repair of pot hole on link road Ispur to Pandoga via Kyarian Km 0/00 to 2/175 (SH: Patch work at RD 1/300 to 1/780)									
S. No.	Description of work	Quantity	Unit	Figures	Words	Estimated Cost		One month AMOUNT	
						Estimated Money	Time limit	Estimated Money	One month
				Figures	Words	RATE In		AMOUNT	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	5.48	Per cubic metre	1400.00	Rupees One thousand four hundred only				7672
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 Kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government	73.20	Per square metre	55.00	Rupees Fifty five only				4026
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2, 503 and 508.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	292.80	Per square metre	300.00	Rupees Three hundred only				87840
						<b>Total:</b>			<b>99538</b>
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)A(17)20212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Exedutive Engineer  
Haroli Division  
HP.PWD.,Haroli

28

631

Schedule of quantity

Name of work:- Repair of pot hole on Jaijon Modh to Tahliwal chowk via Bhai ka Modh road Km. 0/00 to 17/500 (SH: Repair of pot hole at Rd. 28/500 to 29/500 & 33/00 to 34/00)							Estimated Cost: Rs	₹ 99,550
							Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000	
						Amount		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government.	16.50	cum	1300	Rupees One Thousand Three Hundred Only	21450		
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government.	220.00	sqm	55.00	Rupees FiftyFive Only	12100		
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty, malkhana ,toll tax, GST, labour cess or other taxes imposed by the Government.	220.00	sqm	300.00	Rupees Three Hundred Only	66000		
					Total	99550		
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Handwritten signature

Executive Engineer,  
H.P.P.W.D. Division Haroli

630

29

Schedule of quantity

Name of work:- Repair of pot hole on Ajouli Santoshgarh Polian road Km. 0/00 to 17/400		Estimated Cost: Rs		Time:-		
(SH: Repair of pot hole at Rd. 4/00 to 8/00)		₹ 99,550		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including pre-mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll, tax, GST, labour cess or other taxes imposed by the Government.	16.50	cum	1300	Rupees One Thousand Three Hundred Only	21450
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	220.00	sqm	55.00	Rupees FiftyFive Only	12100
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	220.00	sqm	300.00	Rupees Three Hundred Only	66000
					Total	99550
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

30

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umrali Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400.		Estimated Cost: Rs	₹ 98,670			
( SH: P/L CC Pavement in main road at Rd. 2/519 to 2/530.50).		Time:-	One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.18	CUM.	6500.00	(Rupees Six thousand five hundred only)	98670
					Total:	98670
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

**Schedule of quantity**

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs	₹ 98,970			
(SH: C/O Retaining wall at Rd. 1/188.60 to 1/194.30 Rhs)		Time:-	One month			
DESCRIPTION		Earnest Money:-				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.16	Cum.	160.00	Rupees One Hundred Sixty Only	985
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.60	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94379
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each	160.00	Rupees One Hundred Sixty Only	1600
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.65	Cum.	550.00	Rupees Five Hundred Fifty Only	2006
					Total	98970
<p>Note 1] All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p> <p>2] The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures &amp; words are mandatory by the contractor, other wise the tender will be rejected</p>						
					<b>Executive Engineer,</b> <b>H.P.P.W.D. Division Haroli</b> <b>Distt. Una (H.P.)</b>	

624

32

**Schedule of quantity**

Name of work:-Repair of pot hole on Una Rampur Haroli Jaijon Road Km. 0/00 to 23/00		Estimated Cost: Rs		₹ 98,906		
(SH: Repair of pot hole at Rd. 16/200 to 16/234)		Time:-		One month		
S.NO	DESCRIPTION	Earnest Money:-				
		Qty	Unit	T.Rate		
				Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	20.40	Cum	160.00	Rupees One Hundred Sixty Only	3264
2	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	20.40	Cum	240.00	Rupees Two Hundred Fourty Only	4896
3	Construction of Gravel /Soil aggregate base/sub base Nominal Maximum size Grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with Tractor mount appropriate grading arrangements on prepared surface, mixing by mix place method at OMC with Tractor mount appropriate rotavator attachment and compaction with three wheel 80-100kN static Roller capacity to achieve the desired density, complete as per Specification contained in Para 2.2, 3.6 and 3.7 of IRC SP 77-2008. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	10.20	Cum	1100.00	Rupees One Thousand One Hundred Only	11220

4	<p>Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	13.60	Cum	1400.00	Rupees One Thousand Four Hundred Only	19040
5	<p>Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification MORD 2014 clause 502 and as per direction of Engineer-in-charge . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	68.00	Sqm	55.00	Rupees FiftyFive Only	3740
6	<p>Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg.per sqm(Zero point twenty five to zero point thirty kilogram)per square metre.on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification MORD 2014 clause 503. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	68.00	Sqm	21.00	Rupees TwentyOne Only	1428
7	<p>Providing and laying 50mm thick dense bituminous macadam with VG-30 hot mix plant using crushed aggregates of grading as per table 500.4.500.3 premixed with bituminous binder 4.5 percent (minimum), transported to site upto a lead of any metre laid over a previously prepared surface with paver finisher to the required grade level and alignment and rolled to achieve the desired compaction as per technical specification clause 504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	3.40	Cum	9550.00	Rupees Nine Thousand Five Hundred Fifty Only	32470

8	<p>Providing and laying 30mm thick (thirty millimetre) thick bituminous concrete with 100-120 ( one hundred to one hundred twenty ) batch type HMP, producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading premixed with bitumen binder VG-30 @ (five point four percent) minimum of mix and filler ,transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH 2014 specification clause No. 509 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..</p>	2.04	Cum	11200.00	Rupees Eleven Thousand Two Hundred Only	22848	
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p>							
<p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A(3)1/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B/A(3)1/2020-1 Dated 07.10.2021</p>							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							
						Total	98906



**Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)**

33

625

Schedule of quantity

Name of work:-Repair of pot hole on Una Rampur Haroli Jaijon Road Km. 0/00 to 23/00		Estimated Cost: Rs		₹ 99,197		
(SH: Repair of pot hole at Rd. 16/234 to 16/268.10)		Time:-		One month		
S.NO	DESCRIPTION	Earnest Money:-				
		Qty	Unit	T.Rate		
				Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	20.46	Cum	160.00	Rupees One Hundred Sixty Only	3274
2	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	20.46	Cum	240.00	Rupees Two Hundred Fourty Only	4910
3	Construction of Gravel /Soil aggregate base/sub base Nominal Maximum size Grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with Tractor mount appropriate grading arrangements on prepared surface, mixing by mix place method at OMC with Tractor mount appropriate rotavator attachment and compaction with three wheel 80-100kN static Roller capacity to achieve the desired density, complete as per Specification contained in Para 2.2, 3.6 and 3.7 of IRC SP 77-2008. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.23	Cum	1100.00	Rupees One Thousand One Hundred Only	11253

4	<p>Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..</p>	13.64	Cum	1400.00	Rupees One Thousand Four Hundred Only	19096
5	<p>Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification MORD 2014 clause 502 and as per direction of Engineer-in-charge . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..</p>	68.20	Sqm	55.00	Rupees FiftyFive Only	3751
6	<p>Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg.per sqm(Zero point twenty five to zero point thirty kilogram)per square metre.on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification MORD 2014 clause 503. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..</p>	68.20	Sqm	21.00	Rupees TwentyOne Only	1432
7	<p>Providing and laying 50mm thick dense bituminous macadam with VG-30 hot mix plant using crushed aggregates of grading as per table 500.4.500.3 premixed with bituminous binder 4.5 percent (minimum), transported to site upto a lead of any metre laid over a previously prepared surface with paver finisher to the required grade level and alignment and rolled to achieve the desired compaction as per technical specification clause 504.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..</p>	3.41	Cum	9550.00	Rupees Nine Thousand Five Hundred Fifty Only	32566

<p>8</p> <p>Providing and laying 30mm thick (thirty millimetre) thick bituminous concrete with 100-120 ( one hundred to one hundred twenty ) batch type HMP, producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading premixed with bitumen binder VG-30 @ (five point four percent) minimum of mix and filler ,transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH 2014 specification clause No. 509 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	2.05	Cum	11200.00	Rupees Eleven Thousand Two Hundred Only	22915
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 &amp; Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p>				Total	99197
<p>Percentage quoted rate in figures</p>					
<p>Percentage quoted rate in words</p>					
<p>Note -Rate quoted in figures &amp; words are mandatory by the contractor, other wise the tender will be rejected</p>					

*H*

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

34

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umrali Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400.		Estimated Cost: Rs		₹ 97,812		
( SH: P/L CC Pavement in main road at Rd. 2/507.60 to 2/519).		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealent, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malakhana toll tax, GST, labour cess or other taxes imposed by the Government.	15.05	CUM.	6500.00	(Rupees Six thousand five hundred only)	97812
					<b>Total:</b>	<b>97812</b>
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	<b>Percentage quoted rate in Figures</b>					
	<b>Percentage quoted rate in words</b>					
	<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>					

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

35

**Schedule of quantity**

Name of Work: Balance work for the Improvement of College Infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (HP)							Estimated Cost: Rs	₹ 99,352
(SH: Leveling work of Play Ground) Phase-I							Time:-	One month
DESCRIPTION							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	197.58	sqm Cum	160.00	(Rupees one hundred and sixty only)	31612.00		
2	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	282.25	sqm Cum	240.00	(Rupees Two hundred forty only)	67740.00		
					Total	99352		
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (HP)

36

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umrail Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/		Estimated Cost: Rs	₹ 99,528			
( SH: P/L CC Pavement in main road at Rd. 2/496 to 2/507.60).		Time:-	One month			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501.. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.31	CUM.	6500.00	(Rupees Six thousand five hundred only)	99528
					Total:	99528
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

37

607

Schedule of quantity

Name of work:- Repair of pot hole on Una Rampur Haroli Jaijon Road Km. 0/00 to 23/00		Estimated Cost: Rs		Time:-		One month	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	2000
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.58	Cum	160.00	Rupees One Hundred Sixty Only	3293	
2	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material within all leads and lifts and other incidentals as per MORD specification 2014, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.58	Cum	240.00	Rupees Two Hundred Forty Only	4939	
3	Construction of Gravel / Soil aggregate base/sub base Nominal Maximum size Grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with Tractor mount appropriate grading arrangements on prepared surface, mixing by mix place method at OMC with Tractor mount appropriate rotavator attachment and compaction with three wheel 80-100kN static Roller capacity to achieve the desired density, complete as per Specification contained in Para 2.2, 3.6 and 3.7 of IRC SP 77-2008, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.29	Cum	1100.00	Rupees One Thousand One Hundred Only	11319	
4	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	13.72	Cum	1400.00	Rupees One Thousand Four Hundred Only	19208	
5	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification MORD 2014 clause 502 and as per direction of Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	68.60	Sqm	55.00	Rupees FiftyFive Only	3773	

6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg.per sqm(Zero point twenty five to zero point thirty kilogram)per square metre.on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification MORD 2014 clause 503. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax.GST,labour cess or other taxes imposed by the Government.	68.60	Sqm	21.00	Rupees TwentyOne Only	1441
7	Providing and laying 50mm thick dense bituminous macadam with VG-30 hot mix plant using crushed aggregates of grading as per table 500.4.500.3 premixed with bituminous binder 4.5 percent (minimum), transported to site upto a lead of any metre laid over a previously prepared surface with paver finisher to the required grade level and alignment and rolled to achieve the desired compaction as per technical specification clause 504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax.GST,labour cess or other taxes imposed by the Government.	3.41	Cum	9550.00	Rupees Nine Thousand Five Hundred Fifty Only	32566
8	Providing and laying 30mm thick (thirty millimetre) thick bituminous concrete with 100-120 ( one hundred to one hundred twenty ) batch type HMP, producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading premixed with bitumen binder VG-30 @ (five point four percent) minimum of mix and filler ,transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH 2014 specification clause No. 509 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax.GST,labour cess or other taxes imposed by the Government.	2.06	Cum	11200.00	Rupees Eleven Thousand Two Hundred Only	23050
					Total	99589
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

637

38

SCHEDULE OF QUANTITY									
Name of work : Repair of pot hole on link road to village Khad Km 0/00 to 2/240 (SH: Patch work at RD 1/400 to 1/570)									
S. No.	Description of work	Quantity	Unit	Figures	Words	Estimated Cost		One month AMOUNT	
						RATE In	Amount	RATE In	Amount
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	9.84	Per cubic metre	1400.00	Rupees One three hundred fifty only				13776
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty,malkhana toll taxes,GST, labour cess or taxes imposed by the Government	131.15	Per square metre	55.00	Rupees Fifty five only				7213
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904 2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	262.30	Per square metre	300.00	Rupees Three hundred only				78690
						<b>Total:</b>		<b>99679</b>	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 & Govt. of HP vide letter No.PBW(B)A(3) 1/2020-1 dated 7.10.2021									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt.of HP vide letter No.PBW(B)A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3) 1/2020-1 dated 7.10.2021									
<b>Percentage quoted rate in Figures</b>									
<b>Percentage quoted rate in words</b>									
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>									

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

635

739

SCHEDULE OF QUANTITY						
Name of work : Repair of pot hole on Panjwar Bathri road Km 0/00 to 34/00(SH: Patch work at RD 0/00 to 3/00)						
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Providing . laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by flipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government..	7.03	Per cubic metre	1400.00	Rupees One thousand four hundred only	9842
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentials. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government	93.78	Per square metre	55.00	Rupees Fifty five only	5158
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government..	281.33	Per square metre	300.00	Rupees Three hundred only	84399
				<b>Total:</b>		<b>99399</b>
				<b>Percentage quoted rate in Figures</b>		
				<b>Percentage quoted rate in words</b>		
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

  
 Executive Engineer  
 Haroli Division  
 HP.PWD., Haroli

100

Schedule of quantity

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs	₹ 99,450			
(SH: C/O Retaining wall at Rd. 1/194.30 to 1/200 Rhs)		Time:-	One month			
EARNST MONEY:-		Rate in words	Amount			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.16	Cum.	160.00	Rupees One Hundred Sixty Only	985
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.60	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94379
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.00	Each nos	160.00	Rupees One Hundred Sixty Only	2080
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.65	Cum.	550.00	Rupees Five Hundred Fifty Only	2006
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total		99450
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,

H.P.W.D. Division Haroli

Distt. Una (H.P.)

644

51

SCHEDULE OF QUANTITY									
Name of work : Repair of pot hole on Panjwar Bathri road Km 0/00 to 34/00(SH: Patch work at RD 3/00 to 6/00)									
S. No.	Description of work	Quantity	Unit	RATE IN		Estimated Cost	Earnest Money	Time limit	AMOUNT
				Figures	Words				
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, maikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	7.01	Per cubic metre	1400.00	Rupees One thousand four hundred only	9814			
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, maikhana toll taxes, GST, labour cess or taxes imposed by the Government	93.50	Per square metre	55.00	Rupees Fifty five only	5143			
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion, 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2, 503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, maikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	280.50	Per square metre	300.00	Rupees Three hundred only	84150			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)/A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)/A(3) 1/2020-1 dated 7.10.2021									
<b>Percentage quoted rate in Figures</b>									
<b>Percentage quoted rate in words</b>									
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>									
<b>Total:</b>									<b>99107</b>

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

42

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umrali Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/ ( SH: P/L CC Pavement in main road at Rd. 2/484.50 to 2/496).		Estimated Cost: Rs	₹ 98,670			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501.. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.18	CUM.	6500.00	(Rupees Six thousand five hundred only)	98670
					<b>Total:</b>	<b>98670</b>
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20						
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note: Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

13

628

Schedule of quantity

Name of work:-Repair of pot hole on Una Rampur Haroli Jaijon Road Km. 0/00 to 23/00 (SH: Repair of pot hole at Rd. 15/400 to 16/200)							Estimated Cost: Rs Time:-	₹ 99,550 One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	Earnest Money:-	2000
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.50	cum	1300	Rupees One Thousand Three Hundred Only	21450		
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	220.00	sqm	55.00	Rupees FiftyFive Only	12100		
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	220.00	sqm	300.00	Rupees Three Hundred Only	66000		
					Total	99550		
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

**Schedule of quantity**

Name of Work: Balance work for the improvement of College infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (HP)							Estimated Cost: Rs
(SH: Leveling work of Play Ground) Phase-II							Time:-
EARNST MONEY:-							One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	198.45	sqm C/m	160.00	(Rupees one hundred and sixty only)	31752.00	
2	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	283.50	C/m sqm	240.00	(Rupees Two hundred forty only)	68040.00	
					Total	99792	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

45

Schedule of quantity

Name of Work :-C/O retaining wall Near Sheetia Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-III)under MMGSY							Estimated Cost: Rs	₹ 99,258
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.38	Cum.	170.00	Rupees one hundred seventy Only	1255		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.29	Cum.	3300.00	Rupees three thousand three hundred only	93357		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510		
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.52	Cum.	550.00	Rupees five hundred fifty only	4136		
						Total:	99258	
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

**SCHEDULE OF QUANTITY**

**Name of work : Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una ( SH:C/O breast wall near Septic Tank - Phase-I )- Deposit work**

S. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost
				Figures	Words	
				AMOUNT		
						99957
						2000
						One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.22	Per cubic metre	160.00	Rupees One hundred sixty only	675
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement: four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.73	Per cubic metre	3400.00	Rupees three thousand three hundred only	97682
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 6.14, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Each	160.00	Rupees One hundred sixty only	1600
					<b>Total:</b>	<b>99957</b>
	<b>NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/20212 dated 7.8.2018</b>					
	<b>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 &amp; Govt. of HP vide letter No.PBW(B)A(3) 1/2020-1 dated 7.10.2021</b>					
	<b>Percentage quoted rate in Figures</b>					
	<b>Percentage quoted rate in words</b>					
	<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>					

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

636

47

SCHEDULE OF QUANTITY									
Name of work : Repair of pot hole on Panjawan Bathri road Km 0/00 to 34/00(SH: Patch work at RD 6/00 to 9/00)									
S. No.	Description of work	Quantity	Unit	Figures	Words	Estimated Cost		One month	
						RATE In	Amount	Estimated Cost	Earnest Money
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government...	7.05	Per cubic metre	1400.00	Rupees One thousand four hundred only	99688	2000		
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 Kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government	94.05	Per square metre	55.00	Rupees Fifty five only			5173	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing jack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2, 503 and 508. 1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government...	282.15	Per square metre	300.00	Rupees Three hundred only			84645	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt of HP vide letter No.PBW(B)/A(31/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)/A(3) 1/2020-1 dated 7.10.2021									
<b>Percentage quoted rate in Figures</b>									
<b>Percentage quoted rate in words</b>									
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>									
						<b>Total:</b>		<b>99688</b>	

  
 Executive Engineer  
 Haroli Division  
 HP.PWD.,Haroli

626


518

Name of work:- Repair of pot hole on Una Rampur Haroli Jaijon Road Km. 0/00 to 23/00		Estimated Cost: Rs		₹ 99,392		
(SH: Repair of pot hole at Rd. 16/268.10 to 16/302.30)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
Earnest Money:-						
2000						
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.52	Cum	160.00	Rupees One Hundred Sixty Only	3283
2	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.52	Cum	240.00	Rupees Two Hundred Fourty Only	4925
3	Construction of Gravel /Soil aggregate base/sub base Nominal Maximum size Grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with Tractor mount appropriate grading arrangements on prepared surface, mixing by mix place method at OMC with Tractor mount appropriate rotavator attachment and compaction with three wheel 80-100KN static Roller capacity to achieve the desired density, complete as per Specification contained in Para 2.2, 3.6 and 3.7 of IRC SP 77-2008, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.26	Cum	1100.00	Rupees One Thousand One Hundred Only	11286
4	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c/o material with in all leads and lift, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	13.68	Cum	1400.00	Rupees One Thousand Four Hundred Only	19152

5	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification MORD 2014 clause 502 and as per direction of Engineer-in-charge . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	68.40	Sqm	55.00	Rupees FiftyFive Only	3762
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg.per sqm(Zero point twenty five to zero point thirty kilogram)per square metre.on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom.on the prepared granular surfaces treated with primer including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	68.40	Sqm	21.00	Rupees TwentyOne Only	1436
7	Providing and laying 50mm thick dense bituminous macadam with VG-30 hot mix plant using crushed aggregates of grading as per table 500.4,500.3 premixed with bituminous binder 4.5 percent (minimum), transported to site upto a lead of any metre laid over a previously prepared surface with paver finisher to the required grade level and alignment and rolled to achieve the desired compaction as per technical specification clause 504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.41	Cum	9550.00	Rupees Nine Thousand Five Hundred Fifty Only	32566
8	Providing and laying 30mm thick (thirty millimetre) thick bituminous concrete with 100-120 ( one hundred to one hundred twenty ) batch type HMP, producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading premixed with bitumen binder VG-30 @ (five point four percent) minimum of mix and filler ,transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH 2014 specification clause No. 509 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.05	Cum	11200.00	Rupees Eleven Thousand Two Hundred Only	22982
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					
					Total	99392

**Schedule of quantity**

Name of Work: Balance work for the improvement of College infrastructure at SDWG Govt. College Beetan Tehsil Haroli Distt. Una (HP)		Estimated Cost: Rs		₹ 98,699				
(SH: Leveling work of Play Ground & re-painting of existing stage shed and main gate) Phase-IV		Time:-		One month				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	2000	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	151.20	Cum sqm	160.00	(Rupees one hundred and sixty only)			24192.00
2	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete., including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	216.00	Cum sqm	240.00	(Rupees Two hundred forty only)			51840.00
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	101.06	Cum sqm	85.00	(Rupees eighty five only)			8590.00
4	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	96.10	Sqm. sqm	85.00	(Rupees eighty five only)			8169.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C.grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.53	cum	3850.00	(Rupees Three thousand fifty forty only)			5908.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total			98699
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures							
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

  
**Executive Engineer,**  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

**Schedule of quantity**

Name of Work :- C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-IV) under MMGSY							Estimated Cost: Rs	₹ 98,071
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.29	Cum.	170.00	Rupees one hundred seventy Only	1239		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	27.95	Cum.	3300.00	Rupees three thousand three hundred only	92235		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510		
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.43	Cum.	550.00	Rupees five hundred fifty only	4087		
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						Total:	98071	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

**Schedule of quantity**

Name of Work :-C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-IX) under MIMGSY							Estimated Cost: Rs	₹ 97,787
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation: by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.27	Cum.	170.00	Rupees one hundred seventy Only	1236		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	27.87	Cum.	3300.00	Rupees three thousand three hundred only	91971		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510		
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.40	Cum.	550.00	Rupees five hundred fifty only	4070		
					Total:	97787		

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

643

59

SCHEDULE OF QUANTITY						
Name of work : Repair of pot hole on link road to village Pandoga from Gagret road Km 0/00 to 2/640(SH: Patch work at RD 0/300 to 0/915)		Estimated Cost	99394			
		Earnest Money	2000			
		Time limit	One month			
S. No.	Description of work	Quantity	Unit	Figures	RATE In	AMOUNT
					Words	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government...	7.02	Per cubic metre	1400.00	Rupees One thousand four hundred only	9828
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malkhana toll taxes, GST, labour cess or taxes imposed by the Government	93.79	Per square metre	55.00	Rupees Fifty five only	5158
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion , 20mm thick premix carpet VG-30 and seal coat type B specification clause 1904.2, 503 and 508.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government...	281.36	Per square metre	300.00	Rupees Three hundred only	84408
				<b>Total:</b>		<b>99394</b>
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt of HP vide letter No.PBW(B) A(311/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

Executive Engineer  
Haroli Division  
HP.PWD., Haroli

59

619

Schedule of quantity

Name of work:- Repair of pot hole on link road to Co-Operative society Haroli via GSSS Haroli Km. 0/00 to 2/225.		Estimated Cost: Rs		Time:-		
(SH: Repair of pot hole at Rd. 0/00 to 1/00)		₹ 98,193		One month		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	16.28	cum	1300	Rupees One Thousand Three Hundred Only	21158
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	217.00	sqm	55.00	Rupees FiftyFive Only	11935
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	217.00	sqm	300.00	Rupees Three Hundred Only	65100
					Total	98193
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


  
**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

54

SCHEDULE OF QUANTITY

						98542	
Name of work : Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (		Estimated Cost		Earnest Money		2000/-	
SH:C/O breast wall near rain harvesting Tank - Phase-V )- Deposit work		Time limit		One month			
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.88	Per cubic metre	160.00	Rupees One hundred sixty only		301
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.77	Per cubic metre	3400.00	Rupees three thousand three hundred only		43418
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204. 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.00	Each	160.00	Rupees One hundred sixty only		1120

4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	210.60	Per cubic metre	255.00	Rupees two hundred sixty only	53703
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	98542
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

  
 Executive Engineer,  
 H.P.W.D. Division Haroli  
 Distt. Una (H.P.)

56

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umrali Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/4 (SH: P/L CC Pavement in main road at Rd. 2/461.50 to 2/473.10).		Estimated Cost: Rs	₹ 99,528			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel), laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealent, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501.. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.31	CUM.	6500.00	(Rupees Six thousand five hundred only)	99528
					<b>Total:</b>	<b>99528</b>
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
<b>Percentage quoted rate in Figures</b>						
<b>Percentage quoted rate in words</b>						
<b>Note:- Rate quoted in figures &amp; words are mandatory by the contractor, otherwise the tender will be rejected.</b>						

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

56

Schedule of quantity

Name of Work :-C/O retaining wall Near Sheetla Mata Mandir Ispur G.P. Ispur (SH: C/O R/wall alongwith Mandir -Phase-V)under MMSGY							Estimated Cost: Rs	₹ 98,662
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.34	Cum.	170.00	Rupees one hundred seventy Only	1248		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.12	Cum.	3300.00	Rupees three thousand three hundred only	92796		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi. royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees one hundred seventy Only	510		
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.47	Cum.	550.00	Rupees five hundred fifty only	4109		
					Total:	98662		
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018								
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

(57)

Schedule of quantity

Name of work:- Balance work for the Upgradation of link road Umraili Dhillwan Heeran- Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/ (SH: P/L CC Pavement in main road at Rd. 2/473.10 to 2/484.50).		Estimated Cost: Rs	₹ 97,812			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and laying Panel concrete, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement [minimum 430 kg per cum (four hundred thirty cubic metre)] or any other type as per Clause 1501.2.2 M30 (M- Thirty) (Grade), coarse and fine aggregates conforming to IS:383 (IS: three hundred eighty three), maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed & plate vibrator & finished in continuous operation including provision of contraction & expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixture as approved, curing of concrete slabs for 14-days (fourteen - days), curing compound (where specified) and water finishing to lines & grades as per drawing and Technical Specifications Clause 1501. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.05	CUM.	6500.00	(Rupees Six thousand five hundred only)	97812
					Total:	97812


Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

**SCHEDULE OF QUANTITY**

Name of work : Balance work for the C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una ( SH: Providing and fixing collapsible steel shutter & water storage tanks)- Deposit work

Estimated Cost 99926  
 Earnest Money 2000  
 Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing and fixing in position collapsible steel shutter with vertical channel 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rail of T- iron 40x40x6mm with 40mm dia steel pull complete with bolts, nuts locking arrangements, stopping handles including applying a priming coat of approved steel primer complete per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.42	Per square metre	5920.00	Rupees five thousand nine hundred twenty only	43926	
2	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12201 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank 1000 litre Sintex or equivalent ( minimum 3 layer) make including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4000.00	Per Litre	14.00	Rupees fourteen only	56000	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(X)(17/20212 dated 7.8.2018						<b>Total:</b>	<b>99926</b>
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

  
**Executive Engineer**  
 Haroli Division  
 HP.PWD, Haroli