OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 9524-33 dated 09-02-2026.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095, Telephone No. 01894-228030, Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Enginee HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approve and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as reach in his office on or before on **16.02.2026 up to 11:00 A.M.** and the same shall be opened on the same day **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can b obtained from his office on cash payment (non refundable) on **13.02.2026** up to **4:00 PM** and the application for issu of tender from shall be received on **13.02.2026** up to **11:00 AM.** The applications for issue of tender forms shou accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Savi Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. Th offer of the tender shall be kept open for **75** days:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages 92.50Mtr. Span PSC Box Girder Single lane Bridge over Negual Khad on Paprola Alampur road at RD 2/770 (SH:- Removal of slips at Rd 2/750 to 2/780) NDRF/PDNA	499500.00	10000.00	Two Month	350/-
2	Restoration of rain Damages on Panchrukhi to Lambagaon road Km 10/00 to 22/00 (SH:-C/O C/O wire crate breast wall at RD 20/165 to 20/205) Under PDNA	425952.00	8600.00	Two Month	350/-
3	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O U/S/S Approach (Harsi side) of existing 54.464 Mtr. Span Double lane bridge over Sari Khad at Km 23/285) (Under PDNA)	498862.00	10000.00	Two Month	350/-
4	Restoration of rain Damages on Kutballah to Pantehr road Km 0/00 to 1/660 (SH:-P/L Cement concrete pavement from 1/430 to 1/485 including protection wall adjoining Nalla & 1/050 to 1/075) Under PDNA	499712.00	10000.00	Two Month	350/-
5	C/O Utility Stadium at Jaisinghpur Distt. Kangra (HP) (SH:- C/O Boundary wall from SBI Chowk from 0/098 to 0/0128) (Deposit) Balance work	498923.00	10000.00	Two Month	350/-
6	Restoration of rain Damages on Gander Barram Kangain road Km 0/00 to 5/00 (SH:- C/O 900 mm dia RCC Hume pipe culvert at Rd 2/503 with wing walls D/S/S) Under PDNA	472200.00	9500.00	Two Month	350/-
7	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O U/S/S Approach (Harsi side) of bridge over Sari Khad at Km 23/285) (Under PDNA)	499112.00	10000.00	Two Month	350/-

-------Continued page- 2----

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / committments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 9524-33 **Dated:** 09-02-2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
4-6. All the Assistant Engineers under this Division.
7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

(1)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages 92.50Mtr. Span PSC Box Girder Single lane Bridge over Negual Khad on Paprola Alampur road at Rd 2/770 (SH:-Removal of slips at Rd 2/750 to 2/780) NDRF/PDNA	**Estimated cost Rs.**	**499500.00**
	Earnest Money Rs.	**1000.00**
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	5550.00	90.00	Rupees Ninety Only	Per cubic metre.	499500.00
	Total					**499500.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Panchrukhi to Lambagaon road Km 10/00 to 22/00 (SH:- C/O C/O wire crate breast wall at RD 20/165 to 20/205) **Under PDNA**

Estimated cost Rs.	**425952.00**
Earnest Money Rs.	**8600.00**
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	90.00	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	20250.00
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechnical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	150.91	112.00	Rupees One Hundred Twelve Only	Per cubic metre.	16902.00

3	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	129.60	3000.00	Rupees Three Thousand Only	Per cubic metre	388800.00
	Total					**425952.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O U/S/S Approach (Harsi side) of existing 54.464 Mtr. Span Double lane bridge over Sari Khad at Km 23/285) (Under PDNA)

Estimated cost Rs.	**498862.00**
Earnest Money Rs.	**10000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	42.68	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	9603.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	55.76	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	276012.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	36.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic Metre	135000.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	22.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5500.00

5	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	16.32	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	15504.00
6	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	34.13	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	8533.00
7	Demolishing cement concrete Manually/by mechanical means including disposal of material within 50 metre lead as per specification and as per direction of Engineer - in- Charge Nominal concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) or equivalent. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	52.50	927.80	Rupees Nine Hundred Twenty Seven And Paise Eighty Only	Per Cubic Metre	48710.00
	Total					**498862.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(4)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Kutballah to Pantehr road Km 0/00 to 1/660 (SH:-P/L Cement concrete pavement from 1/430 to 1/485 including protection wall adjoining Nalla & 1/050 to 1/075) **Under PDNA**	**Estimated cost Rs.**	**499712.00**
	Earnest Money Rs.	**10000.00**
	Time Limits	**Two Month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	22.99	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	5173.00

2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government	15.47	2050.00	Rupees Two Thousand Fifty Only	Per Cubic Metre	31714.00
3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	54.3	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	230775.00

4	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement thickness as per design and laid over a prepared sub base with 43(forty three) grade cement or any type as per clause 1501 M-30 (M- thirty) grade, design mix cement concrete, coarse and fine aggregates conforming to IS:383(three hundred eighty three), maximum size of coarse aggregate not exceeding 25mm(twenty five millimetre) mixed in a concrete mixer of not less than 0.2 (zero point two) cubic meter capacity and appropriate weight batcher using approved mix design, laid in approved fixed side form work (steel channel), laying and fixing of 125(one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing, spreading the concrete with shovels, rakes,compacted using needle, screed and plate vibrators and finished in continuous opreation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant,dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs using curing compound (where specified) and water, finishing to line and grade as per drawing and M.O.R.D. technical specification clause 1501 as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government	30.94	7500.00	Rupees Seven Thousand Five Hundred Only	Per Cubic Metre	232050.00
	Total					**499712.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			**%**	
		Less (-)			**%**	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Utility Stadium at Jaisinghpur Distt. Kangra (HP) (SH:- C/O Boundary wall from SBI ChowK from 0/098 to 0/0128) **(Deposit)** BALANCE WORK

Estimated cost Rs.	**498923.00**
Earnest Money Rs.	**10000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.00	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	2250.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.80	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic Metre	6750.00

3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	7.50	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	31875.00
4	Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (one cement : six coarse sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and as per the direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.08	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	34048.00
5	Steel work welded in built up sections Anarkali type cast iron jali /Railing work including cutting hoisting and fixing in position and applying a paint in gratings framed guard bares ladders railings and similar work etctera complete including carriage of materials within all leads lifts and other incidentals and as per direction of the Engineer-in-charge. The rate is inclusive of octroi, royality, malkana and all type of taxes imposed by the Government. .	2650.00	160.00	Rupees One Hundred Sixty Only	Per Kilogram	424000.00
	Total					**498923.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gander Barram Kangain road Km 0/00 to 5/00 (SH:- C/O 900 mm dia RCC Hume pipe culvert at Rd 2/503 with wing walls D/S/S) Under PDNA	**Estimated cost Rs.**	**472200.00**
	Earnest Money Rs.	**9500.00**
	Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	74.75	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	16819.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.75	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	8663.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	10.41	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	54653.00

4	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi,royality,Malkana, toll tax , or other taxes imposed by the Government.	7.50	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Running metres	28875.00
5	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	93.40	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	359590.00
6	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	14.40	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	3600.00
	Total					**472200.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 25/00 (SH:-C/O U/S/S Approach (Harsi side) of bridge over Sari Khad at Km 23/285) (Under PDNA)

Estimated cost Rs.	**499112.00**
Earnest Money Rs.	**10000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	42.68	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	9603.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	55.76	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	276012.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	36.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic Metre	135000.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	23.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5750.00

5	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	16.32	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	15504.00
6	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	34.13	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	8533.00
7	Demolishing cement concrete Manually/by mechanical means including disposal of material within 50 metre lead as per specification and as per direction of Engineer - in- Charge Nominal concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) or equivalent. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	52.50	927.80	Rupees Nine Hundred Twenty Seven And Paise Eighty Only	Per Cubic Metre	48710.00
	Total					**499112.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur