



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 12/02/2026 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 09/02/2026 up to 10:00 A.M. to 12:00 P.M. and tender form can be had from this office on 10/02/2026 from 2:00 P.M. to 5:00 Pm. The earnest money as shown against each in the shape of F.D R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contract or	Time
1	R/O Restoration of Rain damages on Mohan Ghatti to rada Malu Ghatgalu Bhatwar and Matroo road km RD 1/360 to 4/360 (SH: Providing and Laying G-II and Cement Concrete pavement at RD 01/480 to 1/557) under NDF Deposit SID:NDF/2023/573)	Rs.57,854/-	Rs.1,200/-	Rs. 350/-	Class "D"	Three Months
2	R/O Restoration of Rain Damages on link road to Balakupi chowk to village Jhalwan (GP Jalpehar) (SH:- Providing and Laying Cement Concrete pavement at RD 0/825 to 0/857.80, 0/185 to 0/300) under SDF Deposit SID:SDF/2022/398)	Rs. 98,660/-	Rs.2,000/-	Rs. 350/-	Class "D"	Three Months
3	C/O link road from Drobri to Chhamb Km/-/0 to 1/0 GP Khadihar (SH: P/L cement concrete pavement in km. 0/200 to 0/237 (under Deposit SID:SDF/2019/338.	Rs.99,062/-	Rs.2,000/-	Rs. 350/-	Class "D"	Three Months
4	R/O link road from village Patta km/-/0 to 0/700 in GP Tullah (SH: Providing & laying Kharanja soling & cement concrete pavement in km. 0/0 to 0/018 (under Deposit SID:SDF/2019/336.)	Rs.66,492/-	Rs.1,300/-	Rs. 350/-	Class "D"	Three Months
5	R/O link road Kolang to GHS Kolang in GP Kolang (SH: Providing & laying Kharanja soling & cement concrete pavement in km. 0/0 to 0/013.50 (under Deposit SID: VKV/2019/905.)	Rs.49,680/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
6	R/O restoration of rain damages on Bajroun Ropri road Km/-/0 to 1/640 in GP Ropri (SH: Construction of parapets at various RD.s (under Deposit SID:SDF/2021/1228.)	Rs.79,558/-	Rs.1,600/-	Rs. 350/-	Class "D"	Three Months
7	R/O Restoration damages on Lower Patta road Km. in GP Bhagair Raktal (SH: Construction of retaining wall at km. 0/675 to 0/681 (under Deposit SID:SDF/2022/407.	Rs.98,631/-	Rs.2,000/-	Rs. 350/-	Class "D"	Three Months
8	R/O road from Joginder Nagar Sarkaghat at Machhial near home of Man Singh in GP Chalarag (SH: Construction of retaining wall in km. 7/450 to 7/452.60 (under Deposit SID:SDF/2019/439. (0.60Lacs)	Rs.58,301/-	Rs.1,200/-	Rs. 350/-	Class "D"	Three Months
9	C/O Ambulance road to village Chhattar FLU GP Masoli (SH: Construction of retaining/edge wall at km. 0/120 to 0/127 (under Deposit SID:BSP/2021/413. (0.50Lacs)	Rs.53,696/-	Rs.1,100/-	Rs. 350/-	Class "D"	Three Months
10	R/O road from Patti to Bharog in km/-/0 to 1/200 GP Ner Gharwasra (S.H:- Providing & laying cement concrete pavement between km. 1/300 to 1/318 (under Deposit SID:NDF/2019/853. (0.60Lacs)	Rs.56,788/-	Rs.1,100/-	Rs. 350/-	Class "D"	Three Months
11	Construction of Link road NH-154 to Chhanagdhar in GP Ropa Padhar (Sh:-ROFD/FC in km. 0/340 to 0/380 (under Deposit SID:VKV/2022/346	Rs.49,794/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
12	R/O Restoration of damages on link road NH-154 to Village Panchhyan and Lundhra in GP Kadhar (SH:- Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/075 to 0/098 under Deposit SID: SDF/2022/396)	Rs.98,391/-	Rs.2,000/-	Rs. 350/-	Class "D"	Three Months
13	C/O Ambulance road SC Basti Langna in GP Langna (SH:- Construction of breast wall at RD 0/120 to 0/122.32 under SDP deposit SID:SDP/2020/639)	Rs.48,373/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
14	C/O link road to Village Panjngna from NH-154 Treker Nest (SH: Providing and Laying Cement Concrete Pavement at km 0/180 to 0/195 under Deposit SID: VKV/2021/721)	Rs.49,069/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
15	R/O Ambulance road to Village Shelhan (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/700 to 0/711 under Deposit SID: VKV/2020/402)	Rs.47,593/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
16	R/O Ambulance road from Main Road to Link road Langha (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/700 to 0/711 under Deposit SID: VKV/2019/1662)	Rs.48,634/-	Rs.1,000/-	Rs. 350/-	Class "D"	Three Months
17	Comp. of GSSS Building Outpur (SH: Supply and fixing office bench under deposit SID: BSP/2022/269)	Rs.86,666/-	Rs.1,700/-	Rs. 350/-	Class "D"	Three Months
18	C/O Ambulance road to Chaproo via Gujar Basti from link road Bassi in GP Ner Gharwasra (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/180 to 0/194 under Deposit SID: VKV/2021/459)	Rs.46,169/-	Rs.900/-	Rs. 350/-	Class "D"	Three Months
19	R/O Restoration of Rain damages on Gaduhi to Makoda Khaprotu km 0/00 to 4/00 G.P. Bhararu (SH: Formation Cutting in km 0/180 to 0/270 & 0/345 to 0/690) under Deposit SID : NDF/2023/1339)	Rs.92,033/-	Rs.1,800/-	Rs. 350/-	Class "D"	Three Months

20	Construction of link road from Sajehar to Galmatha (Sh:-Removal of formation deficiency in km. 7/735 to 7/775) under BASP Deposit SID: BSP/2023/1325	Rs.98,301/-	Rs.2,000/-	Rs. 350/	Class "D"	Three Months
21	Construction of Road Harizan Basti Langna km 0/00 to 1/00(SH: Construction of Breast wall at km 0/360 to 0/366.50) Under BASP Deposit SID: BSP/2016/106	Rs.99,487/-	Rs.2,000/-	Rs. 350/	Class "D"	Three Months
22	R/O Restoration of Rain damages on Gaduhi to Makoda Khaprotu km 0/00 to 4/00 G.P. Bhararu (SH: Formation Cutting in km 0/690 to 1/065) under Deposit SID : NDF/2023/1339)	Rs.83,929/-	Rs.1,700/-	Rs. 350/	Class "D"	Three Months
23	Construction of link road from Sajehar to Galmatha (Sh:-Removal of formation deficiency in km. 7/705 to 7/735) under BASP Deposit SID: BS C P/2023/1325	Rs.89,286/-	Rs.1,800/-	Rs. 350/	Class "D"	Three Months
24	Construction of Room at G.S.S.S. Golwan (SH: Providing and laying Tile work) (Under Deposit SDP/2020/717)	Rs.98,301/-	Rs.2,000/-	Rs. 350/	Class "D"	Three Months
25	Construction of Rain Shelter at Chakroad mangrol G.P. Khaddar Under Deposit (SID: SDF/2021/276)	Rs.98,374/-	Rs.2,000/-	Rs. 350/	Class "D"	Three Months
26	Construction of Rain Shelter Near GDC Lad Bharol at Banander Under Deposit (SID: SDF/2022/776)	Rs.98,374/-	Rs.2,000/-	Rs. 350/	Class "D"	Three Months
27	Construction of link road from Shanan Harabag to Village Har GP .Har Gunain (SH:-Construction of RCC hume pipe culvert at Km. 0/905 under Deposit SID :VKV/2021/1931	Rs.45,687/-	Rs.900/-	Rs. 350/	Class "D"	Three Months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
3. For on behalf of Governor of Himachal Pradesh the Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
7. The contractor shall be responsible for rectifying defects noticed within six months from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
8. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc. or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
9. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking he will get complete the works in hand before award of work with in schedule time.
10. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
11. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033.

No. PW-JND-B&R-EA-I/NIT/Press/2025-26- 26766-815 Dated:- 24-01-2026

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Account Branch in this office.
9. Notice Board.
10. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

469

1

E.No- 339

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Mohan Ghatti to Rada Malu Ghatgalu Bhatwar and Matroo road km RD 1/360 to 7/360.
(SH: Providing and Laying G-II & Cement Concrete Pavement at RD 1/480 to 1/557 Under NDF Deposit SID:NDF/2023/573)

Estimate Cost: 57,854.00
Earnest Money: 1,200.00
Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST	17.33	Per Cubic metre	3,338.40	Rupees Three Thousand Three Hundred Thirty Eight And Paise Forty Only	57,854.00
Total						57,854.00

Draft Schedule of Quantity approved for 57,854/-
Fifty Seven Thousand Eight Hundred Fifty four only/-

469

[Signature]
Executive Engineer
B & R Division HP PWD,
Joginder Nagar

(2)

E.No - 340

470

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on link road to Balakrupi Chowk to Village Jhalwan(GP Jhalpehaar (SH: Providing and Laying Cement Concretet Pavement at RD 0/825 to 0/857.80 0/185 to 0/300 Under SDF Deposit (SID: SDE/2022/308))		Estimate Cost: 98,660.00	
		Earnest Money: 2,000.00	
		Time Limit : Three Months	
Sl. No.	Description of work	Rate	
		Figures	Words
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications. M-20 (twenty) grade course and fine aggregate conforming to IS 383. maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time	8,021.10	Rupees Eight Thousand Twenty One And Paise Ten Only
Total			
		98,660.00	

Draft Schedule of Quantity approved for 98,660/- (₹ Ninety Eight Thousand Six Hundred Sixty only) -

470

[Signature]
Executive Engineer
B & R Division HP.P.W.D.
Joginder Nagar

3

EN 373

530

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Drobri to Chhamb Km.0/0 to 1/0 GP Khadihar
(SH: P/L cement concrete pavement in km. 0/200 to 0/237 (under Deposit SID:SDF/2019/338.

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT Rs. P
				Figures	Words		
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time including GST.	11.85	Per Cubic metre	8,359.70	Rupees Eight Thousand Three Hundred Fifty Nine And Paise Seventy Only	99,062.00	2,000.00 Two Months
Total							99,062.00

*Draft Schedule of Quantity approved for 99,062/-
(Ninty nine Hundred Sixty two) only/-*

530

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

EW 372

(4)

(531)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O link road from village Patta km.0/0 to 0/700 in GP Tullah (SH: Providing & laying Kharanja soling & cement concrete pavement in km. 0/0 to 0/018 (under Deposit SID:SDF/2019/336.)				Estimate Cost: 66,492.00 Earnest Money: 1,300.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	8.66	Per Cubic metre	2,378.35	Rupees Two Thousand Three Hundred Seventy Eight And Paise Thirty Five Only	20,597.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	5.49	Per Cubic metre	8,359.70	Rupees Eight Thousand Three Hundred Fifty Nine And Paise Seventy Only	45,895.00
Total						66,492.00

Draft Schedule of Quantity approved for ₹ 66,492/-
(Sixty six Thousand four hundred ninety two) only/-

(531)



Executive Engineer

B & R Division HP.PWD,

Joginder Nagar

371

533

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O link road Kolang to GHS Kolang in GP Kolang
(SH: Providing & laying Kharanja soling & cement concrete pavement in km. 0/0 to 0/013.50 (under Deposit
SID:VKV/2019/905.)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	6.48	Per Cubic metre	2,206.60	Rupees Two Thousand Two Hundred Six And Paise Sixty Only	14,299.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.33	Per Cubic metre	8,171.10	Rupees Eight Thousand One Hundred Seventy One And Paise Ten Only	35,381.00
Total						49,680.00

Draft Schedule of Quantity approved for 49,680/- (Fourty Nine Thousand Six Hundred Eighty) only/-

533

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

534

367

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O restoration of rain damages on Bajrour Ropri road Km.0/0 to 1/640 in GP Ropri (SH: Construction of parapets at various RD,s (under Deposit SID:SDF/2021/1228.)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: 79,558.00 Earnest Money: 1,600.00 Time Limit : Three Months
				Figures	Words	
1	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time including GST.	12.37	Per cubic metre	6,431.50	Rupees Six Thousand Four Hundred Thirty One And Paise Fifty Only	79,558.00
Total						79,558.00

Draft Schedule of Quantity approved for ₹ 79,558/- (Seventy Nine Thousand Five Hundred Fifty Eight Jony/-)

534

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

370

536

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O Restoration damages on Lower Patta road Km. in GP Bhagair Raktal (SH: Construction of retaining wall at km. 0/675 to 0/681 (under Deposit SID:SDF/2022/407).

Estimate Cost: 98,631.00
Earnest Money: 2,000.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	5.88	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	3,810.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	14.10	Per cubic metre	6,176.60	Rupees Six Thousand One Hundred Seventy Six And Paise Sixty Only	87,090.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	5.58	Per cubic metre	1,149.10	Rupees One Thousand One Hundred Forty Nine And Paise Ten Only	6,412.00

536

Description of work

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	5.88	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	3,810.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each	329.65	Rupees Three Hundred Twenty Nine And Paise Sixty Five Only	1,319.00
Total						98,631.00

Draft Schedule of Quantity approved for 98,631 (Ninety Eight Thousand Six Hundred Thirty one only) /-

Executive Engineer

B & R Division HP.PWD,
Joginder Nagar

566

364

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O road from Joginder Nagar Sarkaghat at Machhyal near home of Man Singh in GP Chalarag (SH: Construction of retaining wall in km. 7/450 to 7/452.60 (under Deposit SID:SDF/2019/439. (0.60Lacs)			Estimate Cost: 58,301.00 Earnest Money: 1,200.00 Time Limit : Three Months			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	4.13	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	2,676.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate is inclusive all taxes levy by the government time to time including GST.	8.22	Per cubic metre	6,236.00	Rupees Six Thousand Two Hundred Thirty Six Only	51,260.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	2.65	Per cubic metre	1,149.10	Rupees One Thousand One Hundred Forty Nine And Paise Ten Only	3,045.00

566

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	1,320.00
	Total					58,301.00

*Draft schedule of quantity approved for ₹ 58301/-
(₹ Fifty eight thousand three hundred one) only*

566

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

366

527

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Ambulance road to village Chhattar FLU GP Masoli (SH: Construction of retaining/edge wall at km. 0/120 to 0/127 (under Deposit SID:BSP/2021/413. (0.50Lacs)		Estimate Cost: Earnest Money: Time Limit :		AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words
				Figures	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	4.13	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	8.22	Per cubic metre	6,070.50	Rupees Six Thousand Seventy And Paise Fifty Only
					49,900.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government (time to time including GST.	4.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	1,320.00
Total						53,896.00

*Draft schedule of quantity approved for ₹ 53896/-
(₹ Fifty three thousand eight hundred and ninety six) only*

~~Executive Engineer~~

B & R Division HP.PWD,

Joginder Nagar

567

10

Est. 365

570

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O road from Patti to Bharog in km.0/0 to 1/200 GP Ner Gharwasra (S.H. :Providing & laying cement concrete pavement between km. 1/300 to 1/318 (under Deposit SID:NDF/2019/853. (0.60Lacs)		Estimate Cost:		Earnest Money:		
		Rate		Time Limit :		
No.	Description of work	No. or Qty.	Unit	Figures	Words	AMOUNT Rs. P
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time including GST.	6.97	Per Cubic metre	8,147.55	Rupees Eight Thousand One Hundred Forty Seven And Paise Fifty Five Only	56,788.00
Total						56,788.00

*Draft schedule of quantity approved for 56788/-
(= Fifty six thousand seven hundred eighty eight) only*

570

*Executive Engineer
B & R Division HP.PWD.
Joginder Nagar*

E No. 362

568

DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Link road NH-154 to Chhanagdhhar in GP Ropa Padhar (Sl:-Removal of formation deficiency/ Formation Cutting in km. 0/340 to 0/380) under Deposit SID:VKV/2022/346		Estimate Cost:		Time Limit :		
		Figures	Words			
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT	
				Figures	Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 9.70 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	194.00	Per cubic metre	256.67	Rupees Two Hundred Fifty Six And Paise Sixty Seven Only	49,794.00
Total						49,794.00

*Draft Schedule of Quantity approved for
Rs. 49,794/- C Forty Nine thousand Seven
hundred Ninety four only*

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

(1P)

Eno 413

(571)

DNIT/DRAFT SCHEDULE OF QUANTITY

Sl. No.	Description of work	No. or Qty.	Unit	Estimate Cost:		Earnest Money:	
				Rate		Time Limit:	
				Figures	Words	Rs.	P
		11.05	Per Cubic metre	2,210.00	Rupees Two Thousand Two Hundred Ten Only	2,000.00	24,421.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	9.06	Per Cubic metre	8,164.50	Rupees Eight Thousand One Hundred Sixty Four And Paise Fifty Only		73,970.00
Total							98,391.00

Draft Schedule of Quantity approved for (98,391) Ninety Eight, Thousand Three Hundred Ninety one only/-

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

(571)

13

EoNo - 406

569

DNT/DRAFT SCHEDULE OF QUANTITY

(Sub Head:-

Name of Work : C/O Ambulance road SC Basti Langna in GP Langna

Construction of breast wall at RD 0/120 to 0/122.2 under SDP deposit SID:SDP/2020/639)

Estimate Cost: 48,373.00
Earnest Money: 1,000.00
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	4.70	Per cubic metre	201.75	Rupees Two Hundred One And Paise Seventy Five Only	948.00	
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	2.32	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	1,503.00	

569

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water .dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and M.O.R.D technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	7.3?	Per cubic metre	6,174.95	Rupees Six Thousand One Hundred Seventy Four And Paise Ninety Five Only	45,262.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall. return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	2.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	660.00
Total						48,373.00

*Draft schedule of quantity approved for ₹ 48373/-
(₹ Forty eight thousand three hundred seventy three only)*

*Executive Engineer
B & R Division HP.PWD,
Joginder Nagar*

569

ENs. 414.

(14)

(572)

DNIT/DRAFT SCHEDULE OF QUANTITY

Work : C/O link road to Village Panjnga from NH-154 Treker Nest
 SID: Providing and Laying Cement Concrete Pavement at km 0/180 to 0/195 under Deposit SID: VKV/2021/721

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :
				Figures	Words	
	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	6.01	Per Cubic metre	8,164.50	Rupees Eight Thousand One Hundred Sixty Four And Paise Fifty Only	49,069.00 1,000.00 One Month
Total						49,069.00

Draft Schedule of Quantity approved for ₹ 49,069/- (Forty Nine Hundred sixty Nine) only /-

~~Executive Engineer~~
 B & R Division HP.PWD,
 Joginder Nagar

(572)

15

ENo 415

573

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O Ambulance road to Village Shelhan
 (S) Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/700 to 0/711 under Deposit SID:
 (S) KY/2020/402)

Sr.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT Rs. P
				Figures	Words		
1	soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	5.28	Per Cubic metre	2,210.00	Rupees Two Thousand Two Hundred Ten Only	11,669.00	47,593.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time including GST.	4.40	Per Cubic metre	8,164.50	Rupees Eight Thousand One Hundred Sixty Four And Paise Fifty Only	35,924.00	47,593.00
Total							

*Draft Schedule of Quantity approved for Rs 45,593/-
 (Forty Five Thousand Five Hundred Ninety Three) only/-*

~~Executive Engineer~~
 B & R Division HP.PWD,
 Joginder Nagar

573

16

EA. 116

574

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O Ambulance road from Main Road to Link road Langha (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/700 to 0/711 under Deposit SID: WV/2019/1662)		Estimate Cost: 48,634.00 Earnest Money: 1,000.00 Time Limit : One Month		
Description of work	No. or Qty.	Unit	Rate	
			Figures	Words
1 Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentials charges. The rate is inclusive all taxes levy by the government time to time including GST.	2.89	Per Cubic metre	3,404.80	Rupees Three Thousand Four Hundred Four And Paise Eighty Only
2 Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.81	Per Cubic metre	8,065.20	Rupees Eight Thousand Sixty Five And Paise Twenty Only
Total				
				48,634.00

Draft Schedule of Quantity approved for 48,634/- (Rupee Eight Thousand Six Hundred Thirty Five) only.

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

574

(17)

Eno 409

(575)

DNIT/DRAFT SCHEDULE OF QUANTITY

Work : Comp. of GSSS Building Outpur
supply and fixing office bench under deposit SID: BSP/2022/269)

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and fixing Carbon steel Rest Bench for Hospitals, office, Reception and Garden having size of 720 (W) x 580(D) x 790(H) (Seven hundred twenty by five hundred eighty by hundred ninety millimeter) (Chair type bench with back rest. The bench consist Seat & Back processed with 1.2 mm (one point two millimeter) thickness cold rolled MS Sheet and furnished with power coating, Armrest processed with 1.6 mm (one point six millimeter) MS tube and furnished with powercoating, leg processed with 1.00 mm (one millimeter) sheet and furnished with power coating, center support beam processed with 2mm (two millimeter) thickness MS Sheet and furnished with power coating including carriage of material all leads and lifts as per direction of the Engineer-in-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Each	17,333.25	Rupees Seventeen Thousand Three Hundred Thirty Three And Paise Twenty Five Only	86,666.00
Total					86,666.00

Draft Schedule of Quantity approved for Rs. 86,666/- (Eight Six Thousand Six Hundred Sixty Six only) -

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

18

E.No. 408

576

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Ambulance road to Chaproo via Gujar Basti from link road Bassi in GP ~~for~~ Gharwasra (SH: Providing and Laying Kharanja Soling & Cement Concrete Pavement at km 0/180 to 0/194 under Deposit SID: VKV/2021/459)

Estimate Cost: 46,169.00
Earnest Money: 900.00
Time Limit : One Month

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred milimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	6.06	Per Cubic metre	2,189.80	Rupees Two Thousand One Hundred Eighty Nine And Paise Eighty Only	13,270.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.04	Per Cubic metre	8,143.20	Rupees Eight Thousand One Hundred Forty Three And Paise Twenty Only	32,899.00
Total						46,169.00

Draft of Schedule Quantity approved by 46,169/-
(Forty Six Thousand and one Hundred Sixty Nine) only/-

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

576

DNIT/DRAFT SCHEDULE OF QUANTITY No. 417

Name of Work: R/O Restoration of Rain damages on Gaduhi to Makoda Khaprotu km 0/00 to 4/00 G.P. Bhararu (SH: Formation Cutting in km 0/180 to 0/270 & 0/345 to 0/690) under Deposit SID : NDF/2023/1339)		Estimate Cost: 92,033.00 Earnest Money: 1,800.00
Sr. No. 1 Description of work Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 14.98 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	No. or Qty. 374.53 Unit Per cubic metre	Rate Figures 245.73 Words Rupees Two Hundred Forty Five And Paise Seventy Three Only
	AMOUNT Rs. P 92,033.00	
Total		92,033.00

Draft Schedule of Quantity approved for 92,033/- (Ninety Two Thousand and Thirty Three) only.

Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

582

ENo 399

S 8.2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of link road from Sajehar to Galmatha

(Sh:-Removal of formation deficiency in km. 7/735 to 7/775) under BSP Deposit SID: BSP/2023/1325

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :
				Figures	Words	
	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 31.43 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	348.76	Per cubic metre	281.86	Rupees Two Hundred Eighty One And Paise Eighty Six Only	98,301.00 2,000.00 Two Months
Total						98,301.00

Draft Schedule of Quantity approved for 98,301/- (Ninety Eight Thousand Three Hundred one) only/-

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

E.No. 1101

DNIT/DRAFT SCHEDULE OF QUANTITY

(21)

(584)

Name of Work : Construction of Road Harizan Basti Langna km 0/00 to 1/00
 (SH: Construction of Breast wall at km 0/360 to 0/366.50) Under BASP Deposit SID: BSP/2016/106

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	6.83	Per cubic metre	201.75	Rupees Two Hundred One And Paise Seventy Five Only	1,378.00
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	3.25	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	2,106.00

(584)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is * all taxes levy by the government time to time including GST.	15.28	Per cubic metre	6,174.95	#NAME? <i>Rupees 3 Six thousand and hundred seventy four and paise ninety five only</i>	94,353.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	1,650.00
Total						99,487.00

*Draft Schedule of Quantities approved for F 99487/
(Ninety Nine Thousand four hundred Eight Seven)
only*

*Executive Engineer
B & R Division HP.PWD,
Joginder Nagar*

584

585

585

585

DNIT/DRAFT SCHEDULE OF QUANTITY

of Work: R/O Restoration of Rain damages on Gaduhi to Makoda Khaprotu km 0/00 to 4/00 G.P. Bhararu (SH: Formation Cutting in km 0/690 to 1/065) under Deposit SID : NDF/2023/4339)

Sl. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: 83,929.00 Earnest Money: 1,700.00 Time Limit:
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 13.66 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	341.55	Per cubic metre	245.73	Rupees Two Hundred Forty Five And Paise Seventy Three Only	83,929.00
Total						83,929.00

Draft Schedule of Quantity approved for P-83,292/ (Eighty Three Thousand Ninety Hundred Twenty Nine) only

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

585

E No. 399

886

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of link road from Sajehar to Galmatha

(S) Removal of formation deficiency in km. 7/705 to 7/735) under BASP Deposit SID: BSP/2023/1325

Estimate Cost: 89,286.00
Earnest Money: 1,800.00

Time Limit : Two Months

Rate

Figures

Words

272.04

Rupees Two Hundred Seventy Two And Paise Four Only

Unit

Per cubic metre

No. or Qty.

328.21

Description of work

Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 25.24 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.

Total

89,286.00

Draft Schedule of Quantity approved for P-89,286 (Eight Nine Thousand Two Hundred Eighty Six)

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

886

590622
(590)

DNIT/SCHEDULE OF QUANTITY

Name of work : Construction of Room at G.S.S.S. Golwan
(SH:-Providing and laying Tile work) (Under Deposit SDP/2020/717)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :
				Figures	Words	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer - in - charge.Nominal concrete 1:4:8 (one isto four isto 1:3) and/or leaner mix (i/c equivalent design mix) as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge.The rate is inclusive all taxes levy by the government time to time including GST.	29.89	Per Square Metre	1227.90	Rupees One Thousand Two Hundred Twenty Seven And Paise Ninety Only	98,301.00 2,000.00 Two Months
2	Kota stone slabs 20 mm (twenty millimeter) thick in risers of steps, skirting, dado and pillars laid on 12 mm (Tweleve millimeter) thick cement mortar 1:3 (One cement isto three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge.The rate is inclusive all taxes levy by the government time to time including GST.	29.89	Per Square Metre	1910.10	Rupees One Thousand Nine Hundred Ten And Paise Ten Only	57,093.00
3	Kota stone slab flooring over 25 mm (twenty five millimeter) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (One cement isto four coarse sand) as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge.The rate is inclusive all taxes levy by the government time to time including GST.	2.20	Per Square Metre	2048.10	Rupees Two Thousand Forty Eight And Paise Ten Only	4,506.00
Total						98,301.00

*Draft schedule of quantity checked and approved for
(98301.00) (K. K. Singh) (K. K. Singh) (K. K. Singh)
(one) only*

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

DNIT/SCHEDULE OF QUANTITY

Name of Work : Construction of Rain Shelter at Chakroad mangrol G.P. Khaddar Under Deposit (SID:

DF/2021/276)

Estimate Cost: 98,374.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	

1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks. Blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.53	Per Cubic Meter	243.20	Rupees Two Hundred Forty Three And Paise Twenty Only	372.00
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.50	Per Cubic Meter	1,503.00	Rupees One Thousand Five Hundred Three Only	752.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.31	Per Cubic Meter	6,292.30	Rupees Six Thousand Two Hundred Ninety Two And Paise Thirty Only	1,951.00
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement isto six coarse sand isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with : Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.53	Per Cubic Meter	5,548.60	Rupees Five Thousand Five Hundred Forty Eight And Paise Sixty Only	8,489.00
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (one cement isto one point five sand isto three graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.22	Per Cubic Meter	7,818.00	Rupees Seven Thousand Eight Hundred Eighteen Only	9,538.00

587

ENR 401

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in Lintel, Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.12	Per Square Meter	550.90	Rupees Five Hundred Fifty And Paise Ninety Only	3,372.00
7	Cement concrete flooring 40mm thick (forty millimeter) with 20mm nominal size aggregate (twenty millimetre) with cement concrete 1:2:4 (one cement :two sand:four aggregate) finished with a floating surface neat cement. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Per Square Meter	428.00	Rupees Four Hundred Twenty Eight Only	2,140.00
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	241.05	Per Kilogramme	119.90	Rupees One Hundred Nineteen And Paise Ninety Only	28,902.00
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	151.60	Per Kilogramme	120.60	Rupees One Hundred Twenty And Paise Sixty Only	18,283.00
10	Providing and fixing 0.60mm (zero point six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.67	Per Square Meter	1,603.40	Rupees One Thousand Six Hundred Three And Paise Forty Only	15,505.00
11	Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer In-Charge including carriage of material within all leads and lifts complete in all respect.The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Per Running Meter	746.30	Rupees Seven Hundred Forty Six And Paise Thirty Only	4,478.00

Description of work

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
12	Providing and fixing MS BP sheet 1.66mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.71	Each	2,401.80	Rupees Two Thousand Four Hundred One And Paise Eighty Only	4,107.00
	Painting in Steel work with two or more coat applied @ 0.90 litre/ 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.80 litre/ 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.84	Per Cubic metre	126.30	Rupees One Hundred Twenty Six And Paise Thirty Only	485.00
	Total					98,374.00

*Draft schedule of quantity approved for ₹ 98374.00 -
₹ must eight thousand three hundred seventy four only*


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

DNIT/SCHEDULE OF QUANTITY

Name of Work : Construction of Rain Shelter Near GDC Lad Bharol at Banander Under Deposit (SID: SDF/2022/776)

Estimate Cost: 98,374.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.53	Per Cubic Meter	243.20	Rupees Two Hundred Forty Three And Paise Twenty Only	372.00
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.50	Per Cubic Meter	1,503.00	Rupees One Thousand Five Hundred Three Only	752.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.31	Per Cubic Meter	6,292.30	Rupees Six Thousand Two Hundred Ninety Two And Paise Thirty Only	1,951.00
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement isto six coarse sand isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with : Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.53	Per Cubic Meter	5,548.60	Rupees Five Thousand Five Hundred Forty Eight And Paise Sixty Only	8,489.00
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (one cement isto one point five sand isto three graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.22	Per Cubic Meter	7,818.00	Rupees Seven Thousand Eight Hundred Eighteen Only	9,538.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in Lintel, Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.12	Per Square Meter	550.90	Rupees Five Hundred Fifty And Paise Ninety Only	3,372.00
7	Cement concrete flooring 40mm thick (forty millimeter) with 20mm nominal size aggregate (twenty millimetre) with cement concrete 1:2:4 (one cement :two sand:four aggregate) finished with a floating coat of neat cement. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Per Square Meter	428.00	Rupees Four Hundred Twenty Eight Only	2,140.00
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	241.05	Per Kilogramme	119.90	Rupees One Hundred Nineteen And Paise Ninety Only	28,902.00
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	151.60	Per Kilogramme	120.60	Rupees One Hundred Twenty And Paise Sixty Only	18,283.00
10	Providing and fixing 0.60mm (zero point six zero millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.67	Per Square Meter	1,603.40	Rupees One Thousand Six Hundred Three And Paise Forty Only	15,505.00
11	Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Per Running Meter	746.30	Rupees Seven Hundred Forty Six And Paise Thirty Only	4,478.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
12	Providing and fixing MS BP sheet 1.66mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.71	Each	2,401.80	Rupees Two Thousand Four Hundred One And Paise Eighty Only	4,107.00
13	Painting on Steel work with two or more coat applied @ 0.90 litre/ 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.80 litre/ 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.84	Per Cubic metre	126.30	Rupees One Hundred Twenty Six And Paise Thirty Only	485.00
Total						98,374.00

*Draft schedule of quantity applied for 98374.00
& Qty eight thousand four hundred eighty four*


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

27

589

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Shanan Harabag to Village Har GP .Har Gunain
(SH)-Construction of RCC hume pipe culvert at Km. 0/905 under Deposit SID : VKV/2021/1931

Estimate Cost: 45,687.00
Earnest Money: 900.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT	
					Figures	Words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 500 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other various materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	14.69	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	8,959.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time including GST.	3.87	Per cubic metre	7,452.30	Rupees Seven Thousand Four Hundred Fifty Two And Paise Thirty Only	28,840.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time including GST.	1.21	Per cubic metre	6,519.00	Rupees Six Thousand Five Hundred Nineteen Only	7,888.00
Total						45,687.00

Perk Schedule of Quantity upto part 45,687/-
2 Party Five thousand six hundred fifty seven only

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar