

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026- 12000-02

Dated:- 17/7/2026


To

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:- Publication of Tender Notice (OFFLINE)


Enclosed please find herewith the Tender of works costing above 1.00 Lakh and upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A0(3)/ 8/2025-300858 dated 13-11-2025. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP,PWD; Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **26-02-2026 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **25-02-2026 upto 4:00 P.M.** No application for issue of tender forms will be received on **25-02-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.


Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	C/O link road from Duni to Kashmir Km. 0/00 to 0/800 (SH:- Providing and laying Interlocking pacer block from Km. 0/250 to 0/290)	4,88,808/-	10,000/-	One Month	350/-	"C" & "D" Class
2	C/O link road from Gharat mode to Yalang (G.P.) Kalpa Km. 0/00 to 0/165 (SH:- Providing and laying Kharanja soling from Km. 0/00 to 0/165 and Interlocking paver block Km. 0/00 to 0/038)	4,99,245/-	10,000/-	One Month	350/	"C" & "D" Class
3	C/O link road from Gharat mode to Yalang (G.P.) Kalpa Km. 0/00 to 0/165 (SH:- Providing and laying Interlocking paver block Km. 0/038 to 0/091)	4,93,026/-	10,000/-	One Month	350/	"C" & "D" Class
4	C/O link road from Khawanta to Nainpura Km. 0/00 to 1/500 (SH:- Formation cutting from Km. 0/00 to 0/014, C/O R/wall and B/wall in G.I. wire crate at RD. 0/00 to 0/014)	4,97,056/-	10,000/-	One Month	350/	"C" & "D" Class
5	C/O link road from Khawanta to Nainpura Km. 0/00 to 1/500 (SH:- Formation cutting from Km. 0/014 to 0/063, C/O R/wall and B/wall in G.I. wire crate at RD. 0/014 to 0/063)	4,89,444/-	10,000/-	One Month	350/	"C" & "D" Class
6	C/O link road from Kozang Nallah-II to Meber Khawanta jKm. 0/00 to 5/00 (SH:- C/O R/wall in PCC at RD. 0/010 to 0/027.5)	4,97,628/-	10,000/-	One Month	350/	"C" & "D" Class
7	C/O link road from Kozang Nallah-II to Meber Khawanta jKm. 0/00 to 5/00 (SH:- C/O R/wall in PCC at RD. 0/030 to 0/047.5)	4,99,478/-	10,000/-	One Month	350/	"C" & "D" Class

8	C/O link road from Kozang Nallah-II to Meber Khawanta Km. 0/00 to 5/00 (SH:- C/O R/wall in PCC at RD. 0/050 to 0/067.7)	4,97,307/-	10,000/-	One Month	350/	"C" & "D" Class
---	---	------------	----------	-----------	------	-----------------

Terms and conditions:-

Following documents should accompany the application for tenders:-


1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.


**Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.
Dated: 17/3/26**

No.:- PW/KNR-E-Tender/NIT/2026- 11931-99



Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


**Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.**

CERTIFICATE

Certified that the Tender for work called vide this office Letter No. PW/KNR/E-Tender/2026- 11931-99 dated 17-02-2026 and 8 (Eight) numbers of works are of urgent nature and essential for public safety or restoration of infrastructure.


**Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.**


7

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Duni to Kashmir Km. 0/00 to 0/800

(SH:- Providing and laying interlocking paver block Km 0/250 to 0/290).

Sr. No.	Description of items	Qty.	Rate		Unit	Estimated Cost :-
			In Fig.	In Words		
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement : four coarse sand) : eight graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	18.00	₹ 5,439.15	Rupees Five Thousand Four Hundred ThirtyNine Paise Fifteen Only	Per Cubic meter	₹ 97,905.00
2	Providing and laying 60mm (Sixty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	124.00	₹ 2,288.56	Rupees Two Thousand Two Hundred EightyEight Paise FiftySix Only	Per Square meter	₹ 283,781.00
3	Providing and laying in position reinforced cement concrete 1:1.5:3 (One cement : one point five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter nominal size) excluding the cost of centering, shuttering, finishing and reinforcement in beams, suspended floors, roofs having slope up to 15° (fifteen degree), landings, balconies, shelves, chajjias, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor all level, complete upto all floor level, including entire carriage of materials in all leads and lifts and as per drawing and technical specifications as per the direction of Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.81	₹ 11,167.70	Rupees Thousand Hundred SixtySeven Paise Seventy Only	Per Cubic meter	₹ 87,220.00

Estimated Cost :-

Earnest Money :-

Time :-

One Month

Amount

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Gharat mode to Yalang (G.P. Kalpa) Km. 0/00 to 0/165
(SH:- Providing and laying Kharanja soling from Km. 0/00 to 0/165 and interlocking paver block Km 0/00 to 0/038).

Estimated Cost :- 4,99,245/-

Earnest Money :- 10,000/-

Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and comber including spreading watering and rolling of binding materials moorum or earth etc., including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	49.50	₹ 1,387.00	Rupees Thousand Hundred EightySeven Only	Per Cubic meter	₹ 68,657.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement : four coarse sand) : eight graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	11.97	₹ 5,439.15	Rupees Thousand Hundred ThirtyNine Paise Fifteen Only	Per Cubic meter	₹ 65,107.00
3	Providing and laying 60mm (Sixty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	119.70	₹ 2,110.05	Rupees Thousand Hundred Ten Paise Five Only	Per Square meter	₹ 252,573.00
4	Providing and laying in position reinforced cement concrete 1:1.5:3 (One cement : one point five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter) nominal size) excluding the cost of centering, shuttering, finishing and reinforcement in beams, suspended floors, roofs having slope up to 15° (fifteen degree), landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor all level, complete upto all floor level, including entire carriage of materials in all leads and lifts and as per drawing and technical specifications as per the direction of Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.56	₹ 11,170.70	Rupees Thousand Hundred Paise Seventy Only	Per Cubic meter	₹ 50,938.00

(2)


5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	108.00	₹ 573.80	Rupees Five Hundred SeventyThree Eighty Only	Per Cubic meter	₹ 61,970.00
Total:-						₹ 499,245.00


Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Khawanta to Nainpura Km. 0/00 to 1/500 (SH:- ormation cutting from Km 0/00 to 0/014, C/O R/Wall and B/Wall in G.I. wire crate at RD 0/00 to 0/014).		Estimated Cost :-	4,97,056/-			
		Earnest Money :-	10,000/-			
		Time :-	One Month			
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 6.22 cum., falling which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	43.93	₹ 261.73	Rupees Two Hundred SixtyOne SeventyThree Only	Per Cubic meter	₹ 11,498.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.24	₹ 261.05	Rupees Two Hundred SixtyOne Only	Per Cubic meter	₹ 7,894.00

3	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.50	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 184,739.00
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	100.80	₹ 2,906.00	Rupees Two Thousand Nine Hundred Six Only	Per Cubic meter	₹ 292,925.00
Total in figures:-						₹ 497,056.00
Total in Words:-				Rupees Four Lakh NinetySeven Thousand FiftySix Only		
Quoted Percentage rate upto three Digits :-		(+)/(-)				


Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Khawanta to Nainpura Km. 0/00 to 1/500 (SH:- Formation cutting from Km 0/014 to 0/063, C/O R/Wall and B/Wall in G.I. wire crate at RD 0/014 to 0/063).		Estimated Cost :-	4,89,444/-			
		Earnest Money :-	10,000/-			
		Time :-	One Month			
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 25.34 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	178.84	₹ 261.68	Rupees Two Hundred SixtyOne SixtyEight Only	Per Cubic meter	₹ 46,799.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.48	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 3,258.00

(5)

7

SCHEDULE O. QUANTITY

Name of work:- C/O link road from Kozang Nallah-II to Meber Khawanta Km. 0/00 to 5/00 (SH:- C/O R/Wall in PCC at RD 0/030 to 0/047.5).		Estimated Cost :-	4,99,478/-			
		Earnest Money :-	10,000/-			
		Time	One Month			
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	91.88	₹ 275.25	Rupees Two Hundred SeventyFive Paise TwentyFive Only	Per Cubic meter	₹ 25,290.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.99	₹ 4,263.50	Rupees Four Thousand Two Hundred SixtyThree Paise Fifty Only	Per Cubic meter	₹ 21,275.00
3	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	70.23	₹ 6,250.65	Rupees Six Thousand Two Hundred Fifty Paise SixtyFive Only	Per Cubic meter	₹ 438,983.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia (One hundred millimeter diameter) PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.00	₹ 290.20	Rupees Two Hundred Ninety Paise Twenty Only	Each	₹ 13,930.00
Total in figures:-						
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
		Rupees Four Lakh NinetyNine Thousand Four Hundred SeventyEight Only				₹ 499,478.00
		(+)/(-)				

Executive Engineer
Executive Engineer
 Kaipa Division
 HP. PWD, Kaipa

SCHEDULE OF QUANTITY

Name of work:- C/O link road from Kozang Nallah-II to Meber Khawanta Km. 0/00 to 5/00
(SH:- C/O R/Wall in PCC at RD 0/050 to 0/067.7).

Sr. No.	Description of items	Qty.	Rate		Unit	Estimated Cost
			In Fig.	In Words		
						Estimated Cost :- 4,97,307/- Earnest Money :- 10,000/- Time :- One Month Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.05	₹ 275.25	Rupees Two Hundred SeventyFive Paise TwentyFive Only	Per Cubic meter	₹ 17,905.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.04	₹ 4,263.50	Rupees Four Thousand Two Hundred SixtyThree Paise Fifty Only	Per Cubic meter	₹ 21,488.00
3	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	71.03	₹ 6,250.65	Rupees Six Thousand Two Hundred Fifty Paise SixtyFive Only	Per Cubic meter	₹ 443,984.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia (One hundred millimeter diameter) PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.00	₹ 290.20	Rupees Two Hundred Ninety Paise Twenty Only	Each	₹ 13,930.00
Total in figures:-						₹ 497,307.00
Total in Words:-						Rupees Four Lakh NinetySeven Thousand Three Hundred Seven Only
Quoted Percentage rate upto three Digits :-						(+)/(-)


Executive Engineer
Kaipa Division
HP. PWD, Kaipa