

**NOTICE INVITING TENDER**

Scaled percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **16.02.2026 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **13.02.2026 up to 4.30 P.M.** The tender applications for issue of tender forms will be received in this office on **13.02.2026 up to 11.30 A.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Restoration of Road G.T.L.N.S km. 0/00 to 28/00)(SH- Providing and Fixing Damaged Bridge Railing at RD 24/010 and Road Side Edge Wall at Various RDs)	99419/-	2000/-	350/-	Two Month
2.	Restoration of Road Against JSV Deposit Under HPPWD Sub Division Lunj Various Roads)(SH- Providing and laying Cement Concrete Patches at Various RDs)	98074/-	2000/-	350/-	Two Month
3.	Preparation of forest diversion case under FRA, 2006 for the C/O link road Dhinu to SC Basti Gajrehra (Kulthi) Length km. 0/000 to 1/200)(SH- Preparation of forest diversion case at RD 0/130 to 0/720=0.590 Metre)(Under FRA,2006)	42950/-	900/-	350/-	Two Month
4.	Repair and Maintenance of NGO'S Bhawan at Kangra)(SH- Wood work, Tile flooring & Wood Paint etc.(Deposit work)	99926/-	2000/-	350/-	Two Month
5.	A/R & M/O to HPPWD Rest House at Ranital (SH- Distempering and painting etc.)	59653/-	1200/-	350/-	One Month
6.	A/R & M/O to HPPWD Rest House at Ranital)(SH- Supplying and Placing Plastic Chairs, Dressing Table, Wood Work Frame, Plank Ceiling & Glass Panes etc.)	95806/-	2000/-	350/-	One Month
7.	Special Repair of HPPWD Rest House at Lunj)(SH- Supplying and Placing Plastic Chairs, Dressing Table Distempering and Painting etc.)	98190/-	2000/-	350/-	One Month

**Certified that tender of above works are being called of urgent nature in public interest.**

**TERMS & CONDITIONS:-**

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


  
Executive Engineer,  
HPPWD, Division, Kangra,  
Distt. Kangra (H.P.)

(On behalf of Governor of Himachal Pradesh)

Dated: - 5/2/26

Endst:- No.PW/KD/CB/Tenders/2025-26-  
Copy is forwarded to:-

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.

  
Executive Engineer,  
HPPWD, Division, Kangra,  
Distt. Kangra (H.P.)

7363-69

### SCHEDULE OF QUANTITY

NAME OF WORK:- RESTORATION OF ROAD GAGGAL TIARA LUNJ NAGROTA SURIAN KM 0600 TO 2800(SH- PROVIDING AND FIXING DAMAGED BRIDGE RAILING AT RD.24010 AND ROAD SIDE EDGE WALL AT VARIOUS RDS)		Estimated Cost:- Earnest Money:- Time Limit:-	99419.00 2000/- Two Months			
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, trusses, landings etc. of stair cases, railing including use of chequered plate wherever required all complete. as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	90.21	Per Kg.	124.00	Rupees One Hundred & Twenty Four Only	11186.00
2	Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix:1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm(forty millimetre) nominal size with minimum cement contents 220 kg/cum ( two hundred twenty kilogram per cubic metre) in or under water and curing complete including pumping or bailing out water, de-watering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	15.44	Per Cubic metre	5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only	88233.00
		Total:				99419.00

  
 EXECUTIVE ENGINEER  
 KANGRA DIVISION  
 H.P. P.W.D. KANGRA

EXCESS = \_\_\_\_\_ %

LESS = \_\_\_\_\_ %

### SCHEDULE OF QUANTITY

NAME OF WORK:- RESTORATION OF ROAD AGAINST JSV DEPOSIT UNDER HPPWD SUB DIVISION LUNJ VARIOUS ROADS(SH:- PROVIDING AND LAYING CEMENT CONCRETE PATCHES AT VARIOUS RDS		Estimated Cost:- Earnest Money:- Time Limit:-			
		98074.00 2000/- Two Months	AMOUNT		
Sr. No	Description of work	Qty	Unit	Rates	
				In Figures	In Words
1	Earthwork in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks( where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etc.etc as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer - in -Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and up to any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150 mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer in charge including carriage of materials with in all leads and lifts and other incidental. The rate including of octroi, markhana, tolltax, sale Tax or other taxes imposed by the government.	6.17	Per Cubic meters	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only
2	Providing and laying spreading and compacting stone aggregate of specified size to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled road/ vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ bedding material to fill up interstices of coarse aggregate, watering and compacting to the required density. 63mm to 45 mm size stone aggregate, <b>Grading-II</b> as per technical specifications clause 405. By Mechanically Meats, as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental. The rate including of octroi, royalty, Markhana, toll tax, GST or other taxes imposed by the government.	4.24	Per Cubic meters	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only
3	Providing and laying Plain/ reinforced concrete in open Foundation complete as per drawing and technical specifications Clauses 802, 1202.8, 1203(P.C.C. M-25 nominal mix 1:1.5:3) as per the direction of the Engineer - in -charge including carriage of material with in all leads and lifts and other incidentals. The rate including of octroi, royalty, Markhana, toll tax, GST or other taxes imposed by the Government.	11.32	Per Cubic meters	7450.85	Rupees Seven Thousand Four Hundred & Fifty - Paise Eighty Five Only
Total:					
					98074.00

EXCESS = \_\_\_\_\_ %

LESS = \_\_\_\_\_ %

  
 EXECUTIVE ENGINEER  
 KANGRA DIVISION  
 HP PWD, KANGRA

**SCHEDULE OF QUANTITY**


**NAME OF WORK:-** Preparation of forest diversion case under FRA, 2006 for the construction of Link road Dhinu to SC Basti Gajrehra (kulthi) Length km. 0/000 to 1/200.(SH:- Preparation of Forest Diversion Case at RD 0/130 to 0/720= 0.590 Metre ) under FRA, 2006)

Sr .No.	Sub-Head and items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Preparation of KML File, Topo Sheet Map, Alternative Map and Geo Referenced Digital map of proposed land. Preparation of 3 number of proposal folders including Reclamation Plan, Cost Benefit Analysis, Muck Management, complete in all respect. Assistance to User Agency to attend the queries and clarification sought by Forest Department. The Rates are inclusive of all equipment within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, Sale Tax, GST or other taxes imposed by the Government.	1.00	Each	40000.00	Rupees Fourty Thousand Only	40000.00
2	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. The rate including octroi, royalty, Malkana toll tax, Sale tax, GST or other taxes imposed by the Government.	0.590	Per/ Km.	5000.00	Rupees Five Thousand Only	2950.00
<b>Total</b>						<b>42950.00</b>

Estimate cost- 42950.00  
Earnest money- 900.00  
Time limit- Two month.

EXCESS= %

LESS = %

  
 Executive Engineer  
 Kangra Division  
 HPPWD Kangra

**N G O S SCHEDULE OF QUANTITY**

NAME OF WORK :- REPAIR AND MAINTENANCE OF NIGOSHAWAN AT KANSRA(SH - WOOD WORK, TILE FLOORING & WOOD PAINTING ETC.(DEPOSIT WORK)

Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
				TWO MONTH		
					99926.00	2000.00
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 35 mm thick 2nd class teak wood as per the direction of Engineer-in-Charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	6.91	Per Square metres	3556.00	Rupees Three Thousand Nine Hundred & Fifty Only	35195.00
2	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws 35 mm thick shutters. Second class teak wood as per the direction of Engineer-in-Charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	3.89	Per Square metres	3450.00	Rupees Three Thousand Four Hundred & Fifty Only	13421.00
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, Flooring in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete size 600x600 mm (Kajaria Somany, Nilco orient) as per the direction of Engineer-in-Charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	28.91	Per Square metres	1500.00	Rupees One Thousand Five Hundred Only	42365.00
4	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, Skirting in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete size 600x600 mm (Kajaria Somany, Nilco orient) as per the direction of Engineer-in-Charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	1.95	Per Square metres	1479.80	Rupees One Thousand Four Hundred & Seventy Nine - Paise Eighty Only	2886.00
5	Applying priming coat over new wood and wood based surfaces with Nerolac/Asian or its equivalent after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter) sand papering and kniting with Ready mixed paint brushing wood primer pink, as per the direction of Engineer-in-Charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	37.96	Per Square metres	38.95	Rupees Thirty Eight - Paise Ninety Five Only	1479.00

6	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 liter/10 sqm over an under coat of primer applied @ 0.75 liter/10 sqm of approved brand and manufacturer (Asian,Burger,Merolac.) as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	37.95 ✓	Per Square metres ✓	54.30 ✓	Rupees Ninety Four - Paise Thirty Only ✓	3560.00 ✓
Total:						99926.00

EXCESS = \_\_\_\_\_ %

LESS = \_\_\_\_\_ %

  
 Executive Engineer,  
 HPPWD Kangra  
 Division Kangra

### SCHEDULE OF QUANTITY

NAME OF WORK:-AR & M/O TO HP-PWD REST HOUSE AT RANTAL(SH:- DISTEMPERING AND PAINTING ETC.		Estimated Cost:- 59653.00				
		Earnest Money:- 1200.00				
		Time Limit:- One Month				
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Distemping with 1st quality acrylic distemper (ready mixed)having VOC less than 50 gms/litre,of approved manufacture of required dhade and colour complete as per manufactures specifications( Asian,Burger,Nerolac,) as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	498.15	Per Square metres	56.25	Rupees Fifty Six - Paise Twenty Five Only	28021.00
2	as per 15489:2004, Alkali & fungile resistance,dirt resistant exterior paint of required shade(Company Depot Tinted)with silicon additives New work(Two or more coats applied @ 1.43 litre/710 sqm over and including/priming coat of exterior primer ( Asian,Burger,Nerolac,) as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	144.69	Per Square metres	110.05	Rupees One Hundred & Ten - Paise Five Only	15923.00
3	Repairs of plaster of thickness 12mm to 20mm in patches of area 2.5 square meters and under, including cutting the patche in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground all with cement mortar 1:4(Cement:4 fine sand)as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	2.35	Per Square metres	264.35	Rupees Two Hundred & Sixty Four - Paise Thirty Five Only	621.00
4	Painting wood work with Deluxe Mult Surface Paint of required shade.Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm.of approved brand and manufacture( Asian,Burger,Nerolac,) as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	160.00	Per Square metres	94.30	Rupees Ninety Four - Paise Thirty Only	15088.00
<b>Total:</b>						<b>59653.00</b>

EXCESS = \_\_\_\_\_ %

LESS = \_\_\_\_\_ %

  
 Executive Engineer,  
 HPPWD Kangra  
 Division Kangra.

**SCHEDULE OF QUANTITY**

NAME OF WORK:-A/R & M/O TO HP.PWD REST HOUSE AT RANITALSH:- SUPPLYING AND PLACING PLASTIC CHAIRS . DRESSING TABLE, WOOD WORK FRAME, PLANK CEILING & GLASS PANES, ETC.		Estimated Cost- Earnest Money- Time Limit:-		95806.00 2000.00 One Month		
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Supplying and placing one no dressing table ( 75centimetre x 90centimetre) with drawer and storage door mirror contemporary wooden dressing table as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	11210.00	Rupees Eleven Thousand Two Hundred & Ten Only	11210.00
2	Supplying and placing Supreme plastic chairs, with armrest dimensions standard size seat shape Rectangular load capacity 125 kg brand supreme plastic without cushion as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	25.00	Each	1416.00	Rupees One Thousand Four Hundred & Sixteen Only	35400.00
3	Providing wood work in frames of doors, windows, clearstory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners shall be paid for separately (Sal Wood) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	0.033	Per Cubic metres	91310.9	Rupees Ninety One Thousand Three Hundred & Ten - Paise Ninety Only	3013.00
4	Providing and fixing wooden plank ceiling with planks over lapping each other and jointed with wood screw/frame work to be paid for separately list class kail wood 12mm thick as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	22.16	Per Square metres	1800.00	Rupees One Thousand Eight Hundred Only	39888.00
5	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4mm (Weight not less than 10kg/sqm) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.69	Per Square metres	772.45	Rupees Seven Hundred & Seventy Two - Paise Fourty Five Only	1305.00

6	Providing and fixing wooden moulded beading to door and window frames with iron screw, plugs and priming coat on unexposed surface etc. Complete second class teak wood 50x20mm as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government	25.80	Per Square metres	193.40	Rupees One Hundred & Ninety Three - Paise Fourty Only	4990.00		
<b>Total:</b>								95806.00

EXCESS = \_\_\_\_\_ %

LESS = \_\_\_\_\_ %

  
 Executive Engineer,  
 HPPWD Kangra  
 Division Kangra.

