



O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.

Web: www.hppwd.gov.in, e-mail: ee-karc-hp@nic.in DDO KNR04-651 Phone No-01786-292897

Registered

No:- PW- BHNR-B&R-EA-I-Tender Notice/2025-26- 11277 Dated:-12/02/2026

To

The Executive Engineer (IT Cell),
Nigam Bihar, Himachal Pradesh Shimla-2.


Subject:- Publication of Notice Inviting Tender.

Sir,

I am enclosing herewith the “**Notice Inviting Tender**” alongwith “**Schedule of Quantity**” for uploading on Department website as per Notification No. **PWD-B-A0(3)/1/2024-241828 dated 18.09.2025** issued by the Additional Chief Secretary (PW) to the Govt. of HP & circulated by the Engineer-in-Chief, HP.PWD., office letter No.PW/CTR/32-20/Genl Inst/ GCC/2025-10063-10163 dated 27.09.2025 for favour of information and necessary action. The works attached in list is very urgent nature. It is requested that the same may kindly be got published.

DA: - Notice Inviting Tender/Schedule of Quantity.

Yours Faithfully


**Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.**





O/o the Executive Engineer, Karchham Division, HP.PWD: Bhabanagar 172115.
Web: www.hppwd.gov.in, e-mail: ee-karc-hp@nic.in Phone No-01786-292897

NOTICE INVITING TENDER

Sealed percentage tender(s) on PWD form No.6 & 8 are hereby invited by the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on **20.02.2026** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **19.02.2026** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without earnest money or through FAX.


Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of form
1	R/R damages on Chaura to Majhgaon (Rupi) road Km 0/00 to 27/050. (SH:-C/O R/Wall at RD 8/685 to 8/724).	460985	9300	Two months	350/-
2	R/R damages on link road Chaura to Chhota Kamba 0/00 to 15/00.(SH:-C/O Edge/Wall in P.C.C 1:2:4 at RD 2/810 to 2/820 and ROFD B/W washout portion at RD 2/810 to 2/835).	286226	5800	Two months	350/-
3	R/R damages on Chaura to Majhgaon (Rupi) road Km 0/00 to 27/050. (C/O B/Wall at RD 9/150 to 9/170).	289923	5800	Two months	350/-
4	R/R damages on link road to Village Thach 0/00 to 3/500. (SH:-C/O R/Wall in P.C.C 1:4:8 at RD 0/570 to 0/580).	172214	3500	Two months	350/-
5	C/O EMRS at Nichar Distt Kinnaur.(Hiring of Excavator cum loader working condition for Removal of Muck from Basketball court).(EMRS)	498750	10000	Two months	350/-
6	R/R damages on link road from NH-05 to forest rest house Chaura Km 0/00 to 3/500.(SH:-C/O B/Wall in at RD 0/005 to 0/039).	492933	9900	Two months	350/-
7	R/R Damages on link road from Company area to Shorang Km 0/00 to 3/500.(SH:-Hiring of Excavator cum loader working condition for Removal of Slips /Boulders/debris on in between Km 0/00 to 1/500).	137500	2800	One month	350/-
8	R/R damages link road to Village Gharshu 0/00 to 3/500.(SH:-P/L Kahranja stone soling in Km 0/550 to 0/620, 1/345 to 1/415, 1/500 to 1/580, 1/620 to 1/670 & 1/800 to 1/850).	499110	10000	Two months	350/-
9	R/R damages on link road Chaura to Chhota Kamba Km. 0/00 to 15/00. (SH:- C/o R/Wall in P.C.C. 1:4:8: at RD 5/590 to 5/605, 5/800 to 5/821 & 5/915 to 5/930).	433020	8700	Two months	350/-
10	R/R damages on Palingi to Nichar road 0/00 to 16/00. (SH:-C/O R/Wall in P.C.C 1:4:8 at RD 5/100 to 5/128).	480118	9700	Two months	350/-
11	C/O EMRS at Nichar Distt Kinnaur.(SH:-Hiring of Tipper (5.5 cum capacity) in working condition for shifting of muck from site of Girls hostel No .03). (EMRS)	498800	10000	One month	350/-
12	R/R damages on Chaura to Majhgaon (Rupi) road Km 0/00 to 27/050. (SH:-C/O B/Wall in P.C.C 1:4:8 at RD 16/935 to 16/955).	280650	5700	One month	350/-
13	R/R damages on Palingi to Nichar road 0/00 to 16/00(SH:-C/O R/Wall in wire crates in Km 5/150 to 5/170).	494528	9900	Two months	350/-

14	R/R damages on Hot Water spring to Village Nathpa road Km. 0/00 to 9/735. SH:- C/o R/Wall at RD 5/335 to 5/349.80).	496452	10000	Two months	350/-
15	R/R damages on link road Chaura to Chota Kamba 0/00 to 15/00.(SH:-R/Wall in Wire crates in Km 13/384 to 13/392 & 13/400 to 13/417).	493794	9900	Two months	350/-
16	R/R damages on link road to Village Thach 0/00 to 3/500. (SH:- C/O R/Wall in P.C.C 1:4:8 at RD 2/490 to 2/511.50).	460925	9300	Two months	350/-
17	R/R damages on road from Katgaon to Katgaon Kanda Km 0/00 to 5/500.(SH:-C/O R/Wall at RD 1/170 to 1/191.50).	494677	9900	Two months	350/-
18	R/R damages link road Karchham to Sapni Km 0/00 to 8/300 (SH:-C/O Random rubble masonry R/ Wall at RD 7/730 to 7/740).	479286	9600	Two months	350/-
19	R/R damages on Yangpa-Kraba road Km 0/00 to 1/300. (SH:-C/O R/Wall at RD 0/080 to 0.095).	481985	9700	Two months	350/-
20	R/R damages on link road Chaura to Majhgaon (Rupi) road Km 0/00 to 27/050. (SH:-R/Wall in Wire crates in Km 16/020 to 16/040).	281353	5700	Two months	350/-
21	R/R damages on link road to Village Thach 0/00 to 3/500.(SH:-C/O R/Wall in P.C.C 1:4:8 at RD 2/170 to 2/185).	481784	9700	Two months	350/-
22	R/R damages on Link road to Village Nanspo to upper Tranda road Km 0/00 to 3/500.(SH:-C/O R/ Wall in C.C 1:4:8 at RD 3/410 to 3/414 and Kharanja Soling and CC 1:2:4 at RD 3/390 to 3/450).	255857	5200	Two months	350/-

SPECIAL CONDITIONS

1. The material shall be arranged by the contractor himself.
2. The detail of documents to be attached with the application is given below.
 - i Latest copy of renewal enlistment.
 - ii Copy of Pan Card.
 - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractors are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labour cess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractors enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification.
13. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.
14. Cement should be purchased from H.P. State Civil Supply Corporation.
15. GST will be deducted from each bill as per latest instruction of the Government.
16. L-1 bidder shall be borne an additional performance security for unbalanced financial bid in accordance with the Govt. Notification PBW(B) A(3)1/2020-1 dated 07.10.2021.




Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.

No.PW/BHNR/B&R/EA-I-Tender Notice/2025-26- 11267-76

Dated:-12/02/2026

Copy forwarded for information to the:-

1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (SZ) HP.PWD, Shimla-1
3. Superintending Engineer, 11th Circle, HP.PWD, Rampur
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.


Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.




O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.


Web: www.hppwd.gov.in e-mail: ee-karc-hp@nic.in DDO KNR04-651 Phone No-01786-292897

CERTIFICATE

Certified that the tenders of the works invited vide this office

NIT No.PW/BHNR/B&R/EA-I-Tender Notice/2025-26- **1126776** Dated:- **12/02/2026**

is urgent nature in exigency of Public interest.


Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.



Draft Schedule of Quantity

Job-1

Estimated Cost:- 460985.00

Earnest Money:- 9300.00

Time:- Two Months

Name of work:- R/R damages on Chaura to Majhgaun (Rupi) road km 0/00 to 27/050.
Sub Head:- C/O R/ wall at RD 8/685 to 8/724.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	26.33	300	Rupees Three Hundred Only	Per cubic metre	7899.00
2	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	83.27	5259.15	Rupees Five Thousand Two Hundred Fifty Nine and Fifteen Paisas Only	Per Cubic Meter	437929.00
3	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.93	4285.30	Rupees Four Thousand Two Hundred Eighty Five and Thirty Paisas Only	Per Cubic Meter	12556.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	2601.00
					Total	460985.00

Draft schedule of Quantity approved for amounting to Rs 460985/-only.

[Signature]

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

Draft Schedule of Quantity

Job-2

Estimated Cost:- 286226.00

Earnest Money:- 5800.00

Time:- Two Months

Name of work:- R/R damages on link road Chaura to chota Kamba 0/00 to 15/00.
Sub Head:- C/O Edge /wall in P.C.C 1:2:4 at RD 2/810 to 2/820 and ROFD B/W Washout portion at RD 2/810 to 2/835.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Cutting in earth work in all depths and heights in hard rock with chiseling and wedging out of rock (where blasting is prohibited), or setting out to the required lines grades, side slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer-in-charge at site according to the HPPWD specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the useful material along road side which shall not be less than 171.71 cubic meter failing which recovery @ Rs. 300/- per cubic meter shall be effected and transportation of the un usefull material for filling in roadway embankments for grade improvement and level to required grades and then disposing off all surplus excavated material in acquired width of the road or on approved dumping site through all modes of transportations including head load, animal loads or mechanical means along with its leveling and fine dressing and carriage of all labour machinery, materials, tools, equipments and safety measured and other incidentals necessary to complete the work by mechanical means and or labor (if any required complete as per the direction of Engineer-in-Charge). Any loss to the public and private property during the course of execution and transportation of useful and un usefull materials shall be absolute responsibility of the contractor which shall have to be dully compensated by him to full extent complete in all respects and in all cases.	548.00	474.70	Rupees Four Hundred Seventy Four and Seventy Paises Only	Per cubic metre	260136.00
2	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	3.60	300	Rupees Three Hundred Only	Per cubic metre	1080.00
3	Providing and laying plain cement concrete Grade M-20(Twenty) nominal mix 1:2:4 (one cement: two sand: four graded crushed stone aggregate 20mm (twenty milimetre) nominal size concrete for plain/reinforced concrete in open foundations complete including form work as per drawings and Technical Specifications Clause 802, 803, 1202 & 1203 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	3.60	6947.3	Rupees Six Thousand Nine Hundred Forty Seven and Thirty Paises Only	Per cubic metre	25010.00
					Total	286226.00

Draft schedule of Quantity approved for amounting to Rs 286226.00 only

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

Draft Schedule of Quantity

Job-3

Estimated Cost:- 289923.00
 Earnest Money:- 5800.00
 Time:- Two Months

Name of work:- R/R damages on Chaura to Majhgaun (Rupi) road km 0/00 to 27/050.
Sub Head:- C/O B/ wall at RD 9/150 to 9/170.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	20.25	300	Rupees Three Hundred Only	Per cubic metre	6075.00
2	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.50	5259.15	Rupees Five Thousand Two Hundred Fifty Nine and Fifteen Paises Only	Per Cubic Meter	276105.00
3	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.20	4285.30	Rupees Four Thousand Two Hundred Eighty Five and Thirty Paises Only	Per Cubic Meter	5142.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	2601.00
					Total	289923.00

Draft schedule of Quantity approved for amounting to Rs 289923.00/only.

[Signature]

**Executive Engineer,
 Karchham Division, HPPWD.,
 Karchham at Bhaba Nagar**

192

Draft Schedule of Quantity

Job-4

Estimated Cost:- 172214.00

Earnest Money:- 3500.00

Time:- Two Months

Name of work:- R/R damages on link road to village Thach 0/00 to 3/500.

Sub Head:- C/O R/ wall in P.C.C 1:4:8 at RD 0/570 to 0/580.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	12.00	300	Rupees Three Hundred Only	Per cubic metre	3600.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.50	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per Cubic Meter	166013.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	2601.00
					Total	172214.00

Draft schedule of Quantity approved for amounting to Rs 172214.00

[Signature]

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagara

193

Job No-5

Draft Schedule of Quantity

Estimated Cost:- 498750.00
Earnest Money:- 10000.00
Time:- Two Months

Name of work:- C/O EMRS at Nichar Distt Kinnaur.

Sub Head:- Hiring of Excavator cum loader working condition for Removal of Muck from Basketball court .(EMRS)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Excavator cum loader in working condition having a 1.00 (one) cubic metre bucket capacity for removal of slips, snow, glaciers and debris and their loading with free of cost including P.O.L. operation staff, repair charges of machinery etcetra. The actual working hour shall be counted for payment. Any damages to the private/ public property during the execution shall be the absolutely responsibility of the owner. The work shall be executed as per the entire satisfaction and direction of Engineer-in-Charge with in all leads lifts complete in all respect.	399.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per hour	498750.00
					Total	498750.00

Draft schedule of Quantity approved for amounting to Rs 498750/-only


Executive Engineer
Karchham Division (B&R).
HP;PWD Bhabanagar

194

Draft Schedule of Quantity

Job-6

Estimated Cost:-
Earnest Money:-
Time:-

492933.00
9900.00
Two Months

Name of work:- R/R damages on link road from NH-05 to forest rest house Chaura Km 0/00 to 3/500.
Sub Head:- C/O B/ wall in at RD 0/005 To 0/039.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	183.40	300	Rupees Three Hundred Only	Per cubic metre	55020.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	80.92	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per Cubic Meter	426469.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	44.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	11444.00
					Total	492933.00

Draft schedule of Quantity approved for amounting to Rs: 492933.00/-only.

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar

1915

Job No. 7


Draft Schedule of Quantity

Estimated Cost:- 137500.00
Earnest Money:- 2800.00
Time:- One Months

Name of work:-RR Damages on link road from Company area to Shorang km 0/00 to 3/500.
Sub Head:- Hiring of Excavator cum loader working condition for Removal of Slips /Boulders/debris on in between Km 0/00 to 1/500.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Excavator cum loader in working condition having a 1.00 (one) cubic metre bucket capacity for removal of slips, snow, glaciers and debris and their loading with free of cost including P.O.L. operation staff, repair charges of machinery etcetra. The actual working hour shall be counted for payment. Any damages to the private/ public property during the execution shall be the absolutely responsibility of the owner. The work shall be executed as per the entire satisfaction and direction of Engineer-in-Charge with in all leads lifts complete in all respect.	110.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per hour	137500.00
					Total	137500.00

Draft schedule of Quantity approved for amounting to Rs: 137500.00/-only.


Executive Engineer
Karchham Division (B&R).
HP;PWD Bhabanagar

196

Draft Schedule of Quantity

Job- 8

Estimated Cost:- 499110.00

Earnest Money:- 10000.00

Time:- Two Months

Name of work:- R/R damages on link road to village Gharshu 0/00 to 3/500.

Sub Head:- P/L Kharanja stone soling in km 0/550 to 0/620, 1/345 to 1/415, 1/500 to 1/580, 1/620 to 1/670 & 1/800 to 1/850.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	154.00	300	Rupees Three Hundred Only	Per cubic metre	46200.00
2	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per HP.PWD. specification. 100mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	231.00	1960.65	Rupees One Thousand Nine Hundred Sixty and Sixty Five Paisas Only	Per Cubic Meter	452910.00
					Total	499110.00

Draft schedule of quantity approved for amounting to Rs. 499110.00/- only

[Signature]

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar

Draft Schedule of Quantity

Job-9

Estimated Cost:- 433020.00

Earnest Money:- 8700.00

Time:- Two Months

Name of work:- R/R damages on link road Chaura to Chota Kamba 0/00 to 15/00.

Sub Head:- C/O R/ wall in P.C.C 1:4:8 at RD 5/590 to 5/605, 5/800 to 5/821 & 5/915 to 5/930.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	45.90	300	Rupees Three Hundred Only	Per cubic metre	13770.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.81	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paises Only	Per Cubic Meter	415348.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	15.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	3902.00
					Total	433020.00

Draft schedule of Quantity approved for amounting to Rs: 433020.00/-only


 Executive Engineer,
 Karchham Division, HPPWD.,
 Karchham at Bhaba Nagar

198

Draft Schedule of Quantity

Job- 16

Estimated Cost:-

480118.00

Earnest Money:-

9700.00

Time:-

Two Months

Name of work:- R/R damages on Palingi to Nichar road 0/00 to 16/00.
Sub Head:- C/O R/ wall in P.C.C 1:4:8 at RD 5/100 to 5/128.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	33.60	300	Rupees Three Hundred Only	Per cubic metre	10080.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	88.20	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per Cubic Meter	464836.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	20.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	5202.00
					Total	480118.00

Draft schedule of Quantity approved for amounting to Rs:- 480118.00 only

Jub

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar

199

Job-11

Draft Schedule of Quantity

Estimated Cost:- 498800.00
Earnest Money:- 10000.00
Time:- One Months

Name of work:- C/O EMRS at Nichar Distt Kinnaur.

Sub Head:- Hiring of tipper (5.5 cum capacity) in working condition for shifting of muck from site of Girls hostel No. 03 (EMRS)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire stisfaction of the Engineer -in -charge. The tipper shoud work minimum 7 hours from 9.00 AM to 5.00 PM daily.Any loss to public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper , driver and repair work shall have to be borne by the tipper owner. The detaail log book shall be maintained at site which should be daily verified by the Engineer -in -charge.	86.00	5800.00	Rupees Five Thousand Eight Hundred Only	Per hour	498800.00
					Total	498800.00

Draft schedule of Quantity approved for amounting to Rs:- 498800.00/- only

[Signature]

Executive Engineer
Karchham Division (B&R).
HP;PWD Bhabanagar

200

Draft Schedule of Quantity

Job- 12

Estimated Cost:- 280650.00

Earnest Money:- 5700.00

Time:- One Months

Name of work:- R/R damages on Chaura to Majhgaun (Rupi) road km 0/00 to 27/050.

Sub Head:- C/O B/ wall in P.C.C 1:4:8 at RD 16/935 to 16/955.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	18.00	300	Rupees Three Hundred Only	Per cubic metre	5400.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	51.24	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per Cubic Meter	270048.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	20.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	5202.00
					Total	280650.00

Draft schedule of Quantity approved for amounting Rs. 280650.00/- only.

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

Draft Schedule of Quantity

Job- 13

Estimated Cost:- 494528.00

Earnest Money:- 9900.00

Time:- Two Months

Name of work:- RR damages on Palingi to Nichar road 0/00 to 16/00

Sub Head:- C/O R/ wall in Wire Crates in km 5/150 to 5/170.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	45.00	300.00	Rupees Three Hundred Only	Per cubic metre	13500.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire conforming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	151.20	3181.40	Rupees Three Thousand One Hundred Eighty One and Forty Paisas Only	Per cubic metre	481028.00
					Total	494528.00

Draft schedule of Quantity approved for amounting to Rs:- 494528.00/- only

[Signature]

Executive Engineer,

Karchham Division, HPPWD.,

Karchham at Bhaba Nagar,

202

Job- 14

Estimated Cost:- 496452.00
Earnest Money:- 10000.00
Time:- Two Months

Draft Schedule of Quantity

Name of work:- R/R damages on Hot water spring to village Naptha road km 0/00 to 9/735.
Sub Head:- C/O R/ Wall at RD 5/335 to 5/349.80.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	49.14	300.00	Rupees Three Hundred Only	Per cubic metre	14742.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	35.52	5281.00	Rupees Five Thousand Two Hundred Eighty One Only	Per cubic metre	187581.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	54.32	5106.10	Rupees Five Thousand One Hundred Six and Ten Paisas Only	Per cubic metre	277363.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm (One hundred milimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	12.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	each	3121.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	14.06	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	13645.00
					Total	496452.00

Draft schedule of quantity approved for amounting to Rs. 496452.00/- only

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar, Jh

Draft Schedule of Quantity

Job- 15

Estimated Cost:- 493794.00


Earnest Money:- 9900.00

Time:- Two Months

Name of work:- R/R damages on link road Chaura to Chota Kamba 0/00 to 15/00.
 Sub Head:- R/wall in Wire crates in km 13/384 to 13/392 & 13/400 to 13/417.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	60.90	300.00	Rupees Three Hundred Only	Per cubic metre	18270.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire conforming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	149.47	3181.40	Rupees Three Thousand One Hundred Eighty One and Forty Pisas Only	Per Cubic Meter	475524.00
					Total	493794.00

Draft schedule of Quantity approved for amounting to Rs + 493794.00/- only


 Executive Engineer,
 Karchham Division, HPPWD.,
 Karchham at Bhaba Nagar.

204

Draft Schedule of Quantity

Job- 16

Estimated Cost:- 460925.00

Earnest Money:- 9300.00

Time:- Two Months

Name of work:- RR damages on link road to village Thach 0/00 to 3/500.

Sub Head:- C/O R /wall in P.C.C 1:4:8 at RD 2/490 to 2/511.50.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	34.40	300.00	Rupees Three Hundred Only	Per cubic metre	10320.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	84.71	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per cubic metre	446443.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	16.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	4162.00
					Total	460925.00

Draft schedule of quantity approved for amounting to Rs:- 460925/- only.

[Signature]
 Executive Engineer,
 Karchham Division, HPPWD.,
 Karchham at Bhaba Nagar.

205

Draft Schedule of Quantity

Job- 17

494677.00

9900.00

Two Months

Estimated Cost:-

Earnest Money:-

Time:-

Name of work:- RR damages on road from Katgoan to Katgoan Kanda Km 0/00 to 5/500.
Sub Head:- C/O B/ Wall at RD 1/170 to 1/191.50.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	95.68	300.00	Rupees Three Hundred Only	Per cubic metre	28704.00
2	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.10	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paises Only	Per cubic metre	30520.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	80.63	5278.05	Rupees Five Thousand Two Hundred Seventy Eight and Five Paises Only	Per cubic metre	425569.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	38.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	each	9884.00
					Total	494677.00

Draft schedule of Quantity approved for amounting to Rs. 494677.00/- only.

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

206

Draft Schedule of Quantity

Job- 18

479286.00

Estimated Cost:-

9600.00

Earnest Money:-

Two Months

Time:-

Name of work:- RR damages link road karchham to sapni Km 0/00 to 8/300

Sub Head:- C/O Random rubble masonry R/ wall at RD 7/730 to 7/740.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	33.75	300.00	Rupees Three Hundred Only	Per cubic metre	10125.00
2	Proiding and laying cement concrete 1:4:8 (One cement : four sand : eight graded stone aggregate 25mm (Twenty Five millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per drawing and technical specification clause 802, 803, 1202 & 1203 as per HPPWD specification within all leads and lifts and as per the direction of Engineer-in-charge.	5.75	5294.80	Rupees Five Thousand Two Hundred Ninety Four and Eighty Paisas Only	Per cubic metre	30445.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	77.70	5295.60	Rupees Five Thousand Two Hundred Ninety Five and Sixty Paisas Only	Per cubic metre	411468.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred milimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	32.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	8323.00
5	Back filling behind Retaining wall with granular material complete as per drawing and M.O.R.D. technical specification clause 1204.3.8. Including carriage of material within all lead and lifts and other incidentals.	19.50	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	18925.00
					Total	479286.00

Draft schedule of Quantity approved for amounting to Rs 479286.00 only

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar

207

Draft Schedule of Quantity

Job- 19

Estimated Cost:- 481985.00
Earnest Money:- 9700.00
Time:- Two Months

Name of work:- R/R damages on Yangpa-Kraba road Km 0/00 to 1/300.
Sub Head:- C/O R/ wall at RD 0/080 to 0/095.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	53.69	300	Rupees Three Hundred Only	Per cubic metre	16107.00
2	Providing and laying cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.11	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paisas Only	Per cubic metre	26264.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	79.17	5281.00	Rupees Five Thousand Two Hundred Eighty One Only	Per Cubic Meter	418097.00
4	Construction of embankment with approved material obtained from borrow pits within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and as per the entire satisfaction and direction of Engineer-in-charge.	25.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	6503.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	15.47	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per Cubic Meter	15014.00
					Total	481985.00

Draft schedule of Quantity approved for amounting to Rs: 481985.00/- only.

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

Draft Schedule of Quantity

Job- 20

Estimated Cost:- 281353.00

Earnest Money:- 5700.00

Time:- Two Months

Name of work:- R/R damages on link road Chaura to Majhgaun (Rupi) road Km 0/00 to 27/050
 Sub Head:- R/wall in Wire crates in km 16/020 to 16/040.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	21.60	300.00	Rupees Three Hundred Only	Per cubic metre	6480.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire conforming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	86.40	3181.40	Rupees Three Thousand One Hundred Eighty One and Forty Paises Only	Per Cubic Meter	274873.00
					Total	281353.00

Draft schedule of Quantity approved for amounting to Rs:- 281353.00/- only.


 Executive Engineer,
 Karchham Division, HPPWD.,
 Karchham at Bhaba Nagar

Draft Schedule of Quantity

Job- 21

Estimated Cost:- 481784.00

Earnest Money:- 9700.00

Time:- Two Months

Name of work:- R/R damages on Link road to village Thach 0/00 to 3/500.
Sub Head:- C/O R/ wall in P.C.C 1:4:8 at RD 2/170 to 2/185.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	16.20	300	Rupees Three Hundred Only	Per cubic metre	4860.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	90.00	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paises Only	Per Cubic Meter	474323.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred milimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	2601.00
					Total	481784.00

Draft schedule of Quantity approved for amounting to Rs:- 481784.00/-only

[Signature]

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

Draft Schedule of Quantity

Job- 22

255857.00

Estimated Cost:-

5200.00

Earnest Money:-

Two Months

Time:-

Name of work:- R/R damages on Link road to village Nanspo to upper Tranda Road km 0/00 to 3/500.

Sub Head:- C/O R/ wall in C.C 1:4:8 at RD 3/410 to 3/414 and Kharanja Soling and CC 1:2:4 AT rd 3/390 to 3/450.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	35.60	300	Rupees Three Hundred Only	Per cubic metre	10680.00
2	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per Hp.PWD. specification. 100mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	33.20	1960.65	Rupees One Thousand Nine Hundred Sixty and Sixty Five Paisas Only	Per cubic metre	65094.00
3	Providing and laying plain cement concrete Grade M -20(Twenty) nominal mix 1:2:4 (one cement: two sand: four graded crushed stone aggregate 20mm (twenty millimeter) nominal size concrete for plain/reinforced concrete in open foundations complete including form work as per drawings and Technical Specifications Clause 802, 803, 1202 & 1203 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	21.75	6947.3	Rupees Six Thousand Nine Hundred Forty Seven and Thirty Paisas Only	Per cubic metre	151104.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.40	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five	Per Cubic Meter	28459.00
5	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04-3.7 within all leads and lifts and as per direction of Engineer-in-charge.	2.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	520.00
					Total	255857.00

Draft schedule of Quantity approved for amounting to 255857.00/- only

Executive Engineer,
Karchham Division, HPPWD.,
Karchham at Bhaba Nagar.

