

**Enlistment OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

14241

Dated:- 21-2-2026

To

**The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.**

Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

**Executive Engineer,
B&R Division,
HP PWD Karsog**

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in
Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **01.03.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM** on **28.02.2026** for which the application should reach in this office **upto 1.00 PM 28.02.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Katanda to Mahog road Km. 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips in Km. 0/00 to 6/00)	98,900/-	2,000/-	One Month	350/-
2	R/R damages on Katanda to Mahog road Km. 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips in Km. 6/00 to 10/500)	98,900/-	2,000/-	One Month	350/-
3	R/R damages on Dhamun to Sog via Mahavan Damehal Shilh Tharli road Km. 0/00 to 3/800 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One Month	350/-
4	R/R damages on Khadargali to Somakothi road Km. 0/00 to 4/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One month	350/-
5	R/R damages on Bakhrot Sanarli Kelodhar Luhri road KM. 0/00 to 41/800 (SH:- Hiring of JCB/Excavator cum loader for snow clearance /removal of slips between RD 0/00 to 13/00)	98,900/-	2,000/-	One month	350/-
6	R/R damages on Seri Shout road Km. 0/00 to 16/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 8/00)	98,900/-	2,000/-	One month	350/-
7	R/R damages on Chithadharti to Nag Sunani road Km. 0/00 to 1/435 (SH:- C/o unlined drain surface and removal of slips at various RDs in Km. 0/00 to 1/435)	98,431/-	2,000/-	One month	350/-
8	A/R & M/O Residential Building at Churag Tehsil Karsog Distt. Mandi H.P. (SH:- P/L painting work in AE Residence & Balance painting work of JE Residence)	99,679/-	2,000/-	One month	350/-
9	R/R damages on Kelodhar to Dogra road Km. 0/00 to 2/700 (SH:- Removal of land slide slips at various RDs between Km. 0/830 to 1/010) VKV/2024/1209	99,792/-	2,000/-	One month	350/-
10	R/R damages on Kelodhar Dogra road Km. 0/00 to 2/700 (SH:- Removal of land slide slips at various RDs between Km. 1/060 to 1/240) VKV/2024/2509	99,936/-	2,000/-	One month	350/-

11	R/R damages on Kuthar Rashog Deyom road Km. 0/00 to 9/00 (SH:- Hiring of JCB/Excavator cum loader on ndaily wages basis for removal of snow/slips)	98900/-	2,000/-	One month	350/-
12	R/R damages on Khaneol Sidh Chawasi road Km. 0/00 to 6/00 (SH:- Hiring of JCB/Excavator cum loader on ndaily wages basis for removal of snow/slips)	98900/-	2,000/-	One month	350/-
13	A/R & M/O AE Office Building at Karsog Tehsil Karsog Distt. Mandi H.P. (SH:- P/F wood frame in roof work)	69,832/-	1,400/-	One month	350/-
14	R/R damages on Katanda Mahog road Km. 0/00 to 10/500 (SH:- hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 5/00 to 10/500)	98900/-	2,000/-	One month	350/-
15	R/R damages on Mahog Gawala road Km. 0/00 to 19/00 (SH:- hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98900/-	2,000/-	One month	350/-
16	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One month	350/-
17	R/R damages on Khaneol to Sidh Chawasi road Km. 0/00 to 7/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One month	350/-
18	R/R damages on Chouridhar to Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of Air Compressor for blasting and hiring of JCB rock breaker for breaking/removal of rock/boulders at various RDs)	99,744/-	2,000/-	Two month	350/-
19	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 0/945 to 0/975, 1/225 to 1/285) under PDNA 2023	4,21,689/-	8,500/-	Two months	350/-
20	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RDs between RD 0/575 to 0/645, 0/720 to 0/750) under PDNA 2023	3,45,605/-	7,000/-	Two months	350/-
21	R/R damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- ROFD at RDs 4/430 to 4/490, 4/840 to 4/915, 8/730 to 8/790, 9/120 to 9/195, 9/240 to 9/315)) under PDNA	4,69,534/-	9,400/-	Two months	350/-
22	R/R damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 7/020 to 7/038) under PDNA	4,90,685/-	9,900/-	Two months	350/-
23	R/R damages on Chouridhar to Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of Air Compressor for blasting and hiring of JCB rock breaker for breaking/removal of rock/boulders at various RDs)	99,744/-	2,000/-	Two month	350/-
24	R/R damages on Kheel Pangna road Km. 0/00 to 11/600, Jachh Sarahi road KM. 0/00 to 5/00, Pangna majhangan road Km. 0/00 to 8/00 and Kenchimod to Mashog road KM. 0/00 to 3/500(SH:- hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One month	350/-
25	R/r damages on Shimla Mandi road Km. 80/00 to 90/00 (SH:- C/o unlined surface and maintenance of earthen shoulder at various RDs between Km. 85/00 to 90/00) balance work	91,191/-	1,900/-	One month	350/-
26	R/R damages on Shimla Mandi road Km. 80/00 to 90/00 (SH:- C/o unlined drain surface and maintenance of earthen shoulders at various RDs between Km. 80/00 to 85/00) balance work	93,875/-	1,900/-	One month	350/-
27	R/R damages on Karsog Bye pass road Km. 0/00 to 1/300 (SH:- C/o PCC R/wall at RD 0/410 to 0/424) under PDNA 2023	4,99,434/-	10,000/-	Two months	350/-
28	R/R damages on Karsog Bye pass road Km. 0/00 to 1/300 (SH:- C/o PCC R/wall at RD 0/424 to 0/438) under PDNA 2023	4,98,207/-	10,000/-	Two months	350/-

29	R/R damages on Seri Shout road Km. 0/00 to 19/00 (SH:- removal of slips in various RDs Km. 0/00 to 10/00) under PDNA	99,086/-	2,000/-	One month	350/-
30	R/R damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH:- ROFD at RDs 2/015 to 2/075, 2/300 to 2/360, 2/975 to 3/005, 3/180 to 3/248 and 3/875 to 3/920) under PDNA	4,72,658/-	9,500/-	Two months	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act. :
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

14235-40

Dated:- 21-2-2026

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Katanda to Mahog road Km. 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips in Km. 0/00 to 6/00)

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words					Zero and Paise Zero Only	

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Katanda to Mahog road Km. 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips in Km. 6/00 to 10/500)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures		Select			98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer
Karsog Division,
UPPWD Karsog

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Dhamun to Sog via Mahawan Damehal Shihl Tharli road Km. 0/00 to 3/800 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures					98900.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
SPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Khadargali to Somakothi road Km. 0/00 to 4/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damage on Bakhrot Sanarli Kelodhar Luhri road Km 0/00 to 41/800 (SH:-Hiring of JCB /Excavator cum loader for Snow Clearence/removal slips between RD 0/00 to 13/00).

Sr.No	Sub-Head and Items of works	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator for Snow clearence/removal of slips from the road surface by mechanical means and disposing it on the valley side as per month and IRC specification 48-1998.The machine/JCB should work 7hours daily.Any loss of public property and accident etc the contractor is fully responsible during the executiton of work.The POL and -operation staff for the machine & repair charges of machinery will be provided by the owner.The repair charges of machinery during the execution of work will be borne by the Contractor or asper direction of Engineer-In-charge including carriage of material within all leads lifts and other incidentals.(taking thrice in winter	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero only
Total in Figure					98900.00	
Quoted Rate In Figure						
Quoted Rate In Words						


Executive Engineer
Karsog Division
HPPWD,Karsog

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Seri Shout road Km. 0/00 to 16/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 8/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures		Select 1150.00 2150.00		98900.00		
Quoted Rate in Words				Zero and Paise Zero Only		

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98431
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Chitadharthu to Nag Sunani Road Km 0/00 to 1/435 (Sh:- C/O Unlined drain surface & Removal of slips at various Rd's in Km 0/00 to 1/435).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	751.83	Per Cubic Metre	120.00	90220.00	Rupees Ninety Thousand Two Hundred Twenty and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	345.00	Per Running Metre	23.80	8211.00	Rupees Eight Thousand Two Hundred Eleven and Paise Zero Only
Total in Figures					98431.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
JHPPWD, Karsog.


Percentage Bill of Quantity

Estimated Cost 99679
Earnest Money 2000
Time One month

Name of Work:- A/R & M/O Residential building at Churag Tehsil Karsog Distt. Mandi (H.P) (Sh:- P/L Painting work in AE Residence & Balance Painting work of JE Residence).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm(fifty gram) /litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company . Depot Tinted) with silicon additives.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.					
1.1	Old work (Two or more coats applied @1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	192.70	SQM	297.10	57251.00	Rupees Fifty Seven Thousand Two Hundred Fifty One and Paise Zero Only
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.					
2.1	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	86.91	SQM	188.85	16413.00	Rupees Sixteen Thousand Four Hundred Thirteen and Paise Zero Only
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm thick with 20 mm nominal size stone aggregate as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	3.00	SQM	473.25	1420.00	Rupees One Thousand Four Hundred Twenty and Paise Zero Only
4	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	0.41	SQM	6046.10	2479.00	Rupees Two Thousand Four Hundred Seventy Nine and Paise Zero Only

5	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete :20 mm dia as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.20	Rmt	630.45	4539.00	Rupees Four Thousand Five Hundred Thirty Nine and Paise Zero Only
6	Providing and fixing M.S. double acting spring hinges bright finished with necessary screws etc. complete.100 mm as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.00	each	192.65	385.00	Rupees Three Hundred Eighty Five and Paise Zero Only
7	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete 100mm as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.00	each	160.65	321.00	Rupees Three Hundred Twenty One and Paise Zero Only
8	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete :150x10 mm as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.00	each	131.75	264.00	Rupees Two Hundred Sixty Four and Paise Zero Only
9	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :cement mortar 1:4 (1 cement : 4 coarse sand) as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	4.50	SQM	764.55	3440.00	Rupees Three Thousand Four Hundred Forty and Paise Zero Only
10	15 mm cement plaster on the rough side of single or half brick wall of mix :1:4 (1 cement: 4 fine sand) as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.00	SQM	253.30	2280.00	Rupees Two Thousand Two Hundred Eighty and Paise Zero Only
11	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1000.00	ltrs	10.05	10050.00	Rupees Ten Thousand Fifty and Paise Zero Only
12	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0 mm thick glass panes as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	0.90	SQM	929.50	837.00	Rupees Eight Hundred Thirty Seven and Paise Zero Only
Quoted Rate in Words						



 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99792
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar to Doghra Road Km. 0/00 to 2/700 (SH:- Removal of land slide slips at various RD's between Km 0/830 to 1/010) VKV/2024/1209.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	831.60	Per Cubic Metre	120.00	99792.00	Rupees Ninety Nine Thousand Seven Hundred Ninety Two and Paise Zero Only
Total In Figures					99792.00	
Quoted Rate In Figures					0	
Quoted Rate In Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99936
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar to Doghra Road Km. 0/00 to 2/700 (SH:- Removal of land slide slips at various RD's between Km 1/060 to 1/240) VKV/2024/2509.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	832.80	Per Cubic Metre	120.00	99936.00	Rupees Ninety Nine Thousand Nine Hundred Thirty Six and Paise Zero Only
Total in Figures					99936.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kuthed Rashog Deyom Road Km. 0/00 to 9/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the execution of work will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures				Select	98900.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:-R/R Damages on Khaneol to Sidh Chowsi Km. 0/00 to 6/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 69832.00
Earnest Money 1400
Time One Month

Name of Work:- A/R & M/O AE office building at Karsog Tehsil Karsog Distt. Mandi H.P. (SH:- P/F wood fram in roof work)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed position and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	0.68	Per Cubic Meter	94003.30	63922.00	Rupees Sixty Three Thousand Nine Hundred Twenty Two and Paise
2	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (thirty five kilogram) and door width upto 700mm (seven hundred millimeter) with necessary accessories and screws etc. complete and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.00	Each	2082.50	4165.00	Rupees Four Thousand One Hundred Sixty Five and Paise Zero Only
3	Providing and fixing 300 x 16 mm (three hundred into sixteen millimeter) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	2.00	Each	697.70	1395.00	Rupees One Thousand Three Hundred Ninety Five and Paise Zero Only
4	Providing and fixing 100 mm (one hundred millimeter) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS as per IS : 1868) transparent or dyed to required colour or shade, necessary screws etc. and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	4.00	Each	87.40	350.00	Rupees Three Hundred Fifty and Paise Zero Only
Total in Figures					69832.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Katanda Mahog Km 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 5/00 to 10/500)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures		Select		98900.00		
Quoted Rate in Words				Zero and Paise Zero Only		

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Name of Work:- R/R Damages on Mahog Gawala road Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
CHRPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Name of Work:- R/R Damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	#NAME? Rupees Ninety Eight Thousand Nine Hundred only.
Quoted Rate in Figures		Select			98900.00	
Quoted Rate in Words				#NAME?		

Executive Engineer,
Karsog Division,


Percentage Schedule of Quantity

Name of Work:- R/R Damages on Khaneol to Sidh Chowasi road Km. 0/00 to 7/00 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	#NAME? Rupees Ninety eight thousand nine hundred only.
Quoted Rate in Figures		Select			98900.00	
Quoted Rate in Words				#NAME?		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99744
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Chauridhar to Kotlu road Km 0/00 to 8/00 (SH:- Hiring of Air Compressor for Blasting & hiring of JCB Rock Breaker for breaking/removal of rock/boulders at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Hiring of air compressor with ractor and jack hammer for hole cutting in all kind of soil fuel, oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on his own risk and cost. Actually working hours will be deployed at any location as desired by the Engineer-in-Charge. Any loss to the public/private property or any accidents etc. should be the absolute by him in all cases. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	12.00	Per Day	4712.00	56544.00	Rupees Fifty Six Thousand Five Hundred Forty Four and Paise Zero Only
2	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required locationk actual working will be accounted for payment and propwr disposal of muck/debris will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	24.00	Per Hours	1800.00	43200.00	Rupees Forty Three Thousand Two Hundred and Paise Zero Only
Total in Figures					99744.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 421689
Earnest Money 8500
Time Two Months

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RD's between RD 0/945 to 0/975, 1/255 to 1/285) Under PDNA 2023.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs.	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 202.18 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 60654/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1166.40	Per Cubic Meter	361.53	421689.00	Rupees Four Lakhs Twenty One Thousand Six Hundred Eighty Nine and Paise Zero Only
Total in Figures					421689.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 345605
Earnest Money 7000
Time Two Months

Name of Work:- R/R Damages on Alsindi to Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- ROFD at various RD's between RD 0/575 to 0/645, 0/720 to 0/750) Under PDNA 2023.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. p	Total Amount with all taxes Including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 165.70 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 49710/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	955.45	Per Cubic Meter	361.72	345605.00	Rupees Three Lakhs Forty Five Thousand Six Hundred Five and Paise Zero Only
Total in Figures					345605.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 469534
Earnest Money 9400
Time Two months
9/315) Under PDNA.

Name of Work:- R/R Damages on Mamail Mehandi Road km 0/00 to 19/00 (SH:- ROFD at RD's Km 4/430 to 4/490, 4/840 to 4/915, 8/730 to 8/790, 9/120 to 9/195, 9/240 to

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 197.68 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.59304/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1406.38	Per Cubic Metre	333.86	469534.00	Rupees Four Lakhs Sixty Nine Thousand Five Hundred Thirty Four and Paise Zero Only
Total in Figures					469534.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

490685.00
9900
Two Months

Name of Work:- R/R Damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 7/020 to 7/038) Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	40.50	Per Cubic Meter	390.20	15803.00	Rupees Fifteen Thousand Eight Hundred Three and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	81.00	Per Cubic Meter	5500.00	445500.00	Rupees Four Lakhs Forty Five Thousand Five Hundred and Paise Zero Only
3	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	12.96	Per Cubic Meter	1460.95	18934.00	Rupees Eighteen Thousand Nine Hundred Thirty Four and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred milimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	28.00	Each	373.15	10448.00	Rupees Eighteen Thousand Nine Hundred Thirty Four and Paise Zero Only
Total in Figures					490685.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99056
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Chauridhar to Kotlu road Km 0/00 to 8/00 (SH:- Hiring of Air Compressor for Blasting & hiring of JCB Rock Breaker for breaking/removal of rock/boulders at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Hiring of air compressor with ractor and jack hammer for hole cutting in all kind of soil fuel, oil lubricants and wages of operating staff, any repair during operation and shifting of machinery from on place to other, required location will be carried out by the owner on his own risk and cost. Actually working hours will be deployed at any location as desired by the Engineer-in-Charge. Any loss to the public/private property or any accidents etc. should be the absolute by him in all cases. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	13.00	Per Day	4712.00	61256.00	Rupees Sixty One Thousand Two Hundred Fifty Six and Paise Zero Only
2	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required locationk actual working will be accounted for payment and propwr disposal of muck/debris will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	21.00	Per Hours	1800.00	37800.00	Rupees Thirty Seven Thousand Eight Hundred and Paise Zero Only
Total in Figures					99056.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

98900
2000
One Month

Name of Work:- R/R Damages on Kheel Pangna road Km 0/00 to 11/600, Jachh Sarahi road Km . 0/00 to 5/00, Pangna Manjhangar road Km. 0/00 to 8/00 and Kenchimor to Mashog road Km . 0/00 to 3/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words					Zero and Paise Zero Only	

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Assistant Engineer
Pangna Sub Division
HPPWD Pangna

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

91191
1900
One Month

Name of Work:- R/R Damages on Shimla Mandi road Km. 80/00 to 90/00(SH:- C/O unlined drain surface and maintenance of earthen shoulder at various RD's between Km 85/00 to 90/00)(balance work).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1850.10	Per Running Meter	21.80	40332.00	Rupees Forty Thousand Three Hundred Thirty Two and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2311.76	Per Square Meter	22.00	50859.00	Rupees Fifty Thousand Eight Hundred Fifty Nine and Paise Zero Only
Total in Figures					91191.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 93875
Earnest Money 1900
Time One Month

Name of Work:- R/R Damages on Shimla Mandi road Km. 80/00 to 90/00(SH:- C/O unlined drain surface and maintenance of earthen shoulder at various RD's between Km 80/00 to 85/00)(balance work).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1950.00	Per Running Meter	21.80	42510.00	Rupees Forty Two Thousand Five Hundred Ten and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2334.75	Per Square Meter	22.00	51365.00	Rupees Fifty One Thousand Three Hundred Sixty Five and Paise Zero Only
					93875.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.


Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

499434.00
10000
Two Months

Name of Work:- R/R Damages on Karsog By Pass road Km. 0/00 to 1/300 (SH:- C/O PCC R/Wall at RD 0/410 to 0/424) Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	26.18	Per Cubic Meter	390.20	10215.00	Rupees Ten Thousand Two Hundred Fifteen and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.46	Per Cubic Meter	5500.00	453530.00	Rupees Four Lakhs Fifty Three Thousand Five Hundred Thirty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	373.15	7463.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	19.32	Per Cubic Meter	1460.96	28226.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
Total in Figures					499434.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.


Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

498207.00
10000
Two Months

Name of Work:- R/R Damages on Karsog By Pass road Km. 0/00 to 1/300 (SH:- C/O PCC R/Wall at RD 0/424 to 0/438) Under PDNA 2023.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	26.18	Per Cubic Meter	390.20	10215.00	Rupees Ten Thousand Two Hundred Fifteen and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.46	Per Cubic Meter	5500.00	453530.00	Rupees Four Lakhs Fifty Three Thousand Five Hundred Thirty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	373.15	7463.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	18.48	Per Cubic Meter	1460.96	26999.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
Total in Figures					498207.00	
Quoted Rate in Figures						
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

99086
2000
One Month

Name of Work:- R/R Damages on Seri Shout Road Km. 0/00 to 19/00 (SH:- Removal of slips in various RD's Km 0/00 to 10/00) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	825.72	Per Cubic Metre	120.00	99086.00	Rupees Ninety Nine Thousand Eighty Six and Paise Zero Only
Total in Figures					99086.00	
Quoted Rate in Figures					0	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 472658
Earnest Money 9500
Time Two months

Name of Work:- R/R Damages on Mamail Mehandi Road km 0/00 to 19/00 (SH:- ROFD at RD's Km 2/015 to 2/075, 2/300 to 2/360, 2/945 to 3/005, 3/180 to 3/248, & 3/875 to 3/920) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 201.83 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.60549/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1408.06	Per Cubic Metre	335.68	472658.00	Rupees Four Lakhs Seventy Two Thousand Six Hundred Fifty Eight and Paise Zero Only
Total in Figures					472658.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.