

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2025-2026- 25123-24 Dated:-

28/4/26

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer
HPPWD., Division Kasumpti
Shimla

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 02-03-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 02-03-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 03-03-2026 .up to 10:30 AM |
| 4. Date of opening of tender:- | 03-03-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimate d cost	EMD(R s.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contract or
1	A/R & M/O O/O Prosecution department Block No-22 SDA Complex (SH:- Repair of E road side drain. Providing and fixing Grating and disposal of rubbish etc under Parimahal section)	99871	2000	350/-	30 days	Class-D
2	A/A & M/O various roads under Shimla sub division No.1(SH:- Maintenance of drain. culverts and Shoulder white washing) Rd.00 to 17/840	87914	1800	350/-	30 days	Class-D
3	A/R & M/O to various Type-1 to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Providing and Fixing Cupboard in Type-II Set No. 612 Under Kausmpti Section)	97636	2000	350/-	30 days	Class-D
4	A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Repair of roof of Glass House in Type-VI Set No. 5 and repair of railing and grating under Kausmpti Section).	83936	1700	350/-	30 days	Class-D
5	A/R & M/O to Type-I to VI Qtrs. At Mehli Shimla. (SH:- Providing Painting/Distempering Type-IV Set No. 17,18 Windsor Cottage Set No. 2 and 4 at Mehli Shimla).	99918	2000	350/-	30 days	Class-D
6	Reconstruction & Restoration on Link road to Village Chelly 0/000 to 1/000 (SH:- Construction of Retaining Wall at RD 0/630 to 0/635). (Under PDNA).	241180	4900	350/-	30 days	Class-D
7	A/R & M/O various Type - I to Type VI Qtrs of GAD at Kasumpti Shimla (SH:- Refixing of damaged interlocking paver block in near head water tank at Kasumpti Shimla.	84670	1800	350/-	30 days	Class-D
8	C/O link road from Gumma to Kanda road Km 0/00 to 3/210 (SH:- Preparation of Geo referenced Digital Map and collection data for FRA.	70000	1500	350/-	30 days	Class-D
9	C/O link road from Mashobra to Dhani road Km 0/00 to 1/00 (SH:- Preparation of Geo referenced Digital Map and collection data for FRA.	70000	1500	350/-	30 days	Class-D
10	C/O Zila Parishad Bhawan at Sanjulli Dhalli bye (SH:- P/F MS Steel ornamental fancing & prepainted sheet therein).	91897	1900/-	350/-	30 days	Class-D
11	C/O Link road from Kanola to Chhabalari Km. 0/00 to 4/00 (SH:- Preparation of Geo referenced Digital Map and collection data for FRA Km. 0/00 4/00).	70000/-	1500/-	350/-	30 days	Class-D
12	A/R & M/O to various Residential QTrs under kasumpti Sub Division Shimla-9 (SH:- Supplying of material to sub Division No VIII Mehli Section Shimla-9).	99350/-	2000/-	350/-	30 days	Class-D
13	A/R & M/O to various Residential QTrs under kasumpti Sub Division Shimla-9 (SH:- Supplying of material to sub Division No VIII Mehli Section Shimla-9).	99446/-	2000/-	350/-	30 days	Class-D
14	A/R & M/O various type-I to Type-VI GAD Qtrs at Parimahal kasumpti Shimla-9 (SH:- External Repair and Painting in type-III Sets No.53 & 56 under Parimahal Section).	99154/-	2000/-	350/-	30 days	Class-D
15	Restoation of Rain damages on Dharech to Khangna to kawanti road km. 0/00 to 8/700 (SH:- Constrction of R/wall at RD. 0/315 to 0/333)(Under PDNA).	490895/-	9900/-	350/-	30 days	Class-D
16	A/R & M/O various type-I to Type-VI GAD Qtrs at Parimahal kasaumpti Shimla-9 (SH:- External Repair and painting in type-III sets No.52 & 55 under Parimahal section).	98000/-	1900/-	350/-	30 days	Class-D
17	R/R damages on mashobra to Bhaikalty road Km. 0/00 18/00 (SH:- R/Wall at RD 3/915 to 3/931.40 (Under PDNA).	499844/-	9997/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enrollment/registration of contractor in appropriate class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R^o from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.
- 14.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2025-2026-

25125-36

Dated :-

21/2/20

Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Dsitt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99871.00		
Name of Work :- A/R & M/O O/O Prosecution department Block No -22 SDA Complex (SH:- Repair of road side drain , Providing and fixing Grating and disposal of rubbish etc under Parimahal section)					Earnest Money :-2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Disposal of muck /denris/ excavated earth upto site approved by Municipal Corporation surrounding Shimla upto all leads and lifts as per directions of the Engineer-in-Charge.	26.32	Cum	620.00	Rupees Six Hundred Twenty Only	Per Cubic Metre	16318.00
2	Steel work welded in built up sections, and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	360.00	Kgs	105.00	Rupees One Hundred Five Only	Per KilogramMetre	37800.00
3	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enamel paint.	5.76	Sqm	70.00	Rupes Seventy Only	Per Square Meter	403.00
4	Providing and fixing Copper oxidised fittings (Iron) (i) Butt hinges 75x47x1.70mm	8.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	960.00
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	2.30	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	2875.00
6	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(One cement:Four sand:Eight graded stone aggregate 20mm(Twenty milimetre) nominal size).	1.15	Cum	5900.00	Rupees Five Thousand Nine Hundred Only	Per Cubic Metre	6785.00
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty milimetre) nominal size)	4.75	Cum	6800.00	Rupees Six Thousand Eight Hundred Only	Per Cubic Metre	32300.00

8	Stone soling properly hand packed filling interstices with Kharanja stone and including watering and ramming consolidating with hand durnet complete under floor to the requisite gradient and camber including spreading watering and rolling of binding materials complete as per HP PWD specification 100mm spread thickness (finished work including materials and labour) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.80	Cum	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic Metre	2430.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	99871.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

T/s No. 24640-41 dated 18-2-26 Amounting to Rs. 102887/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY								
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:87,914.00		
Name of Work :- A/A &M/O various roads under Shimla sub division No.I(SH:- Maintenance of drain,culverts and Shoulder white washing) Rd.00 to17/840						Earnest Money :-1,800 .00		
						Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	The maintenance of drains include erosion, repair, clearing, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4000.00	Rmt	4.60	Rupces Four and Paise Sixty Only	Per Running Meter	18400.00	
2	Maintenance of Hume pipe culvert by way of cleaning, Erosion repair to cracks parapets wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	8.00	No	2278.00	Rupces Two Thousand Two Hundred Seventy Eight Only	Each	18224.00	
3	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	16250.00	Sqm	3.00	Rupces Three Only	Per Square Metre	48750.00	
4	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	86.40	Sqrm	29.40	Rupces Twenty Nine and Paise	Per Square Metre	2540.00	
							Total	87914.00
Quoted rates Percentage in figures								
Quoted rates Percentage in words								
							G.Total	

1. Rates should be quoted for all heights including all leads and lifts.

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved for Rs.87,914/- Only (Rupees Eighty seven Thousand nine hundred fourteen only) vide DNIT Register Sr.No. 911 the financial year 2025-26.T/S No. 263839 Dated 18-2-26 amounting to Rs. 99,551/-

Executive Engineer
HP PWD Division.

Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA, DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 97,636.00		
NAME OF WORK:- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Providing and Fixing Cupboard in Type-II Set No. 612 Under Kausmpti Section).					Earnest Money :- 2,000.00		
).)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	36.00	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per Square Meter	50400.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (summica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	12.96	Sqm	900.00	Rupees Nine Hundred Only	Per Square meter	11664.00
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 9mm (Nine milimetre)thick	15.05	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Meter	14298.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	87.40	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	5681.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	27.00	Nos	50.00	Rupees Fifty Only	Each	1350.00
6	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 100mm	27.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	4050.00
7	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	51.05	Sqm	40.00	Rupees Forty Only	Per Square Meter	2042.00
8	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enemal paint.	51.05	Sqm	70.00	Rupees Seventy Only	Per Square Meter	3574.00

9	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 2nd class deodar wood	0.002	Cum	97000.00	Rupees Ninety Seven Thousand Only	Per Cubic Metre	194.00
10	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square Metre	600.00
11	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	51.05	Sqm	60.00	Rupees Sixty Only	Per Square Meter	3063.00
12	Providing and fixing chromium plated brass curtain rod having wall thickness 1.25mm with two chromium plated brass brackets fixed with C.P. Brass screws and PVC sleeves etc wherever necessary including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 25mm dia.	2.40	Rmt	300.00	Rupees Three Hundred Only	Per Running Metre	720.00
						Total	97636.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

(T/S No. 2487-88. Dated 12-2-26 Amount to
Rs. 100,565/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 83,936.00
NAME OF WORK:- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Repair of roof of Glass House in Type-VI Set No. 5 and repair of railing and grating under Kausmpti Section).	Earnest Money :- 1,700.00
	Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (G.S Sheet).	15.00	Sqm	150.00	Rupees One Hundred Fifty Only	Per Square Metre	2250.00
2	Dismantling steel work in built up sections including distempering and stacking with 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Channels, angles, tees and flats including all gusset plates, bolts nuts, cutting rivets, welding.	283.50	Kgs.	5.00	Rupees Five Only	Per Kilogram	1418.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	279.70	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram Metre	29369.00
4	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. (Labour Rate)	141.75	Kgs	25.00	Rupees Twenty Five Only	Per Kilogram Metre	3544.00
5	Providing and fixing polycarbonated sheet 2.00mm thick in lining with galvanised self driven screws complete with all accessories as required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	15.00	Sqm.	2150.00	Rupees Two Thousand One Hundred Fifty	Per Square Metre	32250.00
6	Providing and fixing Copper oxidised fittings (iron) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Butt hinges: 75x47x 1.70mm	10.00	Nos	100.00	Rupees One Hundred Only	Each	1000.00
7	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign matters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With enamel paint other than white.	10.00	Sqm.	65.00	Rupees Sixty Five Only	Per Square Metre	650.00
8	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	1.22	Cum	1250.00	Rupees One Thousand Two Hundred Fifty	Per Cubic Metre	1525.00

9	Providing and laying cement concrete in retaining walls, return walls, (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (one cement : Two coarse sand) : Four graded stone aggregate 20mm (twenty milimetre) nominal size).	1.22	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	7930.00
10	Providing and Fixing Cemocrete Mainhole cover including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Heavy Grade-M20)	1.00	Nos	4000.00	Rupees Four Thousand Only	Each	4000.00
						Total	83936.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

T/S No. 24095-96 Dated 12.2.26 Amount to
Rs. 86,454/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,918.00	
NAME OF WORK:- A/R & M/O to Type-I to VI Qtrs. At Mehli Shimla. (SH:- Providing						Earnest Money :- 2,000.00	
Painting/Distemping Type-IV Set No. 17,18 Windsor Cottage Set No. 2 and 4 at Mehli Shimla).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	400.00	Sqm	12.00	Rupees Twelve Only	Per Square Meter	4800.00
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	400.00	Sqm	60.00	Rupees Sixty Only	Per Square Meter	24000.00
3	Wall painting (Two or more coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	465.60	Sqm	80.00	Rupees Eighty Only	Per Square Metre	37248.00
4	Painting one coat (excluding priming coat) on new steel/wood and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign matters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With enamel paint other than white.	382.62	Sqm.	65.00	Rupees Sixty Five Only	Per Square Meter	24870.00

5	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Old work (one or more coats)	200.00	Sqm	45.00	Rupees Forty Five Only	Per Square Metre	9000.00
						Total	99918.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

T/S No. 2408586 Dated 12.2.26 Amount to
Rs. 1,02,916/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER Kasumpti DIVISION .

Estimated Cost:- 2,41,180.00

Name of Work :-Reconstruction & Restoration on Link road to Village Chelly 0/000 to 1/000 (SH:- Construction of Retaining Wall at RD 0/630 to 0/635).(Under PDNA).


Earnest Money :- 4,900.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	49.50	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	19800.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: Five sand: Ten graded stone agg 40mm nominal size)	3.60	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	13680.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 M 7.5 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:4:8 (One cement:Four sand:Eight graded stone aggregate 20 mm (Twenty milimetre) nominal size).	43.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	197800.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material. including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.00	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	6300.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7s including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	20.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	3600.00
						Total	241180.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 HPPWD Division,
 Kasumpti Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.					Estimated Cost:-84670.00		
Name of Work :- A/R & M/O various Type - I to Type - VI Qtrs of GAD at Kasumpti Shimla (SH:- Refixing of damaged interlocking paver block in near head water tank at Kasumpti Shimla.					Earnest Money :-1800.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 40 mm	55.00	Sqm	130.00	Rupees One Hundred Thirty Only	Per Square Meter	7150.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size)	3.30	Cum	6900.00	Rupees Six Thousand Nine Hundred Only	Per Cubic Metre	22770.00
3	Disposal of muck /denris/ excavated earth upto site approved by Municipal Corporation surrounding Shimla upto all leads and lifts as per directions of the Engineer-in-Charge	25.00	Cum	650.00	Rupees Six Hundred Fifty Only	Per Cubic Metre	16250.00
4	Refixing 40mm thick factory made cement concrete inter locking paver blocks M- 50 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc all including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge (Labour Rate)	55.00	Sqm	700.00	Rupees Seven Hundred Only	Per Square Metre	38500.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	84670.00

CONDITION:-

- Rates should be quoted for all heights including all leads and lifts.
- Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

T/s No. 2436970 dated 17-2-26 mounting to Rs. 87210/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

524

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:-70000.00		
Name of Work :- C/O link road from Gumma to Kanda road Km 0/00 to 3/210 (SH:- Preparation of Geo					Earnest Money :- 1500.00		
referenced Digital Map and collection data for FRA					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Geo reference digital map and collecting of the data for proposed site including field visit preparation of KMI files with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area of proposed site . Making the aligement in soft copy and submission in hard copy . Processing the case for preparation of forest diversion under forest conservation ACT 2006 (FRA for short) including preparation of revenue paper for land acquire in thee projects & collection of other field data and all relevant document formats mandatory required to be attached with thee case as per latest requirement of of ministry of environment and forest conservation Govt of India letter No. 11-9/98 FC (PT) dated 3 rd august 2009 dehrudun after getting the joint inspection of site including computer typing of six copy to the case biniding complete and gating in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accuately filling in all the formats documents online submission rectifying observations and receiving approvals in all respects as per the direction and complete citification of user Agency and forest Department the rates are inclusive of octop royalty malkans tool GST or other taxes imposed by the government including carriage of all equipments with in all leads and lifts as per direction of Engineer - in charge .	1.00	per case	70000.00	Rs Seventy thousand only	Per Job	70000.00
	Quoted rates Percentage in words						70000.00
							G.Total

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

T/s No. 2437576 dated 17-2-26 Amounting to Rs. 72000/-

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost:-70000.00	
Name of Work :- C/O link road from Mashobra to Dhani road Km 0/00 to 1/00 (SH:- Preparation of Geo referenced Digital Map and collection data for FRA						Earnest Money :- 1500.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Geo reference digital map and collecting of the data for proposed site including field visit preparation of KMI files with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area of proposed site . Making the aligement in soft copy and submission in hard copy . Processing the case for preparation of forest diversion under forest conservation ACT 2006 (FRA for short) including preparation of revenue paper for land acquire in thee projects & collection of other field data and all relevant document formats mandatory required to be attached with thee case as per latest requirement of of ministry of environment and forest conservation Govt of India letter No. 11-9/98 FC (PT) dated 3 rd august 2009 dehrudun after getting the joint inspection of site including computer typing of six copy to the case biniding complete and gating in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accuately filling in all the formats documents online submission rectifying observations and receiving approvals in all respects as per the direction and complete citification of user Agency and forest Department the rates are inclusive of octop royalty malkans tool GST or other taxes imposed by the government including carriage of all equipments with in all leads and lifts as per direction of Engineer - in charge .	1.00	per case	70000.00	Rs Seventy thousand only	Per Job	70000.00
Quoted rates Percentage in words							
G.Total							70000.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual

T/s No. 24377-78 Dated 17-2-26 Amounting to Rs. 72000/-

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

526

DRAFT SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER Kusumpti DIVISION H.P.P.W.D.SHIMLA-3.						Estimated Cost:-91897.00	
Name of Work :- Construction of Zila Parishad Bhawan at Sanjauli Dhalli bye (SH:- Providing and fixing MS Steel ornamental fancing & prepainged sheet there in)						Earnest Money :- 1900.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. in or as per direction of the Engineer- in - Charge .	679.52	Kgs.	105.00	Rs One hundred and five only	Per Kilogram	71350.00
2	Providing and fixing 0.47mm to 0.50mm thick (Zero point thirty seven milimeter) thick prepainged steel both side green in partition with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic ting of 20 micrones over 5 microne primer coating to back coat of polyster of 5 microns over a micrones primer i/c fixing with self drilling screws 55mm size with prepainged it and rubber washer complete with all accessories as required as per the directions of Engineer-in-Charge make TATA Dura shine	15.22	Sqm	1350.00	Rs One thousand three hundred fifty only	Per Square Metre	20547.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	91897.00

CONDITION:-

- Rates should be quoted for all heights including all leads and lifts.
- Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use

DNIT approved for Rs. 91897/- Only vide DNIT Register Sr.No. 526 the financial

T/s No. 24379/88 dated 17-2-2006 Amounting to Rs. 94,659/-

Executive Engineer,
HPPWD Division
Kasumpti Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:-70000.00		
Name of Work :- C/O link road from Kanola to Chhabalari km 0/00 to 4/00 (SH:- Preparation of Geo					Earnest Money :- 1500.00		
referenced Digital Map and collection data for FRA km 0/00 to 4/00)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Geo reference digital map and collecting of the data for proposed site including field visit preparation of KMI files with Geo coordinates along with marking of habitations to be benefited by construction of project and dumping area of proposed site . Making the aligement in soft copy and submission in hard copy . Processing the case for preparation of forest diversion under forest conservation ACT 2006 (FRA for short) including preparation of revenue paper for land acquire in thee projects & collection of other field data and all relevant document formats mandatory required to be attached with thee case as per latest requirement of of ministry of environment and forest conservation Govt of India letter No. 11-9/98 FC (PT) dated 3 rd august 2009 dehrudun after getting the joint inspection of site including computer typing of six copy to the case biniding complete and gating in through from DFO including all the observation if raised at any time by any office and to pursue and resubmit the same by neatly and accuately filling in all the formats documents online submission rectifying observations and receiving approvals in all respects as per the direction and complete citification of user Agency and forest Department the rates are inclusive of octop royalty malkans tool GST or other taxes imposed by the government including carriage of all equipments with in all leads and lifts as per direction of Engineer - in - charge .	1.00	per case	70000.00	Rupees Seventy Thousand Only	Per Job	70000.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
G.Total							70000.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

T/s No. 2238889 dated 27-1-26 Amounting to Rs. 72100/-

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION, H.P.P.W.D., SHIMLA-3.					Estimated Cost Rs :-99350.00		
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Melhi Section Shimla-9).					Earnest Money Rs :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate In figures	In words	Unit	Amount
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Kgs.	350.00	Rupees Three Hundred Fifty Only	Per Kilo-gram	700.00
2	Nails 20mm	4.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	880.00
3	Nails 25MM	4.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	880.00
4	Screw 20,25,30,35mm	10.00	Packet	95.00	Rupees Ninety Five Only	Per Packet	950.00
5	Hexa Blade	10.00	Nos	20.00	Rupees Twenty Only	Each	200.00
6	CP Telephonic Mixer (ESS ESS Premium Range)	5.00	Nos	5750.00	Rupees Five Thousand Seven Hundred Fifty Only	Each	28750.00
7	Powder coated pegs	20.00	Per Peg	55.00	Rupees Fifty Five Only	Per Pegs	1100.00
8	Glass Pan 4mm plain frosted	50.00	Sft	120.00	Rupees One Hundred Twenty Only	Per Square fit	6000.00
9	Looking mirror with PVC frame	10.00	Nos	747.00	Rupees Seven Hundred Forty Seven Only	Each	7470.00
10	Leak Stop	25.00	Kgs	350.00	Rupees Three Hundred Fifty Only	Per Kilo-gram	8750.00
11	G.I. Pipe 1/2" medium	25.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	8750.00
12	G.I. Socket 1/2"	24.00	Nos	40.00	Rupees Forty Only	Each	960.00
13	G.I. Elbow 1/2"	24.00	Nos	50.00	Rupees Fifty Only	Each	1200.00
14	G.I. Tee 1/2"	24.00	Nos	65.00	Rupees Sixty Five Only	Each	1560.00
15	G.I. Union 1/2"	24.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	2880.00
17	P.V.C. Cistern Cera	2.00	Nos	1650.00	Rupees One Thousand Six Hundred Fifty Only	Each	3300.00
18	C.P. Waste 32mm	5.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1250.00
19	Hydraulic door closer Godrej/Clasic/ Krishna Make.	5.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	9450.00
20	CP BIB cock delux long body Make ESS ESS Premium Range	8.00	Nos	1790.00	Rupees One Thousand Seven Hundred Ninety Only	Each	14320.00
Total							99350.00

T/s No. 2501920 dated 21-2-26 amounting to Rs. 602989/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost Rs :-99446.00	
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no.						Earnest Money Rs :- 2000.00	
VIII Mehli Section Shimla-9).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate	Unit	Unit	Amount
				In figures			
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Kgs.	350.00	Rupees Three Hundred Fifty Only	Per Kilo-gram	1400.00
2	Nails 20mm	3.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	660.00
3	Nails 25mm	2.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	440.00
4	Nails 40mm to 100mm	2.00	Kgs.	145.00	Rupees One Hundred Forty Five Only	Per Kilo-gram	290.00
5	Screw 20,25,30,35mm	3.00	Packet	95.00	Rupees Ninety Five Only	Per Packet	285.00
6	Hexa Blade	12.00	Nos	20.00	Rupees Twenty Only	Each	240.00
7	White cement in packing	5.00	Kgs.	45.00	Rupees Forty Five Only	Per Kilo-gram	225.00
8	Powder coated pegs	5.00	Per Peg	55.00	Rupees Fifty Five Only	Per Pegs	275.00
9	Glass Pan 4mm plain frosted	20.00	Sft	120.00	Rupees One Hundred Twenty Only	Per Square fit	2400.00
10	C.P. Door Bolt	5.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	950.00
11	C.P. Curtain rod 20mm thick S.S 304 Grade	10.00	Nos	320.00	Rupees Three Hundred Twenty Only	Each	3200.00
12	Curatain rod M.S. powder coated (Heavy)	12.00	Nos	458.00	Rupees Four Hundred Fifty Eight Only	Each	5496.00
13	Curatin Bracket Powder coated	10.00	Nos	95.00	Rupees Ninety Five Only	Each	950.00
14	Wire mesh fly proof	35.00	Sft	55.00	Rupees Fifty Five Only	Per Square fit	1925.00
15	C.P. curtain bracket any shape	20.00	Nos	48.00	Rupees Forty Eight Only	Each	960.00
16	C.P. iron sliding door bolt 200x16mm	10.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	3300.00
17	C.P iron sliding door bolt 250x 16mm	10.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	3800.00
18	C.P. iron sliding door bolt 300x 16mm	8.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	3600.00
19	Aluminium Handle 150mm HEAVY	5.00	Nos	48.00	Rupees Forty Eight Only	Each	240.00
20	Aluminium tower bolt 100x10mm	5.00	Nos	45.00	Rupees Forty Five Only	Each	225.00
21	Aluminium tower bolt 150x10mm	6.00	Nos	65.00	Rupees Sixty Five Only	Each	390.00

22	Aluminium tower bolt 200x 10mm	5.00	Nos	85.00	Rupees Eighty Five Only	Each	425.00
23	Iron door spring	8.00	Nos	395.00	Rupees Three Hundred Ninety Five Only	Each	3160.00
24	Door stoper S.S Steal	5.00	Nos	175.00	Rupees One Hundred Seventy Five Only	Each	875.00
25	C.P. S.S Gate Hook	10.00	Nos	148.00	Rupees One Hundred Forty Eight Only	Each	1480.00
26	P.V.C. royal Plough	10.00	Packet	69.00	Rupees Sixty Nine Only	Per Packet	690.00
27	M-Seal	10.00	Packet	30.00	Rupees Thirty Only	Per Packet	300.00
28	Leak Stop	12.00	Kgs.	325.00	Rupees Three Hundred Twenty Five Only	Per Kilo-gram	3900.00
29	G.I. Pipe 1/2" medium	10.00	Rmt	300.00	Rupees Three Hundred Only	Per Running Meter	3000.00
30	G.I. Socket 1/2"	5.00	Nos	40.00	Rupees Forty Only	Each	200.00
31	G.I. Elbow 1/2"	5.00	Nos	50.00	Rupees Fifty Only	Each	250.00
32	G.I. Tee 1/2"	5.00	Nos	65.00	Rupees Sixty Five Only	Each	325.00
33	G.I. Union 1/2"	5.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	600.00
34	Brass stop cock 1/2"	5.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2250.00
35	Brass Bib cock 1/2"	5.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2250.00
36	C.P. Pillar cock SS ESS ESS Premium Range	8.00	Nos	1460.00	Rupees One Thousand Four Hundred Sixty Only	Each	11680.00
37	C.P. Bib cock long body make ESS ESS Premium Range	5.00	Nos	1350.00	Rupees One Thousand Three Hundred Fifty Only	Each	6750.00
38	CP Angle cock make Benson Gold	12.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	11280.00
39	Gun Metal full way valve 15mm	12.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	7800.00
40	Brass ball cock heavy	12.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	7800.00
41	G.I. Tank nipple	12.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	1800.00
42	P.V.C. waste pipe 32mm	12.00	Nos	115.00	Rupees One Hundred Fifteen Only	Each	1380.00
	Quoted rates Percentage in words						99446.00
	G.Total						

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

DNIT approved for Rs. 99446.00 Only vide DNIT Register Sr. No. 541 the financial year 2025-26
T/s No. 2502122 dated 21-2-26 amounting to Rs. 102640

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99154.00	
Name of Work:- A/R & M/O various Type -I to Type - VI GAD Qtrs at Parimahal Kasumpti Shimla - 9 (SH:- External Repair and Painting in Type - III Sets No 53& 56 under parimahal Section)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1.00	Finishing wall with weather proof exterior grade emulsion of approved design Apexultima protex) or its equarlied on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	190.35	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square Meter	22842.00
2.00	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	190.35	Sqm	12.00	Rupees Twelve Only	Per Square Metre	2284.00
3.00	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	190.35	Sqm	60.00	Rupees Sixty Only	Per Square Metre	11421.00
4.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	400.00	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	26000.00

5.00	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	7.20	Sqm	300.00	Rupees Three Hundred Only	Per Square Meter	2160.00
6.00	Scaffolding in building side including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	176.00	Sqm.	120.00	Rupees One Hundred Twenty	Per Square Metre	21120.00
7.00	Providing and applying base coat for Apexultima protek including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	190.35	Sqm.	45.00	Rupees Forty Five Only	Per Square Metre	8566.00
8.00	Removing old paint from wooden surfaces including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.() by Scrapping.	50.00	Sqm	45.00	Rupees Forty Five Only	Per Square Metre	2250.00
9.00	Disposal of muck /denris/ excavated earth upto site approved by Municipal Corporation surrounding Shimla upto all leads and lifts as per directions of the Engineer-in-Charge.	4.05	Cum	620.00	Rupees Six Hundred Twenty Only	Per Cubic Metre	2511.00
rjk	G.Total						99154.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 25013-14 dated 21-2-26 Amounting to Rs. 1,02,129/-

Executive Engineer,
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D.,					Estimated Cost:- 4,90,895.00		
Name of Work :-Restoration of Rain damages on Dharech to Khangna to Kawanti road Km 0/000 to 8/700. (Earnest Money:- 9,900.00		
SH:- C/O R/Wall at Rd 0/315 to 0/333).(Under PDNA).					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				in figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineris, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	44.28	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	14391.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineris, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to	9.18	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	3672.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12 (One cement:Six sand: Twelve graded stone agg.40mm nominal size).	9.18	Cum	3600.00	Rupees Three Thousand Six Hundred Only	Per Cubic Metre	33048.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty millimetre) nominal size).	86.58	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic Metre	415584.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred millimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	40.00	Rmt	200.00	Rupees Two Hundred Only	Per Running meter	8000.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	13.50	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	16200.00
						Total	490895.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION H.P.P.W.D., SHIMLA-3.					Estimated Cost:-98000.00		
Name of Work:- A/R & M/O various Type -I to Type - VI GAD Qtrs at Parimahal Kasumpti Shimla - 9 (SH:- External Repair and Painting in Type - III Sets No 52& 55 under parimahal Section)					Earnest Money :-1900.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1.00	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima protex) or its equalied on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	190.35	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square Meter	22842.00
2.00	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	190.35	Sqm	12.00	Rupees Twelve Only	Per Square Metre	2284.00
3.00	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	190.35	Sqm	60.00	Rupees Sixty Only	Per Square Metre	11421.00
4.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	400.00	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	26000.00

5.00	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	7.20	Sqm	300.00	Rupees Three Hundred Only	Per Square Meter	2160.00
6.00	Scaffolding in building side including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	176.00	Sqm.	120.00	Rupees One Hundred Twenty Only	Per Square Metre	21120.00
7.00	Providing and applying base coat for Apexultima protek including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	190.35	Sqm.	45.00	Rupees Forty Five Only	Per Square Metre	8566.00
8.00	Removing old paint from wooden surfaces including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.() by Scrapping.	65.00	Sqm	45.00	Rupees Forty Five Only	Per Square Metre	2925.00
9.00	Disposal of muck /denris/ excavated earth upto site approved by Municipal Corporation surrounding Shimla upto all leads and lifts as per directions of the Engineer-in-Charge.	1.10	Cum	620.00	Rupees Six Hundred Twenty Only	Per Cubic Metre	682.00
rjk	G.Total						98000.00

T/s No. 25015/16 dated 21-2-26 Amounting to Rs. 600940/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

Executive Engineer
Kasumpti Division
HP PWD Shimla-3.

SCHEDULE OF QUANTITY.

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 499844.00

Name of Work :- R/R Damages on Mashobra to Bhaikaly Road Km 0/00 to 18/00 (SH :- C/O R/Wall at RD 3/915 to 3/931.40 (Under PDNA)

Earnest Money :- 9997.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	69.54	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	22601.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious mater, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	7.71	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	3084.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a)PCC 1:6:12 (40 mm aggregate)	7.71	Cum	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	26214.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a)PCC 1:4:8 aggregate 20 mm(Twenty millimetre) nominal size).	95.25	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	438150.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 HPSR 2009 Item No 12.14 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.30	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	2415.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	41.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	7380.00
					Total		499844.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-

(T/S No. 234/19 Dated. 2.2.26 Amount to Rs.....T /S
Amount 514839.00

Executive Engineer,
HP PWD Division
Kasumpti Shimla