

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NO:-PW-SD-CB/Tender/NIT/2020-Vol-XI- 7381  
To

Dated- 20/02/2026


The Executive Engineer (IT) Cell,  
HP. PWD, Nirman Bhawan, Nigam Vihar,  
HP. PWD, Shimla -2.

Subject: - Regarding publication of Tender notice on departmental website.  
Sir,

With reference to the notification issued by the Secretary (PW) to the Government of Himachal Pradesh No. PWD-A0(3) 1/2024-241828 Dt. Shimla-2 the 18/09/2025. Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

*Certified that the work mentioned in the Tender Notice are urgent in nature.*

Encl:-As above.

  
Executive Engineer,  
Spiti B&R Division,  
HP. PWD, KAZI

-----

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
\*NOTICE INVITING TENDER\***

Sealed rate/percentage rate tenders are hereby invited by the Executive Engineer, Spiti B&R Division, HP.PWD, Kaza on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors registered in H.P.P.W.D. in appropriate class so as to reach in this office on or before **02/03/2026 up to 3.00 PM**, and the same shall be opened on the same day at **3.30 PM**, in the presence of the Contractors or their authorized representatives who may be present. The tender forms can be had from this office against cash payment (Non Refundable) on **28/02/2026**.

The tender shall accompany with earnest Money which should be in the shape of NSC/Time Deposit Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned. Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Spiti B&R Division, HP.PWD, Kaza reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders.


Sr. No	Name of Work	Estimated Cost	Earnest Money	Time
1	Name of work: -Hiring of Consultancy for the Construction of Beautification of village Tabo Distt. Lahaul & Spiti. (SH: Preparation of concept drawing, Working Architectural drawings and detailed estimate of whole project as per Architectural Drawing etc).	103605	2000	Two Months
2	Name of work: - Hiring of Consultancy for the Construction of Beautification of Kaza Market and town. (SH: Preparation of concept drawing, Working Architectural drawings and detailed estimate of whole project as per Architectural Drawing etc).	390755	7800	Two Months
3	Name of Work: - Repair and Maintenance Bridge at Sagnam, Distt L&S HP. SH: P/L Steel Truss bridge at damages portion thereof.)-Job-II	457049	9200	Four Months
4	Name of work: - Construction of Cricket Ground at Kaza Soma, Distt Lahaul & Spiti (H.P.). (SH: - C/o Main Gate, Preparation of cricket pitch and C.C. Topping on sitting steeps thereof).	493193	9900	Four Months

  
**Executive Engineer,  
Spiti B&R Division,  
HP. PWD, Kaza**

**TERMS AND CONDITIONS:-**

1. The Contractor/Firm shall have his/their PAN, GST No. & copy of the same be attached with the application.

2. The intending Contractor/Firm Should have attached copy of registration/renewal, copy of registration under EPF & miscellaneous provision Act-1952 with application.
3. The intending Contractors are requested to see the site of the work before submitting the tender.
4. Tender forms for two works only shall be issued to each Contractor who has no previous pending works.
5. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reasons.

  
Executive Engineer,  
Spiti B&R Division,  
CHP. PWD, Kaza

HIMSUCHANA AVAM JANSAMPARK

-----




## Draft Schedule of Quantity.

Estimated cost:-	390755
Earnest money:-	7800
Time Limit:-	Two Months

Name of work: - Hiring of Consultancy for the Construction of Beautification of Kaza Market and town. (SH: Preparation of concept drawing, Working Architectural drawings and detailed estimate of whole project as per Architectural Drawing etc)

Sno	Description of items.	Quantity.	Unit.	Rates.		Amount.
				In figure.	In words.	
1	2	3	4	5	6	7
1	Preparation of concept drawings and working architectural drawings for the construction of Beautification of Kaza Market and town. The job shall also include preparation and submission of detailed estimates based on analysis of rates as per HPSR-2020 and prevailing market rates for all items appearing in the estimate, along with the Draft Schedule of Quantities (SOQ). The scope of work shall further include preparation of high-quality 3-D views, perspective views, and a complete project walkthrough (digital/animated) to clearly demonstrate the proposed beautification works. The consultant shall supply soft and hard copies of the estimates, DNTT, drawings, 3-D views, and walkthroughs in triplicate, and shall also be responsible for obtaining approval of the same from the Divisional Office / Circle Office / Chief Engineer Office (SZ), Shimla, complete in all respects, as per the directions of the Engineer-in-Charge.	1.00	Job	390755.00	Rupees Three Lakh Ninety Thousand Seven Hundred & Fifty Five Only	390755
<b>Total:-</b>						<b>390755</b>

Sr.No 100 For the year 2025-26  
 Draft Schedule of Quantity approved for Rs. 390755 / Only  
 In word Rupees Three Lakh Ninety Thousand Seven Hundred & Fifty Five  
 Only

  
 Executive Engineer,  
 Spiti B&R Division,  
 H.P.P.W.D; Kaza.


**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Repair and Maintenance Bridge at Sagnam, Distt L&S HP. SH: P/L Steel Truss bridge at damages portion thereof.)-Job-II

Estimated Cost: -	457049
Earnest Money: -	9200
Time: -	Four Months

Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material in all leads and lifts & as per the direction of Engineer-in-Charge.	3236.20	Per Kg.	141.23	Rupees One Hundred & Fourty One - Paise Twenty Three Only	457049.00
<b>Total:-</b>						457049

Sr.No 141 For the year 2025-26  
 In Words:- Rupees Four Lakh Fifty Seven Thousand & Fourty Nine Only  
 Draft Schedule of Quantity approved for Rs. 457049 / Only

  
 Executive Engineer,  
 Spiti B&R Division,  
 H.P.P.W.D:Kaza.

## Draft Schedule of Quantity.

		Estimated cost:-		493193		
		Earnest money:-		9900		
		Time Limit:-		Four Months		
<b>Name of work :- Construction of Cricket Ground at Kaza Soma, Distt Lahaul &amp; Spiti (H.P.). (SH:- C/o Main Gate, Preparation of cricket pitch and C.C. Topping on sitting steps thereof).</b>						
Sno	Description of items.	Quantity.	Unit.	Rates.		Amount.
				In figure.	In words.	
1	2	3	4	5	6	7
1	Earth work inexcavationby mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting outtheexcavatedsoil anddisposal ofsurplus excavatedsoil asdirected,withinaleadof 50 m. All kind of soil and Ordinary rock as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	44.26	Per Cubic Meter	384.11	Rupees Three Hundred & Eighty Four - Paise Eleven Only	17001
2	Centering and shuttering including strutting, propping etc. and removal of form for as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.					
2.1	Foundations, footings, bases of columns, etc. for mass concrete	3.60	Per Square Meter	313.54	Rupees Three Hundred & Thirteen - Paise Fifty Four Only	1129
2.2	Columns, Pillars, Piers, Abutments, Posts and Struts	9.60	Per Square Meter	785.47	Rupees Seven Hundred & Eighty Five - Paise Fourty Seven Only	7541
3	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	13.65	Per Cubic Meter	2098.75	Rupees Two Thousand & Ninety Eight - Paise Seventy Five Only	28648


4	<p>Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.</p>	9.46	Per Cubic Meter	8650.94	Rupees Eight Thousand Six Hundred & Fifty - Paise Ninety Four Only	81838
5	<p>Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.</p>	1.93	Per Cubic Meter	12185.10	Rupees Twelve Thousand One Hundred & Eighty Five - Paise Ten Only	23517
6	<p>Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 5.2.2 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.</p>	0.72	Per Cubic Meter	13331.24	Rupees Thirteen Thousand Three Hundred & Thirty One - Paise Twenty Four Only	9598
6	<p>Providing and laying factory made Precast concrete solid blocks of 200 mm thickness of grade M10 made of C&amp;D waste from approved manufacturer in superstructure above plinth level up to floor V level, Cement mortar 1:6 (1 cement : 6 coarse sand) as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.</p>	3.60	Per Cum	9422.82	Rupees Nine Thousand Four Hundred & Twenty Two - Paise Eighty Two Only	33922

	steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more. as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	347.50	P.Kg	114.61	Rupees One Hundred & Fourteen - Paise Sixty One Only	39829
8	20 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand) as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	19.20	Per Square Meter	480.37	Rupees Four Hundred & Eighty - Paise Thirty Seven Only	9223
9	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	19.20	Per Square Meter	171.82	Rupees One Hundred & Seventy One - Paise Eighty Two Only	3299
10	Finishing walls with textured exterior paint of required shade : New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	19.20	Per Square Meter	269.38	Rupees Two Hundred & Sixty Nine - Paise Thirty Eight Only	5172
11	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	186.00	Kg.	165.12	Rupees One Hundred & Sixty Five - Paise Twelve Only	30712

	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size). as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	17.43	Per Cum	10737.13	Rupees Ten Thousand Seven Hundred & Thirty Seven - Paise Thirteen Only	187148
13	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	26.68	Per Sqm	153.16	Rupees One Hundred & Fifty Three - Paise Sixteen Only	4086
14	Printing new letter and figures of any shade with Lettering with black Japan paint of approved brand and manufacture. All complete as per HP.PWD specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges in all floors heights and levels.	5240.00	per letter per cm	2.01	Rupees Two - Paise One Only	10530
					<b>Total:-</b>	<b>493193</b>

Sr.No 158 For the year 2025-26

Draft Schedule of Quantity approved for Rs. 493193 / Only  
In word Rupees Four Lakh Ninety Three Thousand One Hundred & Ninety Three Only

  
Executive Engineer,  
Spiti B&R Division,  
H.P.P.W.D; Kaza.