



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Kotla Behar Division HPPWD Kotla Behar

Web:- www.hppwd.gov.in. Email:- eepwd-kotlabehar-hp@nic.in Phone No:- 01970-253516

Fax No. 01970-253516

No.PW/KB/CB/Tenders/2025-26/-
To

8555-70

Dated: - 9/2/2026

The Director,
Information & Publication Department,
H.P. Shimla-171002.
e-mail:- tendersforgiriraj@gmail.com.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.

Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, HPPWD Circle, Dehra.
2. The Assistant Engineer, Sub Division, HPPWD
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt of C Branch in this office.
6. Notice Board.

Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Kotla Behar Division HPPWD Kotla Behar

Web:- www.hppwd.gov.in. Email:- eepwd.kotlabehar-hp@nic.inn

Phone No:- 01970-253516

NOTICE INVITING TENDER.

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Kotla Behar Division HPPWD Kotla Behar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD , for the following works; so as to reach this office on **18.02.2026 up to 10.30 A.M.** and same will be opened on the same day at **11.00 A.M.** in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **16.02.2026 upto 1:30 P.M.**. The tender form can be had from the office of Executive Engineer Kotla Behar Division HPPWD Kotla Behar on cash payment (Non-refundable) on **17.02.2026** during office hours **2:00 P.M. to 4:00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Kotla Behar Division HPPWD Kotla Behar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from, earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions.. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required along with latest returns, Copy of PAN Card, EPF along with latest returns failing which no tender form will be issued to him. All the required documents must be attached with the application.**

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Eligible Class
1	C/o link road from Chamukha Bangana road to civil Hospital Pirsaluhi, Tehsil Rakkar, Distt. Kanagra HP Km. 0/0 to 0/360 (SH: Balance work of 900mm dia hume pipe culvert at RD 0/250) under MMGSY	99902.00	2000/-	350/-	One Month	C & D
2	C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/752.50 to 0/771) under OTMNP.	99096.00	2000/-	350/-	One Month	C & D
3	A/R & M/O Various roads under Pragpur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts & Sign boards etc in Section Rakkar)	99972.00	2000/-	350/-	One Month	C & D
4	RRD on various roads under HPPWD Sub Division Dada Siba (SH:Hiring of Three wheel 80-100 kN Static Roller for various works in Section Kotla)	97750.00	2000/-	350/-	One Month	C & D
5	RRD on various roads under Dada Siba Sub Division, Section Terrace (SH:- Maintenance of earthen shoulders of various roads) Job-2	99750.00	2000/-	350/-	One Month	C & D
6	C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/375 to 0/405 and 0/795 to 0/806) under OTMNP.	99275.00	2000/-	350/-	One Month	C & D
7	RRD Jhurni Mod (Chintpurni Talwara road) to Bassi Nangal via Sunhet Km. 0/0 to 3/315 (SH: C/o Edge wall at RD 1/855 to 1/892)	73493.00	2000/-	350/-	One Month	C & D
8	C/o link road from Chamukha Bangana road to civil Hospital Pirsaluhi, Tehsil Rakkar, Distt. Kanagra HP Km. 0/0 to 0/360(SH: Balance work of 900mm dia hume pipe culvert at RD 0/250) under MMGSY	98994.00	2000/-	350/-	One Month	C & D

9	A/R & M/O Various roads under Pragpur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts & Sign boards etc in Section Pragpur)	99974.00	2000/-	350/-	One Month	C &D
10	RRD on various roads under HPPWD Sub Division Pragpur (SH:Hiring of Three wheel 80-100 kN Static Roller for various works in Section Pragpur).	99450.00	2000/-	350/-	One Month	C &D
11	RRD Jhurni Mod (Chintpurni Talwara road) to Bassi Nangal via Sunhet Km. 0/0 to 3/315 (SH: C/o Edge wall at RD 1/855 to 1/892)	60117.00	2000/-	350/-	One Month	C &D
12	C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/736 to 0/749.50) under OTMNP.	99786.00	2000/-	350/-	One Month	C &D

Certified that the tenders for Job No. 1 to 12 are of urgent nature and in public interest.

HIM SUCHANA AYAM JAN SAMPARK.

Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar
On behalf of Governor of Himachal Pradesh

BILL OF QUANTITY

Estimate Cost :- Rs.99902/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Name of work:- C/o link road from Chamukha Bangana road to civil Hospital Pirsaluhi, Tehsil Rakkar, Distt. Kanagra HP Km. 0/0 to 0/360 (SH:
Balance work of 900mm dia hume pipe culvert at RD 0/250) under MMGSY

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in all type of sub structure like toe wall, abutment etcetra in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in open foundation etcetra including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	13.53 Cubic metre	4554.00	Rupees Four Thousand Five Hundred Fifty Four Only	Per cubic metre	61,616.00
2	Providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diametre reinforced cement concrete light duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (One cement isto two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101.5 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, GST, toll tax, sale tax or other taxes imposed by the Government.	5.00 Running metre	3900.00	Rupees Three Thousand Five Hundred Nirety Only	Per running metre	19,500.00

<p>3 Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in according to MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including levelling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.</p>	93.93 Cubic metre	200.00	Rupees Two Hundred Twenty Nine Only	Per Cubic metre	18,786.00
<p>TOTAL</p>					99,902.00
<p>Quoted Rate in Figure</p>					
<p>Quoted Rate in Words</p>					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Name of work:- C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/752.50 to 0/771) under OTMNP.

Estimate Cost :- Rs. 99,096/-

Earnest Money :-Rs. 2000/-

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved material obtained from borrow pits with all lift transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with all lead as per Technical Specification Clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	430.85 Cubic metre	230.00	Rupees Two Hundred Twenty Nine Only	Per cubic metre	99,096.00
TOTAL						99,096.00
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Estimate Cost :- Rs. 99,972/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Name of work:- A/R & M/O Various roads under Pragnpur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts & Sign boards etc in Section Rakkar)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	24.00	Rupees Twenty Four Only	Per square metre	574.00
2	Painting two coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	88.00	Rupees Eighty Eight Only	Per square metre	2105.00
3	Painting two coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	75.64 Square metre	91.00	Rupees Ninety One Only	Per square metre	6883.00
4	Writing letter in figures of any surface with black Japan Paint (stops, commas, hyphens and the like not to be measured and paid separately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	25000.00 Per Cm height per letter	2.95	Rupees Two And Paise Ninety Five Only	Per centimet re height per letter	73750.00
5	Painting index hands normal size or arrows(up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00 Figure	59.50	Rupees Fifty Nine And Paise Fifty Only	Per figure	16660.00
TOTAL						99,972.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Estimate Cost :- Rs. 97,750/-
 Earnest Money :-Rs. 2000/-
 Time Limit :- One Month.

Name of work:-RRD on various roads under HPPWD Sub Division Dada Siba (SH:Hiring of Three wheel 80-100 KN
 Static Roller for various works in Section Kotla)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Three wheel 80-100 KN Static Roller for compaction/rolling work of surface dressing, embankment in layers in all kind of soils as per direction of Engineer-in-Charge. Any loss of the public/private property or any accident etecetra heppened during the course of hiring period/execution shall be the absolute responsibility of the owner of Static Roller which shall have to be fully compensated by the contractor in all cases. The fuel and operational staffor machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which shoul be duly verified by Engineer-in-Charge. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	115.00 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	97750.00
TOTAL						97,750.00
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

BILL OF QUANTITY

Name of work:- RRD on various roads under Dada Siba Sub Division, Section Terrace (SH:- Maintenance of earthen shoulders of various roads) Job-2

Estimate Cost :- Rs. 99750/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2100.00 Square Metre	47.50	Rupees Two Hundred Twenty Nine Only	Per square metre	99,750.00
TOTAL						99,750.00
			Quoted Rate in Figure % above/below			
			Quoted Rate in Words			

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY


Name of work:- C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/375 to 0/405 and 0/795 to 0/806) under OTMNP.

Estimate Cost :- Rs. 99,275/-

Earnest Money :-Rs. 2000/-

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved material obtained from borrow pits with all lift transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with all lead as per Technical Specification Clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	431.63 Cubic metre	230.00	Rupees Two Hundred Twenty Nine Only	Per cubic metre	99,275.00
TOTAL						99,275.00
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Name of work:- RRD Jhurmi Mod (Chintpurni Talwara road) to Bassi Nangal via Sunhet Km. 0/0 to 3/315 (SH: C/o Edge wall at RD 1/855 to 1/892)

Estimate Cost :- Rs. 73,493/-
Earnest Money :-Rs. 1500/-
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	8.57 Cubic metre	229.00	Rupees Two Hundred Twenty Nine Only	Per Cubic metre	1,963.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in all type of sub structure like toe wall, abutment etcetra in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in open foundation etcetra including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	15.55 Cubic metre	4600.00	Rupees Three Thousand Four Hundred Ninety One Only	Per Cubic metre	71,530.00
TOTAL						73,493.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				


 Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

BILL OF QUANTITY

Name of work:- C/o link road from Chamukha Bangana road to civil Hospital Pirsaluhi, Tehsil Rakkar, Distt. Kanagra HP Km. 0/0 to 0/360(SH):
Balance work of 900mm dia hume pipe culvert at RD 0/250) under MMSGY

Estimate Cost :- Rs. 98994/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	10.38 Cubic metre	229.00	Rupees Two Hundred Twenty Nine Only	Per Cubic metre	2,377.00
2	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundations for all Type of structure, such as Drains and the like including pumping or bailing out water/ dewatering removal of the slush which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	21.79 Cubic metre	4434.00	Rupees Four Thousand Four Hundred Thirty Four Only	Per Cubic metre	96,617.00
TOTAL						98,994.00
		Quoted Rate in Figure		% above/below		
		Quoted Rate in Words				

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Name of work:- A/R & M/O Various roads under Pragpur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts & Sign boards etc in Section Pragpur)

Estimate Cost :- Rs. 99,974/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	24.00 Square metre	24.00	Rupees Twenty Four Only	Per square metre	576.00
2	Painting two coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	88.00	Rupees Eighty Eight Only	Per square metre	2105.00
3	Painting two coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	75.64 Square metre	91.00	Rupees Ninety One Only	Per square metre	6883.00
4	Writing letter in figures of any surface with black Japan Paint (stops, commas, hyphens and the like not to be measured and paid separately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	25000.00 Per.Cm height per letter	2.95	Rupees Two And Paise Ninety Five Only	Per centimet re height per letter	73750.00
5	Painting index hands normal size or arrows(up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00 Figure	59.50	Rupees Fifty Nine And Paise Fifty Only	Per figure	16660.00
TOTAL						99,974.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.

BILL OF QUANTITY

Estimate Cost :- Rs. 99450/-
Earnest Money :-Rs. 2000/-
Time Limit :- One Month.

Name of work:-RRD on various roads under HPPWD Sub Division Pragnpur (SH:Hiring of Three wheel 80-100 KN Static Roller for various works in Section Pragnpur).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Three wheel 80-100 KN Static Roller for compaction/rolling work of surface dressing, embankment in layers in all kind of soils as per direction of Engineer-in-Charge. Any loss of the public/private property or any accident etecetra heppened during the course of hiring period/execution shall be the absolute responsibility of the owner of Static Roller which shall have to be fully compensated by the contractor in all cases. The fuel and operational staffor machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which shoul be duly verified by Engineer-in-Charge. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	117.00 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	99450.00
TOTAL						99,450.00
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.



BILL OF QUANTITY

Estimate Cost :- Rs. 60,117/-
Earnest Money :-Rs. 1300/-
Time Limit :- One Month.

Name of work:- RRD Jhurmi Mod (Chintpurni Talwara road) to Bassi Nangal via Sunhet Km. 0/0 to 3/315 (SH: C/o Edge wall at RD 1/855 to 1/892)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	7.01 Cubic metre	229.00	Rupees Two Hundred Twenty Nine Only	Per Cubic metre	1,605.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in all type of sub structure like toe wall, abutment etcetra in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in open foundation etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	12.72 Cubic metre	4600.00	Rupees Three Thousand Four Hundred Ninety One Only	Per Cubic metre	58,512.00
TOTAL						60,117.00
		Quoted Rate in Figure		% above/below		
		Quoted Rate in Words				

Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.


BILL OF QUANTITY

Name of work:- C/O Kanol to Kalakkad GP Katoh road Km. 0/0 to 1/300 (SH: C/o balance work of embankment from RD 0/736 to 0/749.50) under OTMNP.

Estimate Cost :- Rs. 99,786/-
Earnest Money :-Rs. 2000/-

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved material obtained from borrow pits with all lift transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with all lead as per Technical Specification Clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate including Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	433.85 Cubic metre	230.00	Rupees Two Hundred Twenty Nine Only	Per cubic metre	99,786.00
TOTAL						99,786.00
Quoted Rate in Figure						
Quoted Rate in Words						
% above/below						


Executive Engineer,
Kotla Behar Division,
HPPWD Kotla Behar.