

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-MDI(P)E-Tender-NIT/2025-26- 17731-37 Dated:- 25/2/26

To

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,  
Mandi Division No.I,  
HP. PWD at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**\*NOTICE INVITING TENDER\***

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 07.03.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 06.03.2026 upto 12:00 Noon.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Thaltukhod to Graman road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 1/260 to 1/264.40)	94,253.49	1900/-	350/-	One month
2	Restoration of rain damages on Thaltukhod to Graman road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at R.D. 1/260.80 to 1/264.40)	94,253.49	1900/-	350/-	One month
3	Restoration of rain damaged on Tikkan to Silhbudhani Thaltukhod road Km 0/00 to 16/500. (SH:- Hiring of earth cutting/ excavating machine for removal of snow/ slips) (Job No.1)	98,900.00	2000/-	350/-	One month
4	Restoration of rain damaged on Balh to Tikkan road, Tikkar Sarni Road, Ropa Kathog & others roads. (SH:- Hiring of earth cutting/ excavating machine for removal of snow/ slips) (Job No.2)	98,900	2000/-	350/-	One month
5	SDF/2025/1229, R/O (Repair of) Restoration of road damages on Dharmehar Tarswan Drager Gadhgaun km 0/00 to 5/00 Mohal: (SH:- Hiring of earth cutting/ excavating machine for removal of slips & repair of pot holes) (Job No.1)	98,900.00	2000/-	350/-	One month
6	SDF/2025/1229, R/O (Repair of) Restoration of road damages on Dharmehar Tarswan Drager Gadhgaun km 0/00 to 5/00 Mohal. (SH:- Hiring of earth cutting/ excavating machine for removal of slips & repair of pot holes) (Job No.2)	98,900.00	2000/-	350/-	One month
7	BSP/2024/317 " Restoration of damages due ot incessant rain Cloud Brust in respect of Boaching Lapas road at RD 0/00 to 4/00. (SH:- Hiring of earth cutting/ Excavating machine for removal of slips)	98,900.00	2000/-	350/-	One month
8	SDP/2023/468, R/O (Repair of) Jhula to Uhal River Village Bugat Mohal. (SH:- Construction of steps towards for Jhula at Uhal river)	83,645.53	1700/-	350/-	One month

9	Restoration of rain damages on Various road in Kataula Section under Kamnad, Sub-Division, HPPWD, Kamnad (SH:- Hiring of Tipper for carriage of mucks, Stone/ Boulder, Debris of slips etc. ) (i) Kataula Bodandhar Kundakh Tihri Kalang Patons road (ii) Malwara Batheri Khalboot road (iii) Shegali Prasher road and others roads etc.)	88,500.00	1800/-	350/-	One month
10	Construction of Drang Katindhi road in Km 0/00 to 11/600. (SH:- Construction of Breast Wall at RD 11/344 to 11/350)	96,844.14	1950/-	350/-	One month
11	Restoration of rain damages on Shegali Prashar road Km 0/00 to 22/510. (PDNA-2023) (SH:- Construction of retaining wall at RD 0/526 to 0/528)	89,109.61	1800/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

  
 Executive Engineer,  
 Mandi Division No. I,  
 HPPWD, at Padhar Distt. Mandi (H.P.)  
 on behalf of Governor of Himachal Pradesh

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 94356.58  
 Earnest Money Rs:- 1900.00  
 Time:- one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar. Name of work :- Restoration of Rain Damages on Thaltukhod to Graman road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 1/257.20 to 1/260.80).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
9	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	7.06	Per cubic metre	491.80	3472.11	Rupees Three Thousand Four Hundred Seventy Two and Paise Eleven Only
10	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.52	Per cubic metre	4879.60	85490.59	Rupees Eighty Five Thousand Four Hundred Ninety and Paise Fifty Nine Only
11	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	282.90	1697.40	Rupees One Thousand Six Hundred Ninety Seven and Paise Forty Only
12	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.51	Per cubic metre	1472.70	3696.48	Rupees Three Thousand Six Hundred Ninety Six and Paise Forty Eight Only
<b>Total in figure :</b>					<b>94356.58</b>	<b>Rupees Ninety Four Thousand Three Hundred Fifty Six and Paise Fifty Eight Only</b>
<b>Total in Words :</b>					<b>Rupees Ninety Four Thousand Three Hundred Fifty Six and Paise Fifty Eight Only</b>	

Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 94253.49

Earnest Money Rs:- 1900.00

Time:- one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
 Name of work :- Restoration of Rain Damages on Thaltukhod to Graman road km.0/00 to 5/00. (PDNA-2023). (Sub Head :- Construction of Retaining wall at R.D. 1/260.80 to 1/264.40).

Contract No:-

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
9	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	7.06	Per cubic metre	491.80	Rupees Three Thousand Four Hundred Seventy Two and Paise Eleven Only
10	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.52	Per cubic metre	4879.60	Rupees Eighty Five Thousand Four Hundred Ninety and Paise Fifty Nine Only
11	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	282.90	Rupees One Thousand Six Hundred Ninety Seven and Paise Forty Only
12	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.44	Per cubic metre	1472.70	Rupees Three Thousand Five Hundred Ninety Three and Paise Thirty Nine Only
<b>Total in figure :</b>					<b>94253.49</b> Rupees Ninety Four Thousand Two Hundred Fifty Three and Paise Nine Only

**Total in Words :** Rupees Ninety Four Thousand Two Hundred Fifty Three and Paise Forty Nine Only

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar

3

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs :- 98900.00  
Earnest Money Rs :- 2000.00  
Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damaged on Tikkan to Silhbudhani Thaltukhod Road 0/00 to 16/500. (Sub Head:- Hiring of earth cutting/excavating machine for removal of snow/slips). (Job No.1)

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of Item	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting /snow including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor. Only actual working hours will be accounted for the payment. Earth cutting/ removal of slips, excavation in all kind of soils including loading into tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Hundred Only
<b>Total in figure :</b>					<b>98900.00</b>	<b>Rupees Ninety Eight Thousand Hundred Only</b>
<b>Total in Words :</b>					<b>Rupees Ninety Eight Thousand Nine Hundred Only</b>	

**Conditions:-** contractor should have his /her own machinery or he /she should have an agreement with the owner of the machinery.

Executive Engineer,  
Mandi Division No-1,  
HP. PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs :- 98900.00  
 Earnest Money Rs :- 2000.00  
 Time :- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.

**Name of work :-** Restoration of rain damaged on Balh to Tikkan Road, Ropa Kathog & others roads. (Sub Head:- Hiring of earth cutting/excavating machine for removal of snow/slips). (Job No.2)

**Contract No. :**

**Bidder Name :**

**SCHEDULE OF WORKS**

Sr. No.	Description of Item	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting /snow including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hours will be accounted for the payment. Earth cutting/ removal of slips, excavation in all kind of soils including loading into tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in figure :</b>					98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in Words :</b>					Rupees Ninety Eight Thousand Nine Hundred Only	

Conditions:- contractor should have his /her own machinery or he /she should have an agreement with the owner of the machinery.

Executive Engineer,  
 Mandi Division No-I,  
 HP. PWD, at Padhar.

*ge...*

3

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 98900.00  
Earnest Money Rs:- 2000.00  
Time:- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No. 1 HP. PWD. at Padhar.  
**Name of work:** - SDF/2025/1229,R/O (Repair of) Restoration of road damages on Dharmehar Tarswan Drager Gadhgaun Km 0/00 to 5/00 Mohal.(Sub Head:- Hiring of earth cutting / excavating machine for removal of slips & repair of pot holes) (Job No.1)

**Contact No. :**  
**Bidder Name:**

**SCHEDULE OF WORKS**

Sr. No	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes including GST in Rs. P.	Total Amount with all taxes Including GST in words
1	Hiring of earth cutting/ excavating machineries to be deployed for earth cutting / excavating/ removal of slips, boulders including cost of fuel Oil, Lubricants and wages of operating staff any repair/ breakage during operation will be carried out by the contractor at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hours will be accounted for the payment. Earth cutting removal of slips, boulder Excavation in all kinds of soils, including loading in to tipper/trucks and disposed of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in -Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in figure :</b>					98900.00	Rupees Ninety Thousand Nine Hundred Only
<b>Total in Words :</b>					Rupees Ninety Eight Thousand Nine Hundred Only	

Executive Engineer,  
Mandi Division No-1,  
HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 98900.00

Earnest Money Rs:- 2000.00

Time:- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

**Name of work :-** SDF/2025/1229,R/O (Repair of) Restoration of road damages on Dharmehar Tarswan Drager Gadhgaun Km 0/00 to 5/00 Mohal.(Sub Head:- Hiring of earth cutting / excavating machine for removal of slips & repair of pot holes) (Job No.2)

**Contact No. :**

**Bidder Name:**

**SCHEDULE OF WORKS**

Sr. No	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes Including GST in words
1	Hiring of earth cutting/ excavating machineries to be deployed for earth cutting / excavating/ removal of slips, boulders including cost of fuel Oil, Lubricants and wages of operating staff any repair/ breakage during operation will be carried out by the contractor at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hours will be accounted for the payment. Earth cutting removal of slips, boulder Excavation in all kinds of soils, including loading in to tipper/trucks and disposed of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in -Charge.	86.00	Per Hours	1150.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in figure :</b>					98900.00 Rupees Ninety Thousand Nine Hundred Only
<b>Total in Words :</b>					Rupees Ninety Eight Thousand Nine Hundred Only

Executive Engineer,  
Mandi Division No-I,  
HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 98900.00  
 Earnest Money Rs:- 2000.00  
 Time:- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No. 1 HP PWD. at Padhar.

**Name of work :-** "BSP/2024/317" Restoration of damages due to ~~increas~~ Rain Cloud Burst in respect of Boaching Lapas Rulang road at RD 0/00 to 4/00) (Sub Head:- Hiring of Earth cutting/Excavating machine for removal of slips)

**Contact No. :**

**Bidder Name:**

**SCHEDULE OF WORKS**

Sr. No.	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes including GST in Rs. P.	Total Amount with all taxes including GST in words
1	Hiring of earth cutting/ excavating machineries to be deployed for earth cutting / excavating/ removal of slips, boulders including cost of fuel Oil, Lubricants and wages of operating staff any repair/ breakage during operation will be carried out by the contractor at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hours will be accounted for the payment. Earth cutting removal of slips, boulder Excavation in all kinds of soils, including loading in to tipper/trucks and disposed of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in -Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in figure :</b>					98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in Words :</b>					Rupees Ninety Eight Thousand Nine Hundred Only	

Executive Engineer,  
 Mandi Division No-1,  
 HP. PWD. at Padhar. *ge*

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 83645.53

Earnest Money Rs:- 1700.00

Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- SDP/2023/468, R/O (Repair of) Jhula at Uhal River village Bugat Mohal: (Sub Head:- Construction of steps towards for Jhula at Uhal river.)

Contract No:-

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.11	Per cubic metre	522.50	1102.48	Rupees One Thousand One Hundred Two and Paise Forty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : six graded,crushed stone aggregate 10mm (ten millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.21	Per cubic metre	5808.80	82543.05	Rupees Eighty Two Thousand Five Hundred Forty Three and Paise Five Only
<b>Total in figure :</b>					<b>83645.53</b>	<b>Rupees Eighty Three Thousand Six Hundred Forty Five and Paise Fifty Three Only</b>
<b>Total in Words :</b>					<b>Rupees Eighty Three Thousand Six Hundred Forty Five and Paise Fifty Three Only</b>	

Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar

**Percentage Rate Bill of Quantity**

Estimated Cost:- 88500.00  
 Earnest Money:- 1800.00  
 Time:- One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.

**Name of work :-** Restoration of rain damages on Various Road in Kataula Section under Kamand, Sub-Division HP.PWD. Kamand (Sub Head:- Hiring of Tipper for carriage of Mucks, Stone/Boulder, Debris of slips etc). (i) Kataula Bodandhar Kundakh Tihri Kalang Patons road (ii) Malwara Batheri Khalboot road (iii) Shegali Prasher road and others roads etc).

**Contact No.:**

**Bidder Name:**

**SCHEDULE OF WORKS**

Sr. No	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes Including GST in Rs. P.	Total Amount with all taxes Including GST in words.
1	Hiring of tipper of 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) for carriage of earth/debris, boulder and other construction materials from various location etc. complete including wages of tipper driver, cleaner and P.O.L. any repair / damage during work will be absolute responsibility of the contractor/owner tipper has to work at least 8 (eight) hours per day. Only actual working day shall be accounted for the payment. No payment will be made for sunday and holidays as well as certain day if there is no work to the entire satisfaction of Engineer-in-Charge.	30.00	days	2950.00	88500.00	Rupees Eighty Eight Thousand Five Hundred Fifty Only.
<b>Total In figure :</b>					88500.00	Rupees Eighty Eight Thousand Five Hundred Fifty Only.
<b>Total In Words :</b>					Rupees Eighty Eight Thousand Five Hundred Fifty Only.	

Executive Engineer  
 Mandi Division no 1  
 HPPWD at Padhar

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 96844.14  
 Earnest Money Rs:- 1950.00  
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.  
 Name of work :- Construction of Drang Katindhi road in Km. 0/00 to 11/600 (Sub Head:- Construction of Breast wall at R.D. 11/344 to 11/350).

Contract No. :  
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	2.96	Per cubic metre	159.90	473.30	Rupees Four Hundred Seventy Three and Paise Thirty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.06	Per cubic metre	4448.90	93693.83	Rupees Ninety Three Thousand Six Hundred Ninety Three and Paise Eighty Three Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	267.70	2677.00	Rupees Two Thousand Six Hundred Seventy Seven Only
<b>Total in figure :</b>					96844.14	Rupees Three Lakh Sixty Six Thousand Eight Hundred Thirty and Paise Fifteen Only
<b>Total in Words :</b>					<b>Rupees Ninety Six Thousand Eight Hundred Forty Four and Paise Fourteen Only</b>	

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 89109.61  
 Earnest Money Rs:- 1800.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Shegji Prashar road km. 0/00 to 22/510. (PDNA -2023). (Sub Head:- Construction of retaining wall at R.D. 0/526 to 0/528).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.40	Per cubic metre	491.80	5114.72	Rupees Five Thousand One Hundred Fourteen and Paise Seventy Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.29	Per cubic metre	4549.70	78664.31	Rupees Seventy Eight Thousand Six Hundred Sixty Four and Paise Thirty One Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.00	Each	272.30	1089.20	Rupees One Thousand Eighty Nine and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.88	Per cubic metre	1472.70	4241.38	Rupees Four Thousand Two Hundred Forty One and Paise Thirty Eight Only
<b>Total in figure :</b>					<b>89109.61</b>	<b>Rupees Eighty Nine Thousand One Hundred Nine and Paise Sixty One Only</b>
<b>Total in Words :</b>					<b>Rupees Eighty Nine Thousand One Hundred Nine and Paise Sixty One Only</b>	

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.